

Solicitation Questions and Answers

FFD answers in red below.

#	SOW Reference	Question	Answer
1.	Zone Panel	A-190 Note 10 calls out for new zone alarm panel. Electrical 1-E-101 does not show one in that location. Is new zone panel to be installed?	
2.	Zone Alarm Panel	A-210 Note 13.1 & 12.6 zone alarm panel. Electrical 1-E-103 does not show one in that location. Is new zone panel to be installed?	
3.		Please disregard the first two RFI questions (error)	Disregarded, questions are from a different site walk.
4.	Mech	What are the specifications for the commercial portable medical air and vacuum skids?	Exterior medical air and vacuum skids to meet or exceed capacities shown in the equipment schedules on P-0.01.
5.	Mech	Who is the manufacturer of the skids and what are the model numbers?	Exterior skids to be submitted and supplied by the contractor upon FFD review and approval.
6.	Mech	How are the skids protected from the elements?	Exterior skids to be enclosed in weatherproof enclosure, NEMA 4 minimum.
7.	Mech	Do the exterior connections remain after the project?	Exterior connections to remain, refer to equipment schedule on plansheet P-0.01 for provisions to lock the exterior connections.
8.	Mech	On sheet P-1.02 note #2 states to have the piping as high as possible. The plans shows installing a purge valve before the piping goes down to the units. That valve will only be accessible from a ladder. Should it be closer to the unit?	On plansheet P-1.02, install purge valves near MAC-1 and VAC-1 to be accessible from the ground before piping elevates over existing duct.
9.	Mech	What is the size of the purge valves?	Purge valves to be full pipe size as shown on plansheet P-1.02.