

Date: 8/17/2022**Project:** Renovate and Consolidate Inpatient Functions
Bldg 113**To:** Stone Group Architects**Project #:** VAMC 568-14-110
WPE: BR21020**From:** West Plains Engineering
1750 Rand Road
Rapid City, SD 57702**Project Location:** Ft. Meade, SD**Addendum Number:** Addendum 0003

To: All prime contract bidders and all others to whom Drawings and Specifications have been issued by the Engineer. Acknowledge receipt of the Addendum by inserting its number and date on the Bid Form. Failure to do so may subject bidder to disqualification. This Addendum forms a part of the Contract Documents. It modifies them as follows:

Drawings

Sheet MJ103:

1. For Comment #4 under the Air Handling Unit Schedule, the steam humidifier shall be provided with 5 psi LPS steam at a load of 74 lbs/h. Humidifier shall be installed on the supply ductwork leaving the unit. Ductwork shall be stainless steel for 1 ft before and 4 ft after the humidifier, pitched to a drain, with a 3/4" condensate drain piped to the nearest floor drain.
2. For Comment #5 under the Air Handling Unit Schedule, the steam humidifier shall be provided with 5 psi LPS steam at a load of 39.3 lbs/h. Humidifier shall be installed on the supply ductwork leaving the unit. Ductwork shall be stainless steel for 1 ft before and 4 ft after the humidifier, pitched to a drain, with a 3/4" condensate drain piped to the nearest floor drain.
3. For Comment #6 under the Air Handling Unit Schedule, the steam humidifier shall be provided with 5 psi LPS steam at a load of 91.4 lbs/h. Humidifier shall be installed on the supply ductwork leaving the unit. Ductwork shall be stainless steel for 1 ft before and 4 ft after the humidifier, pitched to a drain, with a 3/4" condensate drain piped to the nearest floor drain.

END OF DOCUMENT – MSH/MRS