

Scope of Work
568A4-22-206 Repairs of Storm Damage
VA Black Hills Health Care System, Hot Springs, SD

General Scope:

Contractor shall provide construction services to include roofing, concrete, and general construction to repair storm damage at the VA Medical Center (VAMC) in Hot Springs, South Dakota. This project consists of replacement of damaged clay tile, replacement of glass windows, roof repair, downspout replacement, concrete replacement, and various other items to address hail/storm damage at Hot Springs. The period of performance for this work is 90 days from issuance of Notice to Proceed (NTP). Work shall include but not be limited to the following:

- Remove and replace existing sheathing and Spanish clay tiles over ice/water shield at locations shown on the drawings.
- Remove and replace flashing on Building 12.
- Remove and replace 16 damaged and/or broken glass panels of Building 1 dome.
- Remove existing and replace with new awning of Building 43.
- Remove existing lath and plaster fountain and replace with new concrete fountain.
- Remove existing and replace new gutter on Building 9.

VHA Supplemental Contract Requirements for Combatting COVID-19:
Contractor employees who work in or travel to VHA locations must comply with the following:

- a. Documentation requirements:
 - 1) If fully vaccinated, contractors shall show proof of vaccination.
 - i. **NOTE:** *Acceptable proof of vaccination includes a signed record of immunization from a health care provider or pharmacy, a copy of the COVID-19 Vaccination Record Card (CDC Form MLS-319813_r, published on September 3, 2020), or a copy of medical records documenting the vaccination.*
 - 2) If unvaccinated, contractors shall show negative COVID-19 test results dated within three calendar days prior to desired entry date. Test must be approved by the Food and Drug Administration (FDA) for emergency use or full approval. This includes tests available by a doctor's order or an FDA approved over-the-counter test that includes an affiliated telehealth service.
 - 3) Documentation cited in this section shall be digitally or physically maintained on each contractor employee while in a VA facility and is subject to inspection prior to entry to VA facilities and after entry for spot inspections by Contracting Officer Representatives (CORs) or other hospital personnel.

- 4) Documentation will not be collected by the VA; contractors shall, at all times, adhere to and ensure compliance with federal laws designed to protect contractor employee health information and personally identifiable information.

Contractor employees are subject to daily screening for COVID-19 and may be denied entry to VA facilities if they fail to pass screening protocols. As part of the screening process contractors may be asked screening questions found on the [COVID-19 Screening Tool](#). Check regularly for updates.

- a. Contractor employees who work away from VA locations, but who will have direct contact with VA patients shall self-screen utilizing the [COVID-19 Screening Tool](#), in advance, each day that they will have direct patient contact and in accordance with their person or persons who coordinate COVID-19 workplace safety efforts at covered contractor workplaces. Contractors shall, at all times, adhere to and ensure compliance with federal laws designed to protect contractor employee health information and personally identifiable information.

Contractor must immediately notify their COR or Contracting Officer if contract performance is jeopardized due to contractor employees being denied entry into VA Facilities.