

Solicitation Questions and Answers

#	SOW Reference	Question	Answer
1.	Spec Section 013526 Safety Requirements, 1.7 C.	Please confirm that the prime contractor's superintendent cannot fulfill the SSHO duties for this project.	Correct, the superintendent and the SSHO need to be separate people.
2.	Drawings - Tunnel E1/AS1.01 Keynote	The referenced keynote states, "provide a unit cost to replace conduit, conductors...". There is no place to provide unit costs on the Price Schedule. Please confirm if unit pricing for this work is required.	All work shown or anticipated, and the costs associated, need to be adequately covered and should be shown in their perspective division.
3.	Existing conditions - Building 7 Roof	Is there a current warranty on the building 7 roof? If so, who holds the current warranty?	There is no current warranty on this roof.
4.	Existing conditions Div 4	Can material submittals be supplied to match existing requirements?	Follow Division 4 for required materials.
5.	Limited NTP	Will the VA consider a Limited NTP for procuring materials?	Generally, the use of administrative NTP's are not encouraged. The contract construction days usually accounts for all construction and administrative duties.
6.	Door Specs	Note P1 on plan page AS1.04 indicating a NEW stainless-steel door, frame and hardware. When going to the spec book I do not see a spec section for stainless steel. Please confirm/clarify if this is to be stainless steel and if a spec section could be issued	Follow the notes for the stainless door as listed on the drawings sheet AS1.04. Refer to Addendum document for HW-1A hardware group information added to Spec 08 71 00 and is applicable to sheet AS1.04 Note P1. See "S06 Q_A Atch 1 - Revised Specification Section 08 71 00 - 7 pages"
7.	Salt Room	Clarification on the Salt Room: Ferrogard is called out on the plans SS5.0 Section B, I believe this call out should be the epoxy coating as detailed under Project Area "B" New Framing Plan on sheet SS1.02 although the spec. section 09 96 56 only calls out coating the ceiling and walls	Correct, epoxy coating should be applied to the floor, walls, and ceiling.

		and not the floor.	
8.	Salt Room	Confirming understanding of what the VA is looking for in the Salt Room - applying the Ferrogard to the existing walls prior to the new walls being installed and then all new surfaces: walls, ceiling plank and floor will be coated with the epoxy coating. Is this correct?	Substitute epoxy for Ferrogard. Epoxy to be installed on existing walls, and new walls, floor, and ceiling.
9.	Epoxy	Epoxy Crack injection is only called out on four columns and a single location on the ceiling in building 7, and 2 locations in the tunnel. While looking through the pictures in Specs part 1 file there are 3 locations that look like epoxy injection would be needed (Photos E11, E14 & E15). Should it be assumed that these will be injected although not called out?	Yes, these should be injected. Per drawings, if locations of distress are found not shown on drawings, contact EOR and Owner to verify and repair.
10.	Concrete Epoxy	Is there any spec section or specific info for the desired epoxy crack injection scope and items?	Contractor to provide material for architect/engineer approval. Spec for Epoxy Joint Filler states "Two component, 100 percent solids compound, with a minimum shore D hardness of 50" and bonding admixture to be "Non-rewettable, polymer modified, bonding compound."