

Solicitation Questions and Answers

#	SOW Reference	Question	Answer
1.	Reference: AS1.02, B1 Building 7 Utility Plan	Reference: AS1.02, B1 Building 7 Utility Plan Question: There is sprinkler piping shown on the building 7 Utility Plan but there is no fire sprinkler work called out. Please confirm there is no fire sprinkler work required.	Confirmed; no fire sprinkler work is anticipated, but fire sprinkler lines will need to be protected and temporarily supported as required to complete the structural work (ref. keyed note M1).
2.	Electrical	At grid line 4, the J-Boxes above the gear would appear to be in the way of construction and in the way of the A2 constructed wall and beam detail. (Grid line 5 is another example.) Is it the intent of the documents to move these items as required? Or, should this be handled on a case by case condition where more than a supporting framework for conduits is required to complete that construction area as alluded to on sheet AS1-02, keyed note E1, bullet point #3?	Generally, items will need to be handled on a case-by-case basis. In the case of the large custom j-boxes over the electrical gear in Electrical room 106A, remove the existing j-boxes and replace with new custom j-boxes to accommodate the rated gypsum board enclosure. Refer to Addendum 2 for additional information.