

# **Specifications**

Black Hills Veterans Affairs Health Care System
Pine Ridge VA Clinic

# EHRM Infrastructure Upgrades

Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121


100% Construction Documents Submission

March 31, 2022

BANCROFT ARCHITECTS + ENGINEERS

700 Nicholas Bivd. Suite 300 | Elk Grove Village, IL 60007
847.952.9362 | www.bancroft-ae.com

# SPECIFICATIONS VOL 02 DIVISIONS 21-48



#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

# SECTION 22 05 11 COMMON WORK RESULTS FOR PLUMBING

# PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. The requirements of this Section shall apply to all sections of Division 22.
- B. Definitions:
  - 1. Exposed: Piping and equipment exposed to view in finished rooms.
  - 2. Exterior: Piping and equipment exposed to weather be it temperature, humidity, precipitation, wind or solar radiation.
- C. Abbreviations/Acronyms:
  - 1. ABS: Acrylonitrile Butadiene Styrene
  - 2. AC: Alternating Current
  - 3. ACR: Air Conditioning and Refrigeration
  - 4. A/E: Architect/Engineer
  - 5. AFF: Above Finish Floor
  - 6. AFG: Above Finish Grade
  - 7. AI: Analog Input
  - 8. AISI: American Iron and Steel Institute
  - 9. AO: Analog Output
  - 10. ASHRAE: American Society of Heating Refrigeration, Air Conditioning Engineers
  - 11. ASJ: All Service Jacket
  - 12. ASME: American Society of Mechanical Engineers
  - 13. ASPE: American Society of Plumbing Engineers
  - 14. AWG: American Wire Gauge
  - 15. BACnet: Building Automation and Control Network
  - 16. BAg: Silver-Copper-Zinc Brazing Alloy
  - 17. BAS: Building Automation System
  - 18. BCuP: Silver-Copper-Phosphorus Brazing Alloy
  - 19. bhp: Brake Horsepower
  - 20. Btu: British Thermal Unit
  - 21. Btu/h: British Thermal Unit per Hour
  - 22. BSG: Borosilicate Glass Pipe
  - 23. C: Celsius

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- 24. CA: Compressed Air
- 25. CD: Compact Disk
- 26. CDA: Copper Development Association
- 27. CGA: Compressed Gas Association
- 28. CFM: Cubic Feet per Minute
- 29. CI: Cast Iron
- 30. CLR: Color
- 31. CO: Contracting Officer
- 32. COR: Contracting Officer's Representative
- 33. CPVC: Chlorinated Polyvinyl Chloride
- 34. CR: Chloroprene
- 35. CRS: Corrosion Resistant Steel
- 36. CWP: Cold Working Pressure
- 37. CxA: Commissioning Agent
- 38. dB: Decibels
- 39. db(A): Decibels (A weighted)
- 40. DCW: Domestic Cold Water
- 41. DDC: Direct Digital Control
- 42. DFU: Drainage Fixture Units
- 43. DHW: Domestic Hot Water
- 44. DHWR: Domestic Hot Water Return
- 45. DHWS: Domestic How Water Supply
- 46. DI: Digital Input
- 47. DI: Deionized Water
- 48. DISS: Diameter Index Safety System
- 49. DN: Diameter Nominal
- 50. DO: Digital Output
- 51. DOE: Department of Energy
- 52. DVD: Digital Video Disc
- 53. DWG: Drawing
- 54. DWH: Domestic Water Heater
- 55. DWS: Domestic Water Supply
- 56. DWV: Drainage, Waste and Vent
- 57. ECC: Engineering Control Center
- 58. EL: Elevation
- 59. EMCS: Energy Monitoring and Control System

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- 60. EPA: Environmental Protection Agency
- 61. EPACT: Energy Policy Act
- 62. EPDM: Ethylene Propylene Diene Monomer
- 63. EPT: Ethylene Propylene Terpolymer
- 64. ETO: Ethylene Oxide
- 65. F: Fahrenheit
- 66. FAR: Federal Acquisition Regulations
- 67. FD: Floor Drain
- 68. FDC: Fire Department (Hose) Connection
- 69. FED: Federal
- 70. FG: Fiberglass
- 71. FNPT: Female National Pipe Thread
- 72. FOR: Fuel Oil Return
- 73. FOS: Fuel Oil Supply
- 74. FOV: Fuel Oil Vent
- 75. FPM: Fluoroelastomer Polymer
- 76. FSK: Foil-Scrim-Kraft Facing
- 77. FSS: VA Construction & Facilities Management, Facility Standards Service
- 78. FU: Fixture Units
- 79. GAL: Gallon
- 80. GCO: Grade Cleanouts
- 81. GPD: Gallons per Day
- 82. GPH: Gallons per Hour
- 83. GPM: Gallons per Minute
- 84. HDPE: High Density Polyethylene
- 85. HEFP: Healthcare Environment and Facilities Program (replacement for OCAMES)
- 86. HEX: Heat Exchanger
- 87. Hg: Mercury
- 88. HOA: Hands-Off-Automatic
- 89. HP: Horsepower
- 90. HVE: High Volume Evacuation
- 91. Hz: Hertz
- 92. ID: Inside Diameter
- 93. IE: Invert Elevation

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

94. INV: Invert

95. IPC: International Plumbing Code

96. IPS: Iron Pipe Size

97. IW: Indirect Waste

98. IWH: Instantaneous Water Heater

99. Kg: Kilogram

100. kPa: Kilopascal

101. KW: Kilowatt

102. KWH: Kilowatt Hour

103. lb: Pound

104. lbs/hr: Pounds per Hour

105. LNG: Liquid Natural Gas

106. L/min: Liters per Minute

107. LOX: Liquid Oxygen

108. L/s: Liters per Second

109. m: Meter

110. MA: Medical Air

111. MAWP: Maximum Allowable Working Pressure

112. MAX: Maximum

113. MBH: 1000 Btu per Hour

114. MED: Medical

115. MER: Mechanical Equipment Room

116. MFG: Manufacturer

117. mg: Milligram

118. mg/L: Milligrams per Liter

119. ml: Milliliter

120. mm: Millimeter

121. MIN: Minimum

122. MV: Medical Vacuum

123. N2: Nitrogen

124. N20: Nitrogen Oxide

125. NC: Normally Closed

126. NF: Oil Free Dry (Nitrogen)

127. NG: Natural Gas

128. NIC: Not in Contract

129. NO: Normally Open

Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

02/17/2022

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- 130. NOM: Nominal
- 131. NPTF: National Pipe Thread Female
- 132. NPS: Nominal Pipe Size
- 133. NPT: Nominal Pipe Thread
- 134. NTS: Not to Scale
- 135.02: Oxygen
- 136. OC: On Center
- 137. OD: Outside Diameter
- 138. OSD: Open Sight Drain
- 139. OS&Y: Outside Stem and Yoke
- 140. PA: Pascal
- 141. PBPU: Prefabricated Bedside Patient Units
- 142. PD: Pressure Drop or Difference
- 143. PDI: Plumbing and Drainage Institute
- 144. PH: Power of Hydrogen
- 145. PID: Proportional-Integral-Differential
- 146. PLC: Programmable Logic Controllers
- 147. PP: Polypropylene
- 148. ppb: Parts per Billion
- 149. ppm: Parts per Million
- 150. PSI: Pounds per Square Inch
- 151. PSIA: Pounds per Square Inch Atmosphere
- 152. PSIG: Pounds per Square Inch Gauge
- 153. PTFE: Polytetrafluoroethylene
- 154. PVC: Polyvinyl Chloride
- 155. PVDF: Polyvinylidene Fluoride
- 156. RAD: Radians
- 157. RO: Reverse Osmosis
- 158. RPM: Revolutions Per Minute
- 159. RTD: Resistance Temperature Detectors
- 160. RTRP: Reinforced Thermosetting Resin Pipe
- 161. SAN: Sanitary Sewer
- 162. SCFM: Standard Cubic Feet per Minute
- 163. SDI: Silt Density Index
- 164. SMACNA: Sheet Metal and Air Conditioning Contractors National Association

Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- 165. SPEC: Specification
- 166. SPS: Sterile Processing Services
- 167. SQFT/SF: Square Feet
- 168. SS: Stainless Steel
- 169. STD: Standard
- 170. SUS: Saybolt Universal Second
- 171. SWP: Steam Working Pressure
- 172. TD: Temperature Difference
- 173. TDH: Total Dynamic Head
- 174. TEFC: Totally Enclosed Fan-Cooled
- 175. TEMP: Temperature
- 176. TFE: Tetrafluoroethylene
- 177. THERM: 100,000 Btu
- 178. THHN: Thermoplastic High-Heat Resistant Nylon Coated Wire
- 179. THWN: Thermoplastic Heat & Water Resistant Nylon Coated Wire
- 180. TIL: Technical Information Library http://www.cfm.va.gov/til/indes.asp
- 181. T/P: Temperature and Pressure
- 182. TYP: Typical
- 183. USDA: U.S. Department of Agriculture
- 184. V: Vent
- 185. V: Volt
- 186. VA: Veterans Administration
- 187. VA CFM: VA Construction & Facilities Management
- 188. VA CFM CSS: VA Construction & Facilities Management, Consulting Support Service
- 189. VAC: Vacuum
- 190. VAC: Voltage in Alternating Current
- 191. VAMC: Veterans Administration Medical Center
- 192. VHA OCAMES: This has been replaced by HEFP.
- 193. VSD: Variable Speed Drive
- 194. VTR: Vent through Roof
- 195. W: Waste
- 196. WAGD: Waste Anesthesia Gas Disposal
- 197. WC: Water Closet
- 198. WG: Water Gauge

Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- 199. WOG: Water, Oil, Gas
- 200. WPD: Water Pressure Drop
- 201. WSFU: Water Supply Fixture Units

# 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- C. Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT.
- D. Section 01 81 13, SUSTAINABLE CONSTRUCTION REQUIREMENTS.
- E. Section 01 91 00, GENERAL COMMISSIONING REQUIREMENTS.
- F. Section 02 82 11, TRADITIONAL ASBESTOS ABATEMENT.
- G. Section 03 30 00, CAST-IN-PLACE CONCRETE: Concrete and Grout.
- H. Section 05 31 00, STEEL DECKING: Building Components for Attachment of Hangers.
- I. Section 05 36 00, COMPOSITE METAL DECKING: Building Components for Attachment of Hangers.
- J. Section 05 50 00, METAL FABRICATIONS.
- K. Section 07 60 00, FLASHING AND SHEET METAL: Flashing for Wall and Roof Penetrations.
- L. Section 07 84 00, FIRESTOPPING.
- M. Section 07 92 00, JOINT SEALANTS.
- N. Section 09 91 00, PAINTING.
- O. Section 22 05 12, GENERAL MOTOR REQUIREMENTS FOR PLUMBING EQUIPMENT.
- P. Section 22 07 11, PLUMBING INSULATION.

Q.

- R. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.
- S. Section 26 05 19, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES.
- T. Section 26 29 11, MOTOR CONTROLLERS.

# 1.3 APPLICABLE PUBLICATIONS

- A. The publications listed below shall form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only. Where conflicts occur these specifications and the VHA standard will govern.
- B. American Society of Mechanical Engineers (ASME):

B31.1-2013.....Power Piping

ASME Boiler and Pressure Vessel Code -

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

	09-01-20
	BPVC Section IX-2019 Welding, Brazing, and Fusing Qualifications
С.	American Society for Testing and Materials (ASTM):
	A36/A36M-2019Standard Specification for Carbon Structural
	Steel
	A575-96(2013)elStandard Specification for Steel Bars, Carbon,  Merchant Quality, M-Grades
	E84-2013aStandard Test Method for Surface Burning
	Characteristics of Building Materials
	E119-2012aStandard Test Methods for Fire Tests of
	Building Construction and Materials
D.	<pre>International Code Council, (ICC):</pre>
	IBC-2018International Building Code
	IPC-2018International Plumbing Code
Ε.	Manufacturers Standardization Society (MSS) of the Valve and Fittings
	Industry, Inc:
	SP-58-2018Pipe Hangers and Supports - Materials, Design,
	Manufacture, Selection, Application and
	Installation
F.	Military Specifications (MIL):
	P-21035BPaint High Zinc Dust Content, Galvanizing
	Repair (Metric)
G.	National Electrical Manufacturers Association (NEMA):
	MG 1-2016Motors and Generators
Н.	National Fire Protection Association (NFPA):
	51B-2019 Standard for Fire Prevention During Welding,
	Cutting and Other Hot Work
	54-2018National Fuel Gas Code
	70-2020National Electrical Code (NEC)
	99-2018Healthcare Facilities Code
I.	NSF International (NSF):
	5-2019Water Heaters, Hot Water Supply Boilers, and
	Heat Recovery Equipment
	14-2019Plastic Piping System Components and Related
	Materials
	61-2019Drinking Water System Components - Health
	Effects

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

372-2016......Drinking Water System Components - Lead Content

J. Department of Veterans Affairs (VA):

PG-18-102014(R18)......Plumbing Design Manual PG-18-13-2017(R18).....Barrier Free Design Guide

#### 1.4 SUBMITTALS

- A. Submittals, including number of required copies, shall be submitted in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Information and material submitted under this section shall be marked "SUBMITTED UNDER SECTION 22 05 11, COMMON WORK RESULTS FOR PLUMBING", with applicable paragraph identification.
- C. Contractor shall make all necessary field measurements and investigations to assure that the equipment and assemblies will meet contract requirements, and all equipment that requires regular maintenance, calibration, etc are accessable from the floor or permanent work platform. It is the Contractor's responsibility to ensure all submittals meet the VA specifications and requirements and it is assumed by the VA that all submittals do meet the VA specifications unless the Contractor has requested a variance in writing and approved by COR prior to the submittal. If at any time during the project it is found that any item does not meet the VA specifications and there was no variance approval the Contractor shall correct at no additional cost or time to the Government even if a submittal was approved.
- D. If equipment is submitted which differs in arrangement from that shown, provide documentation proving equivalent performance, design standards and drawings that show the rearrangement of all associated systems. Additionally, any impacts on ancillary equipment or services such as foundations, piping, and electrical shall be the Contractor's responsibility to design, supply, and install at no additional cost or time to the Government. VA approval will be given only if all features of the equipment and associated systems, including accessibility, are equivalent to that required by the contract.
- E. Prior to submitting shop drawings for approval, Contractor shall certify in writing that manufacturers of all major items of equipment have each reviewed drawings and specifications, and have jointly

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- coordinated and properly integrated their equipment and controls to provide a complete and efficient installation.
- F. Submittals and shop drawings for interdependent items, containing applicable descriptive information, shall be furnished together and complete in a group. Coordinate and properly integrate materials and equipment in each group to provide a completely compatible and efficient installation. Final review and approvals will be made only by groups.
- G. Manufacturer's Literature and Data including: Manufacturer's literature shall be submitted under the pertinent section rather than under this section.
  - 1. Electric motor data and variable speed drive data shall be submitted with the driven equipment.
  - 2. Equipment and materials identification.
  - 3. Firestopping materials.
  - 4. Hangers, inserts, supports and bracing. Provide load calculations for variable spring and constant support hangers.
  - 5. Wall, floor, and ceiling plates.
- H. Coordination/Shop Drawings:
  - 1. Submit complete consolidated and coordinated shop drawings for all new systems, and for existing systems that are in the same areas.
  - 2. The coordination/shop drawings shall include plan views, elevations and sections of all systems and shall be on a scale of not less than 1:32 (3/8-inch equal to 1 foot). Clearly identify and dimension the proposed locations of the principal items of equipment. The drawings shall clearly show locations and adequate clearance for all equipment, piping, valves, control panels and other items. Show the access means for all items requiring access for operations and maintenance. Provide detailed coordination/shop drawings of all piping and duct systems. The drawings should include all lockout/tagout points for all energy/hazard sources for each piece of equipment. Coordinate lockout/tagout procedures and practices with local VA requirements.
  - 3. Do not install equipment foundations, equipment or piping until coordination/shop drawings have been approved.

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- 4. In addition, for plumbing systems, provide details of the following:
  - a. Mechanical equipment rooms.
  - b. Hangers, inserts, supports, and bracing.
  - c. Pipe sleeves.
  - d. Duct or equipment penetrations of floors, walls, ceilings, or roofs.
- I. Rigging Plan: Provide documentation of the capacity and weight of the rigging and equipment intended to be used. The plan shall include the path of travel of the load, the staging area and intended access, and qualifications of the operator and signal person.
- J. Plumbing Maintenance Data and Operating Instructions:
  - 1. Maintenance and operating manuals in accordance with Section 01 00 00, GENERAL REQUIREMENTS, Article, INSTRUCTIONS, for systems and equipment.
  - 2. Complete operating and maintenance manuals including wiring diagrams, technical data sheets, information for ordering replacement parts, and troubleshooting guide:
    - a. Include complete list indicating all components of the systems.
    - b. Include complete diagrams of the internal wiring for each item of equipment.
    - c. Diagrams shall have their terminals identified to facilitate installation, operation and maintenance.
  - 3. Provide a listing of recommended replacement parts for keeping in stock supply, including sources of supply, for equipment. Include in the listing belts for equipment: Belt manufacturer, model number, size and style, and distinguished whether of multiple belt sets.
- K. Provide copies of approved plumbing equipment submittals to the TAB Subcontractor.

L.

Μ.

# 1.5 QUALITY ASSURANCE

A. Mechanical, electrical, and associated systems shall be safe, reliable, efficient, durable, easily and safely operable and maintainable, easily and safely accessible, and in compliance with applicable codes as specified. The systems shall be comprised of high quality

institutional-class and industrial-class products of manufacturers that Contract No. 36C26319D0044

Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

are experienced specialists in the required product lines. All construction firms and personnel shall be experienced and qualified specialists in industrial and institutional plumbing.

#### B. Products Criteria:

- 1. Standard Products: Material and equipment shall be the standard products of a manufacturer regularly engaged in the manufacture, supply and servicing of the specified products for at least 5 years. However, digital electronics devices, software and systems such as controls, instruments, computer work station, shall be the current generation of technology and basic design that has a proven satisfactory service record of at least 5 years.
- 2. Equipment Service: There shall be permanent service organizations, authorized and trained by manufacturers of the equipment supplied, located within 160 km (100 miles) of the project. These organizations shall come to the site and provide acceptable service to restore operations within 4 hours of receipt of notification by phone, e-mail or fax in event of an emergency, such as the shut-down of equipment; or within 24 hours in a non-emergency. Names, mail and e-mail addresses and phone numbers of service organizations providing service under these conditions for (as applicable to the project): pumps, compressors, water heaters, critical instrumentation, computer workstation and programming shall be submitted for project record and inserted into the operations and maintenance manual.
- 3. All items furnished shall be free from defects that would adversely affect the performance, maintainability and appearance of individual components and overall assembly.
- 4. The products and execution of work specified in Division 22 shall conform to the referenced codes and standards as required by the specifications. Local codes and amendments enforced by the local code official shall be enforced, if required by local authorities such as the natural gas supplier. If the local codes are more stringent, then the local code shall apply. Any conflicts shall be brought to the attention of the Contracting Officers Representative (COR).

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- 5. Multiple Units: When two or more units of materials or equipment of the same type or class are required, these units shall be of the same manufacturer and model number, or if different models are required they shall be of the same manufacturer and identical to the greatest extent possible (i.e., same model series).
- 6. Assembled Units: Performance and warranty of all components that make up an assembled unit shall be the responsibility of the manufacturer of the completed assembly.
- 7. Nameplates: Nameplate bearing manufacturer's name or identifiable trademark shall be securely affixed in a conspicuous place on equipment, or name or trademark cast integrally with equipment, stamped or otherwise permanently marked on each item of equipment.
- 8. Asbestos products or equipment or materials containing asbestos is prohibited.
- 9. Bio-Based Materials: For products designated by the USDA's bio-based Bio-Preferred Program, provide products that meet or exceed USDA recommendations for bio-based content, so long as products meet all performance requirements in this specifications section. For more information regarding the product categories covered by the Bio-Preferred Program, visit http://www.biopreferred.gov.
- C. Welding: Before any welding is performed, Contractor shall submit a certificate certifying that welders comply with the following requirements:
  - Qualify welding processes and operators for piping according to ASME BPVC, Section IX, "Welding and Brazing Qualifications". Provide proof of current certification to CO.
  - Comply with provisions of ASME B31 series "Code for Pressure Piping".
  - 3. Certify that each welder and welding operator has passed American Welding Society (AWS) qualification tests for the welding processes involved, and that certification is current.
  - 4. All welds shall be stamped according to the provisions of the AWS or ASME as required herein and by the association code.
- D. Manufacturer's Recommendations: Where installation procedures or any part thereof are required to be in accordance with the recommendations of the manufacturer of the material being installed, printed copies of

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

these recommendations shall be furnished to the COR prior to installation. Installation of the item will not be allowed to proceed until the recommendations are received. Failure to furnish these recommendations can be cause for rejection of the material.

- E. Execution (Installation, Construction) Quality:
  - 1. All items shall be applied and installed in accordance with manufacturer's written instructions. Conflicts between the manufacturer's instructions and the contract documents shall be referred to the COR for resolution. Printed copies or electronic files of manufacturer's installation instructions shall be provided to the COR at least 10 working days prior to commencing installation of any item.
  - 2. All items that require access, such as for operating, cleaning, servicing, maintenance, and calibration, shall be easily and safely accessible by persons standing at floor level, or standing on permanent platforms, without the use of portable ladders. Examples of these items include but are not limited to: all types of valves, filters and strainers, transmitters, and control devices. Prior to commencing installation work, refer conflicts between this requirement and contract documents to COR for resolution. Failure of the Contractor to resolve or call attention to any discrepancies or deficiencies to the COR will result in the Contractor correcting at no additional cost or time to the Government.
  - 3. Complete layout drawings shall be required by Paragraph, SUBMITTALS. Construction work shall not start on any system until the layout drawings have been approved by VA.
  - 4. Installer Qualifications: Installer shall be licensed and shall provide evidence of the successful completion of at least five projects of equal or greater size and complexity. Provide tradesmen skilled in the appropriate trade.
  - 5. Workmanship/craftsmanship will be of the highest quality and standards. The VA reserves the right to reject any work based on poor quality of workmanship this work shall be removed and done again at no additional cost or time to the Government.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- F. Upon request by Government, provide lists of previous installations for selected items of equipment. Include contact persons who will serve as references, with current telephone numbers and e-mail addresses.
- G. Guaranty: Warranty of Construction, FAR clause 52.246-21.
- H. Plumbing Systems: IPC, International Plumbing Code. Unless otherwise required herein, perform plumbing work in accordance with the latest version of the IPC. For IPC codes referenced in the contract documents, advisory provisions shall be considered mandatory, the word "should" shall be interpreted as "shall". Reference to the "code official" or "owner" shall be interpreted to mean the COR.
- I. Cleanliness of Piping and Equipment Systems:
  - 1. Care shall be exercised in the storage and handling of equipment and piping material to be incorporated in the work. Debris arising from cutting, threading and welding of piping shall be removed.
  - 2. Piping systems shall be flushed, blown or pigged as necessary to deliver clean systems.
  - 3. The interior of all tanks shall be cleaned prior to delivery and beneficial use by the Government. All piping shall be tested in accordance with the specifications and the International Plumbing Code (IPC). All filters, strainers, fixture faucets shall be flushed of debris prior to final acceptance.
  - 4. Contractor shall be fully responsible for all costs, damage, and delay arising from failure to provide clean systems.

# 1.6 DELIVERY, STORAGE AND HANDLING

- A. Protection of Equipment:
  - 1. Equipment and material placed on the job site shall remain in the custody of the Contractor until phased acceptance, whether or not the Government has reimbursed the Contractor for the equipment and material. The Contractor is solely responsible for the protection of such equipment and material against any damage or theft.
  - 2. Damaged equipment shall be replaced with an identical unit as determined and directed by the COR. Such replacement shall be at no additional cost or additional time to the Government.
  - 3. Interiors of new equipment and piping systems shall be protected against entry of foreign matter. Both inside and outside shall be cleaned before painting or placing equipment in operation.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- 4. Existing equipment and piping being worked on by the Contractor shall be under the custody and responsibility of the Contractor and shall be protected as required for new work.
- 5. Protect plastic piping and tanks from ultraviolet light (sunlight) while in pre-construction. Plastic piping and tanks shall not be installed exposed to sunlight without metal jacketing to block ultraviolet rays.

#### 1.7 AS-BUILT DOCUMENTATION

- A. Submit manufacturer's literature and data updated to include submittal review comments and any equipment substitutions.
- B. Submit operation and maintenance data updated to include submittal review comments, VA approved substitutions and construction revisions shall be in electronic version on CD or DVD inserted into a three—ring binder. All aspects of system operation and maintenance procedures, including applicable piping isometrics, wiring diagrams of all circuits, a written description of system design, control logic, and sequence of operation shall be included in the operation and maintenance manual. The operations and maintenance manual shall include troubleshooting techniques and procedures for emergency situations.

  Notes on all special systems or devices shall be included. A List of recommended spare parts (manufacturer, model number, and quantity) shall be furnished. Information explaining any special knowledge or tools the owner will be required to employ shall be inserted into the As-Built documentation.
- C. The installing Contractor shall maintain as-built drawings of each completed phase for verification; and, shall provide the complete set at the time of final systems certification testing. Should the installing Contractor engage the testing company to provide as-built or any portion thereof, it shall not be deemed a conflict of interest or breach of the 'third party testing company' requirement. Provide record drawings as follows:
  - Red-lined, hand-marked drawings are to be provided, with one paper copy and a scanned PDF version of the hand-marked drawings provided on CD or DVD.
- 2. As-built drawings are to be provided, with a copy of them on AutoCAD version 2019 provided on CD or DVD. The CAD drawings shall use Contract No. 36C26319D0044

Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

multiple line layers with a separate individual layer for each system.

- D. The as-built drawings shall indicate the location and type of all lockout/tagout points for all energy sources for all equipment and pumps to include breaker location and numbers, valve tag numbers, etc. Coordinate lockout/tagout procedures and practices with local VA requirements.
- E. Certification documentation shall be provided to COR 21 working days prior to submitting the request for final inspection. The documentation shall include all test results, the names of individuals performing work for the testing agency on this project, detailed procedures followed for all tests, and provide documentation/certification that all results of tests were within limits specified. Test results shall contain written sequence of test procedure with written test results annotated at each step along with the expected outcome or setpoint. The results shall include all readings, including but not limited to data on device (make, model and performance characteristics\_), normal pressures, switch ranges, trip points, amp readings, and calibration data to include equipment serial numbers or individual identifications, etc.

# 1.8 JOB CONDITIONS - WORK IN EXISTING BUILDING

- A. Building Operation: Government employees will be continuously operating and managing all facilities, including temporary facilities that serve the VAMC.
- B. Maintenance of Service: Schedule all work to permit continuous service as required by the VAMC.
- C. Steam and Condensate Service Interruptions: Limited steam and condensate service interruptions, as required for interconnections of new and existing systems, will be permitted by the COR during periods when the demands are not critical to the operation of the VAMC. These non-critical periods are limited to between 8 pm and 5 am in the appropriate off-season (if applicable). Provide at least 10 working days advance notice to the COR. The request shall include a detailed plan on the proposed shutdown and the intended work to be done along with manpower levels. All equipment and materials must be onsite and

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

verified with plan 5calendar days prior to the shutdown or it will need to be rescheduled.

- D. Phasing of Work: Comply with all requirements shown on contract documents. Contractor shall submit a complete detailed phasing plan/schedule with manpower levels prior to commencing work. The phasing plan shall be detailed enough to provide milestones in the process that can be verified.
- E. Building Working Environment: Maintain the architectural and structural integrity of the building and the working environment at all times.

  Maintain the interior of building at 18 degrees C (65 degrees F)

  minimum. Limit the opening of doors, windows or other access openings to brief periods as necessary for rigging purposes. Storm water or ground water leakage is prohibited. Provide daily clean-up of construction and demolition debris on all floor surfaces and on all equipment being operated by VA. Maintain all egress routes and safety systems/devices.
- F. Acceptance of Work for Government Operation: As new equipment, systems and facilities are made available for operation and these items are deemed of beneficial use to the Government, inspections and tests will be performed. Based on the inspections, a list of contract deficiencies will be issued to the Contractor. After correction of deficiencies as necessary for beneficial use, the Contracting Officer will process necessary acceptance and the equipment will then be under the control and operation of Government personnel.

# PART 2 - PRODUCTS

# 2.1 MATERIALS FOR VARIOUS SERVICES

- A. Steel pipe shall contain a minimum of 25 percent recycled content.
- B. Plastic pipe, fittings and solvent cement shall meet NSF 14 and shall bear the NSF seal "NSF-PW". Polypropylene pipe and fittings shall comply with NSF 14 and NSF 61. Solder or flux containing lead shall not be used with copper pipe.
- C. Material or equipment containing a weighted average of greater than 0.25 percent lead shall not be used in any potable water system intended for human consumption and shall be certified in accordance with NSF 61 or NSF 372.

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- D. In-line devices such as water meters, building valves, check valves, stops, valves, fittings, tanks and backflow preventers shall comply with NSF 61 and NSF 372.
- E. End point devices such as drinking fountains, lavatory faucets, kitchen and bar faucets, ice makers supply stops, and end-point control valves used to dispense drinking water must meet requirements of NSF 61 and NSF 372.

#### 2.2 FACTORY-ASSEMBLED PRODUCTS

- A. Standardization of components shall be maximized to reduce spare part requirements.
- B. Manufacturers of equipment assemblies that include components made by others shall assume complete responsibility for final assembled unit.
  - 1. All components of an assembled unit need not be products of same manufacturer.
  - Constituent parts that are alike shall be products of a single manufacturer.
  - 3. Components shall be compatible with each other and with the total assembly for intended service.
  - 4. Contractor shall guarantee performance of assemblies of components and shall repair or replace elements of the assemblies as required to deliver specified performance of the complete assembly at no additional cost or time to the Government.
- C. Components of equipment shall bear manufacturer's name and trademark, model number, serial number and performance data on a name plate securely affixed in a conspicuous place, or cast integral with, stamped or otherwise permanently marked upon the components of the equipment.
- D. Major items of equipment, which serve the same function, shall be the same make and model.

# 2.3 COMPATIBILITY OF RELATED EQUIPMENT

A. Equipment and materials installed shall be compatible in all respects with other items being furnished and with existing items so that the result will be a complete and fully operational system that conforms to contract requirements.

# 2.4 SAFETY GUARDS

A. Pump shafts and couplings shall be fully guarded by a sheet steel guard, covering coupling and shaft but not bearings. Material shall be

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

minimum 16-gauge sheet steel; ends shall be braked and drilled and attached to pump base with minimum of four 8 mm (1/4 inch) bolts. Reinforce guard as necessary to prevent side play forcing guard onto couplings.

B. All Equipment shall have moving parts protected from personal injury.

#### 2.5 LIFTING ATTACHMENTS

A. Equipment shall be provided with suitable lifting attachments to enable equipment to be lifted in its normal position. Lifting attachments shall withstand any handling conditions that might be encountered, without bending or distortion of shape, such as rapid lowering and braking of load.

# 2.6 ELECTRIC MOTORS, MOTOR CONTROL, CONTROL WIRING (NOT USED)

# 2.7 VARIABLE SPEED MOTOR CONTROLLERS (NOT USED)

#### 2.8 EQUIPMENT AND MATERIALS IDENTIFICATION

- A. Use symbols, nomenclature and equipment numbers specified, shown in the drawings, or shown in the maintenance manuals. Coordinate equipment and valve identification with local VAMC shops. In addition, provide bar code identification nameplate for all equipment which will allow the equipment identification code to be scanned into the system for maintenance and inventory tracking. Identification for piping is specified in Section 09 91 00, PAINTING.
- B. Interior (Indoor) Equipment: Engraved nameplates, with letters not less than 7 mm (3/16 inch) high of brass with black-filled letters, or rigid black plastic with white letters specified in Section 09 91 00, PAINTING shall be permanently fastened to the equipment. Unit components such as water heaters, tanks, coils, filters, etc. shall be identified.
- C. Exterior (Outdoor) Equipment: Brass nameplates, with engraved black filled letters, not less than 7 mm (3/16 inch) high riveted or bolted to the equipment.
- D. Control Items: All temperature, pressure, and controllers shall be labeled and the component's function identified. Identify and label each item as they appear on the control diagrams.
- E. Valve Tags and Lists:
  - Plumbing: All valves shall be provided with valve tags and listed on a valve list (Fixture stops not included).

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- 2. Valve tags: Engraved black filled numbers and letters not less than 15 mm (1/2 inch) high for number designation, and not less than 8 mm (1/4 inch) for service designation on 19 gauge, 40 mm (1-1/2 inches) round brass disc, attached with brass "S" hook or brass chain.
- 3. Valve lists: Valve lists shall be created using a word processing program and printed on plastic coated cards. The plastic-coated valve list card(s), sized 215 mm (8-1/2 inches) by 275 mm (11 inches) shall show valve tag number, valve function and area of control for each service or system. The valve list shall be in a punched 3-ring binder notebook. An additional copy of the valve list shall be mounted in picture frames for mounting to a wall. COR shall instruct Contractor where frames shall be mounted.
- 4. A detailed plan for each floor of the building indicating the location and valve number for each valve shall be provided in the 3-ring binder notebook. Each valve location shall be identified with a color-coded sticker or thumb tack in ceiling or access door.

#### 2.9 FIRESTOPPING

A. Section 07 84 00, FIRESTOPPING specifies an effective barrier against the spread of fire, smoke and gases where penetrations occur for piping. Refer to Section 22 07 11, PLUMBING INSULATION, for pipe insulation.

# 2.10 GALVANIZED REPAIR COMPOUND

A. Mil. Spec. DOD-P-21035B, paint.

# 2.11 PIPE AND EQUIPMENT SUPPORTS AND RESTRAINTS

- A. In lieu of the paragraph which follows, suspended equipment support and restraints may be designed and installed in accordance with the International Building Code (IBC). Submittals based on the International Building Code (IBC) requirements, or the following paragraphs of this Section shall be stamped and signed by a professional engineer registered in the state where the project is located. The Support system of suspended equipment over 227 kg (500 pounds) shall be submitted for approval of the COR in all cases. See the above specifications for lateral force design requirements.
- B. Type Numbers Specified: For materials, design, manufacture, selection, application, and installation refer to MSS SP-58. Refer to Section 05

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- 50 00, METAL FABRICATIONS, for miscellaneous metal support materials and prime coat painting.
- C. For Attachment to Concrete Construction:
  - 1. Concrete insert: Type 18, MSS SP-58.
  - 2. Self-drilling expansion shields and machine bolt expansion anchors: Permitted in concrete not less than 100 mm (4 inches) thick when approved by the COR for each job condition.
  - 3. Power-driven fasteners: Permitted in existing concrete or masonry not less than 100 mm (4 inches) thick when approved by the COR for each job condition.
- D. For Attachment to Steel Construction: MSS SP-58.
  - 1. Welded attachment: Type 22.
  - 2. Beam clamps: Types 20, 21, 28 or 29. Type 23 C-clamp may be used for individual copper tubing up to 23 mm (7/8 inch) outside diameter.
- E. Attachment to Metal Pan or Deck: As required for materials specified in
- F. For Attachment to Wood Construction: Wood screws or lag bolts.
- G. Hanger Rods: Hot-rolled steel, ASTM A36/A36M or ASTM A575 for allowable load listed in MSS SP-58. For piping, provide adjustment means for controlling level or slope. Types 13 or 15 turn-buckles shall provide 40 mm (1-1/2 inches) minimum of adjustment and incorporate locknuts. All-thread rods are acceptable.
- H. Multiple (Trapeze) Hangers: Galvanized, cold formed, lipped steel channel horizontal member, not less than 43 mm by 43 mm (1-5/8 inches by 1-5/8 inches), 2.7 mm (No. 12 gauge), designed to accept special spring held, hardened steel nuts.
  - 1. Allowable hanger load: Manufacturers rating less 91kg (200 pounds).
  - 2. Guide individual pipes on the horizontal member of every other trapeze hanger with 8 mm (1/4 inch) U-bolt fabricated from steel rod. Provide Type 40 insulation shield, secured by two 15 mm (1/2 inch) galvanized steel bands, or insulated calcium silicate shield for insulated piping at each hanger.
- I. Pipe Hangers and Supports: (MSS SP-58), use hangers sized to encircle insulation on insulated piping. Refer to Section 22 07 11, PLUMBING INSULATION for insulation thickness. To protect insulation, provide Type 39 saddles for roller type supports or insulated calcium silicate shields. Provide Type 40 insulation shield or insulated calcium

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

silicate shield at all other types of supports and hangers including those for insulated piping.

- 1. General Types (MSS SP-58):
  - a. Standard clevis hanger: Type 1; provide locknut.
  - b. Riser clamps: Type 8.
  - c. Wall brackets: Types 31, 32 or 33.
  - d. Roller supports: Type 41, 43, 44 and 46.
  - e. Saddle support: Type 36, 37 or 38.
  - f. Turnbuckle: Types 13 or 15.
  - g. U-bolt clamp: Type 24.
  - h. Copper Tube:
    - Hangers, clamps and other support material in contact with tubing shall be painted with copper colored epoxy paint, copper-coated, plastic coated or taped with isolation tape to prevent electrolysis.
    - 2) For vertical runs use epoxy painted, copper-coated or plastic coated riser clamps.
    - 3) For supporting tube to strut: Provide epoxy painted pipe straps for copper tube or plastic inserted vibration isolation clamps.
    - 4) Insulated Lines: Provide pre-insulated calcium silicate shields sized for copper tube.
  - i. Supports for plastic or glass piping: As recommended by the pipe manufacturer with black rubber tape extending 1 inch beyond steel support or clamp. Spring Supports (Expansion and contraction of vertical piping):
    - 1) Movement up to 20 mm (3/4 inch): Type 51 or 52 variable spring unit with integral turn buckle and load indicator.
    - 2) Movement more than 20 mm (3/4 inch): Type 54 or 55 constant support unit with integral adjusting nut, turn buckle and travel position indicator.
  - j. Spring hangers are required on all plumbing system pumps one horsepower and greater.
- 2. Plumbing Piping (Other Than General Types):
  - a. Horizontal piping: Type 1, 5, 7, 9, and 10.
  - b. Chrome plated piping: Chrome plated supports.

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- c. Hangers and supports in pipe chase: Prefabricated system ABS self-extinguishing material, not subject to electrolytic action, to hold piping, prevent vibration and compensate for all static and operational conditions.
- d. Blocking, stays and bracing: Angle iron or preformed metal channel shapes, 1.3 mm (18 gauge) minimum.
- J. Pre-insulated Calcium Silicate Shields:
  - Provide 360-degree water resistant high density 965 kPa (140 psig) compressive strength calcium silicate shields encased in galvanized metal
  - 2. Pre-insulated calcium silicate shields to be installed at the point of support during erection.
  - 3. Shield thickness shall match the pipe insulation.
  - 4. The type of shield is selected by the temperature of the pipe, the load it must carry, and the type of support it will be used with.
    - a. Shields for supporting cold water shall have insulation that extends a minimum of 25 mm (1 inch) past the sheet metal.
    - b. The insulated calcium silicate shield shall support the maximum allowable water filled span as indicated in MSS SP-58. To support the load, the shields shall have one or more of the following features: structural inserts 4138 kPa (600 psig) compressive strength, an extra bottom metal shield, or formed structural steel (ASTM A36/A36M) wear plates welded to the bottom sheet metal jacket.
  - 5. Shields may be used on steel clevis hanger type supports, trapeze hangers, roller supports or flat surfaces.
- K. Seismic Restraint of Piping: Refer to Section 13 05 41, SEISMIC RESTRAINT REQUIREMENTS FOR NON-STRUCTURAL COMPONENTS.

#### 2.12 PIPE PENETRATIONS

- A. Pipe penetration sleeves shall be installed for all pipe other than rectangular blocked out floor openings for risers in mechanical bays.
- B. Pipe penetration sleeve materials shall comply with all firestopping requirements for each penetration.
- C. To prevent accidental liquid spills from passing to a lower level, provide the following:

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- 1. For sleeves: Extend sleeve 25 mm (1 inch) above finished floor and provide sealant for watertight joint.
- 2. For blocked out floor openings: Provide 40 mm (1-1/2 inch) angle set in silicone adhesive around opening.
- 3. For drilled penetrations: Provide 40 mm (1-1/2 inch) angle ring or square set in silicone adhesive around penetration.
- D. Penetrations are prohibited through beams or ribs, but may be installed in concrete beam flanges, with structural engineer prior approval. Any deviation from these requirements must receive prior approval of COR.
- E. Sheet metal, plastic, or moisture resistant fiber sleeves shall be provided for pipe passing through floors, interior walls, and partitions, unless brass or steel pipe sleeves are specifically called for below.
- F. Cast iron or zinc coated pipe sleeves shall be provided for pipe passing through exterior walls below grade. The space between the sleeve and pipe shall be made watertight with a modular or link rubber seal. The link seal shall be applied at both ends of the sleeve.
- G. Galvanized steel or an alternate black iron pipe with asphalt coating sleeves shall be for pipe passing through concrete beam flanges, except where brass pipe sleeves are called for. A galvanized steel sleeve shall be provided for pipe passing through floor of mechanical rooms, laundry work rooms, and animal rooms above basement. Except in mechanical rooms, sleeves shall be connected with a floor plate.
- H. Brass Pipe Sleeves shall be provided for pipe passing through quarry tile, terrazzo or ceramic tile floors. The sleeve shall be connected with a floor plate.
- I. Sleeve clearance through floors, walls, partitions, and beam flanges shall be 25 mm (1 inch) greater in diameter than external diameter of pipe. Sleeve for pipe with insulation shall be large enough to accommodate the insulation plus 25 mm (1 inch) in diameter. Interior openings shall be caulked tight with firestopping material and sealant to prevent the spread of fire, smoke, water and gases.
- J. Sealant and Adhesives: Shall be as specified in Section 07 92 00, JOINT SEALANTS. Bio-based materials shall be utilized when possible.

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

K. Pipe passing through roof shall be installed through a 4.9 kg per square meter copper flashing with an integral skirt or flange. Skirt or flange shall extend not less than 200 mm (8 inches) from the pipe and set in a solid coating of bituminous cement. Extend flashing a minimum of 250 mm (10 inches) up the pipe. Pipe passing through a waterproofing membrane shall be provided with a clamping flange. The annular space between the sleeve and pipe shall be sealed watertight.

#### 2.13 TOOLS AND LUBRICANTS

- A. Furnish, and turn over to the COR, special tools not readily available commercially, that are required for disassembly or adjustment of equipment and machinery furnished.
- B. Grease Guns with Attachments for Applicable Fittings: One for each type of grease required for each motor or other equipment.
- C. Tool Containers: metal, permanently identified for intended service and mounted, or located, where directed by the COR.
- D. Lubricants: A minimum of 0.95 L (1 quart) of oil, and 0.45 kg (1 pound) of grease, of equipment manufacturer's recommended grade and type, in unopened containers and properly identified as to use for each different application. Bio-based materials shall be utilized when possible.

# 2.14 WALL, FLOOR AND CEILING PLATES

- A. Material and Type: Chrome plated brass or chrome plated steel, one piece or split type with concealed hinge, with set screw for fastening to pipe, or sleeve. Use plates that fit tight around pipes, cover openings around pipes and cover the entire pipe sleeve projection.
- B. Thickness: Not less than 2.4 mm (3/32 inch) for floor plates. For wall and ceiling plates, not less than 0.64 mm (0.025 inch) for up to 75 mm (3 inch) pipe, 0.89 mm (0.035 inch) for larger pipe.
- C. Locations: Use where pipe penetrates floors, walls and ceilings in exposed locations, in finished areas only. Wall plates shall be used where insulation ends on exposed water supply pipe drop from overhead. A watertight joint shall be provided in spaces where brass or steel pipe sleeves are specified.

# 2.15 ASBESTOS

A. Materials containing asbestos are prohibited.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

#### PART 3 - EXECUTION

# 3.1 ARRANGEMENT AND INSTALLATION OF EQUIPMENT AND PIPING

- A. Location of piping, sleeves, inserts, hangers, and equipment, access provisions shall be coordinated with the work of all trades. Piping, sleeves, inserts, hangers, and equipment shall be located clear of windows, doors, openings, light outlets, and other services and utilities. Equipment layout drawings shall be prepared to coordinate proper location and personnel access of all facilities. The drawings shall be submitted for review.
- B. Manufacturer's published recommendations shall be followed for installation methods not otherwise specified.
- C. Operating Personnel Access and Observation Provisions: All equipment and systems shall be arranged to provide clear view and easy access, without use of portable ladders, for maintenance, testing and operation of all devices including, but not limited to: all equipment items, valves, backflow preventers, filters, strainers, transmitters, sensors, meters and control devices. All gauges and indicators shall be clearly visible by personnel standing on the floor or on permanent platforms. Maintenance and operating space and access provisions that are shown in the drawings shall not be changed nor reduced.
- D. Structural systems necessary for pipe and equipment support shall be coordinated to permit proper installation.
- E. Location of pipe sleeves, trenches and chases shall be accurately coordinated with equipment and piping locations.

# F. Cutting Holes:

- 1. Holes shall be located to avoid interference with structural members such as beams or grade beams. Holes shall be laid out in advance and drilling done only after approval by COR. If the Contractor considers it necessary to drill through structural members, this matter shall be referred to COR for approval.
- 2. Waterproof membrane shall not be penetrated. Pipe floor penetration block outs shall be provided outside the extents of the waterproof membrane.
- 3. Holes through concrete and masonry shall be cut by rotary core drill. Pneumatic hammer, impact electric, and hand or manual hammer

Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

type drill will not be allowed, except as permitted by COR where working area space is limited.

- G. Minor Piping: Generally, small diameter pipe runs from drips and drains, water cooling, and other services are not shown but must be provided.
- H. Protection and Cleaning:
  - 1. Equipment and materials shall be carefully handled, properly stored, and adequately protected to prevent damage before and during installation, in accordance with the manufacturer's recommendations and as approved by the COR. Damaged or defective items in the opinion of the COR, shall be replaced at no additional cost or time to the Government.
  - 2. Protect all finished parts of equipment, such as shafts and bearings where accessible, from rust prior to operation by means of protective grease coating and wrapping. Close pipe openings with caps or plugs during installation. Pipe openings, equipment, and plumbing fixtures shall be tightly covered against dirt or mechanical injury. At completion of all work thoroughly clean fixtures, exposed materials and equipment.
- I. Concrete and Grout: Concrete and shrink compensating grout 25 MPa (3000 psig) minimum, specified in Section 03 30 00, CAST-IN-PLACE CONCRETE, shall be used for all pad or floor mounted equipment.
- J. Gauges, thermometers, valves and other devices shall be installed with due regard for ease in reading or operating and maintaining said devices. Thermometers and gauges shall be located and positioned to be easily read by operator or staff standing on floor or walkway provided. Servicing shall not require dismantling adjacent equipment or pipe work.
- K. Interconnection of Controls and Instruments: Electrical interconnection is generally not shown but shall be provided. This includes interconnections of sensors, transmitters, transducers, control devices, control and instrumentation panels, alarms, instruments and computer workstations. Comply with NFPA 70.
- L. Domestic cold and hot water systems interface with the HVAC control system for the temperature, pressure and flow monitoring requirements to mitigate legionella. See the HVAC control points list and Section 23

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

09 23, DIRECT DIGITAL CONTROL SYSTEM FOR HVAC and Section 23 09 24, WATER QUALITY MONITORING.

# M. Work in Existing Building:

- 1. Perform as specified in Article, OPERATIONS AND STORAGE AREAS, Article, ALTERATIONS, and Article, RESTORATION of the Section 01 00 00, GENERAL REQUIREMENTS for relocation of existing equipment, alterations and restoration of existing building(s).
- 2. As specified in Section 01 00 00, GENERAL REQUIREMENTS, Article, OPERATIONS AND STORAGE AREAS, make alterations to existing service piping at times that will cause the least interfere with normal operation of the facility.
- N. Work in bathrooms, restrooms, housekeeping closets: All pipe penetrations behind escutcheons shall be sealed with plumbers' putty.
- O. Switchgear Drip Protection: Every effort shall be made to eliminate the installation of pipe above data equipment, and electrical and telephone switchgear. If this is not possible, encase pipe in a second pipe with a minimum of joints. Drain valve shall be provided in low point of casement pipe.

# P. Inaccessible Equipment:

- 1. Where the Government determines that the Contractor has installed equipment not conveniently accessible for operation and maintenance, equipment shall be removed and reinstalled or remedial action performed as directed at no additional cost or additional time to the Government.
- 2. The term "conveniently accessible" is defined as capable of being reached without the use of ladders, or without climbing or crawling under or over obstacles such as electrical conduit, motors, fans, pumps, belt guards, transformers, high voltage lines, piping, and ductwork.

# 3.2 TEMPORARY PIPING AND EQUIPMENT

- A. Continuity of operation of existing facilities may require temporary installation or relocation of equipment and piping. Temporary equipment or pipe installation or relocation shall be provided to maintain continuity of operation of existing facilities.
- B. The Contractor shall provide all required facilities in accordance with the requirements of phased construction and maintenance of service. All

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

piping and equipment shall be properly supported, sloped to drain, operate without excessive stress, and shall be insulated where injury can occur to personnel by contact with operating facilities. The requirements of paragraph 3.1 shall apply.

C. Temporary facilities and piping shall be completely removed back to the nearest active distribution branch or main pipe line and any openings in structures sealed. Dead legs are prohibited in potable water systems. Necessary blind flanges and caps shall be provided to seal open piping remaining in service.

# 3.3 RIGGING

- A. Openings in building structures shall be planned to accommodate design scheme.
- B. Alternative methods of equipment delivery may be offered and will be considered by Government under specified restrictions of phasing and service requirements as well as structural integrity of the building.
- C. All openings in the building shall be closed when not required for rigging operations to maintain proper environment in the facility for Government operation and maintenance of service.
- D. Contractor shall provide all facilities required to deliver specified equipment and place on foundations. Attachments to structures for rigging purposes and support of equipment on structures shall be Contractor's full responsibility.
- E. Contractor shall check all clearances, weight limitations and shall provide a rigging plan designed by a Registered Professional Engineer. All modifications to structures, including reinforcement thereof, shall be at Contractor's cost, time and responsibility.
- F. Rigging plan and methods shall be referred to COR for evaluation prior to actual work.

# 3.4 PIPE AND EQUIPMENT SUPPORTS

A. Where hanger spacing does not correspond with joist or rib spacing, use structural steel channels secured directly to joist and rib structure that will correspond to the required hanger spacing, and then suspend the equipment and piping from the channels. Holes shall be drilled or burned in structural steel ONLY with the prior written approval of the COR.

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- B. The use of chain pipe supports, wire or strap hangers; wood for blocking, stays and bracing, or hangers suspended from piping above shall not be permitted. Rusty products shall be replaced.
- C. Hanger rods shall be used that are straight and vertical. Turnbuckles for vertical adjustments may be omitted where limited space prevents use. A minimum of 15 mm (1/2 inch) clearance between pipe or piping covering and adjacent work shall be provided.
- D. For horizontal and vertical plumbing pipe supports, refer to the International Plumbing Code (IPC) and these specifications.
- E. Overhead Supports:
  - 1. The basic structural system of the building is designed to sustain the loads imposed by equipment and piping to be supported overhead.
  - 2. Provide steel structural members, in addition to those shown, of adequate capability to support the imposed loads, located in accordance with the final approved layout of equipment and piping.
  - 3. Tubing and capillary systems shall be supported in channel troughs.

#### F. Floor Supports:

- Provide concrete bases, concrete anchor blocks and pedestals, and structural steel systems for support of equipment and piping.
   Concrete bases and structural systems shall be anchored and doweled to resist forces under operating and seismic conditions (if applicable) without excessive displacement or structural failure.
- 2. Bases and supports shall not be located and installed until equipment mounted thereon has been approved. Bases shall be sized to match equipment mounted thereon plus 50 mm (2 inch) excess on all edges. Structural drawings shall be reviewed for additional requirements. Bases shall be neatly finished and smoothed, shall have chamfered edges at the top, and shall be suitable for painting.
- 3. All equipment shall be shimmed, leveled, firmly anchored, and grouted with epoxy grout. Anchor bolts shall be placed in sleeves, anchored to the bases. Fill the annular space between sleeves and bolts with a grout material to permit alignment and realignment.
- 4. For seismic anchoring, refer to Section 13 05 41, SEISMIC RESTRAINT REQUIREMENTS FOR NON-STRUCTURAL COMPONENTS.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

#### 3.5 LUBRICATION

- A. All equipment and devices requiring lubrication shall be lubricated prior to initial operation. All devices and equipment shall be field checked for proper lubrication.
- B. All devices and equipment shall be equipped with required lubrication fittings. A minimum of 1 liter (1 quart) of oil and 0.45 kg (1 pound) of grease of manufacturer's recommended grade and type for each different application shall be provided. All materials shall be delivered to COR in unopened containers that are properly identified as to application.
- C. A separate grease gun with attachments for applicable fittings shall be provided for each type of grease applied.
- D. All lubrication points shall be accessible without disassembling equipment, except to remove access plates.
- E. All lubrication points shall be extended to one side of the equipment.

# 3.6 PLUMBING SYSTEMS DEMOLITION

- A. Rigging access, other than indicated in the drawings, shall be provided after approval for structural integrity by the COR. Such access shall be provided at no additional cost or time to the Government. Where work is in an operating plant, approved protection from dust and debris shall be provided at all times for the safety of plant personnel and maintenance of plant operation and environment of the plant.
- B. In an operating plant, cleanliness and safety shall be maintained. The plant shall be kept in an operating condition. Government personnel will be carrying on their normal duties of operating, cleaning and maintaining equipment and plant operation. Work shall be confined to the immediate area concerned; maintain cleanliness and wet down demolished materials to eliminate dust. Dust and debris shall not be permitted to accumulate in the area to the detriment of plant operation. All flame cutting shall be performed to maintain the fire safety integrity of this plant. Adequate fire extinguishing facilities shall be available at all times. All work shall be performed in accordance with recognized fire protection standards including NFPA 51B. Inspections will be made by personnel of the VAMC, and the Contractor shall follow all directives of the COR with regard to rigging, safety, fire safety, and maintenance of operations.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- C. Unless specified otherwise, all piping, wiring, conduit, and other devices associated with the equipment not re-used in the new work shall be completely removed from Government property per Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT. This includes all concrete equipment pads, pipe, valves, fittings, insulation, and all hangers including the top connection and any fastenings to building structural systems. All openings shall be sealed after removal of equipment, pipes, ducts, and other penetrations in roof, walls, floors, in an approved manner and in accordance with plans and specifications where specifically covered. Structural integrity of the building system shall be maintained. Reference shall also be made to the drawings and specifications of the other disciplines in the project for additional facilities to be demolished or handled.
- D. All valves including gate, globe, ball, butterfly and check, all pressure gauges and thermometers with wells shall remain Government property and shall be removed and delivered to COR and stored as directed. The Contractor shall remove all other material and equipment, devices and demolition debris under these plans and specifications. Such material shall be removed from Government property expeditiously and shall not be allowed to accumulate. Coordinate with the COR and Infection Control.

# 3.7 CLEANING AND PAINTING

- A. Prior to final inspection and acceptance of the plant and facilities for beneficial use by the Government, the plant facilities, equipment and systems shall be thoroughly cleaned and painted. Refer to Section 09 91 00, PAINTING.
- B. In addition, the following special conditions apply:
  - 1. Cleaning shall be thorough. Solvents, cleaning materials and methods recommended by the manufacturers shall be used for the specific tasks. All rust shall be removed prior to painting and from surfaces to remain unpainted. Scratches, scuffs, and abrasions shall be repaired prior to applying prime and finish coats.
  - 2. The following Material and Equipment shall NOT be painted:
    - a. Motors, controllers, control switches, and safety switches.
    - b. Control and interlock devices.
    - c. Regulators.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- d. Pressure reducing valves.
- e. Control valves and thermostatic elements.
- f. Lubrication devices and grease fittings.
- g. Copper, brass, aluminum, stainless steel and bronze surfaces.
- h. Valve stems and rotating shafts.
- i. Pressure gauges and thermometers.
- j. Glass.
- k. Name plates.
- 3. Control and instrument panels shall be cleaned and damaged surfaces repaired. Touch-up painting shall be made with matching paint type and color obtained from manufacturer or computer matched.
- 4. Pumps, motors, steel and cast-iron bases, and coupling guards shall be cleaned, and shall be touched-up with the same paint type and color as utilized by the pump manufacturer.
- 5. Temporary Facilities: Apply paint to surfaces that do not have existing finish coats per Section 09 91 00, Painting.
- 6. The final result shall be a smooth, even-colored, even-textured factory finish on all items. The entire piece of equipment shall be repainted, if necessary, to achieve this. Lead based paints shall not be used.

#### 3.8 IDENTIFICATION SIGNS

- A. Laminated plastic signs, with engraved lettering not less than 7 mm (3/16 inch) high, shall be provided that designates equipment function, for all equipment, switches, motor controllers, relays, meters, control devices, including automatic control valves. Nomenclature and identification symbols shall correspond to that used in maintenance manual, and in diagrams specified elsewhere. Attach by chain, adhesive, or screws.
- B. Factory Built Equipment: Metal plate, securely attached, with name and address of manufacturer, serial number, model number, size, and performance data shall be placed on factory-built equipment.
- C. Pipe Identification: Refer to Section 09 91 00, PAINTING.

## 3.9 STARTUP AND TEMPORARY OPERATION

A. Startup of equipment shall be performed as described in the equipment specifications. Vibration within specified tolerance shall be verified

prior to extended operation. Temporary use of equipment is specified in Contract No. 36C26319D0044

Station Project No. 568A4-21-703

Bancroft-AE Project No. 18-121

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

Section 01 00 00, GENERAL REQUIREMENTS, Article, TEMPORARY USE OF MECHANICAL AND ELECTRICAL EQUIPMENT.

## 3.10 OPERATING AND PERFORMANCE TESTS

- A. Prior to the final inspection, all required tests shall be performed as specified in Section 01 00 00, GENERAL REQUIREMENTS, Article, TESTS and submit the test reports and records to the COR.
- B. Should evidence of malfunction in any tested system, or piece of equipment or component part thereof, occur during or as a result of tests, make proper corrections, repairs or replacements, and repeat tests at no additional cost to the Government.
- C. When completion of certain work or systems occurs at a time when final control settings and adjustments cannot be properly made to make performance tests, then conduct such performance tests and finalize control settings during the first actual seasonal use of the respective systems following completion of work. Rescheduling of these tests shall be requested in writing to COR for approval.

## 3.11 OPERATION AND MAINTENANCE MANUALS

- A. All new and temporary equipment and all elements of each assembly shall be included.
- B. Data sheet on each device listing model, size, capacity, pressure, speed, horsepower, impeller size, and other information shall be included.
- C. Manufacturer's installation, maintenance, repair, and operation instructions for each device shall be included. Assembly drawings and parts lists shall also be included. A summary of operating precautions and reasons for precautions shall be included in the Operations and Maintenance Manual.
- D. Lubrication instructions, type and quantity of lubricant shall be included.
- E. Schematic diagrams and wiring diagrams of all control systems corrected to include all field modifications shall be included.
- F. Set points of all interlock devices shall be listed.
- G. Trouble-shooting guide for the control system troubleshooting shall be inserted into the Operations and Maintenance Manual.

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- H. The control system sequence of operation corrected with submittal review comments shall be inserted into the Operations and Maintenance Manual.
- I. Emergency procedures for shutdown and startup of equipment and systems.

# 3.12 COMMISSIONING (NOT USED)

## 3.13 DEMONSTRATION AND TRAINING

A. Provide services of manufacturer's technical representative for 4 hours to instruct each VA personnel responsible in operation and maintenance of the system.

- - - E N D - - -

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

# SECTION 22 05 19 METERS AND GAUGES FOR PLUMBING PIPING

## PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section describes the requirements for water meters and gauges primarily used for troubleshooting the system and to indicate system performance.
- B. A complete listing of common acronyms and abbreviations are included in Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

## 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.
- C. Section 01 81 13, SUSTAINABLE CONSTRUCTION REQUIREMENTS.
- D. Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

## 1.3 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only. Where conflicts occur these specifications and the VHA standard will govern.
- B. American Society of Mechanical Engineers (ASME):

C. American Water Works Association (AWWA):

C700-2015......Cold Water Meters, Displacement Type, Bronze
Main Case

C701-2015......Cold Water Meters-Turbine Type, for Customer Service

C702-20115.....Cold Water Meters - Compound Type

C707-2010 (R2016).....Encoder-Type Remote-Registration Systems for Cold-Water Meters

D. Institute of Electrical and Electronics Engineers (IEEE):

C2-2017......National Electrical Safety Code (NESC)

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

Ε.	International Code Council (ICC):
	IPC-2018International Plumbing Code
F.	National Fire Protection Association (NFPA):
	70-2020National Electrical Code (NEC)
G.	NSF International (NSF):
	61-2019 Drinking Water System Components - Health
	Effects
	372-2016Drinking Water System Components - Lead Content

#### 1.4 SUBMITTALS

- A. Submittals, including number of required copies, shall be submitted in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Information and material submitted under this section shall be marked "SUBMITTED UNDER SECTION 22 05 19, METERS AND GAUGES FOR PLUMBING PIPING", with applicable paragraph identification.
- C. Manufacturer's Literature and Data including: Full item description and optional features and accessories. Include dimensions, weights, materials, applications, standard compliance, model numbers, size, and capacity.
  - 1. Thermometers.
- D. Complete operating and maintenance manual shall including wiring diagrams, technical data sheets, information for ordering replaceable parts, and troubleshooting guide:
  - 1. Include complete list indicating all components of the system.
  - 2. Include complete diagrams of the internal wiring for each item of equipment.
  - 3. Diagrams shall have their terminals identified to facilitate installation, operation and maintenance.

## 1.5 AS-BUILT DOCUMENTATION

A. Comply with requirements in Paragraph "AS-BUILT DOCUMENTATION" of Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

## PART 2 - PRODUCTS

- 2.1 DISPLACEMENT WATER METER (NOT USED)
- 2.2 TURBINE WATER METER (NOT USED)
- 2.3 COMPOUND WATER METER (NOT USED)
- 2.4 WATER METER STRAINER (NOT USED)
- 2.5 WATER METER PROGRAMMING (NOT USED)
- 2.6 WATER METER COMMUNICATION PROTOCOL (NOT USED)
- 2.7 REMOTE READOUT REGISTER (NOT USED)
- 2.8 PRESSURE GAUGES FOR WATER AND SEWAGE USAGE (NOT USED)

#### 2.9 THERMOMETERS

A. Thermometers shall be straight stem, metal case, red liquid-filled thermometer, approximately 175 mm (7 inches) high, 4 degrees C to 100 degrees C (40 degrees F to 212 degrees F). Thermometers shall comply with ASME B40.200.

#### PART 3 - EXECUTION

## 3.1 INSTALLATION

- A. Thermometers shall be installed on the water heater inlet and outlet piping, thermostatic mixing valve outlet piping, and the hot water circulation pump inlet piping.
- B. If an installation is unsatisfactory to the COR, the Contractor shall correct the installation at no additional cost or time to the Government.
- C. Install portable water temperature, pressure and flow meters provided under Section 23 09 23 DIRECT DIGITAL CONTROL SYSTEMS FOR HVAC.

# 3.2 FIELD QUALITY CONTROL

A. The meter assembly shall be visually inspected and operationally tested. The correct multiplier placement on the face of the meter shall be verified.

## 3.3 STARTUP AND TESTING

- A. Perform tests as recommended by product manufacturer and listed standards and under actual or simulated operating conditions and prove full compliance with design and specified requirements. Tests of the various items of equipment shall be performed simultaneously with the system of which each item is an integral part.
- B. When any defects are detected, correct defects and repeat test at no additional cost or time to the Government.

Contract No. 36C26319D0044 Station Project No. 568A4-21-703

Bancroft-AE Project No. 18-121

02/17/2022

09-01-20

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

# 3.4 COMMISSIONING (NOT USED)

# 3.5 DEMONSTRATION AND TRAINING

A. Provide services of manufacturer's technical representative for 4 hours to instruct each VA personnel responsible in operation and maintenance of the system.

- - - E N D - - -

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

# SECTION 22 05 23 GENERAL-DUTY VALVES FOR PLUMBING PIPING

## PART 1 - GENERAL

## 1.1 DESCRIPTION

- A. This section describes the requirements for general-duty valves for domestic water and sewer systems.
- B. A complete listing of common acronyms and abbreviations are included in Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

## 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.
- C. Section 01 81 13, SUSTAINABLE CONSTRUCTION REQUIREMENTS.
- D. Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

# 1.3 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only. Where conflicts occur these specifications and the VHA standard will govern.
- B. American Society of Mechanical Engineers (ASME): A112.14.1-2003......Backwater Valves
- C. American Society of Sanitary Engineering (ASSE):
  - 1001-2017......Performance Requirements for Atmospheric Type

    Vacuum Breakers
  - 1003-2009......Performance Requirements for Water Pressure

    Reducing Valves for Domestic Water Distribution

    Systems
  - 1011-2017......Performance Requirements for Hose Connection

    Vacuum Breakers
  - 1013-2011......Performance Requirements for Reduced Pressure

    Principle Backflow Preventers and Reduced

    Pressure Principle Fire Protection Backflow

    Preventers

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

	Bandroit Architects + Engineers 09-01-20
	1015-2011Performance Requirements for Double Check
	Backflow Prevention Assemblies and Double Check
	Fire Protection Backflow Prevention Assemblies
	1017-2009Performance Requirements for Temperature
	Actuated Mixing Valves for Hot Water
	Distribution Systems
	1020-2004Performance Requirements for Pressure Vacuum
	Breaker Assembly
	1035-2008Performance Requirements for Laboratory Faucet
	Backflow Preventers
	1069-2005Performance Requirements for Automatic
	Temperature Control Mixing Valves
	1070-2015Performance Requirements for Water Temperature
	Limiting Devices
	1071-2012Performance Requirements for Temperature
	Actuated Mixing Valves for Plumbed Emergency
	Equipment
D.	American Society for Testing and Materials (ASTM):
	A126-2004(R2019)Standard Specification for Gray Iron Castings
	for Valves, Flanges, and Pipe Fittings
	A276/A276M-2017Standard Specification for Stainless Steel Bars
	and Shapes
	A536-1984(R2019e)Standard Specification for Ductile Iron
	Castings
	B62-2017Standard Specification for Composition Bronze
	or Ounce Metal Castings
	B584-2014Standard Specification for Copper Alloy Sand
	Castings for General Applications
Ε.	<pre>International Code Council (ICC):</pre>
	IPC-2018International Plumbing Code
F.	Manufacturers Standardization Society of the Valve and Fittings
	<pre>Industry, Inc. (MSS):</pre>
	SP-25-2018Standard Marking Systems for Valves, Fittings,
	Flanges and Unions
	SP-67-2017Butterfly Valves

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

		09-01-2
	SP-70-2011	Gray Iron Gate Valves, Flanged and Threaded
	I	Ends
	SP-71-2018	Gray Iron Swing Check Valves, Flanged and
	<u>-</u>	Threaded Ends
	SP-80-2019	Bronze Gate, Globe, Angle, and Check Valves
	SP-85-2011	Gray Iron Globe & Angle Valves, Flanged and
	:	Threaded Ends
	SP-110-2010	Ball Valves Threaded, Socket-Welding, Solder
		Joint, Grooved and Flared Ends
G.	National Environmental Ba	alancing Bureau (NEBB):
	8th Edition 2015	Procedural Standards for Testing, Adjusting,
	I	Balancing of Environmental Systems
Н.	NSF International (NSF):	
	61-2019	Orinking Water System Components - Health
	I	Effects
	372-2016	Orinking Water System Components - Lead Content
I.	University of Southern Ca	alifornia Foundation for Cross Connection
	Control and Hydraulic Res	search (USC FCCCHR):
	10th Edition	Manual of Cross-Connection Control

# 1.4 SUBMITTALS

- A. Submittals, including number of required copies, shall be submitted in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Information and material submitted under this section shall be marked "SUBMITTED UNDER SECTION 22 05 23, GENERAL-DUTY VALVES FOR PLUMBING PIPING", with applicable paragraph identification.
- C. Manufacturer's Literature and Data including: Full item description and optional features and accessories. Include dimensions, weights, materials, applications, standard compliance, model numbers, size, and capacity.
  - 1. Ball Valves.
  - 2. Gate Valves.
  - 3. Butterfly Valves.
  - 4. Balancing Valves.
  - 5. Check Valves.
  - 6. Globe Valves.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- 7. Water Pressure Reducing Valves and Connections.
- 8. Backwater Valves.
- 9. Backflow Preventers.
- 10. Chainwheels.
- 11. Thermostatic Mixing Valves.
- D. Test and Balance reports for balancing valves.
- E. Complete operating and maintenance manuals including wiring diagrams, technical data sheets, information for ordering replaceable parts and troubleshooting guide:
  - 1. Include complete list indicating all components of the systems.
  - 2. Include complete diagrams of the internal wiring for each item of equipment.
  - 3. Diagrams shall have their terminals identified to facilitate installation, operation and maintenance.
  - 4. Piping diagrams of thermostatic mixing valves to be installed.

# 1.5 DELIVERY, STORAGE, AND HANDLING

- A. Valves shall be prepared for shipping as follows:
  - 1. Protect internal parts against rust and corrosion.
  - 2. Protect threads, flange faces, grooves, and weld ends.
  - 3. Set angle, gate, and globe valves closed to prevent rattling.
  - 4. Set ball and plug valves open to minimize exposure of functional surfaces.
  - 5. Set butterfly valves closed or slightly open.
  - 6. Block check valves in either closed or open position.
- B. Valves shall be prepared for storage as follows:
  - 1. Maintain valve end protection.
  - 2. Store valves indoors and maintain at higher than ambient dew point temperature.
- C. A sling shall be used for large valves. The sling shall be rigged to avoid damage to exposed parts. Hand wheels or stems shall not be used as lifting or rigging points.

# 1.6 AS BUILT DOCUMENTATION

A. Comply with requirements in Paragraph "AS-BUILT DOCUMENTATION" of Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

## PART 2 - PRODUCTS

## 2.1 VALVES, GENERAL

- A. Asbestos packing and gaskets are prohibited.
- B. Bronze valves shall be made with dezincification resistant materials.

  Bronze valves made with copper alloy (brass) containing greater than 15 percent zinc shall not be permitted.
- C. Valves in insulated piping shall have 50 mm or DN50 (2 inch) stem extensions and extended handles of non-thermal conductive material that allows operating the valve without breaking the vapor seal or disturbing the insulation. Memory stops shall be fully adjustable after insulation is applied.
- D. Exposed Valves over 65 mm or DN65 (2-1/2 inches) installed at an elevation over 3.6 m (12 feet) shall have a chain-wheel attachment to valve hand-wheel, stem, or other actuator.
- E. All valves used to supply potable water shall meet the requirements of NSF 61 and NSF 372.
- F. Bio-Based Materials: For products designated by the USDA's bio-based Bio-Preferred Program, provide products that meet or exceed USDA recommendations for bio-based content, so long as products meet all performance requirements in this specifications section. For more information regarding the product categories covered by the Bio-Preferred Program, visit <a href="http://www.biopreferred.gov">http://www.biopreferred.gov</a>.
- G. Refer to Section 01 81 13, SUSTAINABLE CONSTRUCTION REQUIREMENTS for additional sustainable design requirements.

## 2.2 SHUT-OFF VALVES

- A. Cold, Hot and Re-circulating Hot Water:
  - 1. 50 mm or DN50 (2 inches) and smaller: Ball, MSS SP-110, Ball valve shall be full port three piece or two piece with a union design with adjustable stem package. Threaded stem designs are not allowed. The ball valve shall have a SWP rating of 1035 kPa (150 psig) and a CWP rating of 4138 kPa (600 psig). The body material shall be Bronze ASTM B584, Alloy C844. The ends shall be non-lead solder.
  - 2. Less than 100 mm DN100 (4 inches): Butterfly shall have an iron body with EPDM seal and aluminum bronze disc. The butterfly valve shall meet MSS SP-67, type I standard. The butterfly valve shall have a SWP rating of 1380 kPa (200 psig). The valve design shall be lug

Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121 09-01-20

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

type suitable for bidirectional dead-end service at rated pressure. The body material shall meet ASTM A536, ductile iron.

- 3. 100 mm DN100 (4 inches) and greater:
  - a. Class 125, OS&Y, Cast Iron Gate Valve. The gate valve shall meet MSS SP-70 type I standard. The gate valve shall have a CWP rating of 1380 kPa (200 psig). The valve materials shall meet ASTM A126, grey iron with bolted bonnet, flanged ends, bronze trim, and positive-seal resilient solid wedge disc. The gate valve shall be gear operated for sizes under 200 mm or DN200 (8 inches) and crank operated for sizes 200 mm or DN200 (8 inches) and greater.
  - b. Single flange, ductile iron butterfly valves: The single flanged butterfly valve shall meet the MSS SP-67 standard. The butterfly valve shall have a CWP rating of 1380 kPa (200 psig). The butterfly valve shall be lug type, suitable for bidirectional dead-end service at rated pressure without use of downstream flange. The body material shall comply with ASTM A536 ductile iron. The seat shall be EPDM with stainless steel disc and stem.
  - c. Grooved end, ductile iron butterfly valves. The grooved butterfly valve shall meet the MSS SP-67 standard. The grooved butterfly valve shall have a CWP rating of 1380 kPa (200 psig). The valve materials shall be epoxy coated ductile iron conforming to ASTM A536 with two-piece stainless-steel stem, EPDM encapsulated ductile iron disc, and EPDM seal. The butterfly valve shall be gear operated.
- B. Reagent Grade Water: Valves for reagent grade, reverse osmosis, or deionized water service shall be ball type of same material as used for pipe.

## 2.3 MANUAL BALANCING VALVES

A. Hot Water Re-circulating, 75 mm or DN75 (3 inches) and smaller manual balancing valve shall be of bronze body, brass ball construction with glass and carbon filled TFE seat rings and designed for positive shutoff. The manual balancing valve shall have differential pressure read-out ports across the valve seat area. The read out ports shall be fitted with internal EPT inserts and check valves. The valve body shall have 8 mm or DN8 NPT (1/4 inch NPT) tapped drain and purge port. The valves shall have memory stops that allow the valve to close for

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

service and then reopened to set point without disturbing the balance position. All valves shall have calibrated nameplates to assure specific valve settings.

B. Greater than 75 mm or DN75 (3 inches): Manual balancing valves shall be of heavy duty cast iron flanged construction with 861 kPa (125 psig) flange connections. The flanged manual balancing valves shall have either a brass ball with glass and carbon filled TFE seal rings or fitted with a bronze seat, replaceable bronze disc with EPDM seal insert and stainless steel stem. The design pressure shall be 1200 kPa (175 psig) at 121 degrees C (250 degrees F).

#### 2.4 THERMOSTATIC BALANCING VALVES

A. Thermostatic recirculation balancing valves for domestic hot water and domestic cold water application. Thermostatically controlled, spring actuated automatic balancing valve to very recirculation flow to maintain constant return temperatures. Stainless steel body, spring and brass or stainless steel thermal actuator and actuator carrier. Provide with threaded inlet, integral outlet union and stainless steel check valve. PTFE seat seal ring and EPDM body seal.

#### 2.5 CHECK VALVES

- A. 75 mm or DN75 (3 inches) and smaller shall be Class 125, bronze swing check valves with non-metallic disc suitable for type of service. The check valve shall meet MSS SP-80 Type 4 standard. The check valve shall have a CWP rating of 1380 kPa (200 psig). The check valve shall have a Y pattern horizontal body design with bronze body material conforming to ASTM B62, solder joints, and PTFE or TFE disc.
- B. 100 mm or DN100 (4 inches) and greater:
  - 1. Check valves shall be Class 125, iron swing check valve with lever and weight closure control. The check valve shall meet MSS SP-71 Type I standard. The check valve shall have a CWP rating of 1380 kPa (200 psig). The check valve shall have a clear or full waterway body design with gray iron body material conforming to ASTM A126, bolted bonnet, flanged ends, bronze trim.
  - 2. All check valves on the discharge side of submersible sump pumps shall have factory installed exterior level and weight with sufficient weight to prevent the check valve from hammering against the seat when the sump pump stops.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

## 2.6 GLOBE VALVES

- A. 75 mm or DN75 (3 inches) or smaller: Class 150, bronze globe valve with non-metallic disc. The globe valve shall meet MSS SP-80, Type 2 standard. The globe valve shall have a CWP rating of 2070 kPa (300 psig). The valve material shall be bronze with integral seal and union ring bonnet conforming to ASTM B62 with solder ends, copper-silicon bronze stem, PTFE or TFE disc, and malleable iron hand wheel.
- B. Greater than 75 mm or DN75 (3 inches): Similar to above, except with cast iron body and bronze trim, Class 125, iron globe valve. The globe valve shall meet MSS SP-85, Type 1 standard. The globe valve shall have a CWP rating of 1380 kPa (200 psig). The valve material shall be gray iron with bolted bonnet conforming to ASTM A126 with flanged ends, bronze trim, and malleable iron handwheel.

## 2.7 WATER PRESSURE REDUCING VALVE AND CONNECTIONS

- A. 75 mm or DN75 (3 inches) or smaller: The pressure reducing valve shall consist of a bronze body and bell housing, a separate access cover for the plunger, and a bolt to adjust the downstream pressure. The pressure reducing valve shall meet ASSE 1003. The bronze bell housing and access cap shall be threaded to the body and shall not require the use of ferrous screws. The assembly shall be of the balanced piston design and shall reduce pressure in both flow and no flow conditions. The assembly shall be accessible for maintenance without having to remove the body from the line.
- B. 100 mm or DN100 (4 inches) and greater: The pressure reducing valve shall consist of a flanged cast iron body and rated to 1380 kPa (200 psig). The valve shall have a large elastomer diaphragm for sensitive response. The pressure reducing valve shall meet ASSE 1003.
- C. The regulator shall have a tap for pressure gauge.
- D. The regulator shall have a temperature rating of 100 degrees C (212 degrees F) for hot water or hot water return service. Pressure regulators shall have accurate pressure regulation to 6.9 kPa (+/- 1 psig).
- E. Setting: Entering water pressure, discharge pressure, capacity, size, and related measurements shall be as shown on the drawings.
- F. Connections Valves and Strainers: Shut off valves shall be installed on each side of reducing valve and a bypass line equal in size to the

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

regulator inlet pipe shall be installed with a normally closed globe valve. A strainer shall be installed on inlet side of, and same size as pressure reducing valve. A pressure gauge shall be installed on the inlet and outlet of the valve.

## 2.8 BACKWATER VALVE

- A. The backwater valve shall have a cast iron body, automatic thermoplastic type valve seat and flapper suited for water service. The flapper shall be slightly open during periods of non-operation. The pressure reducing valve shall meet ASME Al12.14.1. The cleanout shall be extended to the finish floor and fit with a threaded countersunk plug. A clamping device shall be included when the cleanout extends through the waterproofing membrane.
- B. When the backwater valve is installed greater than 600 mm (24 inches) below the finish floor elevation, a pit or manhole large enough for a repair person can enter to service the backwater valve shall be installed.

## 2.9 BACKFLOW PREVENTERS

- A. A backflow prevention assembly shall be installed at any point in the plumbing system where the potable water supply comes in contact with a potential source of contamination. The backflow prevention assembly shall be approved by the University of Southern California Foundation for Cross Connection Control and Hydraulic Research (USCFCCC).
- B. The reduced pressure principle backflow prevention assembly shall be ASSE listed 1013 with full port OS&Y positive-seal resilient gate valves and an integral relief monitor switch. The main body and access cover shall be epoxy coated ductile iron conforming to ASTM A536 grade 4. The seat ring and check valve shall be the thermoplastic type suited for water service. The stem shall be stainless steel conforming to ASTM A276/A276M. The seat disc shall be the elastomer type suited for water service. The checks and the relief valve shall be accessible for maintenance without removing the device from the line. An epoxy coated wye type strainer with flanged connections shall be installed on the inlet. Reduced pressure backflow preventers shall be installed in the following applications.
  - 1. Deionizers.
  - 2. Sterilizers.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- 3. Dialysis, Deionized or Reverse Osmosis Water Systems.
- 4. Water make up to heating systems, cooling tower, chilled water system, generators, and similar equipment consuming water.
- 5. Water service entrance from loop system.
- 6. Dental equipment.
- 7. Power washer.
- 8. Medical equipment.
- 9. Process equipment.
- 10. Autopsy, on each hot and cold water outlet at each table or sink.
- 11. Reclaimed water systems.
- C. The pipe applied or integral atmospheric vacuum breaker shall be ASSE listed 1001. The main body shall be cast bronze. The seat disc shall be the elastomer type suited for water service. The device shall be accessible for maintenance without removing the device from the service line. The installation shall not be in a concealed or inaccessible location or where the venting of water from the device during normal operation is deemed objectionable. Atmospheric vacuum breakers shall be installed in the following applications.
  - 1. Hose bibs and sinks with threaded outlets.
  - 2. Disposers.
  - 3. Showers (telephone/handheld type).
  - 4. Hydrotherapy units.
  - 5. All kitchen equipment, if not protected by air gap.
  - 6. Ventilating hoods with wash down system.
  - 7. Film processor.
  - 8. Detergent system.
  - 9. Fume hoods.
  - 10. Glassware washers.
  - 11. Service sinks (integral with faucet only).
  - 12. Laundry tubs (integral with faucet only).
  - 13. Sitz baths.
- D. The hose connection vacuum breaker shall be ASSE listed 1011. The main body shall be cast brass with stainless steel working parts. The diaphragm and disc shall be the elastomer type suited for water service. The device shall permit the attachment of portable hoses to

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

hose thread outlets. Hose connection vacuum breakers shall be installed in the following locations requiring non-continuous pressure:

- 1. Hose bibbs and wall hydrants.
- E. The pressure vacuum breaker shall be ASSE listed 1020. The main body shall be brass. The disc and O-ring seal shall be the elastomer type. The valve seat and disc float shall be the thermoplastic type. Tee handle or lever handle shut-off ball valves. Test cocks for testing and draining where freezing conditions occur. All materials shall be suitable for water service. The device shall be accessible for maintenance without removing the device from the service line. The installation shall not be in a concealed or inaccessible location or where the venting of water from the device during normal operation is deemed objectionable. Pressure vacuum breakers shall be installed in the following locations requiring continuous pressure and no backpressure including equipment with submerged inlet connections:

  1. 1. Lawn Irrigation.
- F. The laboratory faucet vacuum breaker shall be ASSE listed 1035. The main body shall be cast brass. Dual check valves with stainless steel working parts. The diaphragm and disc shall be the elastomer type suited for water service. The device shall permit the attachment of portable hoses to laboratory faucets for non-continuous pressure applications.
- G. The double check backflow prevention assembly shall be ASSE listed 1015 and supply with full port, OS&Y, positive-seal, resilient gate valves. The main body and access cover shall be epoxy coated ductile iron conforming to ASTM A536 grade. The seat ring and check valve shall be the thermoplastic type suited for water service. The stem shall be stainless steel conforming to ASTM A276/A276M. The seat disc shall be the elastomer type suited for water service. The first and second check valve shall be accessible for maintenance without removing the device from the line. Double check valves shall be installed in the following location requiring continuous pressure subject to backpressure and backsiphonage conditions.
  - 1. Lawn Irrigation.
  - 2. Food Processing Equipment.
  - 3. Laundry equipment.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

## 2.10 CHAINWHEELS (NOT USED)

## 2.11 THERMOSTATIC MIXING VALVES

- A. Thermostatic Mixing Valves shall comply with the following general performance requirements:
  - 1. Shall meet ASSE requirements for water temperature control.
  - 2. The body shall be cast bronze or brass with corrosion resistant internal parts preventing scale and biofilm build-up. Provide chrome-plated finish in exposed areas.
  - 3. No special tool shall be required for temperature adjustment, maintenance, replacing parts and disinfecting operations.
  - 4. Valve shall be able to be placed in various positions without making temperature adjustment or reading difficult.
  - 5. Valve finish shall be chrome plated in exposed areas.
  - 6. Valve shall allow easy temperature adjustments to allow hot water circulation. Internal parts shall be able to withstand disinfecting operations of chemical and thermal treatment of water temperatures up to 82°C (180°F) for 30 minutes or 50 mg/L (50 ppm) chlorine residual concentration for 24 hours.
  - 7. Parts shall be easily removed or replaced without dismantling the valves, for easy scale removal and disinfecting of parts.
  - 8. Valve shall have a manual adjustable temperature control with locking mechanism to prevent tampering by end user. Outlet temperature shall be visible to ensure outlet temperature does not exceed specified limits, particularly after thermal eradication procedures.
  - 9. Provide mixing valves with integral check valves with screens and stop valves.
- B. Master Thermostatic Water Mixing Valves:
  - 1. Application: Tempered water distribution from hot water source.
  - 2. Standard: ASSE 1017.
  - 3. Pressure Rating: 861 kPa (125 psig).
  - 4. Type: Exposed-mounting or Cabinet-type, as indicated, thermostatically controlled water mixing valve.
  - 5. Connections: Flanged or threaded union inlets and outlet.
  - 6. Thermometers shall be provided to indicate mixed water temperature.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- C. Hi-Lo Water-Mixing-Valve Assemblies:
  - 1. Application: Tempered water distribution from hot water source covering a wide range of flow.
  - 2. Description: Factory-fabricated, cabinet-type or exposed-mounting, thermostatically controlled, water-mixing-valve assembly in two-valve parallel arrangement including pressure regulators, pressure gauges and thermometer.
  - 3. Large-Flow Parallel: Master thermostatic water mixing valve and downstream pressure regulator with pressure gauges on inlet and outlet
  - 4. Small-Flow Parallel: Master thermostatic water mixing valve.
  - 5. Master Thermostatic Mixing Valves: Comply with ASSE 1017.
  - 6. Water Regulator(s): Comply with ASSE 1003. Include pressure gauge on inlet and outlet.
  - 7. Component Pressure Ratings: 861 kPa (125 psig) minimum, unless otherwise indicated.
  - 8. Connections: Soldered or threaded union inlets and outlet.
  - 9. Thermometers shall be provided to indicate mixed water temperature.
- D. Automatic Water Temperature Control Mixing Valves:
  - Application: Gang plumbing fixtures point-of-use when no other mixing at fixtures occurs.
  - 2. Standard: ASSE 1069.
  - 3. Pressure Rating: 861 kPa (125 psig).
  - 4. Type: Thermostatically controlled water mixing valve set at 43 degrees C (110 degrees F).
  - 5. Connections: Threaded union or soldered inlets and outlet.
  - $6.\ \mbox{Thermometers}$  shall be provided to indicate mixed water temperature.
  - 7. Upon cold water supply failure the hot water flow shall automatically be reduced to 0.5 gpm maximum.
- E. Water Temperature Limiting Devices:
  - 1. Application: Single plumbing fixture point-of-use such as sinks or lavatories.
  - 2. Standard: ASSE 1070.
  - 3. Pressure Rating: 861 kPa (125 psig).
  - 4. Type: Thermostatically controlled water mixing valve set at 43 degrees C (110 degrees F).

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- 5. Connections: Threaded union, compression or soldered inlets and outlet.
- 6. Upon cold water supply failure the hot water flow shall automatically be reduced to 0.2 gpm maximum.
- F. Temperature Activated Mixing Valves:
  - 1. Application: Emergency eye/face/drench shower equipment.
  - 2. Standard: ASSE 1071.
  - 3. Pressure Rating: 861 kPa (125 psig).
  - 4. Type: Thermostatically controlled water mixing valve set at 24-30 degrees C (75-85 degrees F).
  - 5. Connections: Soldered or threaded union inlets and outlet.
  - 6. Thermometers shall be provided to indicate mixed water temperature.
  - 7. Upon cold water supply failure the hot water flow shall automatically be reduced to 0.5 gpm maximum.

## PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Valve interior shall be examined for cleanliness, freedom from foreign matter, and corrosion. Special packing materials shall be removed, such as blocks, used to prevent disc movement during shipping and handling.
- B. Valves shall be operated in positions from fully open to fully closed. Guides and seats shall be examined and made accessible by such operations.
- C. Threads on valve and mating pipe shall be examined for form and cleanliness.
- D. Mating flange faces shall be examined for conditions that might cause leakage. Bolting shall be checked for proper size, length, and material. Gaskets shall be verified for proper size and that its material composition is suitable for service and free from defects and damage.
- E. Do not attempt to repair defective valves; replace with new valves.

#### 3.2 INSTALLATION

A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- B. Valves shall be located for easy access and shall be provide with separate support. Valves shall be accessible with access doors when installed inside partitions or above hard ceilings.
- C. Valves shall be installed in horizontal piping with stem at or above center of pipe.
- D. Valves shall be installed in a position to allow full stem movement.
- E. Check valves shall be installed for proper direction of flow and as follows:
  - 1. Swing Check Valves: In horizontal position with hinge pin level and on top of valve.
- F. Install backflow preventers in each water supply to mechanical equipment and systems and to other equipment and water systems that shall be sources of contamination. Comply with authorities having jurisdiction. Locate backflow preventers in same room as connected equipment or system.
  - 1. Install drain for backflow preventers with atmospheric-vent drain connection with air-gap fitting, fixed air-gap fitting, or equivalent positive pipe separation of at least two pipe diameters in drain piping and pipe to floor drain. Locate air-gap device attached to or under backflow preventer. Simple air breaks are prohibited for this application.
- G. Install pressure gauges on outlet of backflow preventers.
- H. Do not install bypass piping around backflow preventers.
- I. Install temperature-actuated water mixing valves with check stops or shutoff valves on inlets.
  - 1. Install thermometers if specified.
  - Install cabinet-type units recessed in or surface mounted on wall as specified.
- J. If an installation is unsatisfactory to the COR, the Contractor shall correct the installation at no additional cost or time to the Government.
- K. Install thermostatic balancing valves with inlet strainer and inlet and outlet isolation valves.

## 3.3 LABELING AND IDENTIFYING

A. Equipment Nameplates and Signs: Install engraved plastic-laminate equipment nameplate or sign on or near each of the following: Contract No. 36C26319D0044
Station Project No. 568A4-21-703

Bancroft-AE Project No. 18-121

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- 1. Calibrated balancing valves.
- 2. Master, thermostatic, water mixing valves.
- 3. Manifold, thermostatic, water-mixing-valve assemblies.
- B. Distinguish among multiple units, inform operator of operational requirements, indicate safety and emergency precautions, and warn of hazards and improper operations, in addition to identifying unit.

# 3.4 ADJUSTING

- A. Valve packing shall be adjusted or replaced after piping systems have been tested and put into service but before final adjusting and balancing. Valves shall be replaced if persistent leaking occurs.
- B. Set field-adjustable flow set points of balancing valves and record data. Ensure recorded data represents actual measured or observed conditions. Permanently mark settings of valves and other adjustment devices allowing settings to be restored. Set and lock memory stops. After adjustment, take measurements to verify balance has not been disrupted or that such disruption has been rectified.
- C. Set field-adjustable temperature set points of temperature-actuated water mixing valves.
- D. Testing and adjusting of balancing valves shall be performed by an independent NEBB Accredited Test and Balance Contractor. A final settings and flow report shall be submitted to the VA Contracting Officer's Representative (COR).

## 3.5 STARTUP AND TESTING

- A. Perform tests as recommended by product manufacturer and listed standards and under actual or simulated operating conditions and prove full compliance with design and specified requirements. Tests of the various items of equipment shall be performed simultaneously with the system of which each item is an integral part.
- B. When any defects are detected, correct defects and repeat test at no additional cost or time to the Government.

## 3.6 COMMISSIONING (NOT USED)

## 3.7 DEMONSTRATION AND TRAINING

A. Provide services of manufacturer's technical representative for 4 hours to instruct each VA personnel responsible in operation and maintenance of the system.

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- - - E N D - - -

09-01-20

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

# SECTION 22 07 11 PLUMBING INSULATION

## PART 1 - GENERAL

## 1.1 DESCRIPTION

- A. Field applied insulation for thermal efficiency and condensation control for the following:
  - 1. Plumbing piping and equipment.

#### B. Definitions:

- 1. ASJ: All Service Jacket, Kraft paper, white finish facing or jacket.
- 2. Air conditioned space: Space having air temperature and/or humidity controlled by mechanical equipment.
- 3. All insulation systems installed within supply, return, exhaust, relief and ventilation air plenums shall be limited to uninhabited crawl spaces, areas above a ceiling or below the floor, attic spaces, interiors of air conditioned or heating ducts, and mechanical equipment rooms shall be noncombustible or shall be listed and labeled as having a flame spread indexes of not more than 25 and a smoke-developed index of not more than 50 when tested in accordance with ASTM E84 or UL 723. Note: ICC IMC, Section 602.2.1.
- 4. Cold: Equipment or piping handling media at design temperature of 15 degrees C (60 degrees F) or below.
- 5. Concealed: Piping above ceilings and in chases and pipe spaces.
- 6. Exposed: Piping and equipment exposed to view in finished areas including mechanical equipment rooms or exposed to outdoor weather. Shafts, chases, unfinished attics, crawl spaces and pipe basements are not considered finished areas.
- 7. FSK: Foil-scrim-Kraft facing.
- 8. Hot: Plumbing equipment or piping handling media above 40 degrees C (104 degrees F).
- 9. Density:  $kg/m^3$  kilograms per cubic meter (Pcf pounds per cubic foot).
- 10. Thermal conductance: Heat flow rate through materials.
  - a. Flat surface: Watts per square meter (BTU per hour per square foot).
  - b. Pipe or Cylinder: Watts per linear meter (BTU per hour per linear foot) for a given outside diameter.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- 11. Thermal Conductivity (k): Watts per meter, per degree K (BTU inch thickness, per hour, per square foot, per degree F temperature difference).
- 12. Vapor Retarder (Vapor Barrier): A material which retards the transmission (migration) of water vapor. Performance of the vapor retarder is rated in terms of permeance (perms). For the purpose of this specification, vapor retarders/vapor barriers shall have a maximum published permeance of .02 perms.
- 13. HWR: Hot water recirculating.
- 14. CW: Cold water.
- 15. SW: Soft water.
- 16. HW: Hot water.
- 17. PVDC: Polyvinylidene chloride vapor retarder jacketing, white.

## 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- C. Section 01 81 13, SUSTAINABLE CONSTRUCTION REQUIREMENTS: Insulation material and insulation production method.
- G. Section 07 84 00, FIRESTOPPING: Mineral fiber and bond breaker behind sealant.
- I. Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING: General mechanical requirements and items, which are common to more than one section of Division 22.
- J. Section 22 05 19, METERS AND GAGES FOR PLUMBING PIPING: Hot and cold water piping.
- K. Section 22 05 23, GENERAL-DUTY VALVES FOR PLUMBING PIPING: Hot and cold water piping.
- L. Section 22 05 33, HEAT TRACING FOR PLUMBING PIPING: Insulation over heating cables.
- M. Section 22 08 00, COMMISSIONING OF PLUMBING SYSTEMS.
- N. Section 23 21 13, HYDRONIC PIPING: electrical heat tracing systems.
- O. Section 26 32 13, ENGINE GENERATORS: Exhaust stacks and muffler.

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

## 1.3 APPLICABLE PUBLICATIONS

A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by basic designation only.

	designation only.	
В.	American Society for Tes	sting and Materials (ASTM):
	B209-2014	Standard Specification for Aluminum and
		Aluminum-Alloy Sheet and Plate
	C411-2011	Standard Test Method for Hot-Surface
		Performance of High-Temperature Thermal
		Insulation
	C449-2007 (R2013)	Standard Specification for Mineral Fiber
		Hydraulic-Setting Thermal Insulating and
		Finishing Cement
	C450-2008 (R2014)	Standard Practice for Fabrication of Thermal
		Insulating Fitting Covers for NPS Piping, and
		Vessel Lagging
	Adjunct to C450	Compilation of Tables that Provide Recommended
		Dimensions for Prefab and Field Thermal
		Insulating Covers, etc.
	C533-2013	Standard Specification for Calcium Silicate
		Block and Pipe Thermal Insulation
	C534/C534M-2014	Standard Specification for Preformed Flexible
		Elastomeric Cellular Thermal Insulation in
		Sheet and Tubular Form
	C547-2015	Standard Specification for Mineral Fiber Pipe
		Insulation
	C552-2014	Standard Specification for Cellular Glass
		Thermal Insulation
	C553-2013	Standard Specification for Mineral Fiber
		Blanket Thermal Insulation for Commercial and
		Industrial Applications
	C591-2013	Standard Specification for Unfaced Preformed
		Rigid Cellular Polyisocyanurate Thermal
		Insulation
	C680-2014	Standard Practice for Estimate of the Heat Gain
		or Loss and the Surface Temperatures of

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

	Bancroft Architects + Engineers	١
	09-01-19 Insulated Flat, Cylindrical, and Spherical	1
	Systems by Use of Computer Programs	
	C612-2014Standard Specification for Mineral Fiber Block	
	and Board Thermal Insulation	
	C1126-2014Standard Specification for Faced or Unfaced	
	Rigid Cellular Phenolic Thermal Insulation	
	C1136-2012Standard Specification for Flexible, Low	
	Permeance Vapor Retarders for Thermal	
	Insulation	
	C1710-2011Standard Guide for Installation of Flexible	
	Closed Cell Preformed Insulation in Tube and	
	Sheet Form	
	D1668/D1668M-1997a (2014)e1 Standard Specification for Glass Fabrics	
	(Woven and Treated) for Roofing and	
	Waterproofing	
	E84-2015aStandard Test Method for Surface Burning	
	Characteristics of Building Materials	
	E2231-2015Standard Practice for Specimen Preparation and	
	Mounting of Pipe and Duct Insulation to Assess	
	Surface Burning Characteristics	
С.	Federal Specifications (Fed. Spec.):	
	L-P-535E-1979Plastic Sheet (Sheeting): Plastic Strip; Poly	
	(Vinyl Chloride) and Poly (Vinyl Chloride -	
	Vinyl Acetate), Rigid.	
D.	International Code Council, (ICC):	
	IMC-2012International Mechanical Code	
Ε.	Military Specifications (Mil. Spec.):	
	MIL-A-3316C (2)-1990Adhesives, Fire-Resistant, Thermal Insulation	
	MIL-A-24179A (2)-1987Adhesive, Flexible Unicellular-Plastic Thermal	
	Insulation	
	MIL-PRF-19565C (1)-1988.Coating Compounds, Thermal Insulation, Fire-and	
	Water-Resistant, Vapor-Barrier	
	MIL-C-20079H-1987Cloth, Glass; Tape, Textile Glass; and Thread,	
	Glass and Wire-Reinforced Glass	

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- G. Underwriters Laboratories, Inc (UL): 723-2008 (R2013)......Standard for Test for Surface Burning Characteristics of Building Materials 1887-2004 (R2013)......Standard for Fire Test of Plastic Sprinkler

Pipe for Visible Flame and Smoke

Characteristics

H. 3E Plus® version 4.1 Insulation Thickness Computer Program: Available from NAIMA with free download; https://insulationinstitute.org/toolsresources/

#### 1.4 SUBMITTALS

- A. Submittals, including number of required copies, shall be submitted in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Information and material submitted under this section shall be marked "SUBMITTED UNDER SECTION 22 07 11, PLUMBING INSULATION", with applicable paragraph identification.
- C. Manufacturer's Literature and Data including: Full item description and optional features and accessories. Include dimensions, weights, materials, applications, standard compliance, model numbers, size, and capacity.
- D. Shop Drawings:
  - All information, clearly presented, shall be included to determine compliance with drawings and specifications and ASTM Designation, Federal and Military specifications.
    - a. Insulation materials: Specify each type used and state surface burning characteristics.
    - b. Insulation facings and jackets: Each type used and state surface burning characteristics.
    - c. Insulation accessory materials: Each type used.
    - d. Manufacturer's installation and fitting fabrication instructions for flexible unicellular insulation shall follow the guidelines in accordance with ASTM C1710.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- e. Make reference to applicable specification paragraph numbers for coordination.
- f. All insulation fittings (exception flexible unicellular insulation) shall be fabricated in accordance with ASTM C450 and the referenced Adjunct to ASTM C450.

## 1.5 QUALITY ASSURANCE

- A. Refer to article QUALITY ASSURANCE, in Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.
- B. Criteria:
  - 1. Comply with NFPA 90A, particularly paragraphs 4.3.3.1 through
    - 4.3.3.6, 4.3.11.2.6, parts of which are quoted as follows:
      - **4.3.3.1** Pipe and duct insulation and coverings, duct linings, vapor retarder facings, adhesives, fasteners, tapes, and supplementary materials added to air ducts, plenums, panels and duct silencers used in duct systems shall have, in the form in which they are used, a maximum flame spread index of 25 without evidence of continued progressive combustion and a maximum smoke developed index of 50 when tested in accordance with ASTM E84 and appropriate mounting practice, e.g. ASTM E2231.
      - 4.3.3.3 Coverings and linings for air ducts, pipes, plenums and panels including all pipe and duct insulation materials shall not flame, glow, smolder, or smoke when tested in accordance with a similar test for pipe covering, ASTM C411, Standard Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation, at the temperature to which they are exposed in service. In no case shall the test temperature be below 121 degrees C (250 degrees F).
      - 4.3.11.2.6.3 Nonferrous fire sprinkler piping shall be listed as having a maximum peak optical density of 0.5 or less, an average optical density of 0.15 or less, and a maximum flame spread distance of 1.5 m (5 ft) or less when tested in accordance with UL 1887, Standard for Safety Fire Test of Plastic Sprinkler Pipe for Visible Flame and Smoke Characteristics.
      - 4.3.11.2.6.8 Smoke detectors shall not be required to meet the provisions of Section 4.3.
  - 2. Test methods: ASTM E84, UL 723, and ASTM E2231.
  - 3. Specified k factors are at 24 degrees C (75 degrees F) mean temperature unless stated otherwise. Where optional thermal insulation material is used, select thickness to provide thermal conductance no greater than that for the specified material. For pipe, use insulation manufacturer's published heat flow tables. For domestic hot water supply and return, run out insulation and

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

condensation control insulation, no thickness adjustment need be  $\mbox{made.}$ 

- 4. All materials shall be compatible and suitable for service temperature, and shall not contribute to corrosion or otherwise attack surface to which applied in either the wet or dry state.
- C. Every package or standard container of insulation or accessories delivered to the job site for use shall have a manufacturer's stamp or label giving the name of the manufacturer, description of the material, and the production date or code.
  - D. Bio-Based Materials: For products designated by the USDA's Bio-Preferred Program, provide products that meet or exceed USDA recommendations for bio-based content, so long as products meet all performance requirements in this specifications section. For more information regarding the product categories covered by the Bio-Preferred Program, visit http://www.biopreferred.gov.

## 1.6 AS-BUILT DOCUMENTATION

- A. Submit manufacturer's literature and data updated to include submittal review comments and any equipment substitutions.
- B. Submit operation and maintenance data updated to include submittal review comments, substitutions and construction revisions shall be in electronic version on compact disc or DVD inserted into a three ring binder. All aspects of system operation and maintenance procedures, including piping isometrics, wiring diagrams of all circuits, a written description of system design, control logic, and sequence of operation shall be included in the operation and maintenance manual. The operations and maintenance manual shall include troubleshooting techniques and procedures for emergency situations. Notes on all special systems or devices such as damper and door closure interlocks shall be included. A List of recommended spare parts (manufacturer, model number, and quantity) shall be furnished. Information explaining any special knowledge or tools the owner will be required to employ shall be inserted into the As-Built documentation.
- C. The installing contractor shall maintain as-built drawings of each completed phase for verification; and, shall provide the complete set at the time of final systems certification testing. As-built drawings are to be provided, and a copy of them in Auto-CAD version 2019

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

provided on compact disk or DVD. Should the installing contractor engage the testing company to provide as-built or any portion thereof, it shall not be deemed a conflict of interest or breach of the 'third party testing company' requirement.

D. Certification documentation shall be provided prior to submitting the request for final inspection. The documentation shall include all test results, the names of individuals performing work for the testing agency on this project, detailed procedures followed for all tests, and certification that all results of tests were within limits specified.

#### 1.7 STORAGE AND HANDLING OF MATERIAL

A. Store materials in clean and dry environment, pipe insulation jackets shall be clean and unmarred. Place adhesives in original containers.

Maintain ambient temperatures and conditions as required by printed instructions of manufacturers of adhesives, mastics and finishing cements.

# PART 2 - PRODUCTS

## 2.1 MINERAL FIBER OR FIBER GLASS

- A. ASTM C612 (Board, Block), Class 1 or 2, density  $48 \text{ kg/m}^3$  (nominal 3 pcf), k = 0.037 (.26) at 24 degrees C (75 degrees F), external insulation for temperatures up to 204 degrees C (400 degrees F).
- B. ASTM C553 (Blanket, Flexible) Type I, Class B-3, Density 16 kg/m $^3$  (nominal 1 pcf), k = 0.045 (0.31) at 24 degrees C (75 degrees F), for use at temperatures up to 204 degrees C (400 degrees F).
- C. ASTM C547 (Pipe Fitting Insulation and Preformed Pipe Insulation), Class 1, k = 0.037 (0.26) at 24 degrees C (75 degrees F), for use at temperatures up to 230 degrees C (446 degrees F) with an all service vapor retarder jacket (ASJ) and with polyvinyl chloride (PVC) premolded fitting covering.

## 2.2 MINERAL WOOL OR REFRACTORY FIBER

A. Comply with Standard ASTM C612, Class 3, 450 degrees C (842 degrees F).

## 2.3 RIGID CELLULAR PHENOLIC FOAM

A. Preformed (molded) pipe insulation, ASTM C1126, Type III, grade 1, k=0.021(0.15) at 10 degrees C (50 degrees F), for use at temperatures up to 121 degrees C (250 degrees F) with vapor retarder and all service vapor retarder jacket (ASJ) and with PVC premolded fitting covering.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

B. Equipment Insulation, ASTM C1126, Type II, grade 1,  $k=0.021\ (0.15)$  at 10 degrees C (50 degrees F), for use at temperatures up to 121 degrees C (250 degrees F) with rigid cellular phenolic insulation and covering, and all service vapor retarder jacket (ASJ).

## 2.4 CELLULAR GLASS CLOSED-CELL

- A. Comply with Standard ASTM C552, density 120 kg/m $^3$  (7.5 pcf) nominal, k = 0.033 (0.29) at 24 degrees C (75 degrees F).
- B. Pipe insulation for use at process temperatures below ambient air to 482 degrees C (900 degrees F) with or without all service vapor retarder jacket (ASJ).
- C. Pipe insulation for use at process temperatures for pipe and tube below ambient air temperatures or where condensation control is necessary are to be installed with a vapor retarder/barrier system of with or without all service vapor retarder sealed jacket (ASJ) system. Without ASJ shall require all longitudinal and circumferential joints to be vapor sealed with vapor barrier mastic.
- D. Cellular glass thermal insulation intended for use on surfaces operating at temperatures between -268 and 482 degrees C (-450 and 900 degrees F). It is possible that special fabrication or techniques for pipe insulation, or both, shall be required for application in the temperature range from 121 to 427 degrees C (250 to 800 degrees F).

# 2.5 POLYISOCYANURATE CLOSED-CELL RIGID

- A. Preformed (fabricated) pipe insulation, ASTM C591, Type IV,

  K=0.027(0.19) at 24 degrees C (75 degrees F), flame spread not over 25,

  smoke developed not over 50, for use at temperatures up to 149 degree C

  (300 degree F) with factory applied PVDC or all service vapor retarder

  jacket with PVC premolded fitting covers.
- B. Equipment and duct insulation, ASTM C591, Type IV, K=0.027(0.19) at 24 degrees C (75 degrees F), for use at temperatures up to 149 degrees C (300 degrees F) with PVDC or all service jacket vapor retarder jacket.

## 2.6 FLEXIBLE ELASTOMERIC CELLULAR THERMAL

A. ASTM C534/C534M, k = 0.039 (0.27) at 24 degrees C (75 degrees F), flame spread not over 25, smoke developed not over 50, for temperatures from minus 4 degrees C (40 degrees F) to 93 degrees C (199 degrees F). Under

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

high humidity exposures for condensation control an external vapor retarder/barrier jacket is required. Consult ASTM C1710.

## 2.7 CALCIUM SILICATE

- A. Preformed pipe Insulation: ASTM C533, Type I and Type II with indicator denoting asbestos-free material.
- B. Premolded Pipe Fitting Insulation: ASTM C533, Type I and Type II with indicator denoting asbestos-free material.
- C. Equipment Insulation: ASTM C533, Type I and Type II.
- D. Characteristics:

Insulation Characteristics		
ITEMS	TYPE I	TYPE II
Surface Temperature, maximum degrees C (degrees F)	649 (1200)	927 (1700)
Density (dry), Kg/m <sup>3</sup> (lb/ ft3)	240 (15)	352 (22)
Thermal conductivity:  Min W/ m K (Btu in/h ft² degrees F)@ mean temperature of 93 degrees C (199 degrees F)	0.065 (0.45)	0.078 (0.540)
Surface burning characteristics: Flame spread Index, Maximum	0	0
Smoke Density index, Maximum	0	0

## 2.8 INSULATION FACINGS AND JACKETS

- A. Vapor Retarder, higher strength with low water permeance = 0.02 or less perm rating, Beach puncture 50 units for insulation facing on pipe insulation jackets. Facings and jackets shall be ASJ or PVDC Vapor Retarder jacketing.
- B. ASJ shall be white finish (kraft paper) bonded to 0.025 mm (1 mil) thick aluminum foil, fiberglass reinforced, with pressure sensitive adhesive closure. Comply with ASTM C1136. Beach puncture is 50 units, suitable for painting without sizing. Jackets shall have minimum 40 mm (1-1/2 inch) lap on longitudinal joints and minimum 75 mm (3 inch) butt strip on end joints. Butt strip material shall be same as the jacket. Lap and butt strips shall be self-sealing type with factory-applied pressure sensitive adhesive.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- C. Vapor Retarder medium strength with low water vapor permeance of 0.02 or less perm rating), Beach puncture 25 units: FSK or PVDC type for concealed ductwork and equipment.
- D. Except for flexible elastomeric cellular thermal insulation (not for high humidity exposures), field applied vapor barrier jackets shall be provided, in addition to the specified facings and jackets, on all exterior piping as well as on interior piping conveying fluids below ambient temperature. The vapor barrier jacket shall consist of a multilayer laminated cladding with a maximum water vapor permeance of 0.001 perms. The minimum puncture resistance shall be 35 cm-kg (30 inch-pounds) for interior locations and 92 cm-kg (80 inch-pounds) for exterior or exposed locations or where the insulation is subject to damage.
- E. Except for cellular glass thermal insulation, when all longitudinal and circumferential joints are vapor sealed with a vapor barrier mastic or caulking, vapor barrier jackets may not be provided. For aesthetic and physical abuse applications, exterior jacketing is recommended. Otherwise field applied vapor barrier jackets shall be provided, in addition to the applicable specified facings and jackets, on all exterior piping as well as on interior piping conveying fluids below ambient temperature. The vapor barrier jacket shall consist of a multilayer laminated cladding with a maximum water vapor permeance of 0.001 perms. The minimum puncture resistance shall be 35 cm-kg (30 inchpounds) for interior locations and 92 cm-kg (80 inch-pounds) for exterior or exposed locations or where the insulation is subject to damage.
- F. Glass Cloth Jackets: Presized, minimum 0.18 kg per square meter (7.8 ounces per square yard), 2070 kPa (300 psig) bursting strength with integral vapor retarder where required or specified. Weather proof if utilized for outside service.
- G. Pipe fitting insulation covering (jackets): Fitting covering shall be premolded to match shape of fitting and shall be PVC conforming to Fed Spec L-P-535E, composition A, Type II Grade GU, and Type III, minimum thickness 0.7 mm (0.03 inches). Provide color matching vapor retarder pressure sensitive tape. Staples, tacks, or any other attachment that

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

penetrates the PVC covering is not allowed on any form of a vapor barrier system in below ambient process temperature applications.

- H. Aluminum Jacket-Piping systems and circular breeching and stacks: ASTM B209, 3003 alloy, H-14 temper, 0.6 mm (0.023 inch) minimum thickness with locking longitudinal joints. Jackets for elbows, tees and other fittings shall be factory-fabricated or with cut aluminum gores to match shape of fitting and of 0.6 mm (0.024 inch) minimum thickness aluminum. Aluminum fittings shall be of same construction with an internal moisture barrier as straight run jackets but need not be of the same alloy. Factory-fabricated stainless steel bands with wing seals shall be installed on all circumferential joints. Bands shall be 15 mm (0.5 inch) wide on 450 mm (18 inch) centers. System shall be weatherproof if utilized for outside service.
- I. Aluminum jacket-Rectangular breeching: ASTM B209, 3003 alloy, H-14 temper, 0.5 mm (0.020 inches) thick with 32 mm (1-1/4 inch) corrugations or 0.8 mm (0.032 inches) thick with no corrugations. System shall be weatherproof if used for outside service.

## 2.9 PIPE COVERING PROTECTION SADDLES

Bancroft-AE Project No. 18-121

A. Cold pipe support: Premolded pipe insulation 180 degrees (half-shells) on bottom half of pipe at supports. Material shall be cellular glass or high density Polyisocyanurate insulation of the same thickness as adjacent insulation. Density of Polyisocyanurate insulation shall be a minimum of  $48 \text{ kg/m}^3$  (3.0 pcf).

Nominal Pipe Size and Accessories Material (Insert Blocks)		
Nominal Pipe Size mm (inches)	Insert Blocks mm (inches)	
Up through 125 (5)	150 (6) long	
150 (6)	150 (6) long	
200 (8), 250 (10), 300 (12)	225 (9) long	
350 (14), 400 (16)	300 (12) long	
450 through 600 (18 through 24)	350 (14) long	

B. Warm or hot pipe supports: Premolded pipe insulation (180 degree half-shells) on bottom half of pipe at supports. Material shall be high Contract No. 36C26319D0044
Station Project No. 568A4-21-703

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

density Polyisocyanurate (for temperatures up to 149 degrees C (300 degrees F)), cellular glass or calcium silicate. Insulation at supports shall have same thickness as adjacent insulation. Density of Polyisocyanurate insulation shall be a minimum of  $48 \text{ kg/m}^3$  (3.0 pcf).

#### 2.10 ADHESIVE, MASTIC, CEMENT

- A. Mil. Spec. MIL-A-3316, Class 1: Jacket and lap adhesive and protective finish coating for insulation.
- B. Mil. Spec. MIL-A-3316, Class 2: Adhesive for laps and for adhering insulation to metal surfaces.
- C. Mil. Spec. MIL-A-24179A, Type II Class 1: Adhesive for installing flexible unicellular insulation and for laps and general use.
- D. Mil. Spec. MIL-PRF-19565C, Type I: Protective finish for outdoor use.
- E. Mil. Spec. MIL-PRFC-19565C, Type I or Type II: Vapor barrier compound for indoor use.
- F. ASTM C449: Mineral fiber hydraulic-setting thermal insulating and finishing cement.
- G. Other: Insulation manufacturers' published recommendations.

#### 2.11 MECHANICAL FASTENERS

- A. Pins, anchors: Welded pins, or metal or nylon anchors with galvanized steel or fiber washer, or clips. Pin diameter shall be as recommended by the insulation manufacturer.
- B. Staples: Outward clinching galvanized steel. Staples are not allowed for below ambient vapor barrier applications.
- C. Wire: 1.3 mm thick (18 gage) soft annealed galvanized or 1.9 mm (14 gage) copper clad steel or nickel copper alloy or stainless steel.
- D. Bands: 13 mm (1/2 inch) nominal width, brass, galvanized steel, aluminum or stainless steel.
- E. Tacks, rivets, screws or any other attachment device capable of penetrating the vapor retarder shall NOT be used to attach/close the any type of vapor retarder jacketing. Thumb tacks sometimes used on PVC jacketing and preformed fitting covers closures are not allowed for below ambient vapor barrier applications.

#### 2.12 REINFORCEMENT AND FINISHES

A. Glass fabric, open weave: ASTM D1668/D1668M, Type III (resin treated) and Type I (asphalt or white resin treated).

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- B. Glass fiber fitting tape: Mil. Spec MIL-C-20079H, Type II, Class 1.
- C. Tape for Flexible Elastomeric Cellular Insulation: As recommended by the insulation manufacturer.
- D. Hexagonal wire netting: 25 mm (one inch) mesh, 0.85 mm thick (22 gage) galvanized steel.
- E. Corner beads: 50 mm (2 inch) by 50 mm (2 inch), 0.55 mm thick (26 gage) galvanized steel; or, 25 mm (1 inch) by 25 mm (1 inch), 0.47 mm thick (28 gage) aluminum angle adhered to 50 mm (2 inch) by 50 mm (2 inch) Kraft paper.
- F. PVC fitting cover: Fed. Spec L-P-535E, Composition A, 11-86 Type II, Grade GU, with Form B Mineral Fiber insert, for media temperature 10 to 121 degrees C (50 to 250 degrees F). Below 10 degrees C (50 degrees F) and above 121 degrees C (250 degrees F) provide mitered pipe insulation of the same type as insulating straight pipe. Provide double layer insert. Provide vapor barrier pressure sensitive tape matching the color of the PVC jacket.

#### 2.13 FIRESTOPPING MATERIAL

A. Other than pipe insulation, refer to Section 07 84 00, FIRESTOPPING.

#### 2.14 FLAME AND SMOKE

A. Unless shown otherwise all assembled systems shall meet flame spread 25 and smoke developed 50 rating as developed under ASTM and UL standards and specifications. See paragraph "Quality Assurance".

### PART 3 - EXECUTION

#### 3.1 GENERAL REQUIREMENTS

- A. Required pressure tests of piping joints and connections shall be completed and the work approved by the Contracting Officer's Representative (COR) for application of insulation. Surface shall be clean and dry with all foreign materials, such as dirt, oil, loose scale and rust removed.
- B. Except for specific exceptions or as noted, insulate all specified equipment, and piping (pipe, fittings, valves, accessories). Insulate each pipe individually. Do not use scrap pieces of insulation where a full length section will fit.
- D. Insulation materials shall be installed with smooth and even surfaces, with jackets and facings drawn tight and smoothly cemented down and

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- sealed at all laps. Insulation shall be continuous through all sleeves and openings, except at fire dampers and duct heaters (NFPA 90A).
- E. Vapor retarders shall be continuous and uninterrupted throughout systems with operating temperature 15 degrees C (60 degrees F) and below. Lap and seal vapor barrier over ends and exposed edges of insulation. Anchors, supports and other metal projections through insulation on cold surfaces shall be insulated and vapor sealed for a minimum length of 150 mm (6 inches).
- F. Install vapor stops with operating temperature 15 degrees C (60 degrees F) and below at all insulation terminations on either side of valves, pumps, fittings, and equipment and particularly in straight lengths every 4.6 to 6.1 meters (approx. 15 to 20 feet) of pipe insulation. The annular space between the pipe and pipe insulation of approx. 25 mm (1 inch) in length at every vapor stop shall be sealed with appropriate vapor barrier sealant. Bio-based materials shall be utilized when possible.
- G. Construct insulation on parts of equipment such as cold water pumps and heat exchangers that must be opened periodically for maintenance or repair, so insulation can be removed and replaced without damage.

  Install insulation with bolted 1 mm thick (20 gage) galvanized steel or aluminum covers as complete units, or in sections, with all necessary supports, and split to coincide with flange/split of the equipment. Do not insulate over equipment nameplate data.
- H. Insulation on hot piping and equipment shall be terminated square at items not to be insulated, access openings and nameplates. Cover all exposed raw insulation with white sealer coating (caution about coating's maximum temperature limit) or jacket material.
- I. Protect all insulations outside of buildings with aluminum jacket using lock joint or other approved system for a continuous weather tight system. Access doors and other items requiring maintenance or access shall be removable and sealable.
- J. Plumbing work not to be insulated unless otherwise noted:
  - 1. Piping and valves of fire protection system.
  - 2. Chromium plated brass piping.
  - 3. Water piping in contact with earth.
  - 4. Distilled water piping.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- K. Apply insulation materials subject to the manufacturer's recommended temperature limits. Apply adhesives, mastic and coatings at the manufacturer's recommended minimum wet or dry film thickness. Bio-based materials shall be utilized when possible.
- L. Elbows, flanges and other fittings shall be insulated with the same material as is used on the pipe straights. Use of polyurethane or polyisocyanurate spray-foam to fill a PVC elbow jacket is prohibited on cold applications.
- M. Firestop Pipe insulation:
  - 1. Provide firestopping insulation at fire and smoke barriers through penetrations. Firestopping insulation shall be UL listed as defined in Section 07 84 00, FIRESTOPPING.
  - 2. Pipe penetrations requiring fire stop insulation including, but not limited to the following:
    - a. Pipe risers through floors
    - b. Pipe chase walls and floors
    - c. Smoke partitions
    - d. Fire partitions
    - e. Hourly rated walls
- N. Freeze protection of above grade outdoor piping (over heat tracing tape): 20 mm (3/4 inch) thick insulation, for all pipe sizes 75 mm (3 inches) and smaller and 25 mm (1 inch) thick insulation for larger pipes. Provide metal jackets for all pipe insulations. Provide freeze protection for cold water make-up piping and equipment where indicated on the drawings as described in Section 23 21 13, HYDRONIC PIPING (electrical heat tracing systems).
- O. Provide vapor barrier systems as follows:
  - 1. All piping exposed to outdoor weather.
- P. Provide metal jackets over insulation as follows:
  - 1. All plumbing piping exposed to outdoor weather.
  - 2. Piping exposed in building, within 1829 mm (6 feet) of the floor, that connects to sterilizers, kitchen and laundry equipment. Jackets may be applied with pop rivets except for cold pipe or tubing applications. Provide aluminum angle ring escutcheons at wall, ceiling or floor penetrations.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- 3. A 50 mm (2 inch) jacket overlap is required at longitudinal and circumferential joints with the overlap at the bottom.
- Q. Provide PVC jackets over insulation as follows:
  - 1. Piping exposed in building, within 1829 mm (6 feet) of the floor, on piping that is not precluded in previous sections.
  - 2. A 50 mm (2 inch) jacket overlap is required at longitudinal and circumferential joints with the overlap at the bottom.

#### 3.2 INSULATION INSTALLATION

- A. Mineral Fiber Board:
  - 1. Vapor retarder faced board: Apply board on pins spaced not more than 300 mm (12 inches) on center each way, and not less than 75 mm (3 inches) from each edge of board. In addition to pins, apply insulation bonding adhesive to entire underside of horizontal metal surfaces. (Bio-based materials shall be utilized when possible.)
    Butt insulation edges tightly and seal all joints with laps and butt strips. After applying speed clips cut pins off flush and apply vapor seal patches over clips.
  - 2. Plain unfaced board:
    - a. Insulation shall be scored, beveled or mitered to provide tight joints and be secured to equipment with bands spaced 225 mm (9 inches) on center for irregular surfaces or with pins and clips on flat surfaces. Use corner beads to protect edges of insulation.
    - b. For hot equipment: Stretch 25 mm (1 inch) mesh wire, with edges wire laced together, over insulation and finish with insulating and finishing cement applied in one coat, 6 mm (1/4 inch) thick, trowelled to a smooth finish.
    - c. For cold equipment: Apply meshed glass fabric in a tack coat 1.5 to 1.7 square meter per liter (60 to 70 square feet per gallon) of vapor mastic and finish with mastic at 0.3 to 0.4 square meter per liter (12 to 15 square feet per gallon) over the entire fabric surface.
  - 3. Cold equipment: 40 mm (1-1/2inch) thick insulation faced with vapor retarder ASJ or FSK. Seal all facings, laps, and termination points and do not use staples or other attachments that may puncture ASJ or FSK.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- a. Water filter, chemical feeder pot or tank.
- b. Pneumatic, cold storage water and surge tanks.
- 4. Hot equipment: 40 mm (1-1/2 inch) thick insulation faced with unsealed ASJ or FSK.
  - a. Domestic water heaters and hot water storage tanks (not factory insulated).
  - b. Booster water heaters for dietetics dish and pot washers and for washdown grease-extracting hoods.
- B. Molded Mineral Fiber Pipe and Tubing Covering:
  - 1. Fit insulation to pipe, aligning all longitudinal joints. Seal longitudinal joint laps and circumferential butt strips by rubbing hard with a nylon sealing tool to assure a positive seal. Staples may be used to assist in securing insulation except for cold piping. Seal all vapor retarder penetrations on cold piping with a generous application of vapor barrier mastic. Provide cellar glass inserts and install with metal insulation shields at outside pipe supports. Install freeze protection insulation over heating cable.
  - 2. Contractor's options for fitting, flange and valve insulation:
    - a. Insulating and finishing cement for sizes less than 100 mm (4 inches) operating at surface temperature of 15 degrees C (60 degrees F) or more.
    - b. Factory premolded, one piece PVC covers with mineral fiber, (Form B), inserts surface temperature of above 4 degrees C (40 degrees F) to 121 degrees C (250 degrees F). Provide mitered preformed insulation of the same type as the installed straight pipe insulation for pipe temperatures below 4 degrees C (40 degrees F). Secure first layer of mineral fiber insulation with twine. Seal seam edges with vapor barrier mastic and secure with fitting tape.
    - c. Factory preformed, ASTM C547 or fabricated mitered sections, joined with adhesive or (hot only) wired in place. (Bio-based materials shall be utilized when possible.) For hot piping finish with a smoothing coat of finishing cement. For cold fittings, 15 degrees C (60 degrees F) or less, vapor seal with a layer of glass fitting tape imbedded between two 2 mm (1/16 inch) coats of vapor barrier mastic.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- d. Fitting tape shall extend over the adjacent pipe insulation and overlap on itself at least 50 mm (2 inches).
- 3. Nominal thickness in millimeters and inches specified in the schedule at the end of this section.

#### C. Rigid Cellular Phenolic Foam:

- Rigid closed cell phenolic insulation may be provided, exterior only, for piping, ductwork and equipment for temperatures up to 121 degrees C (250 degrees F).
- 2. Note the ASTM E84 or UL 723 surface burning characteristics requirements of maximum 25/50 indexes in paragraph "Quality Assurance".
- 3. Provide secure attachment facilities such as welding pins.
- 4. Apply insulation with joints tightly drawn together.
- 5. Apply adhesives, coverings, neatly finished at fittings, and valves.
- 6. Final installation shall be smooth, tight, neatly finished at all edges.
- 7. Minimum thickness in millimeters (inches) specified in the schedule at the end of this section.
- 8. Condensation control insulation: Minimum 25 mm (1 inch) thick for all pipe sizes depending on high humidity exposures.
  - a. Body of roof and overflow drains horizontal runs and offsets (including elbows) of interior downspout piping in all areas above pipe basement.
  - b. Waste piping from electric water coolers and icemakers to drainage system.
  - c. Waste piping located above basement floor from ice making and film developing equipment and air handling units, from equipment (including trap) to main vertical waste pipe.
  - d. MRI quench vent piping.
  - e. Bedpan sanitizer atmospheric vent
  - f. Reagent grade water piping.
  - g. Cold water piping, exterior only.

## D. Cellular Glass Insulation:

1. Pipe and tubing, covering nominal thickness in millimeters and inches as specified in the schedule at the end of this section.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- 2. Underground piping other than or in lieu of that specified in Section 22 11 00, FACILITY WATER DISTRIBUTION: Type II, factory jacketed with a 3 mm laminate jacketing consisting of 3000 mm x 3000 mm (10 ft x 10 ft) asphalt impregnated glass fabric, bituminous mastic and outside protective plastic film.
  - a. 75 mm (3 inches) thick for hot water piping.
  - b. As scheduled at the end of this section for chilled water piping.
  - c. Underground piping: Apply insulation with joints tightly butted. Seal longitudinal self-sealing lap. Use field fabricated or factory made fittings. Seal butt joints and fitting with jacketing as recommended by the insulation manufacturer. Use 100 mm (4 inch) wide strips to seal butt joints.
  - d. Provide expansion chambers for pipe loops, anchors and wall penetrations as recommended by the insulation manufacturer.
  - e. Underground insulation shall be inspected and approved by the COR as follows:
    - 1) Insulation in place before coating.
    - 2) After coating.
  - f. Sand bed and backfill: Minimum 75 mm (3 inches) all around insulated pipe or tank, applied after coating has dried.
  - g. All piping up to 482 degrees C (900 degrees F) requiring protection from physical heavy contact/abuse including in mechanical rooms and exposures to the public.
- 3. Cold equipment: 50 mm (2 inch) thick insulation faced with ASJ.
- E. Polyisocyanurate Closed-Cell Rigid Insulation:
  - Polyisocyanurate closed-cell rigid insulation (PIR) may be provided for exterior piping and equipment for temperature up to 149 degree C (300 degree F).
  - 2. Install insulation, vapor retarder and jacketing per manufacturer's recommendations. Particular attention should be paid to recommendations for joint staggering, adhesive application, external hanger design, expansion/contraction joint design and spacing and vapor retarder integrity.
  - 3. Install insulation with all joints tightly butted (except expansion) joints in hot applications). Provide insulation contractions joints for very cold process temperatures.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- 4. If insulation thickness exceeds 65 mm (2-1/2 inches), install as a double layer system with longitudinal (lap) and butt joint staggering as recommended by manufacturer.
- 5. For cold applications, vapor retarder shall be installed in a continuous manner. No staples, rivets, screws or any other attachment device capable of penetrating the vapor retarder shall be used to attach the vapor retarder or jacketing. No wire ties capable of penetrating the vapor retarder shall be used to hold the insulation in place. Stainless steel banding shall be used for cold applications to attach PVC or metal jacketing.
- 6. Elbows, flanges and other fittings shall be insulated with the same material as is used on the pipe straights. The elbow/ fitting insulation shall be field-fabricated, mitered or factory prefabricated to the necessary size and shape to fit on the elbow/ fitting. Use of polyurethane or polyisocyanurate spray-foam to fill PVC elbow jacket is prohibited on cold applications.
- 7. For cold applications, the vapor retarder on elbows/fittings shall be either mastic-fabric-mastic or 2 mil thick PVDC vapor retarder adhesive tape. Bio-based materials shall be utilized when possible.
- 8. All PVC and metal jacketing shall be installed so as to naturally shed water. Joints shall point down and shall be sealed with either adhesive or caulking (except for periodic slip joints). Bio-based materials shall be utilized when possible.
- 9. Note the NFPA 90A burning characteristic requirements of 25/50 in paragraph "Quality Assurance". Refer to paragraph "General Requirements" for items not to be insulated.
- 10. Minimum thickness in millimeter (inches) specified in the schedule at the end of this section.

#### F. Flexible Elastomeric Cellular Thermal Insulation:

- 1. Apply insulation and fabricate fittings in accordance with the manufacturer's installation instructions and finish with two coats of weather resistant finish as recommended by the insulation manufacturer. External vapor barrier jacketing may be required for expected or anticipated high humidity exposures. See ASTM C1710.
- 2. Pipe and tubing insulation:
- a. Use proper size material. Do not stretch or strain insulation. Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121 02/17/2022

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

- b. To avoid undue compression of insulation, use supports as recommended by the elastomeric insulation manufacturer. Insulation shields are specified under Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.
- c. Where possible, slip insulation over the pipe or tubing prior to connection, and seal the butt joints with adhesive. Where the slip-on technique is not possible, slit the insulation and apply it to the pipe sealing the seam and joints with contact adhesive. Optional tape sealing, as recommended by the manufacturer, may be employed. Bio-based materials shall be utilized when possible.
- 3. Apply sheet insulation to flat or large curved surfaces with 100 percent adhesive coverage. For fittings and large pipe, apply adhesive to seams only.
- 4. Pipe insulation: nominal thickness in millimeters (inches as specified in the schedule at the end of this section.

#### G. Calcium Silicate:

1. Minimum thickness in millimeter (inches) specified below for piping other than in boiler plant.

Nominal Thick	ness Of Cal		te Insulati	.on
Nominal Pipe Size Millimeters (Inches)	Thru 25 (1)	32 to 75 (1-1/4 to 3)	100-200 (4 to 8)	Greater than 200 (8)
93-260 degrees C (199-500 degrees F)(HPS, HPR)	100(4)	125(5)	150(6)	Greater than 150(6)

2. MRI Quench Vent Insulation: Type I, class D, 150 mm (6 inch) nominal thickness.

#### 3.3 COMMISSIONING (NOT USED)

#### 3.4 PIPE INSULATION SCHEDULE

A. Provide insulation for piping systems as scheduled below:

Insulation Thickne	ss Millimeters (Inches)
	Nominal Pipe Size Millimeters (Inches)

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

		1	1	1	09-01-19
Operating Temperature Range/Service	Insulation Material	Less than 25 (1)	25 - 32 (1 - 1 <sup>1</sup> / <sub>4</sub> )	38 - 75 (1½ - 3)	100 (4) and Greater
38-60 degrees C (100-140 degrees F) (Domestic Hot Water Supply and Return)	Mineral Fiber (Above ground piping only)	38 (1.5)	38 (1.5)	50 (2.0)	50 (2.0)
38-60 degrees C (100-140 degrees F) (Domestic Hot Water Supply and Return)	Rigid Cellular Phenolic Foam (Above ground piping only) (exterior locations only)	38 (1.5)	38 (1.5)	50 (2.0)	50 (2.0)
38-60 degrees C (100-140 degrees F) (Domestic Hot Water Supply and Return)	Polyiso- cyanurate Closed-Cell Rigid (Exterior Locations only)	38 (1.5)	38 (1.5)	50 (2.0)	50 (2.0)
38-60 degrees C (100-140 degrees F) (Domestic Hot Water Supply and Return)	Flexible Elastomeric Cellular Thermal (Above ground piping only)	38 (1.5)	38 (1.5)	50 (2.0)	50 (2.0)
38-60 degrees C (100-140 degrees F) (Domestic Hot Water Supply and Return)	Cellular Glass Thermal	38 (1.5)	38 (1.5)	50 (2.0)	50 (2.0)
4-15 degrees C (40-60 degrees F)	Rigid Cellular Phenolic Foam (Above ground piping only) (exterior locations only)	25 (1.0)	25(1.0)	25 (1.0)	25 (1.0)
4-15 degrees C (40-60 degrees F)	Polyiso- cyanurate Closed-Cell Rigid (Exterior Locations only)	25 (1.0)	25(1.0)	25 (1.0)	25 (1.0)
(4-15 degrees C (40-60 degrees F)	Flexible Elastomeric Cellular Thermal (Above	25 (1.0)	25(1.0)	25 (1.0)	25 (1.0)

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-19

				-	,, , , , , , , , , , , , , , , , , , , ,
	ground piping only)				
4-15 degrees C (40-60 degrees F)	Cellular Glass Thermal	38 (1.5)	38 (1.5)	38 (1.5)	38 (1.5)

- - - E N D - - -

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

05-01-21

# SECTION 22 11 00 FACILITY WATER DISTRIBUTION

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. Domestic water systems, including piping, equipment and all necessary accessories as designated in this section.
- B. A complete listing of all acronyms and abbreviations are included in Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

#### 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- C. Section 01 81 13, SUSTAINABLE CONSTRUCTION REQUIREMENTS.
- E. Section 07 84 00, FIRESTOPPING.
- F. Section 07 92 00, JOINT SEALANTS.
- G. Section 09 91 00, PAINTING.
- I. Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.
- J. Section 22 07 11, PLUMBING INSULATION.

## 1.3 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. American Society of Mechanical Engineers (ASME):

A13.1-2007	(R2013)	.Scheme	for Ide	ntificatio	on of Pipir	ng System	ແຮ
B16.3-2011.		.Malleab	le Iron	Threaded	Fittings:	Classes	150
		and 300					

	and 300
B16.9-2012	Factory-Made Wrought Buttwelding Fittings
B16.11-2011	Forged Fittings, Socket-Welding and Threaded
B16.12-2009 (R2014)	.Cast Iron Threaded Drainage Fittings

B16.15-2013	Cast	Copper	Alloy	Threaded	Fittings:	Classes
	125 8	and 250				

B16.18-2012Cast	Copper	Alloy	Solder	Joint	Pressure
Fitti	ings				

B16.22-2013	Wrought	Copper	and	Copper	Alloy	Solder-	-Joint
	Pressure	e Fittir	ngs				

EHRM Infrastructure Upgrades
Bancroft Architects + Engineers

Bancroft Architects + Engineers
05-01-21 B16.24-2011Cast Copper Alloy Pipe Flanges and Flanged
Fittings: Classes 150, 300, 600, 900, 1500, and
2500
ASME Boiler and Pressure Vessel Code -
BPVC Section IX-2015Welding, Brazing, and Fusing Qualifications
C. American Society of Sanitary Engineers (ASSE):
1010-2004Performance Requirements for Water Hammer
Arresters
D. American Society for Testing and Materials (ASTM):
A47/A47M-1999 (R2014)Standard Specification for Ferritic Malleable
Iron Castings
A53/A53M-2012Standard Specification for Pipe, Steel, Black
and Hot-Dipped, Zinc-Coated, Welded and
Seamless
A183-2014Standard Specification for Carbon Steel Track
Bolts and Nuts
A269/A269M-2014e1Standard Specification for Seamless and Welded
Austenitic Stainless Steel Tubing for General
Service
A312/A312M-2015Standard Specification for Seamless, Welded,
and Heavily Cold Worked Austenitic Stainless
Steel Pipes
A403/A403M-2014Standard Specification for Wrought Austenitic
Stainless Steel Piping Fittings
A536-1984 (R2014)Standard Specification for Ductile Iron
Castings
A733-2013Standard Specification for Welded and Seamless
Carbon Steel and Austenitic Stainless Steel
Pipe Nipples
B32-2008 (R2014)Standard Specification for Solder Metal
B43-2014Standard Specification for Seamless Red Brass
Pipe, Standard Sizes
B61-2008 (R2013)Standard Specification for Steam or Valve
Bronze Castings
B62-2009Standard Specification for Composition Bronze
or Ounce Metal Castings

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

	Bancroit Architects + Engineers	01 01
	B75/B75M-2011Standard Specification for Seamless Copper	-01-21 Tube
	B88-2014Standard Specification for Seamless Copper	
	Water Tube	
	B584-2014Standard Specification for Copper Alloy Sa	nd
	Castings for General Applications	
	B687-1999 (R2011)Standard Specification for Brass, Copper,	and
	Chromium-Plated Pipe Nipples	
	C919-2012Standard Practice for Use of Sealants in	
	Acoustical Applications	
	D1785-2012Standard Specification for Poly (Vinyl	
	Chloride) (PVC) Plastic Pipe, Schedules 40	, 80,
	and 120	
	D2000-2012Standard Classification System for Rubber	
	Products in Automotive Applications	
	D2564-2012Standard Specification for Solvent Cements	for
	Poly (Vinyl Chloride) (PVC) Plastic Piping	
	Systems	
	D2657-2007Standard Practice for Heat Fusion Joining	of
	Polyolefin Pipe and Fittings	
	D2855-1996 (R2010)Standard Practice for Making Solvent-Cemen	ted
	Joints with Poly (Vinyl Chloride) (PVC) Pig	pe
	and Fittings	
	D4101-2014Standard Specification for Polypropylene	
	Injection and Extrusion Materials	
	E1120-2008Standard Specification for Liquid Chlorine	
	E1229-2008Standard Specification for Calcium Hypochl	orite
	F2389-2010Standard Specification for Pressure-rated	
	Polypropylene (PP) Piping Systems	
	F2620-2013Standard Practice for Heat Fusion Joining	of
	Polyethylene Pipe and Fittings	
	F2769-2014Standard Specification for Polyethylene of	
	Raised Temperature (PE-RT) Plastic Hot and	
	Cold-Water Tubing and Distribution Systems	
Ε.	American Water Works Association (AWWA):	
	C110-2012Ductile-Iron and Gray-Iron Fittings	
	C151-2009Ductile Iron Pipe, Centrifugally Cast	

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

	Bancroft Architects + Engineers
	05-01-21 C153-2011Ductile-Iron Compact Fittings
	C203-2008Coal-Tar Protective Coatings and Linings for
	Steel Water Pipelines - Enamel and Tape - Hot
	Applied
	C213-2007Fusion-Bonded Epoxy Coating for the Interior
	and Exterior of Steel Water Pipelines
	C651-2014Disinfecting Water Mains
F.	American Welding Society (AWS):
	A5.8M/A5.8-2011-AMD1Specification for Filler Metals for Brazing and
	Braze Welding
G.	International Code Council (ICC):
	IPC-2012International Plumbing Code
Н.	Manufacturers Specification Society (MSS):
	SP-58-2009Pipe Hangers and Supports - Materials, Design,
	Manufacture, Selection, Application, and
	Installation
	SP-72-2010aBall Valves with Flanged or Butt-Welding Ends
	for General Service
	SP-110-2010Ball Valves Threaded, Socket-Welding, Solder
	Joint, Grooved and Flared Ends
I.	NSF International (NSF):
	14-2015Plastics Piping System Components and Related
	Materials
	61-2014aDrinking Water System Components - Health
	Effects
	372-2011Drinking Water System Components - Lead Content
J.	Plumbing and Drainage Institute (PDI):
	PDI-WH 201-2010Water Hammer Arrestors
К.	Department of Veterans Affairs:
	H-18-8-2013Seismic Design Handbook
	H-18-10Plumbing Design Manual

#### 1.4 SUBMITTALS

A. Submittals, including number of required copies, shall be submitted in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

05-01-21

- B. Information and material submitted under this section shall be marked "SUBMITTED UNDER SECTION 22 11 00, FACILITY WATER DISTRIBUTIONS", with applicable paragraph identification.
- C. Manufacturer's Literature and Data including: Full item description and optional features and accessories. Include dimensions, weights, materials, applications, standard compliance, model numbers, size, and capacity.
  - 1. All items listed in Part 2 Products.
- D. Complete operating and maintenance manuals including wiring diagrams, technical data sheets and information for ordering replacement parts:
  - 1. Include complete list indicating all components of the systems.
  - 2. Include complete diagrams of the internal wiring for each item of equipment.
  - 3. Diagrams shall have their terminals identified to facilitate installation, operation and maintenance.

#### 1.5 QUALITY ASSURANCE

- A. A certificate shall be submitted prior to welding of steel piping showing the Welder's certification. The certificate shall be current and no more than one year old. Welder's qualifications shall be in accordance with ASME BPVC Section IX.
- B. All grooved joint couplings, fittings, valves, and specialties shall be the products of a single manufacturer. Grooving tools shall be by the same manufacturer as the groove components.
- C. All pipe, couplings, fittings, and specialties shall bear the identification of the manufacturer and any markings required by the applicable referenced standards.
- D. Bio-Based Materials: For products designated by the USDA's Bio-Preferred Program, provide products that meet or exceed USDA recommendations for bio-based content, so long as products meet all performance requirements in this specifications section. For more information regarding the product categories covered by the Bio-Preferred Program, visit http://www.biopreferred.gov.

#### 1.6 SPARE PARTS

#### 1.7 AS-BUILT DOCUMENTATION

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

05-01-21

- A. Submit manufacturer's literature and data updated to include submittal review comments and any equipment substitutions.
- B. Submit operation and maintenance data updated to include submittal review comments, substitutions and construction revisions shall be in electronic version on compact disc or DVD inserted into a three-ring binder. All aspects of system operation and maintenance procedures, including piping isometrics, wiring diagrams of all circuits, a written description of system design, control logic, and sequence of operation shall be included in the operation and maintenance manual. The operations and maintenance manual shall include troubleshooting techniques and procedures for emergency situations. Notes on all special systems or devices shall be included. A list of recommended spare parts (manufacturer, model number, and quantity) shall be furnished. Information explaining any special knowledge or tools the owner will be required to employ shall be inserted into the As-Built documentation.
- C. The installing contractor shall maintain as-built drawings of each completed phase for verification; and, shall provide the complete set at the time of final systems certification testing. As-built drawings are to be provided, and a copy of them in Auto-CAD version 2019 provided on compact disk or DVD. Should the installing contractor engage the testing company to provide as-built or any portion thereof, it shall not be deemed a conflict of interest or breach of the 'third party testing company' requirement.
- D. Certification documentation shall be provided to COR 10 working days prior to submitting the request for final inspection. The documentation shall include all test results, the names of individuals performing work for the testing agency on this project, detailed procedures followed for all tests, and certificate if applicable that all results of tests were within limits specified. If a certificate is not available, all documentation shall be on the Certifier's letterhead.

## PART 2 - PRODUCTS

#### 2.1 MATERIALS

A. Material or equipment containing a weighted average of greater than 0.25 percent lead are prohibited in any potable water system intended for human consumption and shall be certified in accordance with NSF 61

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

05-01-21

- or NSF 372. Endpoint devices used to dispense water for drinking shall meet the requirements of NSF 61, Section 9.
- B. Plastic pipe, fittings, and solvent cement shall meet NSF 14 and shall be NSF listed for the service intended.

#### 2.2 UNDERGROUND WATER SERVICE CONNECTIONS TO BUILDINGS (NOT USED)

#### 2.3 ABOVE GROUND (INTERIOR) WATER PIPING

- A. Pipe: Copper tube, ASTM B88, Type K or L, drawn. For pipe 150 mm (6 inches) and larger, stainless steel, ASTM A312, schedule 40 shall be used.
- B. Fittings for Copper Tube:
  - 1. Wrought copper or bronze castings conforming to ASME B16.18 and B16.22. Unions shall be bronze, MSS SP-72, MSS SP-110, solder or braze joints. Use 95/5 tin and antimony for all soldered joints.
  - 2. Grooved fittings, 50 to 150 mm (2 to 6 inch) wrought copper ASTM B75/B75M C12200, 125 to 150 mm (5 to 6 inch) bronze casting ASTM B584, C84400. Mechanical grooved couplings, 2070 kPa (300 psig) minimum ductile iron, ASTM A536 Grade 448-310-12 (Grade 65-45-12), or malleable iron, ASTM A47/A47M Grade 22410 (Grade 32510) housing, with EPDM gasket, steel track head bolts, ASTM A183, coated with copper colored alkyd enamel.
  - 3. Mechanically formed tee connection: Form mechanically extracted collars in a continuous operation by drilling pilot hole and drawing out tube surface to form collar, having a height of not less than three times the thickness of tube wall. Adjustable collaring device shall ensure proper tolerance and complete uniformity of the joint. Notch and dimple joining branch tube in a single process to provide free flow where the branch tube penetrates the fitting. Braze joints.
  - 4. Flanged fittings, bronze, class 150, solder-joint ends conforming to ASME B16.24.
- C. Fittings for Stainless Steel:
  - 1. Stainless steel butt-welded fittings, Type 316, Schedule 10, conforming to ASME B16.9.
  - 2. Grooved fittings, stainless steel, Type 316, Schedule 40, conforming to ASTM A403/A403M. Segmentally fabricated fittings are not allowed. Mechanical grooved couplings, ductile iron, 4138 kPa

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

05-01-21

(600 psig), ASTM A536 Grade 448-310-12 (Grade 65-45-12), or malleable iron, ASTM A47/A47M Grade 22410 (Grade 32510) housing, with EPDM gasket, steel track head bolts, ASTM A183, coated with copper colored alkyd enamel.

- D. Adapters: Provide adapters for joining pipe or tubing with dissimilar end connections.
- E. Solder: ASTM B32 alloy type Sb5, HA or HB. Provide non-corrosive flux.
- F. Brazing alloy: AWS A5.8M/A5.8, brazing filler metals shall be BCuP series for copper to copper joints and BAg series for copper to steel joints.
- G. Re-agent Grade Water Piping and Dialysis Water Piping:
  - 1. Polypropylene, ASTM F2389, Schedule 80 pressure pipe without additions of modifiers, plasticizers, colorants, stabilizers or lubricants. Bio-based materials shall be utilized when possible. This virgin un-plasticized pipe and fittings shall transport 10 megohm water with no loss of purity. Provide socket or butt end fittings with ASTM D2657 heat fusion joints.
  - 2. Polyethylene, ASTM F2769, Schedule 80, food and medical grade, capable of transporting 10 megohm water with no loss of purity. Processed by continuous compression molding without the addition of fillers, polymer modifiers or processing aids. Uniform color with no cracks, flaws, blisters or other imperfections in appearance. Provide ASTM D2657 or ASTM F2620 heat fusion butt welded joints. In accordance with manufacturer's recommendations, provide continuous channel support under all horizontal piping.
  - 3. Reverse Osmosis (RO) Water Piping:
    - a. Low Pressure Feed, Reject and Recycle Piping: Less than or equal to 520 kPa (75 psig): ASTM D1785, Schedule 80 PVC, ASTM D2855 socket welded and flanged.
    - b. RO Product Tubing from each Membrane Housing: ASTM D1785, Schedule 80 PVC, ASTM D2855 socket welded and flanged.
    - c. Low Pressure Control and Pressure Gage Tubing: Polyethylene.
    - d. High Pressure Reject and Recycle Piping: Greater than 520 kPa (75 psig): ASTM A269/A269M, Type 304 schedule 10 stainless steel with butt welded joints.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

05-01-21

e. High Pressure Control and Pressure Gage Tubing: 6895 kPa (1000 psig) burst nylon.

#### 2.4 EXPOSED WATER PIPING

- A. Finished Room: Use full iron pipe size chrome plated brass piping for exposed water piping connecting fixtures, casework, cabinets, equipment, and reagent racks when not concealed by apron including those furnished by the Government or specified in other sections.
  - 1. Pipe: ASTM B43, standard weight.
  - 2. Fittings: ASME B16.15 cast bronze threaded fittings with chrome finish.
  - 3. Nipples: ASTM B687, Chromium-plated.
  - 4. Unions: MSS SP-72, MSS SP-110, brass or bronze with chrome finish. Unions 65 mm (2-1/2 inches) and larger shall be flange type with approved gaskets.
- B. Unfinished Rooms, Mechanical Rooms and Kitchens: Chrome-plated brass piping is not required. Paint piping systems as specified in Section 09 91 00, PAINTING.
- 2.5 ETHYLENE OXIDE (ETO) STERILIZER WATER SUPPLY PIPING (NOT USED)

## 2.6 TRAP PRIMER WATER PIPING (NOT USED)

#### 2.7 STRAINERS

- A. Provide on high pressure side of pressure reducing valves, on suction side of pumps, on inlet side of indicating and control instruments and equipment subject to sediment damage and where shown on drawings.

  Strainer element shall be removable without disconnection of piping.
- B. Water: Basket or "Y" type with easily removable cover and brass strainer basket.
- C. Body: Less than 75 mm (3 inches), brass or bronze; 75 mm (3 inches) and greater, cast iron or semi-steel.

## 2.8 DIELECTRIC FITTINGS

A. Provide dielectric couplings or unions between pipe of dissimilar metals.

#### 2.9 STERILIZATION CHEMICALS

- A. Hypochlorite: ASTM E1229.
- B. Liquid Chlorine: ASTM E1120.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

05-01-21

#### 2.10 WATER HAMMER ARRESTER (NOT USED)

#### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. General: Comply with the International Plumbing Code and the following:
  - Install branch piping for water from the piping system and connect to all fixtures, valves, cocks, outlets, casework, cabinets and equipment, including those furnished by the Government or specified in other sections.
  - 2. Pipe shall be round and straight. Cutting shall be done with proper tools. Pipe, except for plastic and glass, shall be reamed to remove burrs and a clean smooth finish restored to full pipe inside diameter.
  - 3. All pipe runs shall be laid out to avoid interference with other work/trades.
  - 4. Install union and shut-off valve on pressure piping at connections to equipment.
  - 5. Pipe Hangers, Supports and Accessories:
    - a. All piping shall be supported per the IPC, H-18-8 Seismic Design Handbook, MSS SP-58, and SMACNA as required.
    - b. Shop Painting and Plating: Hangers, supports, rods, inserts and accessories used for pipe supports shall be shop coated with zinc chromate primer paint. Electroplated copper hanger rods, hangers and accessories may be used with copper tubing.
    - c. Floor, Wall and Ceiling Plates, Supports, Hangers:
      - 1) Solid or split un-plated cast iron.
      - 2) All plates shall be provided with set screws.
      - 3) Pipe Hangers: Height adjustable clevis type.
      - 4) Adjustable Floor Rests and Base Flanges: Steel.
      - 5) Concrete Inserts: "Universal" or continuous slotted type.
      - 6) Hanger Rods: Mild, low carbon steel, fully threaded or
        Threaded at each end with two removable nuts at each end for
        positioning rod and hanger and locking each in place.
      - 7) Pipe Hangers and Riser Clamps: Malleable iron or carbon steel.

        Pipe Hangers and riser clamps shall have a copper finish when
        supporting bare copper pipe or tubing.
      - 8) Rollers: Cast iron.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

05-01-21

- 9) Self-drilling type expansion shields shall be "Phillips" type, with case hardened steel expander plugs.
- 10) Hangers and supports utilized with insulated pipe and tubing shall have 180-degree (minimum) metal protection shield centered on and welded to the hanger and support. The shield thickness and length shall be engineered and sized for distribution of loads to preclude crushing of insulation without breaking the vapor barrier. The shield shall be sized for the insulation and have flared edges to protect vapor-retardant jacket facing. To prevent the shield from sliding out of the clevis hanger during pipe movement, centerribbed shields shall be used.
- 11) Miscellaneous Materials: As specified, required, directed or as noted on the drawings for proper installation of hangers, supports and accessories. If the vertical distance exceeds 6.1 m (20 feet) for cast iron pipe additional support shall be provided in the center of that span. Provide all necessary auxiliary steel to provide that support.
- 12) With the installation of each flexible expansion joint, provide piping restraints for the upstream and downstream section of the piping at the flexible expansion joint. Provide calculations supporting the restraint length design and type of selected restraints. Restraint calculations shall be based on the criteria from the manufacturer regarding their restraint design.
- 6. Install chrome plated cast brass escutcheon with set screw at each wall, floor and ceiling penetration in exposed finished locations and within cabinets and millwork.

#### 7. Penetrations:

a. Firestopping: Where pipes pass through fire partitions, fire walls, smoke partitions, or floors, install a fire stop that provides an effective barrier against the spread of fire, smoke, and gases as specified in Section 07 84 00, FIRESTOPPING.
Completely fill and seal clearances between raceways and openings with the firestopping materials.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

05-01-21

- b. Waterproofing: At floor penetrations, completely seal clearances around the pipe and make watertight with sealant as specified in Section 07 92 00, JOINT SEALANTS. Bio-based materials shall be utilized when possible.
- c. Acoustical sealant: Where pipes pass through sound rated walls, seal around the pipe penetration with an acoustical sealant that is compliant with ASTM C919.
- B. Domestic Water piping shall conform to the following:
  - 1. Grade all lines to facilitate drainage. Provide drain valves at bottom of risers and all low points in system. Design domestic hot and cold water circulating lines with no traps.
  - 2. Connect branch lines at bottom of main serving fixtures below and pitch down so that main may be drained through fixture. Connect branch lines to top of main serving only fixtures located on floor above.

#### 3.2 TESTS

- A. General: Test system either in its entirety or in sections. Submit testing plan to COR 10 working days prior to test date.
- B. Potable Water System: Test after installation of piping and domestic water heaters, but before piping is concealed, before covering is applied, and before plumbing fixtures are connected. Fill systems with water and maintain hydrostatic pressure of 1035 kPa (150 psig) gage for two hours. No decrease in pressure is allowed. Provide a pressure gage with a shutoff and bleeder valve at the highest point of the piping being tested. Pressure gauge shall have 1 psig increments.
- C. Re-agent Grade Water Systems: Fill system with water and maintain hydrostatic pressure of 1380 kPa (200 psig) gage during inspection and prove tight.
- D. All Other Piping Tests: Test new installed piping under 1-1/2 times actual operating conditions and prove tight.
- E. The test pressure shall hold for the minimum time duration required by the applicable plumbing code or authority having jurisdiction.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

05-01-21

#### 3.3 STERILIZATION

- A. After tests have been successfully completed, thoroughly flush and sterilize the interior domestic water distribution system in accordance with AWWA C651.
- B. Use liquid chlorine or hypochlorite for sterilization.

## 3.4 COMMISSIONING (NOT USED)

#### 3.5 DEMONSTRATION AND TRAINING

A. Provide services of manufacturer's technical representative for four hours to instruct VA Personnel in operation and maintenance of the system.

- - - E N D - - -

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

# SECTION 22 13 00 FACILITY SANITARY AND VENT PIPING

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section pertains to sanitary sewer and vent systems, including piping, equipment and all necessary accessories as designated in this section.
- B. A complete listing of common acronyms and abbreviations are included in Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

#### 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- C. Section 01 81 13, SUSTAINABLE CONSTRUCTION REQUIREMENTS.
- D. Section 07 84 00, FIRESTOPPING: Penetrations in rated enclosures.
- E. Section 07 92 00, JOINT SEALANTS: Sealant products.
- F. Section 09 91 00, PAINTING: Preparation and finish painting and identification of piping systems.
- G. Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING: Pipe Hangers and Supports, Materials Identification.
- H. Section 22 07 11, PLUMBING INSULATION.
- I. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS
- J. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

#### 1.3 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only. Where conflicts occur these specifications and the VHA standard will govern.
- B. American Society of Mechanical Engineers (ASME):

ALD.I-ZUU/	A13.1-2007	Identification	of	Pipina	System
------------	------------	----------------	----	--------	--------

A112.36.2M-1991......Cleanouts

A112.6.3-2019......Floor and Trench Drains

B1.20.1-2013......Pipe Threads, General Purpose (Inch)

B16.1-2015......Gray Iron Pipe Flanges and Flanged Fittings
Classes 25, 125, and 250

B16.4-2016......Grey Iron Threaded Fittings Classes 125 and 250

B16.15-2018......Cast Copper Alloy Threaded Fittings, Classes

125 and 250

B16.18-2018......Cast Copper Alloy Solder Joint Pressure

Fittings

B16.21-2016.....Nonmetallic Flat Gaskets for Pipe Flanges

B16.22-2018.....Wrought Copper and Copper Alloy Solder-Joint

Pressure Fittings

B16.23-2016.....Cast Copper Alloy Solder Joint Drainage

Fittings: DWV

B16.24-2016.....Cast Copper Alloy Pipe Flanges and Flanged

Fittings, and Valves: Classes 150, 300, 600,

900, 1500, and 2500

B16.29-2017......Wrought Copper and Wrought Copper Alloy Solder-

Joint Drainage Fittings: DWV

B16.39-2014.....Malleable Iron Threaded Pipe Unions Classes

150, 250, and 300

B18.2.1-2012.....Square, Hex, Heavy Hex, and Askew Head Bolts

and Hex, Heavy Hex, Hex Flange, Lobed Head, and

Lag Screws (Inch Series)

C. American Society of Sanitary Engineers (ASSE):

1001-2017......Performance Requirements for Atmospheric Type

Vacuum Breakers

Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

02/17/2022

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

	Bancro	It Architects + Engineers
	1018-2001	.Performance Requirements for Trap Seal Primer
		Valves - Potable Water Supplied
	1044-2015	Performance Requirements for Trap Seal Primer
		Devices - Drainage Types and Electronic Design
		Types
	1079-2012	Performance Requirements for Dielectric Pipe
		Unions
D.	American Society for Tes	sting and Materials (ASTM):
	A53/A53M-2018	Standard Specification for Pipe, Steel, Black
		And Hot-Dipped, Zinc-coated, Welded and
		Seamless
	A74-2017	Standard Specification for Cast Iron Soil Pipe
		and Fittings
	A888-2018a	Standard Specification for Hubless Cast Iron
		Soil Pipe and Fittings for Sanitary and Storm
		Drain, Waste, and Vent Piping Applications
	B32-2008 (R2014)	Standard Specification for Solder Metal
	в43-2015	Standard Specification for Seamless Red Brass
		Pipe, Standard Sizes
	В88-2016	Standard Specification for Seamless Copper
		Water Tube
	В306-2013	Standard Specification for Copper Drainage Tube
		(DWV)
	B687-1999 (R2016)	Standard Specification for Brass, Copper, and
		Chromium-Plated Pipe Nipples
	B813-2016	Standard Specification for Liquid and Paste
		Fluxes for Soldering of Copper and Copper Alloy
		Tube
	B828-2016	Standard Practice for Making Capillary Joints
		by Soldering of Copper and Copper Alloy Tube
		and Fittings
	C564-2014	Standard Specification for Rubber Gaskets for
		Cast Iron Soil Pipe and Fittings
	D2321-2018	Standard Practice for Underground Installation
		of Thermoplastic Pipe for Sewers and Other
		Gravity-Flow Applications

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

	Bancro	09-01-20			
	D2564-2012(R3018)	.Standard Specification for Solvent Cements for			
		Poly(Vinyl Chloride) (PVC) Plastic Piping			
		Systems			
	D2665-2014	.Standard Specification for Poly(Vinyl Chloride)			
		(PVC) Plastic Drain, Waste, and Vent Pipe and			
		Fittings			
	D2855-2015Standard Practice for Two-Step (Primer and				
		Solvent Cement) Method of Joining Poly(Vinyl			
		Chloride) (PVC) or Chlorinated Poly (Vinyl			
		Chloride) CPVCP Pipe and Piping Components with			
		Tapered Sockets			
	D5926-2015	.Standard Specification for Poly(Vinyl Chloride)			
		(PVC) Gaskets for Drain, Waste, and Vent (DWV),			
		Sewer, Sanitary, and Storm Plumbing Systems			
	F402-2018	.Standard Practice for Safe Handling of Solvent			
		Cements, Primers, and Cleaners Used for Joining			
		Thermoplastic Pipe and Fittings			
	F477-2014	.Standard Specification for Elastomeric Seals			
		(Gaskets) for Joining Plastic Pipe			
	F1545-2015e1	.Standard Specification for Plastic-Lined			
		Ferrous Metal Pipe, Fittings, and Flanges			
Ε.	E. Cast Iron Soil Pipe Institute (CISPI):				
	2006Cast Iron Soil Pipe and Fittings Handbook				
	301-2012	.Standard Specification for Hubless Cast Iron			
		Soil Pipe and Fittings for Sanitary and Storm			
		Drain, Waste, and Vent Piping Applications			
	310-2012	.Specification for Coupling for Use in			
		Connection with Hubless Cast Iron Soil Pipe and			
		Fittings for Sanitary and Storm Drain, Waste,			
		and Vent Piping Applications			
F.	Copper Development Asso	ciation, Inc. (CDA):			
	A4015-14/19	.Copper Tube Handbook			
G.	International Code Coun	cil (ICC):			
	IPC-2018	.International Plumbing Code			

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- $\ensuremath{\mathsf{H.}}$  Manufacturers Standardization Society (MSS):
  - SP-123-2018......Non-Ferrous Threaded and Solder-Joint Unions for Use with Copper Water Tube
- I. National Fire Protection Association (NFPA):

70-2020......National Electrical Code (NEC)

J. Underwriters' Laboratories, Inc. (UL):

508-99 (R2013)......Standard For Industrial Control Equipment

#### 1.4 SUBMITTALS

- A. Submittals, including number of required copies, shall be submitted in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Information and material submitted under this section shall be marked "SUBMITTED UNDER SECTION 22 13 00, FACILITY SANITARY AND VENT PIPING", with applicable paragraph identification.
- C. Manufacturer's Literature and Data including: Full item description and optional features and accessories. Include dimensions, weights, materials, applications, standard compliance, model numbers, size, and capacity.
  - 1. Piping.
  - 2. Floor Drains.
  - 3. Grease Removal Unit.
  - 4. Cleanouts.
  - 5. Trap Seal Protection.
  - 6. Penetration Sleeves.
  - 7. Pipe Fittings.
  - 8. Traps.
  - 9. Exposed Piping and Fittings.
- D. Detailed shop drawing of clamping device and extensions when required in connection with the waterproofing membrane or the floor drain.
- E. Complete operating and maintenance manuals including wiring diagrams, technical data sheets, information for ordering replaceable parts, and troubleshooting guide:
  - 1. Include complete list indicating all components of the systems.
  - 2. Include complete diagrams of the internal wiring for each item of equipment.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

3. Diagrams shall have their terminals identified to facilitate installation, operation and maintenance.

#### 1.5 QUALITY ASSURANCE

- A. Bio-Based Materials: For products designated by the USDA's bio-based Bio-Preferred Program, provide products that meet or exceed USDA recommendations for bio-based content, so long as products meet all performance requirements in this specifications section. For more information regarding the product categories covered by the Bio-Preferred Program, visit http://www.biopreferred.gov.
- B. Refer to Section 01 81 13, SUSTAINABLE CONSTRUCTION REQUIREMENTS for additional sustainable design requirements.

#### 1.6 AS-BUILT DOCUMENTATION

A. Comply with requirements in Paragraph "AS-BUILT DOCUMENTATION" of Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

#### PART 2 - PRODUCTS

## 2.1 SANITARY WASTE, DRAIN, AND VENT PIPING

- A. Cast iron waste, drain, and vent pipe and fittings.
  - 1. Cast iron waste, drain, and vent pipe and fittings shall be used for the following applications:
    - a. Pipe buried in or in contact with earth.
    - b. Sanitary pipe extensions to a distance of approximately 1500 mm (5 feet) outside of the building.
    - c. Interior waste and vent piping above grade.
  - 2. Cast iron Pipe shall be bell and spigot or hubless (plain end or no-hub or hubless).
  - 3. The material for all pipe and fittings shall be cast iron soil pipe and fittings and shall conform to the requirements of CISPI 301, ASTM A888, or ASTM A74.
  - 4. Cast iron pipe and fittings shall be made from a minimum of 95 percent post-consumer recycled material.
  - 5. Joints for hubless pipe and fittings shall conform to the manufacturer's installation instructions. Couplings for hubless joints shall conform to CISPI 310. Joints for hub and spigot pipe shall be installed with compression gaskets conforming to the requirements of ASTM C564.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- B. Copper Tube, (DWV):
  - 1. Copper DWV tube sanitary waste, drain and vent pipe may be used for piping above ground, except for urinal drains.
  - 2. The copper DWV tube shall be drainage type, drawn temper conforming to ASTM B306.
  - 3. The copper drainage fittings shall be cast copper or wrought copper conforming to ASME B16.23 or ASME B16.29.
  - 4. The joints shall be lead free, using a water flushable flux, and conforming to ASTM B32.
- 2.2 PUMP DISCHARGE PIPING (NOT USED)
- 2.3 EXPOSED WASTE PIPING (NOT USED)
- 2.4 SPECIALTY PIPE FITTINGS (NOT USED)
- 2.5 CLEANOUTS (NOT USED)
- 2.6 FLOOR DRAINS (NOT USED)
- 2.7 TRAPS (NOT USED)
- 2.8 PRIMER VALVES AND TRAP SEAL PRIMER SYSTEMS (NOT USED)

#### 2.9 PENETRATION SLEEVES

A. A sleeve flashing device shall be provided at points where pipes pass through membrane waterproofed floors or walls. The sleeve flashing device shall be manufactured, cast iron fitting with clamping device that forms a sleeve for the pipe floor penetration of the floor membrane. A galvanized steel pipe extension shall be included in the top of the fitting that shall extend 50 mm (2 inches) above finished floor and galvanized steel pipe extension in the bottom of the fitting that shall extend through the floor slab. A waterproof caulked joint shall be provided at the top hub.

#### PART 3 - EXECUTION

## 3.1 PIPE INSTALLATION

- A. The pipe installation shall comply with the requirements of the International Plumbing Code (IPC) and these specifications.
- B. Branch piping shall be installed for waste from the respective piping systems and connect to all fixtures, valves, cocks, outlets, casework, cabinets and equipment, including those furnished by the Government or specified in other sections.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- C. Pipe shall be round and straight. Cutting shall be done with proper tools. Pipe shall be reamed to full size after cutting.
- D. All pipe runs shall be laid out to avoid interference with other work.
- E. The piping shall be installed above accessible ceilings where possible.
- F. The piping shall be installed to permit valve servicing or operation.
- G. The piping shall be installed free of sags and bends.
- H. Seismic restraint shall be installed where required by code.
- I. Changes in direction for soil and waste drainage and vent piping shall be made using appropriate branches, bends and long sweep bends.

  Sanitary tees and short sweep quarter bends may be used on vertical stacks if change in direction of flow is from horizontal to vertical. Long turn double wye branch and eighth bend fittings shall be used if two fixtures are installed back to back or side by side with common drain pipe. Straight tees, elbows, and crosses may be used on vent lines. Do not change direction of flow greater than 90 degrees. Proper size of standard increaser and reducers shall be used if pipes of different sizes are connected. Reducing size of drainage piping in direction of flow is prohibited.
- J. Buried soil and waste drainage and vent piping shall be laid beginning at the low point of each system. Piping shall be installed true to grades and alignment indicated with unbroken continuity of invert. Hub ends shall be placed upstream. Required gaskets shall be installed according to manufacturer's written instruction for use of lubricants, cements, and other installation requirements.
- K. Cast iron piping shall be installed according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings"
- L. Aboveground copper tubing shall be installed according to Copper Development Association's (CDA) "Copper Tube Handbook".
- M. If an installation is unsatisfactory to the COR, the Contractor shall correct the installation at no additional cost or time to the Government.

#### 3.2 JOINT CONSTRUCTION

A. Hub and spigot, cast iron piping with gasket joints shall be joined in accordance with CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for compression joints.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- B. Hub and spigot, cast iron piping with calked joints shall be joined in accordance with CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for lead and oakum calked joints.
- C. Hubless or No-hub, cast iron piping shall be joined in accordance with CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hubless piping coupling joints.
- D. For threaded joints, thread pipe with tapered pipe threads according to ASME B1.20.1. The threads shall be cut full and clean using sharp disc cutters. Threaded pipe ends shall be reamed to remove burns and restored to full pipe inside diameter. Pipe fittings and valves shall be joined as follows:
  - 1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is required by the pipe service.
  - 2. Pipe sections with damaged threads shall be replaced with new sections of pipe.
- E. Copper tube and fittings with soldered joints shall be joined according to ASTM B828. A water flushable, lead free flux conforming to ASTM B813 and a lead-free alloy solder conforming to ASTM B32 shall be used.

#### 3.3 SPECIALTY PIPE FITTINGS

- A. Transition coupling shall be installed at pipe joints with small differences in pipe outside diameters.
- B. Dielectric fittings shall be installed at connections of dissimilar metal piping and tubing.

#### 3.4 PIPE HANGERS, SUPPORTS AND ACCESSORIES

- A. All piping shall be supported according to the International Plumbing Code (IPC), Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING, and these specifications. Where conflicts arise between these the code and Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING the most restrictive or the requirement that specifies supports with highest loading or shortest spacing shall apply.
- B. Hangers, supports, rods, inserts and accessories used for pipe supports shall be painted according to Section 09 91 00, PAINTING. Electroplated copper hanger rods, hangers and accessories may be used with copper tubing.
- C. Horizontal piping and tubing shall be supported within 300 mm (12 inches) of each fitting or coupling.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- D. Horizontal cast iron piping shall be supported with the following maximum horizontal spacing and minimum hanger rod diameters:
  - 1. 40 mm or DN40 to 50 mm or DN50 (NPS 1-1/2 inch to NPS 2 inch): 1500 mm (60 inches) with 10 mm (3/8 inch) rod.
  - 2. 75 mm or DN75 (NPS 3 inch): 1500 mm (60 inches) with 15 mm (1/2 inch) rod.
  - 3. 100 mm or DN100 to 125 mm or DN125 (NPS 4 inch to NPS 5 inch): 1500 mm (60 inches) with 18 mm (5/8 inch) rod.
  - 4. 150 mm or DN150 to 200 mm or DN200 (NPS 6 inch to NPS 8 inch): 1500 mm (60 inches) with 20 mm (3/4 inch) rod.
  - 5. 250 mm or DN250 to 300 mm or DN300 (NPS 10 inch to NPS 12 inch): 1500 mm (60 inch) with 23 mm (7/8 inch) rod.
- E. Vertical piping and tubing shall be supported at the base, at each floor, and at intervals no greater than 4.6 m (15 feet).
- F. In addition to the requirements in Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING, Floor, Wall and Ceiling Plates, Supports, Hangers shall have the following characteristics:
  - 1. Solid or split unplated cast iron.
  - 2. All plates shall be provided with set screws.
  - 3. Height adjustable clevis type pipe hangers.
  - 4. Adjustable floor rests and base flanges shall be steel.
  - 5. Hanger rods shall be low carbon steel, fully threaded or threaded at each end with two removable nuts at each end for positioning rod and hanger and locking each in place.
  - 6. Riser clamps shall be malleable iron or steel.
  - 7. Rollers shall be cast iron.
  - 8. See Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING, for requirements on insulated pipe protective shields at hanger supports.
- G. Miscellaneous materials shall be provided as specified, required, directed or as noted in the contract documents for proper installation of hangers, supports and accessories. If the vertical distance exceeds 6.1 m (20 feet) for cast iron pipe additional support shall be provided in the center of that span. All necessary auxiliary steel shall be provided to provide that support.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

H. Cast escutcheon with set screw shall be provided at each wall, floor and ceiling penetration in exposed finished locations and within cabinets and millwork.

#### I. Penetrations:

- 1. Fire Stopping: Where pipes pass through fire partitions, fire walls, smoke partitions, or floors, a fire stop shall be installed that provides an effective barrier against the spread of fire, smoke and gases as specified in Section 07 84 00, FIRESTOPPING. Clearances between raceways and openings shall be completely filled and sealed with the fire stopping materials.
- 2. Water proofing: At floor penetrations, clearances shall be completely sealed around the pipe and make watertight with sealant as specified in Section 07 92 00, JOINT SEALANTS.
- J. Exhaust vents shall be extended separately through roof. Sanitary vents shall not connect to exhaust vents.

#### 3.5 TESTS

- A. Sanitary waste and drain systems shall be tested either in its entirety or in sections.
- B. Waste System tests shall be conducted before trenches are backfilled or fixtures are connected. A water test or air test shall be conducted, as directed.
  - 1. If entire system is tested for a water test, tightly close all openings in pipes except highest opening, and fill system with water to point of overflow. If the waste system is tested in sections, tightly plug each opening except highest opening of section under test, fill each section with water and test with at least a 3 m (10 foot) head of water. In testing successive sections, test at least upper 3 m (10 feet) of next preceding section so that each joint or pipe except upper most 3 m (10 feet) of system has been submitted to a test of at least a 3 m (10 foot) head of water. Water shall be kept in the system, or in portion under test, for at least 15 minutes before inspection starts. System shall then be tight at all joints.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- 2. For an air test, an air pressure of 34 kPa (5 psig) gauge shall be maintained for at least 15 minutes without leakage. A force pump and mercury column gauge shall be used for the air test.
- 3. After installing all fixtures and equipment, open water supply so that all p-traps can be observed. For 15 minutes of operation, all p-traps shall be inspected for leaks and any leaks found shall be corrected.
- 4. Final Tests: Either one of the following tests may be used.
  - a. Smoke Test: After fixtures are permanently connected and traps are filled with water, fill entire drainage and vent systems with smoke under pressure of .25 kPa (1 inch of water) with a smoke machine. Chemical smoke is prohibited.
  - b. Peppermint Test: Introduce 60 ml (2 ounces) of peppermint into each line or stack.

## 3.6 COMMISSIONING (NOT USED)

## 3.7 DEMONSTRATION AND TRAINING

A. Provide services of manufacturer's technical representative for 4hours to instruct each VA personnel responsible in operation and maintenance of the system.

- - - E N D - - -

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

# SECTION 22 34 00 FUEL-FIRED DOMESTIC WATER HEATERS

## PART 1 - GENERAL

#### 1.1 DESCRIPTION

A. This section describes the requirements for installing a complete gas fired domestic water heating system ready for operation including water heaters, thermometers, and all necessary accessories, connections, and equipment.

A complete listing of common acronyms and abbreviations are included in Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

#### 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- C. Section 01 81 13, SUSTAINABLE CONSTRUCTION REQUIREMENTS.
- D. Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

## 1.3 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only. Where conflicts occur these specifications and the VHA standards will govern.
- B. American National Standard Institute (ANSI):

Z21.10.1-2019	er Hea	aters,	Volume	I,	Storage	Wate	er
Heaters	with	Input	Ratings	of	75,000	Btu	per
Hour or	Less						

Z21.10.3-2019Gas-Fired Water	Heaters,	Volume III, Storage
Water Heaters w	with Input	Ratings Above 75,000
Btu per Hour, C	Circulatino	g and Instantaneous

Z21.15-2009 (R2014)	.Manually	Operated	Gas	Valves	s for	r App	oliar	ices,
	Appliance	Connecto	r Va	alves a	and I	Hose	End	Valves

Z21.18-2019	Gas	Appliance	Pressure	Regulators

Z21.20-2005 (R2016) Automatic Gas Ignition Systems and Component	Z21.20-2005 (	(R2016)	Automatic G	Gas Ignition	Svstems	and C	Components
--	---------------	---------	-------------	--------------	---------	-------	------------

Z21.21-2019.....Automatic Valves for Gas Appliances

Z21.22-2015......Relief Valves for Hot Water Supply Systems

Z21.66-2015......Automatic Damper Devices for Use with Gas-Fired Appliances

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

20

	Danciole Alemitects - Engineers	1 _ 2 0
C.	American Society of Heating, Refrigerating and Air-Conditioning	1-20
	Engineers (ASHRAE):	
	90.1-2019Energy Standard for Buildings Except Low-Rise	€
	Residential Buildings	
D.	American Society of Mechanical Engineers (ASME):	
	ASME Boiler and Pressure Vessel Code -	
	BPVC Section IV-2019Rules for Construction of Heating Boilers	
	BPVC Section VIII-1-2019 Rules for Construction of Pressure	
	Vessels, Division 1	
	Form U-1Manufacturer's Data Report for Pressure Vesse	els
	B1.20.1-2013Pipe Threads, General Purpose (Inch)	
	B1.20.7-1991	
	B16.5-2017Pipe Flanges and Flanged Fittings: NPS 1/2	
	through NPS 24 Metric/Inch Standard	
	B16.24-2016Cast Copper Alloy Pipe Flanges, Flanged	
	Fittings, and Valves: Classes 150, 300, 600,	
	900, 1500, and 2500	
	CSD-1-2018Controls and Safety Devices for Automatically	?
	Fired Boilers	
Ε.	National Electrical Manufacturers Association (NEMA):	
	ICS 6-1993 (R2016)Industrial Control and Systems: Enclosures	
F.	National Fire Protection Association (NFPA):	
	54-2018National Fuel Gas Code	
	70-2020National Electrical Code (NEC)	
G.	NSF International (NSF):	
	5-2019Water Heaters, Hot Water Supply Boilers, and	
	Heat Recovery Equipment	
	61-2018Drinking Water System Components - Health	
	Effects	
	372-2016Drinking Water System Components - Lead Conte	∍nt
Н.	Underwriters Laboratories, Inc. (UL):	
	429-2013 (R2020) Standard for Electrically Operated Valves	
	795-2016Standard for Commercial-Industrial Gas Heating	ıg
	Equipment	

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

#### 1.4 SUBMITTALS

- A. Submittals, including number of required copies, shall be submitted in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Information and material submitted under this section shall be marked "SUBMITTED UNDER SECTION 22 34 00, FUEL-FIRED DOMESTIC WATER HEATERS", with applicable paragraph identification.
- C. Manufacturer's Literature and Data Including: Full item description and optional features and accessories. Include dimensions, weights, materials, applications, standard compliance, model numbers, size, and capacity.
  - 1. Water Heaters.
  - 2. Pressure and Temperature Relief Valves.
  - 3. Thermometers.
  - 4. Pressure Gauges.
  - 5. Vacuum Breakers.
  - 6. Expansion Tanks.
  - 7. Heat Traps.
  - 8. Gas Shut-off Valves.
  - 9. Motorized Gas Valves.
  - 10. Gas Pressure Regulators.
  - 11. Manifold Kits.
- D. For each gas fired domestic hot water heater type and size, the following characteristics shall be submitted:
  - 1. Rated Capacities
  - 2. Operating characteristics
  - 3. Electrical characteristics
  - 4. Furnished specialties and accessories
  - 5. A Form U-1 or other documentation stating compliance with the ASME Boiler and Pressure Vessel Code.
- E. Shop drawings shall include wiring diagrams for power, signal and control functions.
- F. Submit documentation indicating compliance with applicable requirements of ASHRAE 90.1 or Energy Star for Service Water Heating.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- G. Complete operating and maintenance manuals including wiring diagrams, technical data sheets, information for ordering replaceable parts, and troubleshooting guide:
  - 1. Include complete list indicating all components of the systems.
  - 2. Include complete diagrams of the internal wiring for each item of equipment.
  - 3. Diagrams shall have their terminals identified to facilitate installation, operation and maintenance.

#### 1.5 QUALITY ASSURANCE

- A. Gas water heaters up to 530 liters (140 gallons) are covered under the FEMP and the ENERGY STAR program. Federal laws and executive orders mandate the purchase of gas water heaters that meet or exceed the ENERGY STAR listed minimum efficiency. Comply with American Society of Heating, Refrigerating and Air- Conditioning Engineers (ASHRAE) for efficiency performance ASHRAE 90.1, "Energy Efficient Design of New Buildings Except Low-Rise Residential Buildings for commercial water heaters."
- B. Electrical components, devices and accessories shall be listed and labeled as defined in NFPA 70 by a qualified testing agency and marked for intended location and application.
- C. ASME code construction shall be a vessel fabricated in compliance with the ASME BPVC Section VIII-1.
- D. Fabricate and label equipment components that will be in contact with potable water to comply with NSF 61 and NSF 372.
- E. The domestic water heater shall be certified and labeled by an independent testing agency.
- F. Bio-Based Materials: For products designated by the USDA's Bio-Preferred Program, provide products that meet or exceed USDA recommendations for bio-based content, so long as products meet all performance requirements in this specifications section. For more information regarding the product categories covered by the Bio-Preferred Program, visit https://www.biopreferred.gov.
- G. Refer to Section 01 81 13, SUSTAINABLE CONSTRUCTION REQUIREMENTS for additional sustainable design requirements.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

#### 1.6 AS-BUILT DOCUMENTATION

A. Comply with requirements in Paragraph AS-BUILT DOCUMENTATION of Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

## PART 2 - PRODUCTS

## 2.1 ATMOSPHERIC, GAS FIRED, STORAGE DOMESTIC WATER HEATERS

- A. The gas fired domestic water heater shall comply with ANSI Z21.10.1. Provide with access for cleaning and disinfection.
- B. The water heater design shall provide a minimum combustion efficiency of 95 percent at operating conditions. Water heater capacities are scheduled on the drawings.
- C. The tank construction shall be ASME BPVC Section VIII-1, steel, glass lined, fabricated with a pressure rating of 1034 kPa (150 psig). Tank shall comply with NSF 61 and NSF 372 for barrier materials for potablewater tank linings.
- D. The tappings (openings) shall be factory-fabricated of materials compatible with the tank and in accordance with appropriate ASME standards for piping connections, pressure and temperature relief valve, pressure gauge, thermometer, drain valve, anode and controls. The tappings shall be in accordance with ASME standards listed below:
  - 1. 50 mm or DN50 (NPS 2 inch) and smaller: Threaded ends according to ASME B1.20.1.
  - 2. 65 mm or DN65 (NPS 2-1/2 inch) and larger: Flanged ends according to ASME B16.5 for steel and stainless-steel flanges, and according to ASME B16.24.
- E. The gas fired burner shall include the following:
  - 1. Thermostatically adjustable.
  - 2. High temperature limit and low water cutoff devices for safety controls.
  - 3. Automatic ignition in accordance with ANSI Z21.20.
  - 4. Automatic damper in accordance with ANSI Z21.66. The automatic dampers shall be electrically operated, automatic vent damper device with size matching draft hood for 300,000 BTUH and below.
- F. Temperature setting shall be set for a minimum water temperature of 60 degrees C (140 degrees F). The temperature setting shall be adjustable. Heaters shall be capable of raising the discharge temperature to 77 to 82 degrees C (170 to 180 degrees F) for thermal eradication.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- G. The insulation shall surround the entire storage tank except connection and controls and shall comply with ASHRAE 90.1.
- H. The jacket shall be steel with enameled finish.
- I. The drain valve shall be corrosion resistant metal. A drain valve shall be installed at the bottom of each tank-type water heater and hot water storage tank. The drain valve inlet shall not be less than 20 mm or DN20 (NPS 3/4 inch) with ASME B1.20.7 garden hose threads.
- J. The combination pressure and temperature relief valve shall be ANSI Z21.22 rated and constructed of all brass or bronze with a self-closing reseating valve.
- K. Special Requirements: NSF 5 construction.
- 2.2 POWER VENT, GAS FIRED, STORAGE DOMESTIC WATER HEATERS (NOT USED)
- 2.3 CONDENSING, GAS FIRED, STORAGE DOMESTIC WATER HEATERS (NOT USED)
- 2.4 CONDENSING, GAS FIRED, SEMI-INSTANTANEOUS DOMESTIC WATER HEATERS (NOT USED)
- 2.5 GAS-FIRED, TANKLESS, DOMESTIC-WATER HEATERS (NOT USED)

#### 2.6 DOMESTIC HOT WATER EXPANSION TANKS

- A. A steel pressure rated tank constructed with welded joints and factory installed butyl rubber diaphragm shall be installed as scheduled. The air precharge shall be set to minimum system operating pressure at tank.
- B. The tappings shall be factory-fabricated steel, welded to the tank and include ASME B1.20.1 pipe thread.
- C. The interior finish shall comply with NSF 61 and NSF 372 barrier materials for potable water tank linings and the liner shall extend into and through the tank fittings and outlets.
- D. The air charging valve shall be factory installed.

## 2.7 HEAT TRAPS

A. Heat traps shall be installed in accordance with ASHRAE 90.1 if not provided integral with the heater.

#### 2.8 COMBINATION TEMPERATURE AND PRESSURE RELIEF VALVES

A. The combination pressure and temperature relief valve shall be ANSI Z21.22 and ASME rated and constructed of all brass or bronze with a self-closing reseating valve. The relief valves shall include a relieving capacity greater than the heat input and include a pressure

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

setting less than the water heater's working pressure rating. Sensing element shall extend into storage tank.

#### 2.9 GAS SHUTOFF VALVES

A. The gas shutoff valve shall be manually operated with proof of closure conforming to ANSI Z21.15.

#### 2.10 MOTORIZED GAS VALVES

- A. Automatic Gas Valves: Comply with ANSI Z21.21 and shall have the following characteristics:
  - 1. Body: Brass or aluminum.
  - 2. Seats and Disc: Nitrile rubber.
  - 3. Springs and Valve Trim: Stainless-steel.
  - 4. Normally closed.
  - 5. Visual position indicator.
  - 6. Electrical operator for actuation by appliance automatic shutoff device.
- B. Electrically Operated Valves: Comply with UL 429 and shall have the following characteristics:
  - 1. Pilot operated.
  - 2. Body: Brass or aluminum.
  - 3. Seats and Disc: Nitrile rubber.
  - 4. Springs and Valve Trim: Stainless-steel.
  - 5. 120-V ac, 60 Hz, Class B, continuous-duty molded coil, and replaceable.
  - 6. NEMA ICS 6, Type 4, coil enclosure.
  - 7. Normally closed.
  - 8. Visual position indicator.

#### 2.11 GAS PRESSURE REGULATORS

A. The gas pressure regulator shall be appliance type, pressure rating matching inlet gas supply temperature, and conforming to ANSI Z21.18.

## 2.12 AUTOMATIC GAS VALVES

A. Each water heater shall incorporate dual over-temperature protection with manual reset, in accordance with ASME BPVC Section IV and ASME CSD-1. The automatic gas valves shall be appliance type, electrically operated, on-off automatic control, and conforming to ANSI Z21.21.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

#### 2.13 THERMOMETERS

A. Thermometers shall be rigid stem or remote sensing, scale or dial type with an aluminum, black metal, stainless-steel, or chromium plated brass case. The thermometer shall be back connected, red liquid (alcohol or organic-based) fill, vapor, bi-metal or gas actuated, with 228 mm (9 inches) high scale dial or circular dial 50 to 127 mm (2 to 5 inches) in diameter graduated from 4 to 100 degrees C (40 to 212 degrees F), with two-degree graduations guaranteed accurate within one scale division. The socket shall be separable, double-seat, micrometer-fittings, with extension neck not less than 63 mm (2-1/2 inches) to clear tank or pipe covering. The thermometer shall be suitable for 19 mm (3/4 inch) pipe threads. Thermometers may be console-mounted with sensor installed in separate thermometer well.

#### 2.14 SUPPORTS

- A. Water heater stands shall be factory-fabricated steel for floor mounting capable of supporting water heater and water a minimum of 457 mm (18 inches) above the floor.
- B. Wall brackets for wall mounted heaters shall be factory-fabricated steel capable of supporting water heater and water.

## 2.15 MANIFOLD KITS

A. For multiple water heater installation, provide factory-fabricated copper manifold kits to include ball-type shutoff valves to isolate each water heater and balancing valves to provide balanced flow through each water heater.

## PART 3 - EXECUTION

## 3.1 INSTALLATION

- A. If an installation is unsatisfactory to the COR, the contractor shall correct the installation at no additional cost or time to the Government.
- B. The water heaters shall be installed on concrete bases unless elevated above the floor. Refer to Section 03 30 00, CAST-IN-PLACE CONCRETE and Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.
- C. The water heaters shall be installed level and plumb and securely anchored.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

- D. The water heaters shall be installed and connected in accordance with manufacturer's written instructions with manufacturer's recommended clearances.
- E. All pressure and temperature relief valves discharge shall be piped to a nearby floor drains with air gap or break.
- F. Thermometers shall be installed on the water heater inlet and outlet piping and shall be positioned such that they can be read by an operator or staff standing on floor or walkway.
- G. Vent piping from gas-train pressure regulators and valves shall be piped to the outside of building and shall conform to NFPA 54.
- H. The thermostatic control shall be set for a minimum setting of 60 degrees C (140 degrees F) for storage heaters.
- I. Shutoff valves shall be installed on the domestic water supply piping to the water heater and on the domestic hot water outlet piping.
- J. All manufacturer's required clearances shall be maintained.
- K. A combination temperature and pressure relief valve shall be installed at the top portion of the storage tank in accordance with manufacturer's recommendations. The sensing element shall extend into the tank. The relief valve outlet drain piping shall discharge by air gap into a floor drain.
- L. Piping type heat traps shall be installed on the inlet and outlet piping of the domestic water heater storage tanks, unless provided integrally with the tanks.
- M. Water heater drain piping shall be installed as indirect waste to spill by air gap into open drains or over floor drains. Hose end drain valves shall be installed at low points in water piping for gas fueled domestic hot water heaters without integral drains.
- N. The type B galvanized or stainless-steel combustion vent shall be installed and sized according to the water heaters recommendations and extended through the roof or wall as allows by the local fuel gas code or NFPA 54. Install vents for condensing heaters in accordance with manufacturer's recommendations.
- O. Dielectric unions shall be provided if there are dissimilar metals between the water heater connections and the attached piping.
- P. Provide vacuum breakers per ANSI Z21.22 on the inlet pipe if the water heater is bottom fed.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-01-20

#### 3.2 LEAKAGE TEST

A. Before piping connections are made, the water heaters shall be tested at a hydrostatic pressure of 1380 kPa (200 psig) and 1654 kPa (240 psig) for a unit with a MAWP of 1104 kPa (160 psig). If any leakage is found on the water heater, the water heater shall be replaced with a new unit at no additional cost to the VA.

#### 3.3 PERFORMANCE TEST

A. Ensure that all the remote water outlets are always tested to a minimum of 43 degrees C (110 degrees F) and a maximum of 49 degrees C (120 degrees F) water flow.

## 3.4 STARTUP AND TESTING


- A. Perform tests as recommended by product manufacturer and listed standards and under actual or simulated operating conditions and prove full compliance with design and specified requirements. Tests of the various items of equipment shall be performed simultaneously with the system of which each item is an integral part.
- B. The tests shall include system capacity, control function, and alarm functions.
- C. When any defects are detected, correct defects and repeat test at no additional cost or time to the Government.

#### 3.5 COMMISSIONING (NOT USED)

## 3.6 DEMONSTRATION AND TRAINING

A. Provide services of manufacturer's technical representative for 4hours to instruct each VA personnel responsible in operation and maintenance of the system.

- - - E N D - - -



## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

## SECTION 23 05 11 COMMON WORK RESULTS FOR HVAC

## PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. The requirements of this Section apply to all sections of Division 23.
- B. Definitions:
  - 1. Exposed: Piping, ductwork, and equipment exposed to view in finished rooms.
  - 2. Exterior: Piping, ductwork, and equipment exposed to weather be it temperature, humidity, precipitation, wind, or solar radiation.
- C. Abbreviations/Acronyms:
  - 1. ac: Alternating Current
  - 2. AC: Air Conditioning
  - 3. ACU: Air Conditioning Unit
  - 4. ACR: Air Conditioning and Refrigeration
  - 5. AI: Analog Input
  - 6. AISI: American Iron and Steel Institute
  - 7. AO: Analog Output
  - 8. ASJ: All Service Jacket
  - 9. AWG: American Wire Gauge
  - 10. BACnet: Building Automation and Control Networking Protocol
  - 11. BAg: Silver-Copper-Zinc Brazing Alloy
  - 12. BAS: Building Automation System
  - 13. BCuP: Silver-Copper-Phosphorus Brazing Alloy
  - 14. bhp: Brake Horsepower
  - 15. Btu: British Thermal Unit
  - 16. Btu/h: British Thermal Unit Per Hour
  - 17. CDA: Copper Development Association
  - 18. C: Celsius
  - 19. CD: Compact Disk
  - 20. CFM: Cubic Foot Per Minute
  - 21. CH: Chilled Water Supply
  - 22. CHR: Chilled Water Return
  - 23. CLR: Color
  - 24. CO: Carbon Monoxide
  - 25. COR: Contracting Officer's Representative

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- 26. CPD: Condensate Pump Discharge
- 27. CPM: Cycles Per Minute
- 28. CPVC: Chlorinated Polyvinyl Chloride
- 29. CRS: Corrosion Resistant Steel
- 30. CTPD: Condensate Transfer Pump Discharge
- 31. CTPS: Condensate Transfer Pump Suction
- 32. CW: Cold Water
- 33. CWP: Cold Working Pressure
- 34. CxA: Commissioning Agent
- 35. dB: Decibels
- 36. dB(A): Decibels (A weighted)
- 37. DDC: Direct Digital Control
- 38. DI: Digital Input
- 39. DO: Digital Output
- 40. DVD: Digital Video Disc
- 41. DN: Diameter Nominal
- 42. DWV: Drainage, Waste and Vent
- 43. EPDM: Ethylene Propylene Diene Monomer
- 44. EPT: Ethylene Propylene Terpolymer
- 45. ETO: Ethylene Oxide
- 46. F: Fahrenheit
- 47. FAR: Federal Acquisition Regulations
- 48. FD: Floor Drain
- 49. FED: Federal
- 50. FG: Fiberglass
- 51. FGR: Flue Gas Recirculation
- 52. FOS: Fuel Oil Supply
- 53. FOR: Fuel Oil Return
- 54. FSK: Foil-Scrim-Kraft facing
- 55. FWPD: Feedwater Pump Discharge
- 56. FWPS: Feedwater Pump Suction
- 57. GC: Chilled Glycol Water Supply
- 58. GCR: Chilled Glycol Water Return
- 59. GH: Hot Glycol Water Heating Supply
- 60. GHR: Hot Glycol Water Heating Return
- 61. gpm: Gallons Per Minute

Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121 02-01-20

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

62. HDPE: High Density Polyethylene

- 63. Hg: Mercury
- 64. HOA: Hands-Off-Automatic
- 65. hp: Horsepower
- 66. HPS: High Pressure Steam (414 kPa (60 psig) and above)
- 67. HPR: High Pressure Steam Condensate Return
- 68. HW: Hot Water
- 69. HWH: Hot Water Heating Supply
- 70. HWHR: Hot Water Heating Return
- 71. Hz: Hertz
- 72. ID: Inside Diameter
- 73. IPS: Iron Pipe Size
- 74. kg: Kilogram
- 75. klb: 1000 lb
- 76. kPa: Kilopascal
- 77. lb: Pound
- 78. lb/hr: Pounds Per Hour
- 79. L/s: Liters Per Second
- 80. L/min: Liters Per Minute
- 81. LPS: Low Pressure Steam (103 kPa (15 psig) and below)
- 82. LPR: Low Pressure Steam Condensate Gravity Return
- 83. MAWP: Maximum Allowable Working Pressure
- 84. MAX: Maximum
- 85. MBtu/h: 1000 Btu/h
- 86. MBtu: 1000 Btu
- 87. MED: Medical
- 88. m: Meter
- 89. MFG: Manufacturer
- 90. mg: Milligram
- 91. mg/L: Milligrams Per Liter
- 92. MIN: Minimum
- 93. MJ: Megajoules
- 94. ml: Milliliter
- 95. mm: Millimeter
- 96. MPS: Medium Pressure Steam (110 kPa (16 psig) through 414 kPa (60 psig))

Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121 02-01-20

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- 97. MPR: Medium Pressure Steam Condensate Return
- 98. MW: Megawatt
- 99. NC: Normally Closed
- 100. NF: Oil Free Dry (Nitrogen)
- 101. Nm: Newton Meter
- 102. NO: Normally Open
- 103. NOx: Nitrous Oxide
- 104. NPT: National Pipe Thread
- 105. NPS: Nominal Pipe Size
- 106. OD: Outside Diameter
- 107. OSD: Open Sight Drain
- 108. OS&Y: Outside Stem and Yoke
- 109. PC: Pumped Condensate
- 110. PID: Proportional-Integral-Differential
- 111. PLC: Programmable Logic Controllers
- 112. PP: Polypropylene
- 113. PPE: Personal Protection Equipment
- 114. ppb: Parts Per Billion
- 115. ppm: Parts Per Million
- 116. PRV: Pressure Reducing Valve
- 117. PSIA: Pounds Per Square Inch Absolute
- 118. psig: Pounds Per Square Inch Gauge
- 119. PTFE: Polytetrafluoroethylene
- 120. PVC: Polyvinyl Chloride
- 121. PVDC: Polyvinylidene Chloride Vapor Retarder Jacketing, White
- 122. PVDF: Polyvinylidene Fluoride
- 123. rad: Radians
- 124. RH: Relative Humidity
- 125. RO: Reverse Osmosis
- 126. rms: Root Mean Square
- 127. RPM: Revolutions Per Minute
- 128. RS: Refrigerant Suction
- 129. RTD: Resistance Temperature Detectors
- 130. RTRF: Reinforced Thermosetting Resin Fittings
- 131. RTRP: Reinforced Thermosetting Resin Pipe
- 132. SCFM: Standard Cubic Feet Per Minute

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- 133. SPEC: Specification
- 134. SPS: Sterile Processing Services
- 135. STD: Standard
- 136. SDR: Standard Dimension Ratio
- 137. SUS: Saybolt Universal Second
- 138. SW: Soft water
- 139. SWP: Steam Working Pressure
- 140. TAB: Testing, Adjusting, and Balancing
- 141. TDH: Total Dynamic Head
- 142. TEFC: Totally Enclosed Fan-Cooled
- 143. TFE: Tetrafluoroethylene
- 144. THERM: 100,000 Btu
- 145. THHN: Thermoplastic High-Heat Resistant Nylon Coated Wire
- 146. THWN: Thermoplastic Heat & Water-Resistant Nylon Coated Wire
- 147. T/P: Temperature and Pressure
- 148. USDA: U.S. Department of Agriculture
- 149. V: Volt
- 150. VAC: Vacuum
- 151. VA: Veterans Administration
- 152. VAC: Voltage in Alternating Current
- 153. VA CFM: VA Construction & Facilities Management
- 154. VA CFM CSS: VA Construction & Facilities Management, Consulting Support Service
- 155. VAMC: Veterans Administration Medical Center
- 156. VHA OCAMES: Veterans Health Administration Office of Capital Asset Management Engineering and Support
- 157. VR: Vacuum condensate return
- 158. WCB: Wrought Carbon Steel, Grade B
- 159. WG: Water Gauge or Water Column
- 160. WOG: Water, Oil, Gas

# 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- C. Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT.
- D. Section 05 50 00, METAL FABRICATIONS.
- E. Section 07 84 00, FIRESTOPPING.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- F. Section 07 92 00, JOINT SEALANTS.
- G. Section 09 91 00, PAINTING.
- H. Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING and EQUIPMENT.
- I. Section 23 82 00, CONVECTION HEATING AND COOLING UNITS.
- J. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.
- K. Section 26 05 19, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES.
- L. Section 26 29 11, MOTOR CONTROLLERS.

#### 1.3 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only. Where conflicts occur these specifications and the VHA standard will govern.
- B. Air Movement and Control Association (AMCA): 410-1996.............Recommended Safety Practices for Users and Installers of Industrial and Commercial Fans
- C. American Society of Mechanical Engineers (ASME):

B31.1-2018.....Power Piping

B31.9-2014.....Building Services Piping

ASME Boiler and Pressure Vessel Code:

BPVC Section IX-2019 Welding, Brazing, and Fusing Qualifications

- D. American Society for Testing and Materials (ASTM):
  - A36/A36M-2014......Standard Specification for Carbon Structural Steel
  - A575-1996(R2018)......Standard Specification for Steel Bars, Carbon,

    Merchant Quality, M-Grades
- ${\tt E.}$  Association for Rubber Products Manufacturers (ARPM):

  - IP-24-2016......Specifications for Drives Using Synchronous Belts
  - IP-27-2015.....Specifications for Drives Using Curvilinear
    Toothed Synchronous Belts

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

F. Manufacturers Standardization Society (MSS) of the Valve and Fittings
Industry, Inc.:

SP-58-2018............Pipe Hangers and Supports-Materials, Design,
Manufacture, Selection, Application, and
Installation

SP-127-2014a.......Bracing for Piping Systems: Seismic-WindDynamic Design, Selection, and Application

G. Military Specifications (MIL):
MIL-P-21035B-2013......Paint High Zinc Dust Content, Galvanizing
Repair (Metric)

H. National Fire Protection Association (NFPA):
70-201..........National Electrical Code (NEC)
101-2018.............National Electrical Code
I. Department of Veterans Affairs (VA):
PG-18-10-2016........Physical Security and Resiliency Design Manual

#### 1.4 SUBMITTALS

- A. Submittals, including number of required copies, shall be submitted in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Information and material submitted under this section shall be marked "SUBMITTED UNDER SECTION 23 05 11, COMMON WORK RESULTS FOR HVAC", with applicable paragraph identification.
- C. Contractor shall make all necessary field measurements and investigations to assure that the equipment and assemblies will meet contract requirements, and all equipment that requires regular maintenance, calibration, etc are accessable from the floor or permanent work platform. It is the Contractor's responsibility to ensure all submittals meet the VA specifications and requirements and it is assumed by the VA that all submittals do meet the VA specifications unless the Contractor has requested a variance in writing and approved by COR prior to the submittal. If at any time during the project it is found that any item does not meet the VA specifications and there was no variance approval the Contractor shall correct at no additional cost or time to the Government even if a submittal was approved.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- D. If equipment is submitted which differs in arrangement from that shown, provide documentation proving equivalent performance, design standards and drawings that show the rearrangement of all associated systems. Additionally, any impacts on ancillary equipment or services such as foundations, piping, and electrical shall be the Contractor's responsibility to design, supply, and install at no additional cost or time to the Government. VA approval will be given only if all features of the equipment and associated systems, including accessibility, are equivalent to that required by the contract.
- E. Prior to submitting shop drawings for approval, Contractor shall certify in writing that manufacturers of all major items of equipment have each reviewed contract documents, and have jointly coordinated and properly integrated their equipment and controls to provide a complete and efficient installation.
- F. Submittals and shop drawings for interdependent items, containing applicable descriptive information, shall be furnished together.

  Coordinate and properly integrate materials and equipment to provide a completely compatible and efficient installation.
- G. Mock-ups: Mock-ups are required for critical items and typical component installations replicated numerous times throughout the project as indicated in the individual Division 23 sections. The COR and VAMC representatives shall review and approve the mock-up prior to installation of additional applicable components.
- H. Coordination/Shop Drawings:
  - 1. Submit complete consolidated and coordinated shop drawings for all new systems, and for existing systems that are in the same areas.
  - 2. The coordination/shop drawings shall include plan views, elevations and sections of all systems and shall be on a scale of not less than 1:32 (3/8-inch equal to one foot). Clearly identify and dimension the proposed locations of the principal items of equipment. The drawings shall clearly show locations and adequate clearance for all equipment, piping, valves, control panels and other items. Show the access means for all items requiring access for operations and maintenance. Provide detailed coordination/shop

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

drawings of all piping and duct systems. The drawings should include all lockout/tagout points for all energy/hazard sources for each piece of equipment. Coordinate lockout/tagout procedures and practices with local VA requirements.

- 3. Do not install equipment foundations, equipment or piping until coordination/shop drawings have been approved.
- 4. In addition, for HVAC systems, provide details of the following:
- a. Mechanical equipment rooms.
- b. Hangers, inserts, supports, and bracing.
- c. Pipe sleeves.
- d. Duct or equipment penetrations of floors, walls, ceilings, or roofs.
- I. Manufacturer's Literature and Data: Include full item description and optional features and accessories. Include dimensions, weights, materials, applications, standard compliance, model numbers, size, and capacity. Submit under the pertinent section rather than under this section.
  - 1. Submit belt drive with the driven equipment. Submit selection data for specific drives when requested by the COR.
  - 2. Submit electric motor data and variable speed drive data with the driven equipment.
  - 3. Equipment and materials identification.
  - 4. Fire-stopping materials.
  - 5. Hangers, inserts, supports and bracing. Provide complete stress analysis for variable spring and constant support hangers.
  - 6. Wall, floor, and ceiling plates.
- J. Rigging Plan: Provide documentation of the capacity and weight of the rigging and equipment intended to be used. The plan shall include the path of travel of the load, the staging area and intended access, and qualifications of the operator and signal person.
- K. HVAC Maintenance Data and Operating Instructions:
  - Maintenance and operating manuals in accordance with Section 01 00 00, GENERAL REQUIREMENTS, Article, INSTRUCTIONS, for systems and equipment.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- 2. Complete operating and maintenance manuals including wiring diagrams, technical data sheets, information for ordering replacement parts, and troubleshooting guide:
- a. Include complete list indicating all components of the systems.
- b. Include complete diagrams of the internal wiring for each item of equipment.
- c. Diagrams shall have their terminals identified to facilitate installation, operation and maintenance.
- 3. Provide a listing of recommended replacement parts for keeping in stock supply, including sources of supply, for equipment. Include in the listing belts for equipment: Belt manufacturer, model number, size and style, and distinguished whether of multiple belt sets.
- L. Provide copies of approved HVAC equipment submittals to the TAB Subcontractor.

## 1.5 QUALITY ASSURANCE

- A. Mechanical, electrical and associated systems shall be safe, reliable, efficient, durable, easily and safely operable and maintainable, easily and safely accessible, and in compliance with applicable codes as specified. The systems shall be comprised of high quality institutional-class and industrial-class products of manufacturers that are experienced specialists in the required product lines. All construction firms and personnel shall be experienced and qualified specialists in industrial and institutional HVAC.
- B. Flow Rate Tolerance for HVAC Equipment: Section 23 05 93, TESTING, ADJUSTING, AND BALANCING FOR HVAC.
- C. Equipment Vibration Tolerance:
  - 1. Refer to Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING and EQUIPMENT. Equipment shall be factory-balanced to this tolerance and re-balanced on site, as necessary.
  - 2. After HVAC air balance work is completed and permanent drive sheaves are in place, perform field mechanical balancing and adjustments required to meet the specified vibration tolerance.
- D. Products Criteria:
  - 1. Standard Products: Material and equipment shall be the standard products of a manufacturer regularly engaged in the manufacture of

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

the products for at least 3 years (or longer as specified elsewhere). The design, model and size of each item shall have been in satisfactory and efficient operation on at least three installations for approximately three years. However, digital electronics devices, software and systems such as controls, instruments, computer work station, shall be the current generation of technology and basic design that has a proven satisfactory service record of at least three years. See other specification sections for any exceptions and/or additional requirements.

- 2. Refer to all other sections for quality assurance requirements for systems and equipment specified therein.
- 3. All items furnished shall be free from defects that would adversely affect the performance, maintainability and appearance of individual components and overall assembly.
- 4. The products and execution of work specified in Division 33 shall conform to the referenced codes and standards as required by the specifications. Local codes and amendments shall be enforced, along with requirements of local utility companies. The most stringent requirements of these specifications, local codes, or utility company requirements shall always apply. Any conflicts shall be brought to the attention of the COR.
- 5. Multiple Units: When two or more units of materials or equipment of the same type or class are required, these units shall be of the same manufacturer and model number, or if different models are required they shall be of the same manufacturer and identical to the greatest extent possible (i.e., same model series).
- 6. Assembled Units: Performance and warranty of all components that make up an assembled unit shall be the responsibility of the manufacturer of the completed assembly.
- 7. Nameplates: Nameplate bearing manufacturer's name or identifiable trademark shall be securely affixed in a conspicuous place on equipment, or name or trademark cast integrally with equipment, stamped or otherwise permanently marked on each item of equipment.
- 8. Use of asbestos products or equipment or materials containing asbestos is prohibited.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- E. HVAC Equipment Service Providers: Service providers shall be authorized and trained by the manufacturers of the equipment supplied. These providers shall be capable of responding onsite and provide acceptable service to restore equipment operations within 4 hours of receipt of notification by phone, e-mail or fax in event of an emergency, such as the shutdown of equipment; or within 24 hours in a non-emergency. Submit names, mail and e-mail addresses and phone numbers of service personnel and companies providing service under these conditions for (as applicable to the project): fans, air handling units, chillers, cooling towers, control systems, pumps, critical instrumentation, computer workstation and programming.
- F. HVAC Mechanical Systems Welding: Before any welding is performed, Contractor shall submit a certificate certifying that welders comply with the following requirements:
  - 1. Qualify welding processes and operators for piping according to ASME BPVC Section IX. Provide proof of current certification.
  - 2. Comply with provisions of ASME B31 series "Code for Pressure Piping".
  - 3. Certify that each welder and welding operator has passed American Welding Society (AWS) qualification tests for the welding processes involved, and that certification is current.
  - 4. All welds shall be stamped according to the provisions of the AWS or ASME as required herein and by the associated code.
- G. Manufacturer's Recommendations: Where installation procedures or any part thereof are required to be in accordance with the recommendations of the manufacturer of the material being installed, printed copies of these recommendations shall be furnished to the COR with submittals. Installation of the item will not be allowed to proceed until the recommendations are received. Failure to furnish these recommendations can be cause for rejection of the material and removal by the Contractor and no additional cost or time to the Government.
- H. Execution (Installation, Construction) Quality:
  - Apply and install all items in accordance with manufacturer's written instructions. Refer conflicts between the manufacturer's instructions and the contract documents to the COR for resolution. Provide written hard copies and computer files on CD or DVD of

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

manufacturer's installation instructions to the COR with submittals prior to commencing installation of any item. Installation of the item will not be allowed to proceed until the recommendations are received and approved by the VA. Failure to furnish these recommendations is a cause for rejection of the material.

- 2. All items that require access, such as for operating, cleaning, servicing, maintenance, and calibration, shall be easily and safely accessible by persons standing at floor level, or standing on permanent platforms, without the use of portable ladders. Examples of these items include, but are not limited to, all types of valves, filters and strainers, transmitters, control devices. Prior to commencing installation work, refer conflicts between this requirement and contract documents to the COR for resolution. Failure of the Contractor to resolve, or point out any issues will result in the Contractor correcting at no additional cost or time to the Government.
- 3. Complete coordination/shop drawings shall be required in accordance with Article, SUBMITTALS. Construction work shall not start on any system until the coordination/shop drawings have been approved by VA.
- 4. Workmanship/craftsmanship will be of the highest quality and standards. The VA reserves the right to reject any work based on poor quality of workmanship this work shall be removed and done again at no additional cost or time to the Government.
- I. Upon request by Government, provide lists of previous installations for selected items of equipment. Include contact persons who will serve as references, with current telephone numbers and e-mail addresses.
- J. Guaranty: Warranty of Construction, FAR Clause 52.246-21.

## 1.6 DELIVERY, STORAGE AND HANDLING

- A. Protection of Equipment:
  - 1. Equipment and material placed on the job site shall remain in the custody of the Contractor until phased acceptance, whether or not the Government has reimbursed the Contractor for the equipment and material. The Contractor is solely responsible for the protection of such equipment and material against any damage or theft.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- 2. Large equipment such as boilers, chillers, cooling towers, fans, and air handling units if shipped on open trailer trucks shall be covered with shrink on plastics or water proof tarpaulins that provide protection from exposure to rain, road salts and other transit hazards. Protection shall be kept in place until equipment is moved into a building or installed as designed.
- 3. Repair damaged equipment in first class, new operating condition and appearance; or, replace same as determined and directed by the COR. Such repair or replacement shall be at no additional cost or time to the Government.
- 4. Protect interiors of new equipment and piping systems against entry of foreign matter. Clean both inside and outside before painting or placing equipment in operation.
- 5. Existing equipment and piping being worked on by the Contractor shall be under the custody and responsibility of the Contractor and shall be protected as required for new work.
- 6. Protect plastic piping and tanks from ultraviolet light (sunlight).
- B. Cleanliness of Piping and Equipment Systems:
  - Exercise care in storage and handling of equipment and piping material to be incorporated in the work. Remove debris arising from cutting, threading and welding of piping.
  - 2. Piping systems shall be flushed, blown or pigged as necessary to deliver clean systems.
  - 3. Clean interior of all tanks prior to delivery for beneficial use by the Government.
  - 4. Boilers shall be left clean following final internal inspection by Government insurance representative or inspector.
  - 5. Contractor shall be fully responsible for all costs, damage, and delay arising from failure to provide clean systems.

#### 1.7 AS-BUILT DOCUMENTATION

- A. Submit manufacturer's literature and data updated to include submittal review comments and any equipment substitutions.
- $\hbox{B. Submit operation and maintenance data updated to include submittal} \\ \hbox{review comments, VA approved substitutions and construction revisions} \\$

shall be in electronic version on CD or DVD inserted into a three-ring Contract No. 36C26319D0044

Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

binder. All aspects of system operation and maintenance procedures, including applicable piping isometrics, wiring diagrams of all circuits, a written description of system design, control logic, and sequence of operation shall be included in the operation and maintenance manual. The operations and maintenance manual shall include troubleshooting techniques and procedures for emergency situations.

Notes on all special systems or devices shall be included. A List of recommended spare parts (manufacturer, model number, and quantity) shall be furnished. Information explaining any special knowledge or tools the owner will be required to employ shall be inserted into the As-Built documentation.

- C. The installing Contractor shall maintain as-built drawings of each completed phase for verification; and, shall provide the complete set at the time of final systems certification testing. Should the installing Contractor engage the testing company to provide as-built or any portion thereof, it shall not be deemed a conflict of interest or breach of the 'third party testing company' requirement. Provide record drawings as follows:
  - Red-lined, hand-marked drawings are to be provided, with one paper copy and a scanned PDF version of the hand-marked drawings provided on CD or DVD.
  - 2. As-built drawings are to be provided, with a copy of them on AutoCAD version 2019 provided on CD or DVD. The CAD drawings shall use multiple line layers with a separate individual layer for each system.
- D. The as-built drawings shall indicate the location and type of all lockout/tagout points for all energy sources for all equipment and pumps to include breaker location and numbers, valve tag numbers, etc. Coordinate lockout/tagout procedures and practices with local VA requirements.
- E. Certification documentation shall be provided to COR 21 working days prior to submitting the request for final inspection. The documentation shall include all test results, the names of individuals performing work for the testing agency on this project, detailed procedures followed for all tests, and provide documentation/certification that

all results of tests were within limits specified. Test results shall Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121 02/17/2022

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

contain written sequence of test procedure with written test results annotated at each step along with the expected outcome or setpoint. The results shall include all readings, including but not limited to data on device (make, model and performance characteristics\_), normal pressures, switch ranges, trip points, amp readings, and calibration data to include equipment serial numbers or individual identifications, etc.

#### 1.8 JOB CONDITIONS - WORK IN EXISTING BUILDING

- A. Building Operation: Government employees will be continuously operating and managing all facilities, including temporary facilities that serve the VAMC.
- B. Maintenance of Service: Schedule all work to permit continuous service as required by the VAMC.
- C. Steam and Condensate Service Interruptions: Limited steam and condensate service interruptions, as required for interconnections of new and existing systems, will be permitted by the COR during periods when the demands are not critical to the operation of the VAMC. These non-critical periods are limited to between 8 pm and 5 am in the appropriate off-season (if applicable). Provide at least 10 working days advance notice to the COR. The request shall include a detailed plan on the proposed shutdown and the intended work to be done along with manpower levels. All equipment and materials must be onsite and verified with plan 5 days prior to the shutdown or it will need to be rescheduled.
- D. Building Working Environment: Maintain the architectural and structural integrity of the building and the working environment at all times.

  Maintain the interior of building at 18 degrees C (65 degrees F)

  minimum. Limit the opening of doors, windows or other access openings to brief periods as necessary for rigging purposes. Storm water or ground water leakage is prohibited. Provide daily clean-up of construction and demolition debris on all floor surfaces and on all equipment being operated by VA. Maintain all egress routes and safety systems/devices.
- E. Acceptance of Work for Government Operation: As new equipment, systems and facilities are made available for operation and these items are deemed of beneficial use to the Government, inspections will be made

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

and tests will be performed. Based on the inspections, a list of contract deficiencies will be issued to the Contractor. After correction of deficiencies as necessary for beneficial use, the Contracting Officer will process necessary acceptance and the equipment will then be under the control and operation of Government personnel.

## PART 2 - PRODUCTS

#### 2.1 FACTORY-ASSEMBLED PRODUCTS

- A. Provide maximum standardization of components to reduce spare part requirements.
- B. Performance and warranty of all components that make up an assembled unit shall be the responsibility of the manufacturer of the completed assembly.
  - 1. All components of an assembled unit need not be products of same manufacturer.
  - 2. Constituent parts that are alike shall be products of a single manufacturer.
  - 3. Components shall be compatible with each other and with the total assembly for intended service.
  - 4. Contractor shall guarantee performance of assemblies of components, and shall repair or replace elements of the assemblies as required to deliver specified performance of the complete assembly.
- C. Equipment and components of equipment shall bear manufacturer's name and trademark, model number, serial number and performance data on a nameplate securely affixed in a conspicuous place, or cast integral with, stamped or otherwise permanently marked upon the components of the equipment.
- D. Major items of equipment, which serve the same function, must be the same make and model. Exceptions must be approved by the VA, but may be permitted if performance requirements cannot be met.

## 2.2 COMPATIBILITY OF RELATED EQUIPMENT

A. Equipment and materials installed shall be compatible in all respects with other items being furnished and with existing items so that the result will be a complete and fully operational plant that conforms to contract requirements.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

#### 2.3 V-BELT DRIVES (NOT USED)

- 2.4 SYNCHRONOUS BELT DRIVES (NOT USED)
- 2.5 DRIVE GUARDS (NOT USED)

## 2.6 LIFTING ATTACHMENTS

A. Provide equipment with suitable lifting attachments to enable equipment to be lifted in its normal position. Lifting attachments shall withstand any handling conditions that might be encountered, without bending or distortion of shape, such as rapid lowering and braking of load.

#### 2.7 ELECTRIC MOTORS

A. All material and equipment furnished and installation methods shall conform to the requirements of Section 23 05 12, GENERAL MOTOR REQUIREMENTS FOR HVAC AND STEAM GENERATION EQUIPMENT; Section 26 29 11, MOTOR CONTROLLERS; and, Section 26 05 19, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES. Provide all electrical wiring, conduit, and devices necessary for the proper connection, protection and operation of the systems. Provide special energy efficient premium efficiency type motors as scheduled.

## 2.8 VARIABLE SPEED MOTOR CONTROLLERS

- A. Refer to Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS and Section 26 29 11, MOTOR CONTROLLERS for specifications.
- B. Coordinate variable speed motor controller communication protocol with Section 23 09 23, DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC.
- C. Provide variable speed motor controllers with or without a bypass contactor as indicated in contract drawings.
- D. The combination of controller and motor shall be provided by the manufacturer of the driven equipment, such as pumps and fans, and shall be rated for 100 percent output performance. Multiple units of the same class of equipment, i.e. air handlers, fans, pumps, shall be product of a single manufacturer.
- E. Motors shall be premium efficiency type and be approved by the motor controller manufacturer. The controller-motor combination shall be guaranteed to provide full motor nameplate horsepower in variable frequency operation. Both driving and driven motor/fan sheaves shall be fixed pitch.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

F. Controller shall not add any current or voltage transients to the input ac power distribution system, DDC controls, sensitive medical equipment, etc., nor shall be affected from other devices on the ac power system.

#### 2.9 EQUIPMENT AND MATERIALS IDENTIFICATION

- A. Use symbols, nomenclature and equipment numbers specified, shown on the contract documents and shown in the maintenance manuals. Identification for piping is specified in Section 09 91 00, PAINTING.
- B. Use symbols, nomenclature and equipment numbers specified, shown on the contract documents and shown in the maintenance manuals. In addition, provide bar code identification nameplate for all equipment which will allow the equipment identification code to be scanned into the system for maintenance and inventory tracking. Identification for piping is specified in Section 09 91 00, PAINTING.
- C. Interior (Indoor) Equipment: Engraved nameplates, with letters not less than 5 mm (3/16 inch) high of brass with black-filled letters, or rigid black plastic with white letters specified in Section 09 91 00, PAINTING permanently fastened to the equipment. Identify unit components such as coils, filters, fans, etc.
- D. Exterior (Outdoor) Equipment: Brass nameplates, with engraved black filled letters, not less than 5 mm (3/16 inch) high riveted or bolted to the equipment.
- E. Control Items: Label all instrumentation, temperature and humidity sensors, controllers and control dampers. Identify and label each item as they appear on the control diagrams.
- F. Valve Tags and Lists:
  - HVAC and Mechanical Rooms: Provide for all valves other than for equipment in Section 23 82 00, CONVECTION HEATING AND COOLING UNITS and Section 23 36 00, AIR TERMNAL UNITS.
  - 2. Valve tags: Engraved black filled numbers and letters not less than 15 mm (1/2 inch) high for number designation, and not less than 6 mm (1/4 inch) for service designation on 19-gauge 40 mm (1-1/2 inches) round brass disc, attached with brass "S" hook or brass chain.
- 3. Valve lists: Typed or printed plastic coated card(s), sized 215 mm (8-1/2 inches) by 275 mm (11 inches) showing tag number, valve Contract No. 36C26319D0044 Station Project No. 568A4-21-703

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- function and area of control, for each service or system. Punch sheets for a 3-ring notebook.
- 4. Provide detailed plan for each floor of the building indicating the location and valve number for each valve. Identify location of each valve with a color-coded thumb tack in ceiling.

#### G. Ceiling Grid Labels:

- 1. 50 mm (2 inch) long by 15 mm (1/2 inch) wide by 0.025 mm (1 mil) thick UV resistant metalized polyester label with red border color and black custom lettering on white background interior. Peel and stick adhesive backing. Label and adhesive manufactured specifically for use in equipment inventory tagging.
- 2. Custom print labels with above ceiling HVAC equipment numbers.

#### 2.10 FIRESTOPPING

A. Section 07 84 00, FIRESTOPPING specifies an effective barrier against the spread of fire, smoke and gases where penetrations occur for piping and ductwork. Refer to Section 23 07 11, HVAC AND BOILER PLANT INSULATION, for firestop pipe and duct insulation.

#### 2.11 GALVANIZED REPAIR COMPOUND

A. Mil-P-21035B, paint form.

## 2.12 HVAC PIPE AND EQUIPMENT SUPPORTS AND RESTRAINTS

- A. Vibration Isolators: Refer to Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EQUIPMENT.
- B. Supports for Roof Mounted Items:
  - 1. Equipment: Equipment rails shall be galvanized steel, minimum 1.3 mm (18 gauge), with integral baseplate, continuous welded corner seams, factory installed 50 by 100 mm (2 by 4 inches) treated wood nailer, 1.3 mm (18 gauge) galvanized steel counter flashing cap with screws, built-in cant strip, (except for gypsum or tectum deck), minimum height 275 mm (11 inches). For surface insulated roof deck, provide raised cant strip to start at the upper surface of the insulation.
  - 2. Pipe/duct pedestals: Provide a galvanized Unistrut channel welded to U-shaped mounting brackets which are secured to side of rail with galvanized lag bolts.
- C. Pipe Supports: Comply with MSS SP-58. Type Numbers specified refer to this standard. For selection and application comply with MSS SP-58.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

Refer to Section 05 50 00, METAL FABRICATIONS, for miscellaneous metal support materials and prime coat painting requirements.

- D. Attachment to Concrete Building Construction:
  - 1. Concrete insert: MSS SP-58, Type 18.
  - 2. Self-drilling expansion shields and machine bolt expansion anchors: Permitted in concrete not less than 100 mm (4 inches) thick when approved by the COR for each job condition.
  - 3. Power-driven fasteners: Permitted in existing concrete or masonry not less than 100 mm (4 inches) thick when approved by the COR for each job condition.
- E. Attachment to Steel Building Construction:
  - 1. Welded attachment: MSS SP-58, Type 22.
  - 2. Beam clamps: MSS SP-58, Types 20, 21, 28 or 29. Type 23 C-clamp may be used for individual copper tubing up to 23 mm (7/8 inch) outside diameter.
- F. Attachment to existing structure: Support from existing floor/roof frame.
- G. Attachment to Wood Construction: Wood screws or lag bolts.
- H. Hanger Rods: Hot-rolled steel, ASTM A36/A36M or ASTM A575 for allowable load listed in MSS SP-58. For piping, provide adjustment means for controlling level or slope. Types 13 or 15 turn-buckles shall provide 40 mm (1-1/2 inches) minimum of adjustment and incorporate locknuts. All-thread rods are acceptable.
- I. Hangers Supporting Multiple Pipes (Trapeze Hangers): Galvanized, cold formed, lipped steel channel horizontal member, not less than 41 mm by 41 mm (1-5/8 inches by 1-5/8 inches), 2.7 mm (12 gauge), designed to accept special spring held, hardened steel nuts. Trapeze hangers are prohibited for use for steam supply and condensate piping.
  - Allowable hanger load: Manufacturers rating less 91 kg (200 pounds).
  - 2. Guide individual pipes on the horizontal member of every other trapeze hanger with 6 mm (1/4 inch) U-bolt fabricated from steel rod. Provide Type 40 insulation shield, secured by two 15 mm (1/2 inch) galvanized steel bands, or preinsulated calcium silicate shield for insulated piping at each hanger.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- J. Supports for Piping Systems:
  - 1. Select hangers sized to encircle insulation on insulated piping. Refer to Section 23 07 11, HVAC AND BOILER PLANT INSULATION for insulation thickness. To protect insulation, provide Type 39 saddles for roller type supports or preinsulated calcium silicate shields. Provide Type 40 insulation shield or preinsulated calcium silicate shield at all other types of supports and hangers including those for preinsulated piping.
  - 2. Piping Systems except High and Medium Pressure Steam (MSS SP-58):
  - a. Standard clevis hanger: Type 1; provide locknut.
  - b. Riser clamps: Type 8.
  - c. Wall brackets: Types 31, 32 or 33.
  - d. Roller supports: Type 41, 43, 44 and 46.
  - e. Saddle support: Type 36, 37 or 38.
  - f. Turnbuckle: Types 13 or 15. Preinsulate.
  - g. U-bolt clamp: Type 24.
  - h. Copper Tube:
    - Hangers, clamps and other support material in contact with tubing shall be painted with copper colored epoxy paint, plastic coated or taped with non-adhesive isolation tape to prevent electrolysis.
    - 2) For vertical runs use epoxy painted or plastic-coated riser clamps.
    - 3) For supporting tube to strut: Provide epoxy painted pipe straps for copper tube or plastic inserted vibration isolation clamps.
    - 4) Insulated Lines: Provide pre-insulated calcium silicate shields sized for copper tube.
  - i. Supports for plastic piping: As recommended by the pipe manufacturer with black rubber tape extending one inch beyond steel support or clamp.
  - 3. High and Medium Pressure Steam (MSS SP-58):
  - a. Provide eye rod or Type 17 eye nut near the upper attachment.
  - b. Piping 50 mm (2 inches) and larger: Type 43 roller hanger. For roller hangers requiring seismic bracing provide a Type 1 clevis hanger with Type 41 roller attached by flat side bars.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- c. Piping with Vertical Expansion and Contraction:
  - 1) Movement up to 20 mm (3/4 inch): Type 51 or 52 variable spring unit with integral turn buckle and load indicator.
  - 2) Movement more than 20 mm (3/4 inch): Type 54 or 55 constant support unit with integral adjusting nut, turn buckle and travel position indicator.
- 4. Convertor and Expansion Tank Hangers: May be Type 1 sized for the shell diameter. Insulation where required will cover the hangers.

#### 2.13 PIPE PENETRATIONS

- A. Install sleeves during construction for other than blocked out floor openings for risers in mechanical bays.
- B. To prevent accidental liquid spills from passing to a lower level, provide the following:
  - 1. For sleeves: Extend sleeve 25 mm (1 inch) above finished floor and provide sealant for watertight joint.
  - 2. For blocked out floor openings: Provide 40 mm (1-1/2 inch) angle set in silicone adhesive around opening.
  - 3. For drilled penetrations: Provide 40 mm (1-1/2 inch) angle ring or square set in silicone adhesive around penetration.
- C. Penetrations through beams or ribs are prohibited, but may be installed in concrete beam flanges. Any deviation from these requirements must receive prior approval of COR.
- D. Sheet Metal, Plastic, or Moisture-resistant Fiber Sleeves: Provide for pipe passing through floors, interior walls, and partitions, unless brass or steel pipe sleeves are specifically called for below.
- E. Cast Iron or Zinc Coated Pipe Sleeves: Provide for pipe passing through exterior walls below grade. Make space between sleeve and pipe watertight with a modular or link rubber seal. Seal shall be applied at both ends of sleeve.
- F. Galvanized Steel or an alternate Black Iron Pipe with asphalt coating Sleeves: Provide for pipe passing through concrete beam flanges, except where brass pipe sleeves are called for. Provide sleeve for pipe passing through floor of mechanical rooms, laundry work rooms, and animal rooms above basement. Except in mechanical rooms, connect sleeve with floor plate.

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- G. Brass Pipe Sleeves: Provide for pipe passing through quarry tile, terrazzo or ceramic tile floors. Connect sleeve with floor plate.
- H. Sleeves are not required for wall hydrants for fire department connections or in drywall construction.
- I. Sleeve Clearance: Sleeve through floors, walls, partitions, and beam flanges shall be one inch greater in diameter than external diameter of pipe. Sleeve for pipe with insulation shall be large enough to accommodate the insulation. Interior openings shall be caulked tight with fire stopping material and sealant to prevent the spread of fire, smoke, and gases.
- J. Sealant and Adhesives: Shall be as specified in Section 07 92 00, JOINT SEALANTS.

#### 2.14 DUCT PENETRATIONS

- A. Provide curbs for roof mounted piping, ductwork and equipment. Curbs shall be 450 mm (18 inches) high with continuously welded seams, builtin cant strip, interior baffle with acoustic insulation, curb bottom, hinged curb adapter.
- B. Provide firestopping for openings through fire and smoke barriers, maintaining minimum required rating of floor, ceiling or wall assembly. See section 07 84 00, FIRESTOPPING.

#### 2.15 SPECIAL TOOLS AND LUBRICANTS

- A. Furnish, and turn over to the COR, tools not readily available commercially, that are required for disassembly or adjustment of equipment and machinery furnished.
- B. Grease Guns with Attachments for Applicable Fittings: One for each type of grease required for each motor or other equipment.
- C. Refrigerant Tools: Provide system charging/Evacuation equipment, gauges, fittings, and tools required for maintenance of furnished equipment.
- D. Tool Containers: Hardwood or metal, permanently identified for intended service and mounted, or located, where directed by the COR.
- E. Lubricants: A minimum of 0.95 L (1 quart) of oil, and 0.45 kg (1 pound) of grease, of equipment manufacturer's recommended grade and type, in unopened containers and properly identified as to use for each different application.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

# 2.16 WALL, FLOOR AND CEILING PLATES

- A. Material and Type: Chrome plated brass or chrome plated steel, one piece or split type with concealed hinge, with set screw for fastening to pipe, or sleeve. Use plates that fit tight around pipes, cover openings around pipes and cover the entire pipe sleeve projection.
- B. Thickness: Not less than 2.4 mm (3/32 inch) for floor plates. For wall and ceiling plates, not less than 0.64 mm (0.025 inch) for up to 80 mm (3-inch pipe), 0.89 mm (0.035 inch) for larger pipe.
- C. Locations: Use where pipe penetrates floors, walls and ceilings in exposed locations, in finished areas only. Provide a watertight joint in spaces where brass or steel pipe sleeves are specified.

#### 2.17 ASBESTOS

A. Materials containing asbestos are prohibited.

#### PART 3 - EXECUTION

#### 3.1 GENERAL

A. If an installation is unsatisfactory to the COR, the Contractor shall correct the installation at no additional cost or time to the Government.

#### 3.2 ARRANGEMENT AND INSTALLATION OF EQUIPMENT AND PIPING

- A. Location of piping, sleeves, inserts, hangers, and equipment, access provisions shall be coordinated with the work of all trades. The coordination/shop drawings shall be submitted for review. Locate piping, sleeves, inserts, hangers, ductwork and equipment clear of windows, doors, openings, light outlets, and other services and utilities. Equipment coordination/shop drawings shall be prepared to coordinate proper location and personnel access of all facilities. The drawings shall be submitted for review. Follow manufacturer's published recommendations for installation methods not otherwise specified.
- B. Operating Personnel Access and Observation Provisions: Select and arrange all equipment and systems to provide clear view and easy access, without use of portable ladders, for maintenance and operation of all devices including, but not limited to: all equipment items, valves, filters, strainers, transmitters, sensors, control devices. All gauges and indicators shall be clearly visible by personnel standing on the floor or on permanent platforms. Do not reduce or change

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- maintenance and operating space and access provisions that are shown on the contract documents.
- C. Equipment and Piping Support: Coordinate structural systems necessary for pipe and equipment support with pipe and equipment locations to permit proper installation.
- D. Location of pipe sleeves, trenches and chases shall be accurately coordinated with equipment and piping locations.
- E. Cutting Holes:
  - Cut holes through concrete and masonry by rotary core drill.
     Pneumatic hammer, impact electric, and hand or manual hammer type drill is prohibited, except as permitted by COR where working area space is limited.
  - 2. Locate holes to avoid interference with structural members such as slabs, columns, ribs, beams or reinforcing. Holes shall be laid out in advance and drilling done only after approval by COR. If the Contractor considers it necessary to drill through structural members, this matter shall be referred to COR for approval.
  - 3. Do not penetrate membrane waterproofing.
- F. Minor Piping: Generally, small diameter pipe runs from drips and drains, water cooling, and other service are not shown but must be provided.
- G. Electrical Interconnection of Instrumentation or Controls: This generally not shown but must be provided. This includes interconnections of sensors, transmitters, transducers, control devices, control and instrumentation panels, instruments and computer workstations. Devices shall be located so they are easily accessible for testing, maintenance, calibration, etc. The COR has the final determination on what is accessible and what is not. Comply with NFPA 70.
- H. Protection and Cleaning:
  - 1. Equipment and materials shall be carefully handled, properly stored, and adequately protected to prevent damage before and during installation, in accordance with the manufacturer's recommendations and as approved by the COR. Damaged or defective items in the opinion of the COR, shall be replaced.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- 2. Protect all finished parts of equipment, such as shafts and bearings where accessible, from rust prior to operation by means of protective grease coating and wrapping. Close pipe openings with caps or plugs during installation. Tightly cover and protect fixtures and equipment against dirt, water chemical, or mechanical injury. At completion of all work thoroughly clean fixtures, exposed materials and equipment.
- I. Concrete and Grout: Use concrete and non-shrink grout 20 MPa (3000 psig) minimum, specified in Section 03 30 00, CAST-IN-PLACE CONCRETE.
- J. Install gauges, thermometers, valves and other devices with due regard for ease in reading or operating and maintaining said devices. Locate and position thermometers and gauges to be easily read by operator or staff standing on floor or walkway provided. Servicing shall not require dismantling adjacent equipment or pipe work.
- K. Install steam piping expansion joints as per manufacturer's recommendations.
- L. Work in Existing Building:
  - 1. Perform as specified in Article, OPERATIONS AND STORAGE AREAS, Article, ALTERATIONS, and Article, RESTORATION of the Section 01 00 00, GENERAL REQUIREMENTS for relocation of existing equipment, alterations and restoration of existing building(s).
  - 2. As specified in Section 01 00 00, GENERAL REQUIREMENTS, Article, OPERATIONS AND STORAGE AREAS, make alterations to existing service piping at times that will least interfere with normal operation of the facility.
- M. Work in Animal Research Areas: Seal all pipe and duct penetrations with silicone sealant to prevent entrance of insects.
- N. Switchgear/Electrical Equipment Drip Protection: Every effort shall be made to eliminate the installation of pipe above electrical and data/telephone switchgear. If this is not possible, encase pipe in a second pipe with a minimum of joints. Installation of piping, ductwork, leak protection apparatus or other installations foreign to the electrical installation shall not be located in the space equal to the width and depth of the equipment and extending from to a height of 1.8 m (6 feet) above the equipment or to ceiling structure, whichever is lower (NFPA 70).

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

# O. Inaccessible Equipment:

- 1. Where the Government determines that the Contractor has installed equipment not conveniently accessible for operation and maintenance or inspections, equipment shall be removed and reinstalled or remedial action performed as directed at no additional cost or time to the Government.
- 2. The term "conveniently accessible" is defined as capable of being reached without the use of ladders, or without climbing or crawling under or over obstacles such as, but not limited to motors, fans, pumps, belt guards, transformers, high voltage lines, conduit and raceways, piping, hot surfaces, and ductwork. The COR has final determination on whether an installation meets this requirement or not.

# 3.3 TEMPORARY PIPING AND EQUIPMENT

- A. Continuity of operation of existing facilities will generally require temporary installation or relocation of equipment and piping.
- B. The Contractor shall provide all required facilities in accordance with the requirements of phased construction and maintenance of service. All piping and equipment shall be properly supported, sloped to drain, operate without excessive stress, and shall be insulated where injury can occur to personnel by contact with operating facilities. The requirements of Article, ARRANGEMENT AND INSTALLATION OF EQUIPMENT AND PIPING apply.
- C. Temporary facilities and piping shall be completely removed and any openings in structures sealed. Provide necessary blind flanges and caps to seal open piping remaining in service.

#### 3.4 RIGGING

- A. Design is based on application of available equipment. Openings in building structures are planned to accommodate design scheme.
- B. Alternative methods of equipment delivery may be offered by Contractor and will be considered by Government under specified restrictions of phasing and maintenance of service requirements as well as structural integrity of the building.
- C. Close all openings in the building when not required for rigging operations to maintain proper environment in the facility for Government operation and maintenance of service.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- D. Contractor shall provide all facilities required to deliver specified equipment and place on foundations. Attachments to structures for rigging purposes and support of equipment on structures shall be Contractor's full responsibility. Upon request, the Government will check structure adequacy and advise Contractor of recommended restrictions.
- E. Contractor shall check all clearances, weight limitations and shall offer a rigging plan designed by a Registered Professional Engineer.

  All modifications to structures, including reinforcement thereof, shall be at Contractor's cost, time and responsibility.
- F. Follow approved rigging plan.
- G. Restore building to original condition upon completion of rigging work.

# 3.5 PIPE AND EQUIPMENT SUPPORTS

- A. Where hanger spacing does not correspond with joist or rib spacing, use structural steel channels designed by a structural engineer, secured directly to joist and rib structure that will correspond to the required hanger spacing, and then suspend the equipment and piping from the channels. Drill or burn holes in structural steel only with the prior approval of the COR.
- B. Use of chain pipe supports; wire or strap hangers; wood for blocking, stays and bracing; or, hangers suspended from piping above are prohibited. Replace or thoroughly clean rusty products and paint with zinc primer.
- C. Hanger rods shall be used that are straight and vertical. Turnbuckles for vertical adjustments may be omitted where limited space prevents use. Provide a minimum of 15 mm (1/2 inch) clearance between pipe or piping covering and adjacent work.
- D. HVAC Horizontal Pipe Support Spacing: Refer to MSS SP-58. Provide additional supports at valves, strainers, in-line pumps and other heavy components. Provide a support within one foot of each elbow.
- E. HVAC Vertical Pipe Supports:
  - 1. Up to 150 mm (6-inch pipe), 9 m (30 feet) long, bolt riser clamps to the pipe below couplings, or welded to the pipe and rests supports securely on the building structure.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

 Vertical pipe larger than the foregoing, support on base elbows or tees, or substantial pipe legs extending to the building structure.

# F. Overhead Supports:

- 1. Provide steel structural members, in addition to those shown, of adequate capability to support the imposed loads, located in accordance with the final approved layout of equipment and piping.
- 2. Tubing and capillary systems shall be supported in channel troughs.

# G. Floor Supports:

- Provide concrete bases, concrete anchor blocks and pedestals, and structural steel systems for support of equipment and piping.
   Concrete bases and structural systems shall be anchored and doweled to resist forces under operating and seismic conditions (if applicable) without excessive displacement or structural failure.
- 2. Bases and supports shall not be located and installed until equipment mounted thereon has been approved. Bases shall be sized to match equipment mounted thereon plus 50 mm (2 inch) excess on all edges. Chiller foundations shall have horizontal dimensions that exceed chiller base frame dimensions by at least 150 mm (6 inches) on all sides. Structural contract documents shall be reviewed for additional requirements. Bases shall be neatly finished and smoothed, shall have chamfered edges at the top, and shall be suitable for painting.
- 3. All equipment shall be shimmed, leveled, firmly anchored, and grouted with epoxy grout. Anchor bolts shall be placed in sleeves, anchored to the bases. Fill the annular space between sleeves and bolts with a granular material to permit alignment and realignment.

#### 3.6 MECHANICAL DEMOLITION

A. Rigging access, other than indicated on the contract documents, shall be provided by the Contractor after approval for structural integrity by the COR. Such access shall be provided without additional cost or time to the Government. Where work is in an operating plant, provide

approved protection from dust and debris at all times for the safety of Contract No. 36C26319D0044

Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

plant personnel and maintenance of plant operation and environment of the plant.

- B. In an operating facility, maintain the operation, cleanliness and safety. Government personnel will be carrying on their normal duties of operating, cleaning and maintaining equipment and plant operation. Confine the work to the immediate area concerned; maintain cleanliness and wet down demolished materials to eliminate dust. Debris accumulated in the area to the detriment of plant operation is prohibited. Perform all flame cutting to maintain the fire safety integrity of this plant. Adequate fire extinguishing facilities shall be available at all times. Perform all work in accordance with recognized fire protection standards. Inspection will be made by personnel of the VAMC, and Contractor shall follow all directives of the COR with regard to rigging, safety, fire safety, and maintenance of operations.
- C. Unless specified otherwise, all piping, wiring, conduit, and other devices associated with the equipment not re-used in the new work shall be completely removed from Government property per Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT. This includes all concrete pads, pipe, valves, fittings, insulation, and all hangers including the top connection and any fastenings to building structural systems. All openings shall be sealed after removal of equipment, pipes, ducts, and other penetrations in roof, walls, floors, in an approved manner and in accordance with contract documents where specifically covered. Structural integrity of the building system shall be maintained. Reference shall also be made to the contract documents of the other disciplines in the project for additional facilities to be demolished or handled.
- D. All indicated valves including gate, globe, ball, butterfly and check, all pressure gauges and thermometers with wells shall remain Government property and shall be removed and delivered to COR and stored as directed. The Contractor shall remove all other material and equipment, devices and demolition debris under these contract documents. Such material shall be removed from Government property expeditiously and shall not be allowed to accumulate.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

#### 3.7 CLEANING AND PAINTING

- A. Prior to final inspection and acceptance of the plant and facilities for beneficial use by the Government, the plant facilities, equipment and systems shall be thoroughly cleaned and painted. Refer to Section 09 91 00, PAINTING.
- B. In addition, the following special conditions apply:
  - 1. Cleaning shall be thorough. Solvents, cleaning materials and methods recommended by the manufacturers shall be used for the specific tasks. All rust shall be removed prior to painting and from surfaces to remain unpainted. Repair scratches, scuffs, and abrasions prior to applying prime and finish coats.
  - 2. The following material and equipment shall not be painted:
  - a. Motors, controllers, control switches, and safety switches.
  - b. Control and interlock devices.
  - c. Regulators.
  - d. Pressure reducing valves.
  - e. Control valves and thermostatic elements.
  - f. Lubrication devices and grease fittings.
  - g. Copper, brass, aluminum, stainless steel and bronze surfaces.
  - h. Valve stems and rotating shafts.
  - i. Pressure gauges and thermometers.
  - j. Glass.
  - k. Nameplates.
  - 3. Control and instrument panels shall be cleaned, damaged surfaces repaired, and shall be touched-up with matching paint obtained from panel manufacturer.
  - 4. Pumps, motors, steel and cast-iron bases, and coupling guards shall be cleaned, and shall be touched-up with the same paint type and color as utilized by the pump manufacturer.
  - 5. Temporary Facilities: Apply paint to surfaces that do not have existing finish coats. This may include painting exposed metals where hangers were removed or where equipment was moved or removed.
  - 6. Paint shall withstand the following temperatures without peeling or discoloration:

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- a. Condensate and Feedwater: 38 degrees C (100 degrees F) on insulation jacket surface and 121 degrees C (250 degrees F) on metal pipe surface.
- b. Steam: 52 degrees C (125 degrees F) on insulation jacket surface and 190 degrees C (374 degrees F) on metal pipe surface.
- 7. Final result shall be smooth, even-colored, even-textured factory finish on all items. Completely repaint the entire piece of equipment if necessary to achieve this.
- 8. Lead based paints are prohibited.

# 3.8 IDENTIFICATION SIGNS

- A. Provide laminated plastic signs, with engraved lettering not less than 5 mm (3/16 inch) high, designating functions, for all equipment, switches, motor controllers, relays, meters, control devices, including automatic control valves. Nomenclature and identification symbols shall correspond to that used in maintenance manual, and in diagrams specified elsewhere. Attach by chain, adhesive, or screws.
- B. Factory Built Equipment: Metal plate, securely attached, with name and address of manufacturer, serial number, model number, size, performance.
- C. Pipe Identification: Refer to Section 09 91 00, PAINTING.
- D. Attach ceiling grid label on ceiling grid location directly underneath above-ceiling air terminal, control system component, valve, filter unit, fan etc.

# 3.9 MOTOR AND DRIVES

- A. Use synchronous belt drives only on equipment controlled by soft starters or variable frequency drive motor controllers without a bypass contactor. Use V-belt drives on all other applications.
- B. Alignment of V-Belt Drives: Set driving and driven shafts parallel and align so that the corresponding grooves are in the same plane.
- C. Alignment of Synchronous Belt Drives: Set driving and driven shafts parallel and align so that the corresponding pulley flanges are in the same plane.
- D. Alignment of Direct-Connect Drives: Securely mount motor in accurate alignment so that shafts are per coupling manufacturer's tolerances when both motor and driven machine are operating at normal temperatures.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

#### 3.10 LUBRICATION

- A. All equipment and devices requiring lubrication shall be lubricated prior to initial operation. Field-check all devices for proper lubrication.
- B. All devices and equipment shall be equipped with required lubrication fittings or devices. A minimum of 0.95 liter (1 quart) of oil and 0.45 kg (1 pound) of grease of manufacturer's recommended grade and type for each different application shall be provided; also provide 12 grease sticks for lubricated plug valves. Deliver all materials to COR in unopened containers that are properly identified as to application.
- C. All lubrication points shall be accessible without disassembling equipment, except to remove access plates.
- D. All lubrication points shall be extended to one side of the equipment.

# 3.11 STARTUP, TEMPORARY OPERATION AND TESTING

- A. Perform tests as recommended by product manufacturer and listed standards and under actual or simulated operating conditions and prove full compliance with design and specified requirements. Tests of the various items of equipment shall be performed simultaneously with the system of which each item is an integral part.
- B. When any defects are detected, correct defects and repeat test at no additional cost or time to the Government.
- C. Startup of equipment shall be performed as described in equipment specifications. Vibration within specified tolerance shall be verified prior to extended operation. Temporary use of equipment is specified in Section 01 00 00, GENERAL REQUIREMENTS, Article, TEMPORARY USE OF MECHANICAL AND ELECTRICAL EQUIPMENT.

# 3.12 OPERATING AND PERFORMANCE TESTS

- A. Prior to the final inspection, perform required tests as specified in Section 01 00 00, GENERAL REQUIREMENTS Article, TESTS, and in individual Division 23 specification sections and submit the test reports and records to the COR.
- B. Should evidence of malfunction in any tested system, or piece of equipment or component part thereof, occur during or as a result of tests, make proper corrections, repairs or replacements, and repeat tests at no additional cost or time to the Government.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- C. When completion of certain work or system occurs at a time when final control settings and adjustments cannot be properly made to make performance tests, then conduct such performance tests and finalize control settings for heating systems and for cooling systems respectively during first actual seasonal use of respective systems following completion of work. Rescheduling of these tests shall be requested in writing to COR for approval.
- D. No adjustments may be made during the acceptance inspection. All adjustments shall have been made by this point.

#### 3.13 COMMISSIONING (NOT USED)

# 3.14 DEMONSTRATION AND TRAINING

A. Provide services of manufacturer's technical representative for 4 hours to instruct each VA personnel responsible in operation and maintenance of the system.

---END---

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

# SECTION 23 05 41 NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EQUIPMENT

# PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section specifies the application of noise control measures, and vibration control techniques to boiler plant rotating equipment and parts including chillers, cooling towers, boilers, pumps, fans, compressors, motors and steam turbines.
- B. A complete listing of all common acronyms and abbreviations are included in Section 23 05 11, COMMON WORK RESULTS FOR HVAC. Noise criteria, vibration tolerance and vibration isolation for HVAC and plumbing work.

#### 1.2 RELATED WORK

- A. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA and SAMPLES.
- B. Section 23 05 10, COMMON WORK RESULTS FOR HVAC.
- C. Section 23 31 00, HVAC DUCTS and CASINGS.
- D. Section 23 08 00, COMMISSIONING OF HVAC SYSTEMS.

# 1.3 QUALITY ASSURANCE

- A. Refer to article, QUALITY ASSURANCE in specification Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- B. Noise Criteria:
  - 1. Noise levels in all 8 octave bands due to equipment and duct systems shall not exceed following NC levels:

TYPE OF ROOM	NC LEVEL
Bathrooms and Toilet Rooms	40
Conference Rooms	35
Corridors (Nurse Stations)	40
Corridors (Public)	40
Kitchens	50
Laundries	50
Lobbies, Waiting Areas	40
Locker Rooms	45

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

Offices, Large Open	40
Offices, Small Private	35
Patient Rooms	35
Recreation Rooms	40-45

- 2. For equipment which has no sound power ratings scheduled on the plans, the contractor shall select equipment such that the foregoing noise criteria, local ordinance noise levels, and OSHA requirements are not exceeded. Selection procedure shall be in accordance with ASHRAE Fundamentals Handbook, Chapter 8, Sound and Vibration.
- 3. An allowance, not to exceed 5db, may be added to the measured value to compensate for the variation of the room attenuating effect between room test condition prior to occupancy and design condition after occupancy which may include the addition of sound absorbing material, such as, furniture. This allowance may not be taken after occupancy. The room attenuating effect is defined as the difference between sound power level emitted to room and sound pressure level in room.
- 4. In absence of specified measurement requirements, measure equipment noise levels three feet from equipment and at an elevation of maximum noise generation.
- D. Allowable Vibration Tolerances for Rotating, Non-reciprocating Equipment: Not to exceed a self-excited vibration maximum velocity of 5 mm per second (0.20 inch per second) RMS, filter in, when measured with a vibration meter on bearing caps of machine in vertical, horizontal and axial directions or measured at equipment mounting feet if bearings are concealed. Measurements for internally isolated fans and motors may be made at the mounting feet.

#### 1.4 SUBMITTALS

- A. Submit in accordance with specification Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Manufacturer's Literature and Data:
  - 1. Vibration isolators:
    - a. Floor mountings
    - b. Hangers

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- c. Snubbers
- d. Thrust restraints
- 2. Bases.
- 4. Acoustical enclosures.
- C. Isolator manufacturer shall furnish with submittal load calculations for selection of isolators, including supplemental bases, based on lowest operating speed of equipment supported.

#### 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE):

Handbook 2017......Fundamentals Handbook, Chapter 8, Sound and

- C. American Society for Testing and Materials (ASTM):
  - A123/A123M-2017......Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
  - A307-2016......Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength
  - D2240-05(2010)......Standard Test Method for Rubber Property 
    Durometer Hardness
- D. Manufacturers Standardization (MSS):
  - SP-58-2018......Pipe Hangers and Supports-Materials, Design and Manufacture
- E. Occupational Safety and Health Administration (OSHA):
  - 29 CFR 1960.95.....Occupational Noise Exposure
- F. American Society of Civil Engineers (ASCE):
  - ASCE 7-2017......Minimum Design Loads for Buildings and Other Structures.
- G. American National Standards Institute / Sheet Metal and Air Conditioning Contractor's National Association (ANSI/SMACNA): 001-2008......Seismic Restraint Manual: Guidelines for Mechanical Systems, 3rd Edition.
- H. International Code Council (ICC):

IBC 2018.....International Building Code.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

I. Department of Veterans Affairs (VA):
 H-18-8 2016..........Seismic Design Requirements.

#### PART 2 - PRODUCTS

#### 2.1 GENERAL REQUIREMENTS

- A. Type of isolator, base, and minimum static deflection shall be as required for each specific equipment application as recommended by isolator or equipment manufacturer but subject to minimum requirements indicated herein and in the schedule on the drawings.
- B. Elastometric Isolators shall comply with ASTM D2240 and be oil resistant neoprene with a maximum stiffness of 60 durometer and have a straight-line deflection curve.
- C. Exposure to weather: Isolator housings to be either hot dipped galvanized or powder coated to ASTM B117 salt spray testing standards. Springs to be powder coated or electro galvanized. All hardware to be electro galvanized. In addition provide limit stops to resist wind velocity. Velocity pressure established by wind shall be calculated in accordance with section 1609 of the International Building Code. A minimum wind velocity of 75 mph shall be employed.
- D. Uniform Loading: Select and locate isolators to produce uniform loading and deflection even when equipment weight is not evenly distributed.
- E. Color code isolators by type and size for easy identification of capacity.

# 2.2 SEISMIC RESTRAINT REQUIREMENTS FOR EQUIPMENTS

- A. Bolt pad mounted equipment, without vibration isolators, to the floor or other support using ASTM A307 standard bolting material.
- B. Floor mounted equipment, with vibration Isolators: Type SS. Where Type N isolators are used provide channel frame base horizontal restraints bolted to the floor, or other support, on all sides of the equipment Size and material required for the base shall be as recommended by the isolator manufacturer.
- C. On all sides of suspended equipment, provide bracing for rigid supports and provide restraints for resiliently supported equipment.

#### 2.3 VIBRATION ISOLATORS

A. Floor Mountings:

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- 1. Double Deflection Neoprene (Type N): Shall include neoprene covered steel support plated (top and bottom), friction pads, and necessary bolt holes.
- 2. Spring Isolators (Type S): Shall be free-standing, laterally stable and include acoustical friction pads and leveling bolts. Isolators shall have a minimum ratio of spring diameter-to-operating spring height of 1.0 and an additional travel to solid equal to 50 percent of rated deflection.
- 3. Captive Spring Mount for Seismic Restraint (Type SS):
  - a. Design mounts to resiliently resist seismic forces in all directions. Snubbing shall take place in all modes with adjustment to limit upward, downward, and horizontal travel to a maximum of 6 mm (1/4-inch) before contacting snubbers. Mountings shall have a minimum rating of one G coefficient of gravity as calculated and certified by a registered structural engineer.
  - b. All mountings shall have leveling bolts that must be rigidly bolted to the equipment. Spring diameters shall be no less than 0.8 of the compressed height of the spring at rated load. Springs shall have a minimum additional travel to solid equal to 50 percent of the rated deflection. Mountings shall have ports for spring inspection. Provide an all directional neoprene cushion collar around the equipment bolt.
- 4. Spring Isolators with Vertical Limit Stops (Type SP): Similar to spring isolators noted above, except include a vertical limit stop to limit upward travel if weight is removed and also to reduce movement and spring extension due to wind loads. Provide clearance around restraining bolts to prevent mechanical short circuiting.
- 5. Pads (Type D), Washers (Type W), and Bushings (Type L): Pads shall be natural rubber or neoprene waffle, neoprene and steel waffle, or reinforced duck and neoprene. Washers and bushings shall be reinforced duck and neoprene. Washers and bushings shall be reinforced duck and neoprene. Size pads for a maximum load of 345 kPa (50 pounds per square inch).
- 6. Seismic Pad (Type DS): Pads shall be natural rubber / neoprene waffle with steel top plate and drilled for an anchor bolt. Washers

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

and bushings shall be reinforced duck and neoprene. Size pads for a maximum load of 345 kPa (50 pounds per square inch).

- B. Hangers: Shall be combination neoprene and springs unless otherwise noted and shall allow for expansion of pipe.
  - 1. Combination Neoprene and Spring (Type H): Vibration hanger shall contain a spring and double deflection neoprene element in series. Spring shall have a diameter not less than 0.8 of compressed operating spring height. Spring shall have a minimum additional travel of 50 percent between design height and solid height. Spring shall permit a 15 degree angular misalignment without rubbing on hanger box.
  - 2. Spring Position Hanger (Type HP): Similar to combination neoprene and spring hanger except hanger shall hold piping at a fixed elevation during installation and include a secondary adjustment feature to transfer load to spring while maintaining same position.
  - 3. Neoprene (Type HN): Vibration hanger shall contain a double deflection type neoprene isolation element. Hanger rod shall be separated from contact with hanger bracket by a neoprene grommet.
  - 4. Spring (Type HS): Vibration hanger shall contain a coiled steel spring in series with a neoprene grommet. Spring shall have a diameter not less than 0.8 of compressed operating spring height. Spring shall have a minimum additional travel of 50 percent between design height and solid height. Spring shall permit a 15 degree angular misalignment without rubbing on hanger box.
  - 5. Hanger supports for piping 50 mm (2 inches) and larger shall have a pointer and scale deflection indicator.
  - 6. Hangers used in seismic applications shall be provided with a neoprene and steel rebound washer installed 4' clear of bottom of hanger housing in operation to prevent spring from excessive upward travel
- C. Snubbers: Each spring mounted base shall have a minimum of four all-directional or eight two directional (two per side) seismic snubbers that are double acting. Elastomeric materials shall be shock absorbent neoprene bridge quality bearing pads, maximum 60 durometer, replaceable and have a minimum thickness of 6 mm (1/4 inch). Air gap between hard and resilient material shall be not less than 3 mm (1/8 inch) nor more

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- than 6 mm (1/4 inch). Restraints shall be capable of withstanding design load without permanent deformation.
- D. Thrust Restraints (Type THR): Restraints shall provide a spring element contained in a steel frame with neoprene pads at each end attachment. Restraints shall have factory preset thrust and be field adjustable to allow a maximum movement of 6 mm (1/4 inch) when the fan starts and stops. Restraint assemblies shall include rods, angle brackets and other hardware for field installation.

#### 2.4 BASES

- A. Rails (Type R): Design rails with isolator brackets to reduce mounting height of equipment and cradle machines having legs or bases that do not require a complete supplementary base. To assure adequate stiffness, height of members shall be a minimum of 1/12 of longest base dimension but not less than 100 mm (4 inches). Where rails are used with neoprene mounts for small fans or close coupled pumps, extend rails to compensate overhang of housing.
- B. Integral Structural Steel Base (Type B): Design base with isolator brackets to reduce mounting height of equipment which require a complete supplementary rigid base. To assure adequate stiffness, height of members shall be a minimum of 1/12 of longest base dimension, but not less than 100 mm (four inches).
- C. Inertia Base (Type I): Base shall be a reinforced concrete inertia base. Pour concrete into a welded steel channel frame, incorporating prelocated equipment anchor bolts and pipe sleeves. Level the concrete to provide a smooth uniform bearing surface for equipment mounting. Provide grout under uneven supports. Channel depth shall be a minimum of 1/12 of longest dimension of base but not less than 150 mm (six inches). Form shall include 13-mm (1/2-inch) reinforcing bars welded in place on minimum of 203 mm (eight inch) centers running both ways in a layer 40 mm (1-1/2 inches) above bottom. Use height saving brackets in all mounting locations. Weight of inertia base shall be equal to or greater than weight of equipment supported to provide a maximum peak-to-peak displacement of 2 mm (1/16 inch).
- D. Curb Mounted Isolation Base (Type CB): Fabricate from aluminum to fit on top of standard curb with overlap to allow water run-off and have wind and water seals which shall not interfere with spring action.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

Provide resilient snubbers with 6 mm (1/4 inch) clearance for wind resistance. Top and bottom bearing surfaces shall have sponge type weather seals. Integral spring isolators shall comply with Spring Isolator (Type S) requirements.

#### 2.5 SOUND ATTENUATING UNITS

Refer to specification Section 23 31 00, HVAC DUCTS and CASINGS.

#### 2.6 ACOUSTICAL ENCLOSURES IN MECHANICAL ROOMS (NOT USED)

#### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Vibration Isolation:
  - 1. No metal-to-metal contact will be permitted between fixed and floating parts.
  - 2. Connections to Equipment: Allow for deflections equal to or greater than equipment deflections. Electrical, drain, piping connections, and other items made to rotating or reciprocating equipment (pumps, compressors, etc.) which rests on vibration isolators, shall be isolated from building structure for first three hangers or supports with a deflection equal to that used on the corresponding equipment.
  - 3. Common Foundation: Mount each electric motor on same foundation as driven machine. Hold driving motor and driven machine in positive rigid alignment with provision for adjusting motor alignment and belt tension. Bases shall be level throughout length and width. Provide shims to facilitate pipe connections, leveling, and bolting.
  - 4. Provide heat shields where elastomers are subject to temperatures over 38 degrees C (100 degrees F).
  - 5. Extend bases for pipe elbow supports at discharge and suction connections at pumps. Pipe elbow supports shall not short circuit pump vibration to structure.
  - 6. Non-rotating equipment such as heat exchangers and convertors shall be mounted on isolation units having the same static deflection as the isolation hangers or support of the pipe connected to the equipment.
- B. Inspection and Adjustments: Check for vibration and noise transmission through connections, piping, ductwork, foundations, and walls. Adjust, repair, or replace isolators as required to reduce vibration and noise transmissions to specified levels.

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

#### 3.2 ADJUSTING

- A. Adjust vibration isolators after piping systems are filled and equipment is at operating weight.
- B. Adjust limit stops on restrained spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.
- C. Attach thrust limits at centerline of thrust and adjust to a maximum of 1/4inch (6-mm) movement during start and stop.
- D. Adjust active height of spring isolators.
- E. Adjust snubbers according to manufacturer's recommendations.
- F. Adjust seismic restraints to permit free movement of equipment within normal mode of operation.
- G. Torque anchor bolts according to equipment manufacturer's recommendations to resist seismic forces.

#### 3.3 COMMISSIONING

- A. Provide commissioning documentation in accordance with the requirements of section 23 08 00 COMMISSIONING OF HVAC SYSTEMS for all inspection, start up, and contractor testing required above and required by the System Readiness Checklist provided by the Commissioning Agent.
- B. Components provided under this section of the specification will be tested as part of a larger system. Refer to section 23 08 00 COMMISSIONING OF HVAC SYSTEMS and related sections for contractor responsibilities for system commissioning.

---END---

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

# SELECTION GUIDE FOR VIBRATION ISOLATORS

EQUIPN	MENT	ON GRADE		20FT FLOOR SPAN		30FT FLOOR SPAN		40FT FLOOR SPAN			50FT FLOOR SPAN					
		BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL
REFRIGER	ATION M	ACHIN	IES													
ABSORPTIO	N		D	0.3		SP	0.8		SP	1.5		SP	1.5		SP	2.0
PACKAGED	HERMETIC		D	0.3		SP	0.8		SP	1.5		SP	1.5	R	SP	2.5
OPEN CENT	RIFUGAL	В	D	0.3	В	SP	0.8		SP	1.5	В	SP	1.5	В	SP	3.5
RECIPROCA	TING:															
ALL			D	0.3		SP	0.8	R	SP	2.0	R	SP	2.5	R	SP	3.5
COMPRESS	ORS AND	VACU	JUM P	JMPS					ı	ı					ı	,
UP THROUGH HP	1-1/2		D,L, W	0.8		D,L, W	0.8		D,L, W	1.5		D,L, W	1.5		D,L, W	
2 HP AND O'	VER:															
500 - 750	RPM		D	0.8		S	0.8		S	1.5		S	1.5		S	2.5
750 RPM &	OVER		D	0.8		S	0.8		S	1.5		S	1.5		S	2.5
PUMPS																
CLOSE COUPLED	UP TO 1-1/2 HP					D,L, W			D,L, W			D,L, W			D,L, W	
	2 HP & OVER				I	S	0.8	I	S	1.5	I	S	1.5	I	S	2.0

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

EQUIPMENT		ON GRADE 20FT FLOOR SPAN					SPAN	30FT FLOOR SPAN			40FT	FLOOR	SPAN	50FT FLOOR SPAN		
		BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL
LARGE INLINE	Up to 25 HP					S	0.75		S	1.50		S	1.50			NA
	26 HP THRU 30 HP					S	1.0		S	1.50		S	2.50			NA
	UP TO 10 HP					D,L, W			D,L, W			D,L, W			D,L, W	
BASE MOUNTED	15 HP THRU 40 HP	I	S	1.0	I	S	1.0	I	S	2.0	I	S	2.0	I	S	2.0
	50 HP & OVER	I	S	1.0	I	S	1.0	I	S	2.0	I	S	2.5	I	S	2.5
ROOF FAN	1S															
ABOVE OCCU	JPIED AREA	AS:	1	1	1	1	1	T	Ι	1	1	1	1	<b>I</b>	1	1
5 HP & OV	VER				СВ	S	1.0	СВ	S	1.0	СВ	S	1.0	СВ	S	1.0
CENTRIFU		NS .														
UP TO 50 H			1	1	<b>T</b>	1	1	1	ı	1	T	1	1	<b>T</b>	1	T
UP TO 200	) RPM	В	N	0.3	В	S	2.5	В	S	2.5	В	S	3.5	В	S	3.5
201 - 300	) RPM	В	N	0.3	В	S	2.0	В	S	2.5	В	S	2.5	В	S	3.5
301 - 500	) RPM	В	N	0.3	В	S	2.0	В	S	2.0	В	S	2.5	В	S	3.5
501 RPM 8	§ OVER	В	N	0.3	В	S	2.0	В	S	2.0	В	S	2.0	В	S	2.5

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

EQUIPMENT	C	N GRAD	E	20FT	FLOOR	SPAN	30FT	FLOOR	SPAN	40FT	FLOOR	SPAN	50FT	FLOOR	SPAN
	BASE TYPE	ISOL TYPE	MIN DEFL												
60 HP & OVER:					1	1		1		•	1	1			
UP TO 300 RPM	В	S	2.0	I	S	2.5	I	S	3.5	I	S	3.5	I	S	3.5
301 - 500 RPM	В	S	2.0	I	S	2.0	I	S	2.5	I	S	3.5	I	S	3.5
501 RPM & OVER	В	S	1.0	I	S	2.0	I	S	2.0	I	S	2.5	I	S	2.5
COOLING TOWERS															
UP TO 500 RPM					SP	2.5		SP	2.5		SP	2.5		SP	3.5
501 RPM & OVER					SP	0.75		SP	0.75		SP	1.5		SP	2.5
INTERNAL COMBUSTION	ENGINE	ES													
UP TO 25 HP	I	N	0.75	I	N	1.5	I	S	2.5	I	S	3.5	I	S	4.5
30 THRU 100 HP	I	N	0.75	I	N	1.5	I	S	2.5	I	S	3.5	I	S	4.5
125 HP & OVER	I	N	0.75	I	N	1.5	I	S	2.5	I	S	3.5	I	S	4.5
AIR HANDLING UNIT PA	ACKAGES	3													
SUSPENDED:															
UP THRU 5 HP					Н	1.0									
7-1/2 HP & OVER:		•	•		•	•			•		•	•			
UP TO 500 RPM					H, THR	1.5		H, THR	2.5		H, THR	2.5		H, THR	2.5
501 RPM & OVER					H, THR	0.8		H, THR	0.8		H,TH R	0.8		H,TH R	2.0

# EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

EQUIPMENT	ON GRADE			20FT FLOOR SPAN			30FT FLOOR SPAN			40FT FLOOR SPAN			50FT FLOOR SPAN		
	BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL	BASE TYPE	ISOL TYPE	MIN DEFL
FLOOR MOUNTED:															•
UP THRU 5 HP		D			S	1.0									
7-1/2 HP & OVER:															
UP TO 500 RPM		D		R	S, THR	1.5	R	S, THR	2.5	R	S, THR	2.5	R	S, THR	2.5
501 RPM & OVER		D			S, THR	0.8		S, THR	0.8	R	S, THR	1.5	R	S, THR	2.0
HEAT PUMPS		•	•			•		•	•					•	
ALL		S	0.75		S	0.75		S	0.75	СВ	S	1.5			NA
CONDENSING UNITS															
ALL		SS	0.25		SS	0.75		SS	1.5	СВ	SS	1.5			NA
IN-LINE CENTRIFUGAL	AND V	ANE AXI	AL FAN	S, FLO	OR MOUN	ITED: (	APR 9)								
UP THRU 50 HP:															
UP TO 300 RPM		D		R	S	2.5	R	S	2.5	R	S	2.5	R	S	3.5
301 - 500 RPM		D		R	S	2.0	R	S	2.0	R	S	2.5	R	S	2.5
501 - & OVER		D			S	1.0		S	1.0	R	S	2.0	R	S	2.5
60 HP AND OVER:															
301 - 500 RPM	R	S	1.0	R	S	2.0	R	S	2.0	R	S	2.5	R	S	3.5
501 RPM & OVER	R	S	1.0	R	S	2.0	R	S	2.0	R	S	2.0	R	S	2.5

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

#### NOTES:

- 1. Edit the Table above to suit where isolator, other than those shown, are used, such as for seismic restraints and position limit stops.
- 2. For suspended floors lighter than 100 mm (4 inch) thick concrete, select deflection requirements from next higher span.
- 3. For separate chiller building on grade, pump isolators may be omitted.
- 4. Direct bolt fire pumps to concrete base. Provide pads (D) for domestic water booster pump package.
- 5. For projects in seismic areas, use only SS & DS type isolators and snubbers.
- 6. For floor mounted in-line centrifugal blowers (ARR 1): use "B" type in lieu of "R" type base.
- 7. Suspended: Use "H" isolators of same deflection as floor mounted.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

04-01-20

# SECTION 23 11 23 FACILITY NATURAL-GAS PIPING

#### 1.1 DESCRIPTION

- A. Fuel gas systems, including piping, equipment and all necessary accessories as designated in this section. Fuel gas piping for central boiler plants is not included.
- B. A complete listing of common acronyms and abbreviations are included in Section 23 05 11, COMMON WORK RESULTS FOR HVAC Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.

#### 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- C. Section 01 81 13, SUSTAINABLE CONSTRUCTION REQUIREMENTS.
- D. Section 07 84 00, FIRESTOPPING.
- E. Section 07 92 00, JOINT SEALANTS.
- F. Section 09 91 00, PAINTING.
- G. Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.
- H. Section 22 05 23, GENERAL DUTY VALVES FOR PLUMBING PIPING.
- I. Section 23 09 11, INSTRUMENTATION AND CONTROL FOR BOILER PLANT.
- J. Section 23 21 11, BOILER PLANT PIPING SYSTEMS.

#### 1.3 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only. Where conflicts occur these specifications and the VHA standard will govern.
- B. American Society of Mechanical Engineers (ASME):

B16.3-2019	Malleable	Iron	Threaded	Fittings:	Classes	150
	and 300					

B16.9-2018Factory Made Wrought Buttwelding Fittings
B16.11-2011Forged Fittings, Socket-Welding and Threaded
B16.15-2018Cast Copper Alloy Threaded Fittings: Classes
125 and 250

B16.40-2019...........Manually Operated Thermoplastic Gas Shutoffs and Valves in Distribution Systems

# EHRM Infrastructure Upgrades

	EHRM Infrastructure Upgrades  Bancroft Architects + Engineers
	04-01-20
	B31.8-2018Gas Transmission and Distribution Piping
	Systems
С.	American Society for Testing and Materials (ASTM):
	A47/A47M-2018Standard Specification for Ferritic Malleable
	Iron Castings
	A53/A53M-2018Standard Specification for Pipe, Steel, Black
	and Hot-Dipped, Zinc-Coated, Welded and
	Seamless
	A536-2019Standard Specification for Ductile Iron
	Castings
	A733-2016Standard Specification for Welded and Seamless
	Carbon Steel and Austenitic Stainless-Steel
	Pipe Nipples
	B43-2015Standard Specification for Seamless Red Brass
	Pipe, Standard Sizes
	B687-2016Standard Specification for Brass, Copper, and
	Chromium-Plated Pipe Nipples
	D2513-2019Standard Specification for Polyethylene (PE)
	Gas Pressure Pipe, Tubing, and Fittings
	D2683-2014Standard Specification for Socket-Type
	Polyethylene Fittings for Outside Diameter-
	Controlled Polyethylene Pipe and Tubing
	D3261-2016Standard Specification for Butt Heat Fusion
	Polyethylene (PE) Plastic Fittings for
	Polyethylene (PE) Plastic Pipe and Tubing
D.	American Water Works Association (AWWA):
	C203-2015Coal-Tar Protective Coatings and Linings for
	Steel Water Pipes
Ε.	<pre>International Code Council (ICC):</pre>
	IFGC-2018International Fuel Gas Code
	IPC-2018International Plumbing Code
F.	Manufacturers Standardization Society of the Valve and Fittings
	Industry, Inc. (MSS):
	SP-72-2010aBall Valves with Flanged or Butt-Welding for

Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

General Service

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

04-01-20

	01 01 2
	SP-110-2010Ball Valves Threaded, Socket-Welding, Solder
	Joint, Grooved and Flared Ends
G.	NACE International (NACE):
	SP0274-2011High-Voltage Electrical Inspection of Pipeline
	Coatings
	SP0490-2007Holiday Detection of Fusion-Bonded Epoxy
	External Pipeline Coating of 250 to 760 $\mu m$ (10
	to 30 mil)
Н.	National Fire Protection Association (NFPA):

# 1.4 SUBMITTALS

- A. Submittals, including number of required copies, shall be submitted in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Information and material submitted under this section shall be marked "SUBMITTED UNDER SECTION 23 11 23, FACILITY NATURAL-GAS PIPING", with applicable paragraph identification.
- C. Manufacturer's Literature and Data including: Full item description and optional features and accessories. Include dimensions, weights, materials, applications, standard compliance, model numbers, size, and capacity.
  - 1. Pipe & Fittings.
  - 2. Valves.
  - 3. Strainers.
  - 4. All items listed in Part 2 Products.

54-2018 ......National Fuel Gas Code

- D. Detailed shop drawing of clamping device and extensions when required in connection with the waterproofing membrane.
- E. Complete operating and maintenance manuals including wiring diagrams, technical data sheets, information for ordering replacement parts, and troubleshooting guide:
  - 1. Include complete list indicating all components of the systems.
  - Include complete diagrams of the internal wiring for each item of equipment.
  - 3. Diagrams shall have their terminals identified to facilitate installation, operation and maintenance.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

04-01-20

#### 1.5 AS-BUILT DOCUMENTATION

- A. Submit manufacturer's literature and data updated to include submittal review comments and any equipment substitutions.
- B. Submit operation and maintenance data updated to include submittal review comments, VA approved substitutions and construction revisions shall be in electronic version on CD or DVD inserted into a three-ring binder. All aspects of system operation and maintenance procedures, including applicable piping isometrics, wiring diagrams of all circuits, a written description of system design, control logic, and sequence of operation shall be included in the operation and maintenance manual. The operations and maintenance manual shall include troubleshooting techniques and procedures for emergency situations.

  Notes on all special systems or devices shall be included. A List of recommended spare parts (manufacturer, model number, and quantity) shall be furnished. Information explaining any special knowledge or tools the owner will be required to employ shall be inserted into the As-Built documentation.
- C. The installing contractor shall maintain as-built drawings of each completed phase for verification; and, shall provide the complete set at the time of final systems certification testing. Should the installing contractor engage the testing company to provide as-built or any portion thereof, it shall not be deemed a conflict of interest or breach of the 'third party testing company' requirement. Provide record drawings as follows:
  - Red-lined, hand-marked drawings are to be provided, with one paper copy and a scanned PDF version of the hand-marked drawings provided on CD or DVD.
  - 2. As-built drawings are to be provided, with a copy of them on AutoCAD version 2019 provided on CD or DVD. The CAD drawings shall use multiple line layers with a separate individual layer for each system.
- D. The as-built drawings shall indicate the location and type of all lockout/tagout points for all energy sources for all equipment and pumps to include breaker location and numbers, valve tag numbers, etc.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

04-01-20

Coordinate lockout/tagout procedures and practices with local VA requirements.

E. Certification documentation shall be provided to COR 21 working days prior to submitting the request for final inspection. The documentation shall include all test results, the names of individuals performing work for the testing agency on this project, detailed procedures followed for all tests, and provide documentation/certification that all results of tests were within limits specified. Test results shall contain written sequence of test procedure with written test results annotated at each step along with the expected outcome or setpoint. The results shall include all readings, including but not limited to data on device (make, model and performance characteristics), normal pressures, switch ranges, trip points, amp readings, and calibration data to include equipment serial numbers or individual identifications, etc.

#### 1.6 SYSTEM PRESSURE

A. Natural gas systems unless otherwise noted are designed and materials and equipment selected to prevent failure under gas pressure of 3.49 kPa (0.51 psig) at downstream side of pressure regulator.

# PART 2 - PRODUCTS

#### 2.1 FUEL GAS SERVICE CONNECTIONS TO BUILDING

- A. From inside face of exterior wall to a distance of approximately 1500 mm (5 feet) outside of building.
- B. Pipe: Black steel, ASTM A53/A53M, Schedule 40. Shop-applied pipe coating shall be one of the following types:
  - 1. Coal Tar Enamel Coating: Exterior of pipe and fittings shall be cleaned, primed with Type B primer and coated with hot-applied coal tar enamel with bonded layer of felt wrap in accordance with AWWA C203. Asbestos felt shall not be used; felt material shall be fibrous glass mat in accordance with AWWA C203.
- C. Holiday Inspections: Procedure for holiday inspection: Holiday Inspection shall be conducted on all coatings to determine the presence and number of discontinuities in those coatings using a Tinker & Rasor model AP/W Holiday Detector or equal. Holiday inspection shall be performed in a manner spelled out in the Tinker & Rasor operating

instructions and at a voltage level recommended by the coating Contract No. 36C26319D0044

Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

04-01-20

manufacturer or applicable NACE standard such as SP0274 or SP0490 in the case thermosetting epoxy coating. Holiday Detectors shall be calibrated and supplied with a certificate of calibration from the factory. A calibration of the Holiday Detector shall be performed once every 6 months to verify output voltages are true and correct.

- D. Steel Fittings:
  - 1. Butt weld fittings, wrought steel, ASME B16.9.
  - 2. Socket weld and threaded fittings forged steel, ASME B16.11.
  - 3. Grooved End: Ductile iron (ASTM A536, Grade 65-45-12), malleable iron (ASTM A47/A47M, Grade 32510), or steel (ASTM A53/A53M, Type F or Type E or S, Grade B).
- E. Steel Joints: Welded, ASME B31.8.

# 2.2 EMERGENCY GAS SAFETY SHUT-OFF VALVE

- A. Permits remote shut-off of fuel gas flow to boiler plant.
- B. Type: Manually opened, electrically held open, automatic closing upon power interruption. Pneumatic operator is prohibited.
- C. Performance: Shall shut bubble tight within one second after power interruption. Refer to the drawings for pressure, flow, and valve size requirements.
- D. Service: Natural gas and LP gas.
- E. Construction: UL listed, FM approved, rated for 861 kPa (125 psig) ASME flanged ends for pipe sizes above 50 mm (2 inches), threaded ends for pipe sizes 50 mm (2 inches) and under. Cast iron, cast steel or bronze body, open and shut indicator. Valves for LP gas service shall be rated at 1725 kPa (250 psig).
- F. Control Switch: Mounted at exterior doorways (multiple switches).

  Switch shall also cut the power to the fuel oil pump set. Refer to

  Section 23 09 11, INSTRUMENTATION AND CONTROL FOR BOILER PLANT. Provide
  auxiliary switch to.

# 2.3 FUEL GAS PIPING ABOVE GROUND

- A. Pipe: Black steel, ASTM A53/A53M, Schedule 40.
- B. Nipples: Steel, ASTM A733, Schedule 40.
- C. Fittings:
  - 1. Sizes 50 mm (2 inch) under ASME B16.3 threaded malleable iron.
  - 2. Over 50 mm (2 inch) and up to 100 mm (4 inch) ASME B16.11 socket welded.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

04-01-20

- 3. Over 100 mm (4 inch) ASME B16.9 butt welded.
- D. Joints: Provide welded or threaded joints.
- E. Threaded Metallic Joints: Threaded joints in metallic pipe shall have tapered threads evenly cut. Metal screwed pipe joints shall be made leak-tight by applying Rector Seal No. 5 pipe thread sealant to all threaded joints. Care must be taken to prevent the pipe dope compound from getting inside the internal pipeline. Teflon tape type sealant is prohibited.

#### 2.4 EXPOSED FUEL GAS PIPING

- A. Finished Room: Use full iron pipe size chrome plated brass piping for exposed fuel gas piping connecting fixtures, casework, cabinets, equipment and reagent racks when not concealed by apron including those furnished by the Government or specified in other sections.
  - 1. Pipe: ASTM B43, standard weight.
  - 2. Fittings: ASME B16.15 cast bronze threaded fittings with chrome finish, (125 and 250).
  - 3. Nipples: ASTM B687, Chromium-plated.
  - 4. Unions: 50 mm (2 inches) and smaller MSS SP-72, MSS SP-110, brass or bronze threaded with chrome finish. Unions 65 mm (2-1/2 inches) and larger shall be flange type with approved gaskets.
  - 5. Valves: MSS SP-72, MSS SP-110, brass or bronze with chrome finish.
- B. Unfinished Rooms, Mechanical Rooms and Kitchens: Chrome-plated brass piping is not required. Paint piping systems as specified in Section 09 91 00, PAINTING.

# 2.5 VALVES

- A. Ball Valve: Bronze body, rated for 1034 kPa at 185 degrees C (150 psig at 365 degrees F), 1723 kPa at 121 degrees C (250 psig at 250 degrees F), reinforced TFE seat, stem seal and thrust washer; end entry, threaded ends, UL-listed for natural or LP gas shut off service when used on those services.
- B. Gas Vent Cocks: Type 701: Bronze body, tee handle, rated for 207 kPa at 38 degrees C (30 psig at 100 degrees F), ground plug, rated for tight shut-off on fuel gas service.

# 2.6 WATERPROOFING

A. Provide at points where pipes pass through membrane waterproofed floors or walls in contact with earth.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

04-01-20

- B. Floors: Provide cast iron stack sleeve with flashing device and a underdeck clamp. After stack is passed through sleeve, provide a waterproofed caulked joint at top hub.
- C. Walls: See detail shown on drawings.

#### 2.7 STRAINERS

- A. Provide on high pressure side of pressure reducing valves, on inlet side of indicating and control instruments and equipment subject to sediment damage and where shown on drawings. Strainer element shall be removable without disconnection of piping.
- B. Gas Lines: "Y" type with removable mesh lined brass strainer sleeve.
- C. Body: Smaller than 75 mm (3 inches), brass or bronze; 75 mm (3 inches) and larger, cast iron or semi-steel.

#### 2.8 DIELECTRIC FITTINGS

A. Provide dielectric couplings or unions between ferrous and non-ferrous pipe.

# 2.9 GAS EQUIPMENT CONNECTORS

A. Flexible connectors with Teflon core, interlocked galvanized steel protective casing, AGA certified design.

#### 2.10 FUEL GAS PIPING BELOW GROUND

- A. Thermoplastic (Polyethylene PE): PE pipe and heat fusion fittings shall conform to ASTM D2513, SDR 11 and manufactured for 861 kPa (125 psig) working pressure. Pipe and fittings shall have heat fusion joints PE pipe and fitting materials for heat fusion shall be compatible to ensure uniform melting and a proper bond.
- B. Fittings:
  - 1. Socket Fusion Fittings: ASTM D2683.
  - 2. Butt Fusion Fittings: ASTM D3261, molded and matching pipe dimensions.
- C. Risers: Manufacturer's standard anodeless type riser, transition from plastic to steel pipe with fusion bonded epoxy coating. Inlet connection socket or butt weld or swaged gas-tight construction with O-ring seals, metal insert, and protective sleeve. Outlet or above ground connection end shall be threaded or flanged. Riser shall comply with ASTM A53/A53M, Type F and E, Grade A, Schedule 40.
- D. Polyethylene ball valves, ASME B16.40 shall be manufactured and rated for underground gas service. Operating pressure to 861 kPa (125 psig)

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

04-01-20

(SDR 9.3). Valve shall be maintenance and corrosion free. Polyethylene valves shall be full port opening type. Valves shall be wrench operated. Wrench operated valves shall have a 50 mm (2 inch) square adaptor securely fastened to the valve stem. Polyethylene valves shall be installed by butt fusion method.

# 2.11 VALVE BOXES

A. Provide each valve on buried piping with a plastic or cast iron valve box of a size suitable for the valve. Valve box shall have a round cover with the word "Gas" cast on it. A metal tag or label shall be installed on top or inside of each valve box lid. The tag shall designate the appropriate location number, valve size, and other pertinent information. Each cast iron box shall be given a heavy coat of bituminous paint. Provide adjustable box extensions of length required for depth of buried valve.

#### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. General: Comply with the ICC IFGC, ICC IPC and the following:
  - Install branch piping for fuel gas and connect to all fixtures, valves, cocks, outlets, casework, cabinets and equipment, including those furnished by the Government or specified in other sections.
  - 2. Pipe shall be round and straight. Cutting shall be done with proper tools. Pipe, shall be reamed to full size after cutting.
  - 3. All pipe runs shall be laid out to avoid interference with other work.
  - 4. Install valves with stem in horizontal position whenever possible.

    All valves shall be easily accessible.
  - 5. Install union and shut-off valve on pressure piping at connections to equipment.
  - 6. Pipe Hangers, Supports and Accessories:
    - a. All piping shall be supported per the ICC IFGC.
    - b. Shop Painting and Plating: Hangers, supports, rods, inserts and accessories used for Pipe supports shall be shop coated with red lead or zinc Chromate primer paint. Electroplated copper hanger rods, hangers and accessories may be used with copper tubing.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- c. Floor, Wall and Ceiling Plates, Supports, Hangers:
  - Solid or split unplated cast iron, chrome plated in finished areas.
  - 2) All plates shall be provided with set screws.
  - 3) Pipe Hangers: Height adjustable clevis type.
  - 4) Adjustable Floor Rests and Base Flanges: Steel.
  - 5) Concrete Inserts: "Universal" or continuous slotted type.
  - 6) Hanger Rods: Mild, low carbon steel, fully threaded or
    Threaded at each end with two removable nuts at each end for
    positioning rod and hanger and locking each in place.
  - 7) Riser Clamps: Malleable iron or steel.
  - 8) Rollers: Cast iron.
  - 9) Self-drilling type expansion shields shall be "Phillips" type, with case hardened steel expander plugs.
  - 10) Miscellaneous Materials: As specified, required, directed or as noted on the drawings for proper installation of hangers, supports and accessories.
- 7. Install cast chrome plated escutcheon with set screw at each wall, floor and ceiling penetration in exposed finished locations and within cabinets and millwork.
- 8. Penetrations:
  - a. Fire Stopping: Where pipes pass through fire partitions, fire walls, smoke partitions, or floors, install a fire stop that provides an effective barrier against the spread of fire, smoke and gases as specified in Section 07 84 00, FIRESTOPPING.

    Completely fill and seal clearances between piping and openings with the fire stopping materials.
  - b. Waterproofing: At floor penetrations, completely seal clearances around the pipe and make watertight with sealant as specified in Section 07 92 00, JOINT SEALANTS.
- B. Fuel gas piping shall conform to the following:
  - 1. Entire fuel gas piping installation shall be in accordance with requirements of NFPA 54.
  - 2. Provide fuel gas piping with plugged drip pockets at low points.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

04-01-20

C. If an installation is unsatisfactory to the COR, the Contractor shall correct the installation at no additional cost or time to the Government.

#### 3.2 CLEANING OF SYSTEM AFTER INSTALLATION

A. Clean all piping systems to remove all dirt, coatings and debris.

Remove all valves, controls etc., and reinstall after piping system has been cleaned.

#### 3.3 TESTS

- A. General: Test system either in its entirety or in sections after system is installed or cleaned.
- B. Test shall be made in accordance with Section 406 of the International Fuel Gas Code. The system shall be tested at a minimum of 1.5 times maximum working pressure, but not less than 3 psig (21 kPa) gauge.
- C. System Purging: After completing pressure tests, and before testing a gas-contaminated line, purge line with nitrogen at junction with main line to remove all air and gas. Clear completed line by attaching a test pilot fixture at capped stub-in line at building location and let gas flow until test pilot ignites. Procedures shall conform to NFPA 54 and ASME B31.8.

# 3.4 STARTUP AND TESTING

- A. Perform tests as recommended by product manufacturer and listed standards and under actual or simulated operating conditions and prove full compliance with design and specified requirements. Tests of the various items of equipment shall be performed simultaneously with the system of which each item is an integral part.
- B. When any defects are detected, correct defects and repeat test at no additional cost or time to the Government.

# 3.5 COMMISSIONING (NOT USED)

# 3.6 DEMONSTRATION AND TRAINING

A. Provide services of manufacturer's technical representative for 4 hours to instruct each VA personnel responsible in operation and maintenance of the system.

---END---

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

## SECTION 23 23 00 REFRIGERANT PIPING

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. Field refrigerant piping for direct expansion HVAC systems. Field refrigerant piping and associated drain and condenser water piping for laboratory refrigerators, including required pipe insulation.
- B. Refrigerant piping shall be sized, selected, and designed either by the equipment manufacturer or in strict accordance with the manufacturer's published instructions. The schematic piping diagram shall show all accessories such as, stop valves, level indicators, liquid receivers, oil separator, gauges, thermostatic expansion valves, solenoid valves, moisture separators and driers to make a complete installation.

#### C. Definitions:

- Refrigerating system: Combination of interconnected refrigerant-containing parts constituting one closed refrigeration circuit in which a refrigerant is circulated for the purpose of extracting heat.
  - a. Low side means the parts of a refrigerating system subjected to evaporator pressure.
  - b. High side means the parts of a refrigerating system subjected to condenser pressure.
- 2. Brazed joint: A gas-tight joint obtained by the joining of metal parts with alloys which melt at temperatures higher than 449 degrees C (840 degrees F) but less than the melting temperatures of the joined parts.

### 1.2 RELATED WORK

- A. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Section 11 41 21, WALK IN COOLERS and FREEZERS.
- C. Section 11 53 23, LABORATORY REFRIGERATORS.
- D. Section 11 78 13, MORTUARY REFRIGERATORS.
- G. Section 23 05 11, COMMON WORK RESULTS FOR HVAC.

## 1.3 QUALITY ASSURANCE

- A. Refer to specification Section 23 05 11, COMMON WORK RESULTS FOR HVAC.
- B. Comply with ASHRAE Standard 15, Safety Code for Mechanical Refrigeration. The application of this Code is intended to assure the

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- safe design, construction, installation, operation, and inspection of every refrigerating system employing a fluid which normally is vaporized and liquefied in its refrigerating cycle.
- C. Comply with ASME B31.5: Refrigerant Piping and Heat Transfer Components.
- D. Products shall comply with UL 207 "Refrigerant-Containing Components and Accessories, "Nonelectrical"; or UL 429 "Electrical Operated Valves."

#### 1.4 SUBMITTALS

- A. Submit in accordance with specification Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Shop Drawings:
  - 1. Complete information for components noted, including valves and refrigerant piping accessories, clearly presented, shall be included to determine compliance with drawings and specifications for components noted below:
    - a. Tubing and fittings
    - b. Valves
    - c. Strainers
    - d. Moisture-liquid indicators
    - e. Filter-driers
    - f. Flexible metal hose
    - g. Liquid-suction interchanges
    - h. Oil separators (when specified)
    - i. Gages
    - j. Pipe and equipment supports
    - k. Refrigerant and oil
    - 1. Pipe/conduit roof penetration cover
    - m. Soldering and brazing materials
  - 2. Layout of refrigerant piping and accessories, including flow capacities, valves locations, and oil traps slopes of horizontal runs, floor/wall penetrations, and equipment connection details.
- C. Certification: Copies of certificates for welding procedure, performance qualification record and list of welders' names and symbols.

### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

D. Design Manual: Furnish two copies of design manual of refrigerant valves and accessories.

#### 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- C. American Society of Heating Refrigerating and Air Conditioning Engineers (ASHRAE):
  - 15-2019......Safety Standard for Refrigeration Systems (ANSI)
  - 17-2008.............Method of Testing Capacity of Thermostatic Refrigerant Expansion Valves (ANSI)
  - 63.1-2001......Method of Testing Liquid Line Refrigerant Driers (ANSI)
  - 63.2-2010......Method of Testing Liquid Line Filter Drier Filtration Capability (ANSI)
- D. American National Standards Institute (ANSI):
  - A13.1-2015 Scheme for Identification of Piping Systems Z535.1-2017.....Safety Color Code
- E. American Society of Mechanical Engineers (ASME):
  - B16.22-2018 Wrought Copper and Copper Alloy Solder-Joint Pressure Fittings (ANSI)
  - B16.24-20016 Cast Copper Alloy Pipe Flanges and Flanged Fittings, Class 150, 300, 400, 600, 900, 1500 and 2500 (ANSI)
  - B31.5-2013 Refrigeration Piping and Heat Transfer Components (ANSI)
  - B40.100-2013.....Pressure Gauges and Gauge Attachments
  - B40.200-2008......Thermometers, Direct Reading and Remote Reading
- ${\tt F.}$  American Society for Testing and Materials (ASTM)

## EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

	02-01-20 A126-2014Standard Specification for Gray Iron Castings
	for Valves, Flanges, and Pipe Fittings
	B32-08Standard Specification for Solder Metal
	B88-2016Standard Specification for Seamless Copper
	Water Tube
	B88M-2018Standard Specification for Seamless Copper
	Water Tube (Metric)
	B280-2019Standard Specification for Seamless Copper Tube
	for Air Conditioning and Refrigeration Field
	Service
G.	American Welding Society, Inc. (AWS):Brazing Handbook
	A5.8/A5.8M-2011Standard Specification for Filler Metals for
	Brazing and Braze Welding
Н.	Underwriters Laboratories (U.L.):
	U.L.207-2018Standard for Refrigerant-Containing Components
	and Accessories, Nonelectrical
	U.L.429-2013Standard for Electrically Operated Valves
ъπ •	2 - PRODITOTS

## PART 2 - PRODUCTS

### 2.1 PIPING AND FITTINGS

- A. Refrigerant Piping: For piping up to 100 mm (4 inch) use Copper refrigerant tube, ASTM B280, cleaned, dehydrated and sealed, marked ACR on hard temper straight lengths. Coils shall be tagged ASTM B280 by the manufacturer. For piping over 100 mm (4 inch) use A53 Black SML steel.
- B. Water and Drain Piping: Copper water tube, ASTM B88M, Type B or C (ASTM B88, Type M or L). Optional drain piping material: Schedule 80 flame retardant Polypropylene plastic.
- C. Fittings, Valves and Accessories:
  - 1. Copper fittings: Wrought copper fittings, ASME B16.22.
    - a. Brazed Joints, refrigerant tubing: Cadmium free, AWS A5.8/A5.8M, 45 percent silver brazing alloy, Class BAg-5.
    - b. Solder Joints, water and drain: 95-5 tin-antimony, ASTM B32 (95TA).
  - 2. Steel fittings: ASTM wrought steel fittings.
    - a. Refrigerant piping Welded Joints.
  - 3. Flanges and flanged fittings: ASME B16.24.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

## 4. Refrigeration Valves:

- a. Stop Valves: Brass or bronze alloy, packless, or packed type with gas tight cap, frost proof, back seating.
- b. Pressure Relief Valves: Comply with ASME Boiler and Pressure Vessel Code; UL listed. Forged brass with nonferrous, corrosion resistant internal working parts of high strength, cast iron bodies conforming to ASTM A126, Grade B. Set valves in accordance with ASHRAE Standard 15.
- c. Solenoid Valves: Comply with ARI 760 and UL 429, UL-listed, two-position, direct acting or pilot-operated, moisture and vapor-proof type of corrosion resisting materials, designed for intended service, and solder-end connections. Fitted with suitable NEMA 250 enclosure of type required by location and normally open holding coil.
- d. Thermostatic Expansion Valves: Comply with ARI 750. Brass body with stainless-steel or non-corrosive nonferrous internal parts, diaphragm and spring-loaded (direct-operated) type with sensing bulb and distributor having side connection for hot-gas bypass and external equalizer. Size and operating characteristics as recommended by manufacturer of evaporator and factory set for superheat requirements. Solder-end connections. Testing and rating in accordance with ASHRAE Standard 17.
- e. Check Valves: Brass or bronze alloy with swing or lift type, with tight closing resilient seals for silent operation; designed for low pressure drop, and with solder-end connections. Direction of flow shall be legibly and permanently indicated on the valve body.
- 5. Strainers: Designed to permit removing screen without removing strainer from piping system, and provided with screens 80 to 100 mesh in liquid lines DN 25 (NPS 1) and smaller, 60 mesh in liquid lines larger than DN 25 (NPS 1), and 40 mesh in suction lines. Provide strainers in liquid line serving each thermostatic expansion valve, and in suction line serving each refrigerant compressor not equipped with integral strainer.
- 6. Refrigerant Moisture/Liquid Indicators: Double-ported type having heavy sight glasses sealed into forged bronze body and incorporating

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

means of indicating refrigerant charge and moisture indication. Provide screwed brass seal caps.

- 7. Refrigerant Filter-Dryers: UL listed, angle or in-line type, as shown on drawings. Conform to ARI Standard 730 and ASHRAE Standard 63.1. Heavy gage steel shell protected with corrosion-resistant paint; perforated baffle plates to prevent desiccant bypass. Size as recommended by manufacturer for service and capacity of system with connection not less than the line size in which installed. Filter driers with replaceable filters shall be furnished with one spare element of each type and size.
- 8. Flexible Metal Hose: Seamless bronze corrugated hose, covered with bronze wire braid, with standard copper tube ends. Provide in suction and discharge piping of each compressor.
- 9. Water Piping Valves and Accessories: Refer to specification Section 23 21 13, HYDRONIC PIPING, Section 23 64 00, PACKAGED WATER CHILLERS and Section 13 21 29, CONSTANT TEMPERATURE ROOM.

#### 2.2 GAGES

- A. Temperature Gages: Comply with ASME B40.200. Industrial-duty type and in required temperature range for service in which installed. Gages shall have Celsius scale in 1-degree (Fahrenheit scale in 2-degree) graduations and with black number on a white face. The pointer shall be adjustable. Rigid stem type temperature gages shall be provided in thermal wells located within 1525 mm (5 feet) of the finished floor. Universal adjustable angle type or remote element type temperature gages shall be provided in thermal wells located 1525 to 2135 mm (5 to 7 feet) above the finished floor. Remote element type temperature gages shall be provided in thermal wells located 2135 mm (7 feet) above the finished floor.
- B. Vacuum and Pressure Gages: Comply with ASME B40.100 and provide with throttling type needle valve or a pulsation dampener and shut-off valve. Gage shall be a minimum of 90 mm (3-1/2 inches) in diameter with a range from 0 kPa (0 psig) to approximately 1.5 times the maximum system working pressure. Each gage range shall be selected so that at normal operating pressure, the needle is within the middle-third of the range.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- 1. Suction: 101 kPa (30 inches Hg) vacuum to 1723 kPa (gage) (250 psig).
- 2. Discharge: 0 to 3445 kPa (gage) (0 to 500 psig).

## 2.3 THERMOMETERS AND WELLS (NOT USED)

#### 2.4 PIPE SUPPORTS

A. Refer to specification Section 23 05 11, COMMON WORK RESULTS FOR HVAC.

#### 2.5 ELECTRICAL HEAT TRACING SYSTEM (NOT USED)

#### 2.6 REFRIGERANTS AND OIL

A. Provide EPA approved refrigerant and oil for proper system operation.

#### 2.7 PIPE/CONDUIT ROOF PENETRATION COVER

- A. Prefabricated Roof Curb: Galvanized steel or extruded aluminum 300 mm (12 inches) overall height, continuous welded corner seams, treated wood nailer, 38 mm (1-1/2 inch) thick, 48 kg/cu.m (3 lb/cu.ft.) density rigid mineral fiberboard insulation with metal liner, built-in can't strip (except for gypsum or tectum decks). For surface insulated roof deck, provide raised cant strip (recessed mounting flange) to start at the upper surface of the insulation. Curbs shall be constructed for pitched roof or ridge mounting as required to keep top of curb level.
- B. Penetration Cover: Galvanized sheet metal with flanged removable top. Provide 38 mm (1-1/2 inch) thick mineral fiber board insulation.
- C. Flashing Sleeves: Provide sheet metal sleeves for conduit and pipe penetrations of the penetration cover. Seal watertight penetrations.

## 2.8 PIPE INSULATION FOR DX HVAC SYSTEMS (NOT USED)

## 2.9 PIPE INSULATION FOR WALK-IN COOLERS AND FREEZERS AND LABORATORY REFRIGERATORS AND MORTUARY REFRIGERATORS (NOT USED)

## PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Install refrigerant piping and refrigerant containing parts in accordance with ASHRAE Standard 15 and ASME B31.5
  - Install piping as short as possible, with a minimum number of joints, elbow and fittings.
  - 2. Install piping with adequate clearance between pipe and adjacent walls and hangers to allow for service and inspection. Space piping, including insulation, to provide 25 mm (1 inch) minimum clearance between adjacent piping or other surface. Use pipe sleeves through

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

walls, floors, and ceilings, sized to permit installation of pipes with full thickness insulation.

- 3. Locate and orient valves to permit proper operation and access for maintenance of packing, seat and disc. Generally locate valve stems in overhead piping in horizontal position. Provide a union adjacent to one end of all threaded end valves. Control valves usually require reducers to connect to pipe sizes shown on the drawing.
- 4. Use copper tubing in protective conduit when installed below ground.
- 5. Install hangers and supports per ASME B31.5 and the refrigerant piping manufacturer's recommendations.

#### B. Joint Construction:

- 1. Brazed Joints: Comply with AWS "Brazing Handbook" and with filler materials complying with AWS A5.8/A5.8M.
  - a. Use Type BcuP, copper-phosphorus alloy for joining copper socket fittings with copper tubing.
  - b. Use Type BAg, cadmium-free silver alloy for joining copper with bronze or steel.
  - c. Swab fittings and valves with manufacturer's recommended cleaning fluid to remove oil and other compounds prior to installation.
  - d. Pass nitrogen gas through the pipe or tubing to prevent oxidation as each joint is brazed. Cap the system with a reusable plug after each brazing operation to retain the nitrogen and prevent entrance of air and moisture.
- C. Protect refrigerant system during construction against entrance of foreign matter, dirt and moisture; have open ends of piping and connections to compressors, condensers, evaporators and other equipment tightly capped until assembly.
- D. Pipe relief valve discharge to outdoors for systems containing more than 45 kg (100 lbs) of refrigerant.
- E. Firestopping: Fill openings around uninsulated piping penetrating floors or fire walls, with firestop material. For firestopping insulated piping refer to Section 23 07 11, HVAC, and BOILER PLANT INSULATION.
- F. Seismic Bracing: Refer to specification Section 13 05 41, SEISMIC RESTRAINTS REQUIREMENTS FOR NON-STRUCTURAL COMPONENTS, for bracing of piping in seismic areas.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

#### 3.2 PIPE AND TUBING INSULATION

- A. Refer to specification Section 23 05 11, COMMON WORK RESULTS FOR HVAC.
- B. Apply two coats of weather-resistant finish as recommended by the manufacturer to insulation exposed to outdoor weather.

## 3.3 SIGNS AND IDENTIFICATION

- A. Each refrigerating system erected on the premises shall be provided with an easily legible permanent sign securely attached and easily accessible, indicating thereon the name and address of the installer, the kind and total number of pounds of refrigerant required in the system for normal operations, and the field test pressure applied.
- B. Systems containing more than 50 kg (110 lb) of refrigerant shall be provided with durable signs, in accordance with ANSI A13.1 and ANSI Z535.1, having letters not less than 13 mm (1/2 inch) in height designating:
  - 1. Valves and switches for controlling refrigerant flow, the ventilation and the refrigerant compressor(s).
  - 2. Signs on all exposed high pressure and low pressure piping installed outside the machinery room, with name of the refrigerant and the letters "HP" or "LP."

#### 3.4 FIELD QUALITY CONTROL

- A. Prior to initial operation examine and inspect piping system for conformance to plans and specifications and ASME B31.5. Correct equipment, material, or work rejected because of defects or nonconformance with plans and specifications, and ANSI codes for pressure piping.
- B. After completion of piping installation and prior to initial operation, conduct test on piping system according to ASME B31.5. Furnish materials and equipment required for tests. Perform tests in the presence of Contracting Officer's Representative. If the test fails, correct defects and perform the test again until it is satisfactorily done and all joints are proved tight.
  - 1. Every refrigerant-containing parts of the system that is erected on the premises, except compressors, condensers, evaporators, safety devices, pressure gages, control mechanisms and systems that are factory tested, shall be tested and proved tight after complete installation, and before operation.

### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

02-01-20

- 2. The high and low side of each system shall be tested and proved tight at not less than the lower of the design pressure or the setting of the pressure-relief device protecting the high or low side of the system, respectively, except systems erected on the premises using non-toxic and non-flammable Group A1 refrigerants with copper tubing not exceeding DN 18 (NPS 5/8). This may be tested by means of the refrigerant charged into the system at the saturated vapor pressure of the refrigerant at 20 degrees C (68 degrees F) minimum.
- C. Test Medium: A suitable dry gas such as nitrogen or shall be used for pressure testing. The means used to build up test pressure shall have either a pressure-limiting device or pressure-reducing device with a pressure-relief device and a gage on the outlet side. The pressure relief device shall be set above the test pressure but low enough to prevent permanent deformation of the system components.

## 3.5 SYSTEM TEST AND CHARGING

- A. System Test and Charging: As recommended by the equipment manufacturer or as follows:
  - 1. Connect a drum of refrigerant to charging connection and introduce enough refrigerant into system to raise the pressure to 70 kPa (10 psi) gage. Close valves and disconnect refrigerant drum. Test system for leaks with halide test torch or other approved method suitable for the test gas used. Repair all leaking joints and retest.
  - 2. Connect a drum of dry nitrogen to charging valve and bring test pressure to design pressure for low side and for high side. Test entire system again for leaks.
  - 3. Evacuate the entire refrigerant system by the triplicate evacuation method with a vacuum pump equipped with an electronic gage reading in mPa (microns). Pull the system down to 665 mPa (500 microns) 665 mPa (2245.6 inches of mercury at 60 degrees F) and hold for four hours then break the vacuum with dry nitrogen (or refrigerant). Repeat the evacuation two more times breaking the third vacuum with the refrigeration to be charged and charge with the proper volume of refrigerant.

- - - E N D - - -

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

# SECTION 23 81 00 DECENTRALIZED UNITARY HVAC EQUIPMENT

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section specifies split-systems.
- B. Definitions:
  - 1. Energy Efficiency Ratio (EER): The ratio of net cooling capacity is Btu/h to total rate of electricity input in watts under designated operating conditions (Btu hour/Watt).
  - 2. Seasonal Energy Efficiency Ratio (EER): The ratio of the total cooling output of an air conditioner during its normal annual usage period for cooling in Btu/h divided by total electric energy input in watts during the same period (Btu hour/Watt).
  - 3. Unitary: A Unitary Air Conditioner consists of one or more factory—made assemblies which normally include an evaporator or cooling coil, a compressor and condenser combination, and may include a heating function as well.
  - 4. Where such equipment is provided in more than one assembly the separated assemblies are to be designed to be used together and the requirements of rating are based upon use of matched assemblies.

#### 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES
- C. Section 03 30 00, CAST-IN-PLACE CONCRETE.
- D. Section 07 72 00, ROOF ACCESSORIES.
- E. Section 23 05 11, COMMON WORK RESULTS FOR HVAC.
- F. Section 23 05 41, NOISE and VIBRATION CONTROL FOR HVAC PIPING and EOUIPMENT.
- G. Section 23 05 93, TESTING, ADJUSTING, and BALANCING FOR HVAC.
- H. Section 23 11 23, FACILITY NATURAL-GAS PIPING.
- I. Section 23 23 00, REFRIGERANT PIPING.
- J. Section 23 31 00, HVAC DUCTS and CASINGS.
- K. Section 23 36 00, AIR TERMINAL UNITS.
- L. Section 23 72 00, AIR-TO-AIR ENERGY RECOVERY EQUIPMENT.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

M. Section 28 31 00, FIRE DETECTION and ALARM.

## 1.3 QUALITY ASSURANCE

- A. Refer to specification Section 23 05 11, COMMON WORK RESULTS FOR HVAC.
- B. Safety Standards: ASHRAE Standard 15, Safety Code for Mechanical Refrigeration.

#### 1.4 SUBMITTALS

- A. Submit in accordance with specification Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES
- B. Manufacturer's literature and data:
  - 1. Sufficient information, including capacities, pressure drops, and piping connections clearly presented, shall be included to determine compliance with drawings and specifications for units noted below:
    - a. Unitary air conditioners:
      - 1) Self-contained units
      - 2) Split systems
      - 3) Rooftop units
    - b. Window air conditioners
    - c. Through-the-wall packaged terminal air conditioning units
    - d. Gas-Fired Furnaces
  - 2. Unit Dimensions required clearances, operating weights accessories and start-up instructions.
  - 3. Electrical requirements, wiring diagrams, interlocking and control wiring showing factory installed and portions to be field installed.
  - 4. Mounting and flashing of the roof curb to the roofing structure with coordinating requirements for the roof membrane system.
- C. Certification: Submit proof of specified ARI Certification.
- D. Performance Rating: Submit catalog selection data showing equipment ratings and compliance with required sensible-to-heat-ratio, energy efficiency ratio (EER), and coefficient of performance (COP).
- E. Operating and Maintenance Manual: Submit three copies of Operating and Maintenance manual to Contracting Officer's Representative three weeks prior to final inspection.
- F. Completed System Readiness Checklists provided by the Commissioning Agent and completed by the contractor, signed by a qualified technician and dated on the date of completion, in accordance with the requirements of Section 23 08 00 COMMISSIONING OF HVAC SYSTEMS.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

#### 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. Air-Conditioning, Heating, and Refrigeration Institute (AHRI):
  - 210/240-2017......Performance Rating of Unitary Air-Conditioning and Air-Source Heat Pump Equipment
  - 270-2015..... Sound Rating of Outdoor Unitary Equipment
  - 310/380-2017......Standard for Packaged Terminal Air-Conditioners and Heat Pumps (CSA-C744-04)
  - 340/360-2015......Performance Rating of Commercial and Industrial
    Unitary Air-Conditioning and Heat Pump
    Equipment
  - 520-2004......Performance Rating of Positive Displacement Condensing Units
- C. Air Movement and Control Association (AMCA):
  - 210-2016......Laboratory Methods of Testing Fans for
    Aerodynamic Performance Rating (ANSI)
  - 410-1996......Recommended Safety Practices for Users and
    Installers of Industrial and Commercial Fans
- D. American National Standards Institute (ANSI):
  - S12.51-2017......Acoustics Determination of Sound Power Levels

    of Noise Sources Using Sound Pressure 
    Precision Method for Reverberation Rooms (same
    as ISO 3741:1999)
- E. American Society of Civil Engineers (ASCE)
  - ASCE 7-2017......Minimum Design Loads for Buildings and Other Structures
- F. American Society of Heating, Refrigerating, and Air-Conditioning Engineers (ASHRAE):
  - Handbook 2016......HVAC Systems and Equipment
  - 15-2019......Safety Standard for Refrigeration Systems
    (ANSI)
  - 62.1-2016......Ventilation for Acceptable Indoor Air Quality (ANSI)
- G. American Society of Testing and Materials (ASTM):

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

	03-01-20
	B117-2018Standard Practice for Operating Salt Spray
	(Fog) Apparatus
Н.	Federal Specifications (Fed. Spec.):
	A-A-50502-2009 Air conditioner (Unitary Heat Pump) Air to Air
	(3000-300,000 Btu)
I.	Military Specifications (Mil. Specs.):
	MIL-PRF-26915DPrimer Coating, for Steel Surfaces
J.	National Electrical Manufacturer's Association (NEMA):
	ICS 1-2005Industrial Controls and Systems: General
	Requirements
	MG 1-2019Motors and Generators (ANSI)
К.	National Fire Protection Association (NFPA) Publications:
	90A-2018Standard for the Installation of Air-

Conditioning and Ventilating Systems

#### PART 2 - PRODUCTS

- 2.1 UNITARY AIR CONDITIONERS GENERAL (NOT USED)
- 2.2 SELF-CONTAINED AIR CONDITIONERS (NOT USED)

## 2.3 SPLIT-SYSTEM AIR CONDITIONERS

- A. Description: Factory assembled and tested, wall-mounted unit, with an air-cooled remote condensing unit, and field-installed refrigeration piping.
- B. Concealed Evaporator Components:
  - 1. Chassis: Galvanized steel with flanged edges, removable panels for servicing, and insulation on back of panel.
  - 2. Insulation: Factory-applied duct liner.
  - 3. Drain Pans: Galvanized steel, with connection for drain; insulated and complying with ASHRAE 62.1.
  - 4. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.
  - 5. Refrigerant Coil: Copper tube, with mechanically bonded aluminum fins, complying with AHRI 210/240, and with thermal-expansion valve.
  - 6. Water Coil: Copper tube, with mechanically bonded aluminum fins spaced no closer than 10 fins per 25 mm (1 inch); leak tested to 2070 kPa (300 psig) underwater; and having a modulating control valve.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

- 7. Electric-Resistance Heating Coil: Helical, nickel-chrome, resistance-wire heating elements with refractory ceramic support bushings; automatic-reset thermal cutout; built-in magnetic contactors; manual-reset thermal cutout; airflow proving device; and one-time fuses in terminal box for overcurrent protection. Provide SCR control of electric heating coils as indicated.
- 8. Fan: Forward-curved, double-width wheel of galvanized steel; directly connected to motor.
- 9. Fan Motors: Comply with requirements in Section 23 05 12, GENERAL MOTOR REQUIREMENTS FOR HVAC and STEAM GENERATION EQUIPMENT for multi-tapped, multi-speed motors with internal thermal protection and permanent lubrication.
- 10. Disposable Filters: 25 mm (1 inch) thick, in fiberboard frames with MERV rating of 7 or higher according to ASHRAE 52.2 .
- 11. Wiring Terminations: Connect motor to chassis wiring with plug connection.
- C. Floor-Mounting, Evaporator-Fan Components:
  - 1. Cabinet: Enameled steel with removable panels on front and ends in color selected by Architect.
  - 2. Discharge Grille: Steel with surface-mounted frame.
  - 3. Insulation: Factory-installed duct liner.
  - 4. Drain Pans: Galvanized steel, with connection for drain; insulated and complying with ASHRAE 62.1.
  - 5. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.
  - 6. Coils:
    - a. Refrigerant Coil: Copper tube, with mechanically bonded aluminum fins, complying with AHRI 210/240, and with thermal-expansion valve.
    - b. Water Coil: Copper tube, with mechanically bonded aluminum fins spaced no closer than 10 fins per 25 mm (1 inch); leak tested to 2070 kPa (300 psig) underwater; and having a modulating control valve.
    - c. Electric-Resistance Heating Coil: Helical, nickel-chrome, resistance-wire heating elements with refractory ceramic support bushings; automatic-reset thermal cutout; built-in magnetic

### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

contactors; manual-reset thermal cutout; airflow proving device; and one-time fuses in terminal box for overcurrent protection. Provide minimum two-stage control of electric heating coils as indicated.

- 7. Fan: Direct drive, centrifugal.
- 8. Fan Motors: Comply with requirements in Section 23 05 12, GENERAL MOTOR REQUIREMENTS FOR HVAC and STEAM GENERATION EQUIPMENT for multi-tapped, multi-speed motors with internal thermal protection and permanent lubrication.
- 9. Filters: Disposable, with MERV rating of 7 or higher according to ASHRAE 52.2.
- D. Wall-Mounting, Evaporator-Fan Components:
  - Cabinet: Enameled steel with removable panels on front and ends in color selected by Architect, and discharge drain pans with drain connection.
  - 2. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1. Drain Pan and Drain Connection: Comply with ASHRAE 62.1-2007.
  - 4. Refrigerant Coil: Copper tube, with mechanically bonded aluminum fins, complying with AHRI 210/240, and with thermal-expansion valve.
  - 5. Electric-Resistance Heating Coil: Helical, nickel-chrome, resistance-wire heating elements with refractory ceramic support bushings; automatic-reset thermal cutout; built-in magnetic contactors; manual-reset thermal cutout; airflow proving device; and one-time fuses in terminal box for overcurrent protection.
  - 6. Fan: Direct drive, centrifugal fan.
  - 7. Fan Motors: Comply with requirements in Section 23 05 12, GENERAL MOTOR REQUIREMENTS FOR HVAC and STEAM GENERATION EQUIPMENT for multi-tapped, multi-speed motors with internal thermal protection and permanent lubrication.
  - 8. Filters: Disposable, with MERV rating of 7 or higher according to ASHRAE 52.2.
  - , with MERV rating of 7 or higher according to ASHRAE 52.2.
- F. Air-Cooled, Compressor-Condenser Components:
  - Casing: Steel, finished with baked enamel in color selected by Architect, with removable panels for access to controls, weep holes

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

for water drainage, and mounting holes in base. Service valves, fittings, and gage ports shall be brass and located outside of the casing.

- 2. Compressor: Hermetically sealed scroll with crankcase heater and mounted on vibration isolation. Compressor motor shall have thermal— and current—sensitive overload devices, start capacitor, relay, and contactor.
- 3. Compressor motor with manual-reset, high-pressure switch and automatic-reset, low-pressure switch.
- 4. Refrigerant: R-410A unless otherwise indicated.
- 5. Refrigerant Coil: Copper tube, with mechanically bonded aluminum fins, complying with AHRI 210/240, and with liquid subcooler.
- 6. Fan: Aluminum, propeller type, directly connected to motor.
- 7. Motor: Permanently lubricated, with integral thermal-overload protection.
- 8. Low Ambient Kit: Permit operation down to minus 18 deg C (0 deg F).
- 9. Mounting Base: Polyethylene.
- 10. Minimum Energy Efficiency: Comply with ASHRAE/IESNA 90.1 "Energy Standard for Buildings except Low-Rise Residential Buildings."
- 2.4 ROOFTOP AIR CONDITIONERS (NOT USED)
- 2.5 ROOM-TYPE AIR CONDITIONERS (NOT USED)
- 2.6 PACKAGED TERMINAL AIR CONDITIONERS (NOT USED)
- 2.7 GAS-FIRED FURNACES (NOT USED)

## PART 3 EXECUTION

## 3.1 INSTALLATION

- A. Roof Curb: Install on roof structure or concrete base, level and secure, according to NRCA's "Low-Slope Membrane Roofing Construction Details Manual," Illustration "Raised Curb Detail for Rooftop Air Handling Units and Ducts." ARI Guideline B.
- B. Rooftop Unit Support: Install unit level on structural curbs pilings. Coordinate wall penetrations and flashing with wall construction. Secure rooftop units to structural support with anchor bolts.
- C. Install wind restraints according to manufacturer's written instructions. Wind restrained vibration isolation roof-curb rails are specified in Section 23 05 41, NOISE and VIBRATION CONTROL FOR HVAC PIPING and EQUIPMENT.

### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

- D. Install units level and plumb maintaining manufacturer's recommended clearances and tolerances.
- E. Install water-cooled units with thermometer and pressure gage at the water supply and return connection.
- F. Install vibration spring isolators under base of self-contained unit, with minimum static deflection of 25 mm (1 inch) unless otherwise indicated. Refer to Section 23 05 41, NOISE and VIBRATION CONTROL FOR HVAC PIPING and EOUIPMENT
- G. Install ground-mounting, compressor-condenser components on 100 mm (4-inch) thick, reinforced concrete base; 100 mm (4 inches) larger on each side than unit. Concrete, reinforcement, and formwork are specified in Section 03 30 00, CAST-IN-PLACE CONCRETE. Coordinate anchor installation with concrete base.
- H. Install ground-mounting, compressor-condenser components on polyethylene mounting base.
- I. Install roof-mounting compressor-condenser components on equipment supports specified in Section 07 72 00, ROOF ACCESSORIES. Anchor units to supports with removable, cadmium-plated fasteners.
- K. Install compressor-condenser components on restrained, spring isolators with a minimum static deflection of 25 mm (1 inch) unless otherwise indicated. Refer to Section 23 05 41, NOISE and VIBRATION CONTROL FOR HVAC PIPING and EQUIPMENT.
- L. Install and connect precharged refrigerant tubing to component's quickconnect fittings. Install tubing to allow access to unit.
- M. Install wall sleeves in finished wall assembly and weatherproof.

  Install and anchor wall sleeves to withstand, without damage seismic forces as required by code.

## 3.2 CONNECTIONS

- A. Verify condensate drainage requirements.
- B. Install condensate drain, minimum connection size, with trap and indirect connection to nearest roof drain or area drain.
- C. Install piping adjacent to units to allow service and maintenance.
- D. Gas Piping: Comply with applicable requirements in Section 23 11 23, FACILITY NATURAL-GAS PIPING. Connect gas piping to burner, full size of gas train inlet, and connect with union and shutoff valve with sufficient clearance for burner removal and service.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

- E. Install ducts to termination at top of roof curb. Cut roof decking only as required for passage of ducts. Do not cut out decking under entire roof curb.
- F. Connect supply ducts to units with flexible duct connectors specified in Section 23 31 00, HVAC DUCTS and CASINGS.
- G. Install return-air duct continuously through roof structure.
- H. Install normal-weight, 20.7-MPa (3000-psi), compressive strength (28-day) concrete mix inside roof curb, 100 mm (4 inches) thick.
- I. Ground equipment and install power wiring, switches, and controls for self contained and split systems.
- J. Connect refrigerant piping to coils with shutoff valves on the suction and liquid lines at the coil and a union or flange at each connection at the coil and condenser.
- K. Install ducts to the units with flexible duct connections.
- L. Connect piping with shutoff duty valves on the supply and return side of the coil and unions at all connections and with a throttling valve on the return piping near the coil.
- M. Connect piping with shutoff duty valves on the supply and return side of the water-cooled condenser and unions at all connections and with a throttling valve on the return piping near the condenser
- N. Connect piping with shutoff duty valves and unions on the steam supply and condensate side of the steam coil. On the condensate line near the coil provide a strainer, trap and shutoff valve.

## 3.3 FIELD QUALITY CONTROL

- A. Perform tests and inspections and prepare test reports.
- B. Tests and Inspections: After installing units and after electrical circuitry has been energized, test units for compliance with requirements. Inspect for and remove shipping bolts, blocks, and tiedown straps. After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment. Remove and replace malfunctioning units and retest as specified above.

## 3.4 STARTUP AND TESTING

A. The Commissioning Agent will observe startup and contractor testing of selected equipment. Coordinate the startup and contractor testing

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

schedules with the Contracting Officer's Representative and Commissioning Agent. Provide a minimum of 7 days prior notice.

B. Provide services of manufacturer's technical representative for four hours to instruct VA personnel in operation and maintenance of units.

#### 3.5 COMMISSIONING

- A. Provide commissioning documentation in accordance with the requirements of Section 23 08 00 COMMISSIONING OF HVAC SYSTEMS for all inspection, start up, and contractor testing required above and required by the System Readiness Checklist provided by the Commissioning Agent.
- B. Components provided under this section of the specification will be tested as part of a larger system. Refer to Section 23 08 00 COMMISSIONING OF HVAC SYSTEMS and related sections for contractor responsibilities for system commissioning.

#### 3.6 DEMONSTRATION AND TRAINING

- A. Provide services of manufacturer's technical representative for four hours to instruct VA personnel in operation and maintenance of units.
- B. Submit training plans and instructor qualifications in accordance with the requirements of Section  $23\ 08\ 00$  COMMISSIONING OF HVAC SYSTEMS.

---END---

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

## SECTION 23 82 00 CONVECTION HEATING AND COOLING UNITS

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

This section specifies unit heaters, wall mounted unit heaters

#### 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 09 00, GENERAL COMMISSIONING REQUIREMENTS
- C. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES
- D. Section 13 05 41, SEISMIC RESTRAINT REQUIREMENTS FOR NON-STRUCTURAL COMPONENTS: Seismic restraints for equipment.
- E. Section 23 05 11, COMMON WORK RESULTS FOR HVAC: General mechanical requirements and items, which are common to more than one section of Division 23.
- F. Section 23 05 41, NOISE and VIBRATION CONTROL FOR HVAC PIPING and EQUIPMENT: Noise requirements.
- G. Section 23 05 93, TESTING, ADJUSTING, and BALANCING FOR HVAC: Flow rates adjusting and balancing.
- H. Section 23 31 00, HVAC DUCTS and CASINGS: Ducts and flexible connectors.
- I. Section 23 82 16, AIR COILS: Additional coil requirements.

## 1.3 QUALITY ASSURANCE

Refer to Paragraph, QUALITY ASSURANCE, in Section 23 05 11, COMMON WORK RESULTS FOR HVAC. Provide guarantee in accordance with FAR clause 52.246-21

### 1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Manufacturer's Literature and Data:
  - 1. Unit heaters.
  - 2. Wall Mounted Unit Heaters.
- C. Certificates:
  - 1. Compliance with Article, QUALITY ASSURANCE.
  - 2. Compliance with specified standards.
- D. Operation and Maintenance Manuals: Submit in accordance with Article, INSTRUCTIONS, in Section 01 00 00, GENERAL REQUIREMENTS.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

E. Completed System Readiness Checklists provided by the Commissioning Agent and completed by the contractor, signed by a qualified technician and dated on the date of completion, in accordance with the requirements of Section 23 08 00 COMMISSIONING OF HVAC SYSTEMS.

#### 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. American National Standards Institute / Air Conditioning, Heating and Refrigeration Institute (ANSI/AHRI):

440-2019......Performance Rating of Room Fan Coils National Fire Protection Association (NFPA):

90A-2018.....Standard for the Installation of Air

Conditioning and Ventilating Systems

70-2017.....National Electrical Code

C. Underwriters Laboratories, Inc. (UL):

181-2013......Standard for Factory-Made Air Ducts and Air Connectors

1995-2015......Heating and Cooling Equipment

### PART 2 - PRODUCTS

## 2.1 INDUCTION UNITS (NOT USED)

## 2.2 ROOM FAN-COIL UNITS (NOT USED)

## 2.3 UNIT HEATERS

- A. General: Horizontal or vertical discharge type for steam, hot water or electric heating medium, as indicated.
- B. Casing: Steel sheet, phosphatized to resist rust and finished in baked enamel. Provide hanger supports.
- C. Fan: Propeller type, direct driven by manufacturer's standard electric motor. Provide resilient mounting. Provide fan guard for horizontal discharge units.
- D. Discharge Air Control:
  - 1. Horizontal discharge: Horizontal, adjustable louvers.
  - 2. Vertical discharge: Radial louver diffuser.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

- E. Steam or Hot Water Coil: Aluminum fins bonded to seamless copper tubing by mechanical expansion of the tubing, designed for 517 kPa (75 psig) steam working pressure.
- F. Electric Units: UL listed, factory wired to terminal strips for field connection of power and control wiring.
  - 1. Heating elements: Nickel chromium alloy resistance wire embedded in a magnesium oxide insulating refractory and sealed in corrosion resisting metallic sheath with fins. Three phase heaters shall have balanced phases.
  - 2. Thermal cutout: Manual reset type, which disconnects elements, and motor in the event normal operating temperatures are exceeded.
  - 3. Magnetic contactor: Factory installed with low voltage relay for remote pilot duty thermostat operation.
- G. Controls: Provide field installed remote wall mounted line voltage electric space thermostats to control the unit fan.

## 2.4 CABINET UNIT HEATERS

- A. General: Vertical or horizontal type for steam, hot water or electric heating medium, as indicated.
- B. Cabinet: Not less than 1.3 mm (18 gage) steel with front panel for vertical units and hinged front panel for horizontal units. Finish on exposed cabinet shall be factory-baked enamel in manufacturer's standard color as selected by the Architect. Provide 76 mm (3-inch) high sub-base for vertical floor mounted units.
- C. Fan: Centrifugal blower, direct driven by a single phase, two-speed, electric motor with inherent overload protection. Provide resilient motor/fan mount.
- D. Filter: Manufacturer's standard, one-inch thick, throwaway type MERV 7 filters.
- E. Steam or Hot Water Coil: Aluminum fins bonded to seamless copper tubing by mechanical expansion of the tubing, designed for 517 kPa (75 psi) steam working pressure.
- F. Electric Coil: Spiral sheath or finned-tube construction with Cal-rod resistance elements in aluminum tubes. Units shall be UL listed and factory wired with unit mounted heat switch, magnetic contactors, high temperature cutout safety control, and fan override thermostat.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

G. Factory Mounted Controls: Manual fan starter and three-position (low, high and off) fan speed switch. Provide field installed remote wall mounted line voltage electric space thermostats to control the unit fan.

#### 2.5 WALL-MOUNTED UNIT HEATERS

- A. General: Electric heat, fan driven, thermostatic control, UL listed.
- B. Enclosure:
  - 1. Wall box: Not less than 1.3 mm (18 gage) steel, recessed type.
  - 2. Ribbed 1.6 mm (16 gage) steel front cover.
  - 3. Closely spaced discharge louvers.
  - 4. Concealed screws for locking trim frame to front cover.
  - 5. Finished in baked enamel of manufacturer's standard color with satin finish anodized aluminum trim frame.
- C. Heating Elements: Steel sheath enclosed finned-tube type.
- D. Integral Controls:
  - 1. Two-pole terminal block.
  - 2. Built-in fan delay switch.
  - 3. Automatic reset line voltage internal thermal overheats protection.
  - 4. Built-in thermostat comfort control with adjustment range between -1 to 32 degree C (30-90 degrees F), and manually set "No Heat" position; tamper resistant adjustment by inserting screwdriver through front cover louvers.
- 2.6 CONVECTORS (NOT USED)
- 2.7 FINNED-TUBE RADIATION UNITS (NOT USED)
- 2.8 RADIANT CEILING PANELS (NOT USED)

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Work shall be installed as shown and according to the manufacturer's diagrams and recommendations.
- B. Handle and install units in accordance with manufacturer's written instructions.
- C. Support units rigidly so they always remain stationary. Cross-bracing or other means of stiffening shall be provided as necessary. Method of support shall be such that distortion and malfunction of units cannot occur.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

03-01-20

D. Install fiberglass blanket insulation with a minimum R value of 8 above hydronic radiant panels.

#### 3.2 OPERATIONAL TEST

Refer to Section 23 05 11, COMMON WORK RESULTS FOR HVAC.

#### 3.3 STARTUP AND TESTING

A. The Commissioning Agent will observe startup and contractor testing of selected equipment. Coordinate the startup and contractor testing schedules with the Contracting Officer's Representative and Commissioning Agent. Provide a minimum of 7 days prior notice.


#### 3.4 COMMISSIONING

- A. Provide commissioning documentation in accordance with the requirements of Section 23 08 00 COMMISSIONING OF HVAC SYSTEMS for all inspection, start up, and contractor testing required above and required by the System Readiness Checklist provided by the Commissioning Agent.
- B. Components provided under this section of the specification will be tested as part of a larger system. Refer to Section 23 08 00 COMMISSIONING OF HVAC SYSTEMS and related sections for contractor responsibilities for system commissioning.

## 3.5 DEMONSTRATION AND TRAINING

- A. Provide services of manufacturer's technical representative for four hours to instruct VA personnel in operation and maintenance of units.
- B. Submit training plans and instructor qualifications in accordance with the requirements of Section 23 08 00 COMMISSIONING OF HVAC SYSTEMS.

- - - E N D - - -



## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

# SECTION 26 05 19 LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

## PART 1 - GENERAL

#### 1.1 DESCRIPTION

A. This section specifies the furnishing, installation, connection, and testing of the electrical conductors and cables for use in electrical systems rated 600 V and below, indicated as cable(s), conductor(s), wire, or wiring in this section. For telecommunications grounding see 27-05-26 GROUNDING AND BONDING FOR COMMUNICATIONS SYSTEMS.

#### 1.2 RELATED WORK

- A. Section 07 84 00, FIRESTOPPING: Sealing around penetrations to maintain the integrity of fire-resistant rated construction.
- B. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: Requirements that apply to all sections of Division 26.
- C. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS: Requirements for personnel safety and to provide a low impedance path for possible ground fault currents.
- D. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS: Conduits for conductors and cables.
- E. Section 26 05 41, UNDERGROUND ELECTRICAL CONSTRUCTION: Installation of conductors and cables in manholes and ducts.

### 1.3 QUALITY ASSURANCE

A. Quality Assurance shall be in accordance with Paragraph, QUALIFICATIONS (PRODUCTS AND SERVICES) in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

#### 1.4 SUBMITTALS

- A. Submit in accordance with Paragraph, SUBMITTALS in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, and the following requirements:
  - 1. Shop Drawings:
    - a. Submit sufficient information to demonstrate compliance with drawings and specifications.
    - b. Submit the following data for approval:
      - 1) Electrical ratings and insulation type for each conductor and cable.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

- 2) Splicing materials and pulling lubricant.
- 2. Certifications: Two weeks prior to final inspection, submit the following.
  - a. Certification by the manufacturer that the conductors and cables conform to the requirements of the drawings and specifications.
  - b. Certification by the Contractor that the conductors and cables have been properly installed, adjusted, and tested.

#### 1.5 APPLICABLE PUBLICATIONS

- A. Publications listed below (including amendments, addenda, revisions, supplements and errata) form a part of this specification to the extent referenced. Publications are reference in the text by designation only.
- B. American Society of Testing Material (ASTM):

D2301-10St	andard	Specification	for	Vinyl	Chloride
P	lastic I	Pressure-Sensit	ive	Electi	rical
Ir	nsulatir	ng Tape			

D2304-10	.Test	Method	for	Thermal	Endurance	of	Rigid
	Elec	trical :	Insul	lating Ma	aterials		
D3005-10	.Low-	Temperat	ture	Resistar	nt Vinyl (	.hlo:	ride

Plastic Pressure-Sensitive Electrical
Insulating Tape

- C. National Electrical Manufacturers Association (NEMA):
  - WC 70-09......Power Cables Rated 2000 Volts or Less for the Distribution of Electrical Energy
- D. National Fire Protection Association (NFPA):
  - 70-17......National Electrical Code (NEC)
- E. Underwriters Laboratories, Inc. (UL):

44-14	Thermoset-Ins	sulated W	ires and	Cables

- 83-14......Thermoplastic-Insulated Wires and Cables
- 467-13.....Grounding and Bonding Equipment
- 486A-486B-13.....Wire Connectors
- 486C-13.....Splicing Wire Connectors
- 486D-15.....Sealed Wire Connector Systems
- 486E-15......Equipment Wiring Terminals for Use with

Aluminum and/or Copper Conductors

 $493\hbox{--}07.\dots\dots...\text{Thermoplastic-Insulated Underground Feeder and}$ 

Branch Circuit Cables

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

514B-12......Conduit, Tubing, and Cable Fittings

## PART 2 - PRODUCTS

#### 2.1 CONDUCTORS AND CABLES

- A. Conductors and cables shall be in accordance with ASTM, NEMA, NFPA, UL, as specified herein, and as shown on the drawings.
- B. All conductors shall be copper.
- C. Single Conductor and Cable:
  - 1. No. 12 AWG: Minimum size, except where smaller sizes are specified herein or shown on the drawings.
  - 2. No. 8 AWG and larger: Stranded.
  - 3. No. 10 AWG and smaller: Solid; except shall be stranded for final connection to motors, transformers, and vibrating equipment.
  - 4. Insulation: THHN-THWN and XHHW-2. XHHW-2 shall be used for isolated power systems.
- D. Direct Burial Cable: UF or USE cable.
  - 1. Direct buried grounding cables shall be bare copper.
  - E. Color Code:
    - 1. No. 10 AWG and smaller: Solid color insulation or solid color coating
    - 2. No. 8 AWG and larger: Color-coded using one of the following methods:
      - a. Solid color insulation or solid color coating.
      - b. Stripes, bands, or hash marks of color specified.
      - c. Color using 19 mm (0.75 inches) wide tape.
    - 4. For modifications and additions to existing wiring systems, color coding shall conform to the existing wiring system.
    - 5. Conductors shall be color-coded as follows:

208/120 V	Phase			
Black	A			
Red	В			
Blue	С			
White	Neutral			
* or white with colored (other than green) tracer.				

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

- 6. Lighting circuit "switch legs", and 3-way and 4-way switch "traveling wires," shall have color coding that is unique and distinct (e.g., pink and purple) from the color coding indicated above. The unique color codes shall be solid and in accordance with the NEC. Coordinate color coding in the field with the COR.
- 7. Color code for isolated power system wiring shall be in accordance with the NEC.

#### 2.2 SPLICES

- A. Splices shall be in accordance with NEC and UL.
- B. Above Ground Splices for No. 10 AWG and Smaller:
  - 1. Solderless, screw-on, reusable pressure cable type, with integral insulation, approved for copper and aluminum conductors.
  - 2. The integral insulator shall have a skirt to completely cover the stripped conductors.
  - 3. The number, size, and combination of conductors used with the connector, as listed on the manufacturer's packaging, shall be strictly followed.
- C. Above Ground Splices for No. 8 AWG to No. 4/0 AWG:
  - Compression, hex screw, or bolt clamp-type of high conductivity and corrosion-resistant material, listed for use with copper and aluminum conductors.
  - 2. Insulate with materials approved for the particular use, location, voltage, and temperature. Insulation level shall be not less than the insulation level of the conductors being joined.
  - 3. Splice and insulation shall be product of the same manufacturer.
  - 4. All bolts, nuts, and washers used with splices shall be cadmiumplated steel.
- D. Above Ground Splices for 250 kcmil and Larger:
  - Long barrel "butt-splice" or "sleeve" type compression connectors, with minimum of two compression indents per wire, listed for use with copper and aluminum conductors.
  - 2. Insulate with materials approved for the particular use, location, voltage, and temperature. Insulation level shall be not less than the insulation level of the conductors being joined.
  - 3. Splice and insulation shall be product of the same manufacturer.

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

G. Plastic electrical insulating tape: Per ASTM D2304, flame-retardant, cold and weather resistant.

## 2.3 CONNECTORS AND TERMINATIONS

- A. Mechanical type of high conductivity and corrosion-resistant material, listed for use with copper and aluminum conductors.
- B. Long barrel compression type of high conductivity and corrosion-resistant material, with minimum of two compression indents per wire, listed for use with copper and aluminum conductors.
- C. All bolts, nuts, and washers used to connect connections and terminations to bus bars or other termination points shall be //zincplated//cadmium-plated// steel.

#### 2.4 CONTROL WIRING

- A. Unless otherwise specified elsewhere in these specifications, control wiring shall be as specified herein, except that the minimum size shall be not less than No. 14 AWG.
- B. Control wiring shall be sized such that the voltage drop under in-rush conditions does not adversely affect operation of the controls.

#### 2.5 WIRE LUBRICATING COMPOUND

- A. Lubricating compound shall be suitable for the wire insulation and conduit, and shall not harden or become adhesive.
- B. Shall not be used on conductors for isolated power systems.

#### PART 3 - EXECUTION

## 3.1 GENERAL

- A. Installation shall be in accordance with the NEC, as shown on the drawings, and manufacturer's instructions.
- B. Install all conductors in raceway systems.
- C. Splice conductors only in outlet boxes, junction boxes, pullboxes, manholes, or handholes.
- D. Conductors of different systems (e.g., 120 V and 277 V) shall not be installed in the same raceway.
- E. Install cable supports for all vertical feeders in accordance with the NEC. Provide split wedge type which firmly clamps each individual cable and tightens due to cable weight.
- F. In panelboards, cabinets, wireways, switches, enclosures, and equipment assemblies, neatly form, train, and tie the conductors with non-metallic ties.

## ${\tt EHRM\ Infrastructure\ UpgradesEHRM\ Infrastructure\ Upgrades}$

Bancroft Architects + Engineers

01-01-17

- G. For connections to motors, transformers, and vibrating equipment, stranded conductors shall be used only from the last fixed point of connection to the motors, transformers, or vibrating equipment.
- H. Use expanding foam or non-hardening duct-seal to seal conduits entering a building, after installation of conductors.
- I. Conductor and Cable Pulling:
  - 1. Provide installation equipment that will prevent the cutting or abrasion of insulation during pulling. Use lubricants approved for the cable.
  - 2. Use nonmetallic pull ropes.
  - 3. Attach pull ropes by means of either woven basket grips or pulling eyes attached directly to the conductors.
  - 4. All conductors in a single conduit shall be pulled simultaneously.
  - 5. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- J. No more than three branch circuits shall be installed in any one conduit.
- K. When stripping stranded conductors, use a tool that does not damage the conductor or remove conductor strands.

### 3.2 INSTALLATION IN MANHOLES (NOT USED)

## 3.3 SPLICE AND TERMINATION INSTALLATION

- A. Splices and terminations shall be mechanically and electrically secure, and tightened to manufacturer's published torque values using a torque screwdriver or wrench.
- B. Where the Government determines that unsatisfactory splices or terminations have been installed, replace the splices or terminations at no additional cost to the Government.

#### 3.4 CONDUCTOR IDENTIFICATION

A. When using colored tape to identify phase, neutral, and ground conductors larger than No. 8 AWG, apply tape in half-overlapping turns for a minimum of 75 mm (3 inches) from terminal points, and in junction boxes, pullboxes, and manholes. Apply the last two laps of tape with no tension to prevent possible unwinding. Where cable markings are covered by tape, apply tags to cable, stating size and insulation type.

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

#### 3.5 FEEDER CONDUCTOR IDENTIFICATION

A. In each interior pullbox and each underground manhole and handhole, install brass tags on all feeder conductors to clearly designate their circuit identification and voltage. The tags shall be the embossed type, 40 mm (1-1/2 inches) in diameter and 40 mils thick. Attach tags with plastic ties.

#### 3.6 EXISTING CONDUCTORS

A. Unless specifically indicated on the plans, existing conductors shall not be reused.

#### 3.7 CONTROL WIRING INSTALLATION

- A. Unless otherwise specified in other sections, install control wiring and connect to equipment to perform the required functions as specified or as shown on the drawings.
- B. Install a separate power supply circuit for each system, except where otherwise shown on the drawings.

#### 3.8 CONTROL WIRING IDENTIFICATION AND CONDUIT COLORS:

DATA – BLUE FIRE – RED CONTROLS – GREEN SECURITY – YELLOW

- A. Install a permanent wire marker on each wire at each termination.
- B. Identifying numbers and letters on the wire markers shall correspond to those on the wiring diagrams used for installing the systems.
- C. Wire markers shall retain their markings after cleaning.
- D. In each manhole and handhole, install embossed brass tags to identify the system served and function.

## 3.9 DIRECT BURIAL CABLE INSTALLATION

- A. Tops of the cables:
  - 1. Below the finished grade: Minimum 600 mm (24 inches) unless greater depth is shown.
- C. Work with extreme care near existing ducts, conduits, cables, and other utilities to prevent any damage.
- E. Provide horizontal slack in the cables for contraction during cold weather.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

F. Install the cables in continuous lengths. Splices within cable runs shall not be accepted.

## 3.10 ACCEPTANCE CHECKS AND TESTS

- A. Perform in accordance with the manufacturer's recommendations. In addition, include the following:
  - 1. Visual Inspection and Tests: Inspect physical condition.
  - 2. Electrical tests:
    - a. After installation but before connection to utilization devices, such as fixtures, motors, or appliances, test conductors phaseto-phase and phase-to-ground resistance with an insulation resistance tester. Existing conductors to be reused shall also be tested.
    - b. Applied voltage shall be 500 V DC for 300 V rated cable, and 1000 V DC for 600 V rated cable. Apply test for one minute or until reading is constant for 15 seconds, whichever is longer. Minimum insulation resistance values shall not be less than 25 megohms for 300 V rated cable and 100 megohms for 600 V rated cable.
    - c. Perform phase rotation test on all three-phase circuits.

---END---

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

## SECTION 26 05 26 GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

## PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. THIS SECTION SPECIFIES THE FURNISHING, INSTALLATION, CONNECTION, AND TESTING OF GROUNDING AND BONDING EQUIPMENT, INDICATED AS GROUNDING EQUIPMENT IN THIS SECTION. SEE SECTION 27 05 26 GROUNDING AND BONDING FOR OMMUNICATIONS SYSTEMS
- B. "Grounding electrode system" refers to grounding electrode conductors and all electrodes required or allowed by NEC, as well as made, supplementary, and lightning protection system grounding electrodes.
- C. The terms "connect" and "bond" are used interchangeably in this section and have the same meaning.

#### 1.2 RELATED WORK

- A. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: Requirements that apply to all sections of Division 26.
- B. Section 26 05 19, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES: Low-voltage conductors.
- C. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS: Conduit and boxes.
- D. Section 26 12 19, PAD-MOUNTED, LIQUID-FILLED, MEDIUM-VOLTAGE

  TRANSFORMERS: pad-mounted, liquid-filled, medium-voltage transformers.
- E. Section 26 13 13, MEDIUM-VOLTAGE CIRCUIT BREAKER SWITCHGEAR: Medium-voltage circuit breaker switchgear.
- F. Section 26 23 13, GENERATOR PARALLELING CONTROLS: Generator paralleling controls.
- G. Section 26 13 16, MEDIUM-VOLTAGE FUSIBLE INTERRUPTER SWITCHES: Medium-voltage fusible interrupter switches.
- H. Section 26 22 00, LOW-VOLTAGE TRANSFORMERS: Low-voltage transformers.
- I. Section 26 23 00, LOW-VOLTAGE SWITCHGEAR: Low-voltage switchgear.
- J. Section 26 24 13, DISTRIBUTION SWITCHBOARDS: Low-voltage distribution switchboards.
- K. Section 26 24 16, PANELBOARDS: Low-voltage panelboards.
- L. Section 26 24 19, MOTOR CONTROL CENTERS: Motor control centers.
- M. Section 26 32 13, ENGINE GENERATORS: Engine generators.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

- N. Section 26 36 23, AUTOMATIC TRANSFER SWITCHES: Automatic transfer switches.
- O. Section 26 41 00, FACILITY LIGHTNING PROTECTION: Lightning protection.

## 1.3 QUALITY ASSURANCE

A. Quality Assurance shall be in accordance with Paragraph, QUALIFICATIONS (PRODUCTS AND SERVICES) in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

#### 1.4 SUBMITTALS

- A. Submit in accordance with Paragraph, SUBMITTALS in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, and the following requirements:
  - 1. Shop Drawings:
    - a. Submit sufficient information to demonstrate compliance with drawings and specifications.
    - b. Submit plans showing the location of system grounding electrodes and connections, and the routing of aboveground and underground grounding electrode conductors.
  - 2. Test Reports:
    - a. Two weeks prior to the final inspection, submit ground resistance field test reports to the COR.
  - 3. Certifications:
    - a. Certification by the Contractor that the grounding equipment has been properly installed and tested.

### 1.5 APPLICABLE PUBLICATIONS

- A. Publications listed below (including amendments, addenda, revisions, supplements, and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by designation only.
- B. American Society for Testing and Materials (ASTM):
  - B1-13.....Standard Specification for Hard-Drawn Copper
    Wire
  - B3-13.....Standard Specification for Soft or Annealed Copper Wire
  - B8-11.....Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17
C. Institute of Electrical and Electronics Engineers, Inc. (IEEE):
81-12......IEEE Guide for Measuring Earth Resistivity,
Ground Impedance, and Earth Surface Potentials

of a Ground System Part 1: Normal Measurements

D. National Fire Protection Association (NFPA):

70-17......National Electrical Code (NEC)
70E-15.....National Electrical Safety Code
99-15.....Health Care Facilities

E. Underwriters Laboratories, Inc. (UL):

# PART 2 - PRODUCTS

#### 2.1 GROUNDING AND BONDING CONDUCTORS

- A. Equipment grounding conductors shall be insulated stranded copper, except that sizes No. 10 AWG and smaller shall be solid copper.

  Insulation color shall be continuous green for all equipment grounding conductors, except that wire sizes No. 4 AWG and larger shall be identified per NEC.
- B. Bonding conductors shall be bare stranded copper, except that sizes No. 10 AWG and smaller shall be bare solid copper. Bonding conductors shall be stranded for final connection to motors, transformers, and vibrating equipment.
- C. Conductor sizes shall not be less than shown on the drawings, or not less than required by the NEC, whichever is greater.
- D. Insulation: THHN-THWN and XHHW-2. XHHW-2 shall be used for isolated power systems.

#### 2.2 GROUND RODS

- A. Steel or copper clad steel19 mm (0.75 inch) diameter by 3 M (10 feet) long.
- B. Quantity of rods shall be as shown on the drawings, and as required to obtain the specified ground resistance of 5 ohms.

# 2.3 CONCRETE ENCASED ELECTRODE (NOT USED)

#### 2.4 GROUND CONNECTIONS

A. Below Grade and Inaccessible Locations: Exothermic-welded type connectors.

# ${\tt EHRM} \ \ {\tt Infrastructure} \ \ {\tt UpgradesEHRM} \ \ {\tt Infrastructure} \ \ {\tt Upgrades}$

Bancroft Architects + Engineers

01-01-17

#### B. Above Grade:

- 1. Bonding Jumpers: Listed for use with aluminum and copper conductors. For wire sizes No. 8 AWG and larger, use compression-type connectors. For wire sizes smaller than No. 8 AWG, use mechanical type lugs. Connectors or lugs shall use cadmium-plated steel bolts, nuts, and washers. Bolts shall be torqued to the values recommended by the manufacturer.
- 2. Connection to Building Steel: Exothermic-welded type connectors.
- 3. Connection to Grounding Bus Bars: Listed for use with aluminum and copper conductors. Use mechanical type lugs, with cadmium-plated steel bolts, nuts, and washers. Bolts shall be torqued to the values recommended by the manufacturer.
- 4. Connection to Equipment Rack and Cabinet Ground Bars: Listed for use with copper conductors. Use mechanical type lugs, with cadmiumplated steel bolts, nuts, and washers. Bolts shall be torqued to the values recommended by the manufacturer.

#### 2.5 EQUIPMENT RACK AND CABINET GROUND BARS

A. Provide solid copper ground bars designed for mounting on the framework of open or cabinet-enclosed equipment racks. Ground bars shall have minimum dimensions of 6.3 mm (0.25 inch) thick x 19 mm (0.75 inch) wide, with length as required or as shown on the drawings. Provide insulators and mounting brackets.

### 2.6 GROUND TERMINAL BLOCKS

AT ANY EQUIPMENT MOUNTING LOCATION (E.G., BACKBOARDS AND HINGED COVER ENCLOSURES) WHERE RACK-TYPE GROUND BARS CANNOT BE MOUNTED, PROVIDE MECHANICAL TYPE LUGS, WITH CADMIUM-PLATED STEEL BOLTS, NUTS, AND WASHERS. BOLTS SHALL BE TORQUED TO THE VALUES RECOMMENDED BY THE MANUFACTURER.2.7 GROUNDING BUS BAR

A. Pre-drilled rectangular copper bar with stand-off insulators, minimum 6.3 mm (0.25 inch) thick x 100 mm (4 inches) high in cross-section, length as shown on the drawings, with hole size, quantity, and spacing per detail shown on the drawings. Provide insulators and mounting brackets.

#### PART 3 - EXECUTION

### 3.1 GENERAL

A. Installation shall be in accordance with the NEC, as shown on the drawings, and manufacturer's instructions. Connections to the Triad ground rods shall be clamped, to allow for disconnection and testing.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

# B. System Grounding:

- 1. Secondary service neutrals: Ground at the supply side of the secondary disconnecting means and at the related transformer.
- 2. Separately derived systems (transformers downstream from the service entrance): Ground the secondary neutral.
- C. Equipment Grounding: Metallic piping, building structural steel, electrical enclosures, raceways, junction boxes, outlet boxes, cabinets, machine frames, and other conductive items in close proximity with electrical circuits, shall be bonded and grounded.
- D. For patient care area electrical power system grounding, conform to the latest NFPA 70 and 99.

#### 3.2 INACCESSIBLE GROUNDING CONNECTIONS

A. Make grounding connections, which are normally buried or otherwise inaccessible, by exothermic weld.

#### 3.3 MEDIUM-VOLTAGE EQUIPMENT AND CIRCUITS

- A. Switchgear: Provide a bare grounding electrode conductor from the switchgear ground bus to the grounding electrode system.
- B. Duct Banks and Manholes: Provide an insulated equipment grounding conductor in each duct containing medium-voltage conductors, sized per NEC except that minimum size shall be No. 2 AWG. Bond the equipment grounding conductors to the switchgear ground bus, to all manhole grounding provisions and hardware, to the cable shield grounding provisions of medium-voltage cable splices and terminations, and to equipment enclosures.

# C. Pad-Mounted Transformers:

- 1. Provide a driven ground rod and bond with a grounding electrode conductor to the transformer grounding pad.
- 2. Ground the secondary neutral.
- D. Lightning Arresters: Connect lightning arresters to the equipment ground bus or ground rods as applicable.

# 3.4 SECONDARY VOLTAGE EQUIPMENT AND CIRCUITS

A. Main Bonding Jumper: Bond the secondary service neutral to the ground bus in the service equipment.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

- B. Metallic Piping, Building Structural Steel, and Supplemental
   Electrode(s):
  - 1. Provide a grounding electrode conductor sized per NEC between the service equipment ground bus and all metallic water pipe systems, building structural steel, and supplemental or made electrodes.

    Provide jumpers across insulating joints in the metallic piping.
  - 2. Provide a supplemental ground electrode as shown on the drawings and bond to the grounding electrode system.
- C. Switchgear, Switchboards, Unit Substations, Panelboards, Motor Control Centers, Engine-Generators, Automatic Transfer Switches, and other electrical equipment:
  - 1. Connect the equipment grounding conductors to the ground bus.
  - 2. Connect metallic conduits by grounding bushings and equipment grounding conductor to the equipment ground bus.
- D. Transformers: NOT USED

1

#### 3.5 RACEWAY

- A. Conduit Systems:
  - 1. Ground all metallic conduit systems. All metallic conduit systems shall contain an equipment grounding conductor.
  - 2. Non-metallic conduit systems, except non-metallic feeder conduits that carry a grounded conductor from exterior transformers to interior or building-mounted service entrance equipment, shall contain an equipment grounding conductor.
  - 3. Metallic conduit that only contains a grounding conductor, and is provided for its mechanical protection, shall be bonded to that conductor at the entrance and exit from the conduit.
  - 4. Metallic conduits which terminate without mechanical connection to an electrical equipment housing by means of locknut and bushings or adapters, shall be provided with grounding bushings. Connect bushings with a equipment grounding conductor to the equipment ground bus.
- B. Feeders and Branch Circuits: Install equipment grounding conductors with all feeders, and power and lighting branch circuits.
- C. Boxes, Cabinets, Enclosures, and Panelboards:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

- 1. Bond the equipment grounding conductor to each pullbox, junction box, outlet box, device box, cabinets, and other enclosures through which the conductor passes (except for special grounding systems for intensive care units and other critical units shown).
- 2. Provide lugs in each box and enclosure for equipment grounding conductor termination.

#### D. Wireway Systems:

- Bond the metallic structures of wireway to provide electrical continuity throughout the wireway system, by connecting a No. 6 AWG bonding jumper at all intermediate metallic enclosures and across all section junctions.
- 2. Install insulated No. 6 AWG bonding jumpers between the wireway system, bonded as required above, and the closest building ground at each end and approximately every 16 M (50 feet).
- 3. Use insulated No. 6 AWG bonding jumpers to ground or bond metallic wireway at each end for all intermediate metallic enclosures and across all section junctions.
- 4. Use insulated No. 6 AWG bonding jumpers to ground cable tray to column-mounted building ground plates (pads) at each end and approximately every 15 M (49 feet).
- E. Receptacles shall not be grounded through their mounting screws. Ground receptacles with a jumper from the receptacle green ground terminal to the device box ground screw and a jumper to the branch circuit equipment grounding conductor.
- F. Ground lighting fixtures to the equipment grounding conductor of the wiring system. Fixtures connected with flexible conduit shall have a green ground wire included with the power wires from the fixture through the flexible conduit to the first outlet box.
- G. Fixed electrical appliances and equipment shall be provided with a ground lug for termination of the equipment grounding conductor.
- H. Raised Floors: Provide bonding for all raised floor components as shown on the drawings.
- I. Panelboard Bonding in Patient Care Areas: The equipment grounding terminal buses of the normal and essential branch circuit panel boards serving the same individual patient vicinity shall be bonded together

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

with an insulated continuous copper conductor not less than No. 10 AWG, installed in rigid metal conduit.

# 3.6 OUTDOOR METALLIC FENCES AROUND ELECTRICAL EQUIPMENT

- A. Triad grounds shall be installed in PVC Wells with top of ground rod just below Well Cover.
  - B. Drive ground rods until the top is 300 mm (12 inches) below grade. Attach a No. 4 AWG copper conductor by exothermic weld to the ground rods, and extend underground to the immediate vicinity of fence post. Lace the conductor vertically into 300 mm (12 inches) of fence mesh and fasten by two approved bronze compression fittings, one to bond the wire to post and the other to bond the wire to fence. Each gate section shall be bonded to its gatepost by a 3 mm x 25 mm (0.375 inch x 1 inch) flexible, braided copper strap and ground post clamps. Clamps shall be of the anti-electrolysis type.

# 3.7 CORROSION INHIBITORS

A. When making grounding and bonding connections, apply a corrosion inhibitor to all contact surfaces. Use corrosion inhibitor appropriate for protecting a connection between the metals used.

#### 3.8 CONDUCTIVE PIPING

- A. Bond all conductive piping systems, interior and exterior, to the grounding electrode system. Bonding connections shall be made as close as practical to the equipment ground bus.
- B. In operating rooms and at intensive care and coronary care type beds, bond the medical gas piping and medical vacuum piping at the outlets directly to the patient ground bus.

# 3.9 LIGHTNING PROTECTION SYSTEM

A. Bond the lightning protection system to the electrical grounding electrode system.

# 3.10 MAIN ELECTRICAL ROOM GROUNDING

A. For the 200A Service, Main Electrical Room grounding is provided from the Service Entrance ground Triad. If new 400A meter is installed, the Main Electrical Room grounding will be connected the the grounding triade located at the 400A Meter location. Provide ground bus bar and mounting hardware at each main electrical room where incoming feeders

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

are terminated, as shown on the drawings. Connect to pigtail extensions of the building grounding ring, as shown on the drawings.

#### 3.11 EXTERIOR LIGHT POLES

A. Provide 6.1 M (20 feet) of No. 4 AWG bare copper coiled at bottom of pole base excavation prior to pour, plus additional un-spliced length in and above foundation as required to reach pole ground stud.

#### 3.12 GROUND RESISTANCE

- A. Grounding system resistance to ground shall not exceed 5 ohms. Make any modifications or additions to the grounding electrode system necessary for compliance without additional cost to the Government. Final tests shall ensure that this requirement is met.
- B. Grounding system resistance shall comply with the electric utility company ground resistance requirements.

#### 3.13 GROUND ROD INSTALLATION

- A. Triad grounds shall be installed in PVC Wells with top of ground rod just below Well Cover. For outdoor installations, drive each rod vertically in the earth, until top of rod is 610 mm (24 inches) below final grade.
- B. For indoor installations, leave 100 mm (4 inches) of each rod exposed.
- C. Where buried or permanently concealed ground connections are required, make the connections by the exothermic process, to form solid metal joints. Make accessible ground connections with mechanical pressuretype ground connectors.
- D. Where rock or impenetrable soil prevents the driving of vertical ground rods, install angled ground rods or grounding electrodes in horizontal trenches to achieve the specified ground resistance.

# 3.14 ACCEPTANCE CHECKS AND TESTS

- A. Resistance of the grounding electrode system shall be measured using a four-terminal fall-of-potential method as defined in IEEE 81. Ground resistance measurements shall be made before the electrical distribution system is energized or connected to the electric utility company ground system, and shall be made in normally dry conditions not fewer than 48 hours after the last rainfall.
- B. Resistance measurements of separate grounding electrode systems shall be made before the systems are bonded together. The combined resistance of separate systems may be used to meet the required

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

resistance, but the specified number of electrodes must still be provided.

C. Below-grade connections shall be visually inspected by the COR prior to backfilling. The Contractor shall notify the COR 24 hours before the connections are ready for inspection.

---END---

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

# SECTION 26 05 33 RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS

# PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section specifies the furnishing, installation, and connection of conduit, fittings, and boxes, to form complete, coordinated, grounded raceway systems. Raceways are required for all wiring unless shown or specified otherwise.
- B. Definitions: The term conduit, as used in this specification, shall mean any or all of the raceway types specified.
- C. System Colors

1. SYSTEM	2. CABLE JACKET
3. VOICE	4. WHITE
5. DATA	6. YELLOW
7. DATA	8. GREEN
9. DATA	10. GREY
11. WIRELESS	12. ORANGE
13. VIDEO SURVEILLANCE	14. VIOLET
SURVEILLANCE	
15. NURSE CALL	16. BLUE
17. FIRE ALARM	18. RED
19. BAS & DAS	20. BLACK

#### 1.2 RELATED WORK

- A. Section 06 10 00, ROUGH CARPENTRY: Mounting board for telephone closets.
- B. Section 07 60 00, FLASHING AND SHEET METAL: Fabrications for the deflection of water away from the building envelope at penetrations.
- C. Section 07 84 00, FIRESTOPPING: Sealing around penetrations to maintain the integrity of fire rated construction.
- D. Section 07 92 00, JOINT SEALANTS: Sealing around conduit penetrations through the building envelope to prevent moisture migration into the building.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-18

- E. Section 09 91 00, PAINTING: Identification and painting of conduit and other devices.
- F. Section 13 05 41, SEISMIC RESTRAINT REQUIREMENTS FOR NON-STRUCTURAL COMPONENTS: Conduits bracing.
- G. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: General electrical requirements and items that are common to more than one section of Division 26.
- H. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS: Requirements for personnel safety and to provide a low impedance path for possible ground fault currents.
- I. Section 26 05 41, UNDERGROUND ELECTRICAL CONSTRUCTION: Underground conduits.
- J. Section 31 20 00, EARTHWORK: Bedding of conduits.

#### 1.3 QUALITY ASSURANCE

A. Quality Assurance shall be in accordance with Paragraph, QUALIFICATIONS (PRODUCTS AND SERVICES) in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

#### 1.4 SUBMITTALS

- A. Submit in accordance with Paragraph, SUBMITTALS in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, and the following requirements:
  - 1. Shop Drawings:
    - a. Size and location of main feeders.
    - b. Size and location of panels and pull-boxes.
    - c. Layout of required conduit penetrations through structural elements.
    - d. Submit the following data for approval:
      - 1) Raceway types and sizes.
      - 2) Conduit bodies, connectors and fittings.
      - 3) Junction and pull boxes, types and sizes.
  - 2. Certifications: Two weeks prior to final inspection, submit the following:
    - a. Certification by the manufacturer that raceways, conduits, conduit bodies, connectors, fittings, junction and pull boxes, and all related equipment conform to the requirements of the drawings and specifications.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-18

b. Certification by the Contractor that raceways, conduits, conduit bodies, connectors, fittings, junction and pull boxes, and all related equipment have been properly installed.

#### 1.5 APPLICABLE PUBLICATIONS

- A. Publications listed below (including amendments, addenda, revisions, supplements, and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by designation only.
- B. American Iron and Steel Institute (AISI):

  S100-12......North American Specification for the Design of

  Cold-Formed Steel Structural Members
- - FB2.10-13......Selection and Installation Guidelines for
    Fittings for use with Non-Flexible Conduit or
    Tubing (Rigid Metal Conduit, Intermediate
    Metallic Conduit, and Electrical Metallic
    Tubing)
  - FB2.20-14.....Selection and Installation Guidelines for Fittings for use with Flexible Electrical Conduit and Cable
  - TC-2-13..... Electrical Polyvinyl Chloride (PVC) Tubing and Conduit
- D. National Fire Protection Association (NFPA):
  - 70-17......National Electrical Code (NEC)
- E. Underwriters Laboratories, Inc. (UL):
  - 1-05.....Flexible Metal Conduit
  - 5-16.....Surface Metal Raceway and Fittings
  - 6-07..... Electrical Rigid Metal Conduit Steel

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-18
50-15 Enclosures for Electrical Equipment
360-13Liquid-Tight Flexible Steel Conduit
467-13Grounding and Bonding Equipment
514A-13Metallic Outlet Boxes
514B-12Conduit, Tubing, and Cable Fittings
514C-14Nonmetallic Outlet Boxes, Flush-Device Boxes
and Covers
651-11Schedule 40 and 80 Rigid PVC Conduit and
Fittings
651A-11Type EB and A Rigid PVC Conduit and HDPE
Conduit
797-07Electrical Metallic Tubing
1242-14 Electrical Intermediate Metal Conduit - Steel

# PART 2 - PRODUCTS

#### 2.1 MATERIAL

A. Conduit Size: In accordance with the NEC, but not less than 13 mm (0.5-inch) unless otherwise shown. Where permitted by the NEC, 13 mm (0.5-inch) flexible conduit may be used for tap connections to recessed lighting fixtures.

#### B. Conduit:

- 1. Size: In accordance with the NEC, but not less than 13 mm (0.5-inch) for controls and % in for power.
- 2. Rigid Steel Conduit (RMC): Shall conform to UL 6 and NEMA C80.1.
- 4. Rigid Intermediate Steel Conduit (IMC): Shall conform to UL 1242 and NEMA C80.6.
- 5. Electrical Metallic Tubing (EMT): Shall conform to UL 797 and NEMA C80.3. Maximum size not to exceed 105 mm (4 inches) and shall be permitted only with cable rated 600 V or less.
- 6. Flexible Metal Conduit: Shall conform to UL 1.
- 7. Liquid-tight Flexible Metal Conduit: Shall conform to UL 360.
- 8. Direct Burial Plastic Conduit: Shall conform to UL 651 and UL 651A, heavy wall PVC or high density polyethylene (PE).
- 9. Surface Metal Raceway: Shall conform to UL 5.
- C. Conduit Fittings:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-18

- 1. Rigid Steel and Intermediate Metallic Conduit Fittings:
  - a. Fittings shall meet the requirements of UL 514B and NEMA FB1.
  - b. Standard threaded couplings, locknuts, bushings, conduit bodies, and elbows: Only steel or malleable iron materials are acceptable. Integral retractable type IMC couplings are also acceptable.
  - c. Locknuts: Bonding type with sharp edges for digging into the metal wall of an enclosure.
  - d. Bushings: Metallic insulating type, consisting of an insulating insert, molded or locked into the metallic body of the fitting. Bushings made entirely of metal or nonmetallic material are not permitted.
  - e. Erickson (Union-Type) and Set Screw Type Couplings: Approved for use in concrete are permitted for use to complete a conduit run where conduit is installed in concrete. Use set screws of case-hardened steel with hex head and cup point to firmly seat in conduit wall for positive ground. Tightening of set screws with pliers is prohibited.
  - f. Sealing Fittings: Threaded cast iron type. Use continuous drain-type sealing fittings to prevent passage of water vapor. In concealed work, install fittings in flush steel boxes with blank cover plates having the same finishes as that of other electrical plates in the room.
- 3. Electrical Metallic Tubing Fittings:
  - a. Fittings and conduit bodies shall meet the requirements of UL 514B, NEMA C80.3, and NEMA FB1.
  - b. Only steel or malleable iron materials are acceptable.
  - d. Indent-type connectors or couplings are prohibited.
  - e. Die-cast or pressure-cast zinc-alloy fittings or fittings made of "pot metal" are prohibited.
- 4. Flexible Metal Conduit Fittings:
  - a. Conform to UL 514B. Only steel or malleable iron materials are acceptable.
  - b. Clamp-type, with insulated throat.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

- 5. Liquid-tight Flexible Metal Conduit Fittings:
  - a. Fittings shall meet the requirements of UL 514B and NEMA FB1.
  - b. Only steel or malleable iron materials are acceptable.
  - c. Fittings must incorporate a threaded grounding cone, a steel or plastic compression ring, and a gland for tightening. Connectors shall have insulated throats.
- 6. Direct Burial Plastic Conduit Fittings: Fittings shall meet the requirements of UL 514C and NEMA TC3.
- 7. Surface Metal Raceway Fittings: As recommended by the raceway manufacturer. Include couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, conduit entry fittings, accessories, and other fittings as required for complete system.
- 8. Expansion and Deflection Couplings:
  - a. Conform to UL 467 and UL 514B.
  - b. Accommodate a 19 mm (0.75-inch) deflection, expansion, or contraction in any direction, and allow 30 degree angular deflections.
  - c. Include internal flexible metal braid, sized to guarantee conduit ground continuity and a low-impedance path for fault currents, in accordance with UL 467 and the NEC tables for equipment grounding conductors.
  - d. Jacket: Flexible, corrosion-resistant, watertight, moisture and heat-resistant molded rubber material with stainless steel jacket clamps.

# D. Conduit Supports:

- 1. Parts and Hardware: Zinc-coat or provide equivalent corrosion protection.
- 2. Individual Conduit Hangers: Designed for the purpose, having a pre-assembled closure bolt and nut, and provisions for receiving a hanger rod.
- 3. Multiple Conduit (Trapeze) Hangers: Not less than 38 mm  $\times$  38 mm (1.5 x 1.5 inches), 12-gauge steel, cold-formed, lipped channels; with not less than 9 mm (0.375-inch) diameter steel hanger rods.
- 4. Solid Masonry and Concrete Anchors: Self-drilling expansion shields, or machine bolt expansion.

E. Outlet, Junction, and Pull Boxes: Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

# ${\tt EHRM} \ \ {\tt Infrastructure} \ \ {\tt UpgradesEHRM} \ \ {\tt Infrastructure} \ \ {\tt Upgrades}$

Bancroft Architects + Engineers

01-01-18

- 1. Comply with UL-50 and UL-514A.
- 2. Rustproof cast metal where required by the NEC or shown on drawings.
- 3. Sheet Metal Boxes: Galvanized steel, except where shown on drawings.
- F. Metal Wireways: Equip with hinged covers, except as shown on drawings. Include couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for a complete system.

#### PART 3 - EXECUTION

#### 3.1 PENETRATIONS

- A. Cutting or Holes:
  - 1. Cut holes in advance where they should be placed in the structural elements, such as ribs or beams. Obtain the approval of the COR prior to drilling through structural elements.
  - 2. Cut holes through concrete and masonry in new and existing structures with a diamond core drill or concrete saw. Pneumatic hammers, impact electric, hand, or manual hammer-type drills are not allowed, except when permitted by the COR where working space is limited.
- B. Firestop: Where conduits, wireways, and other electrical raceways pass through fire partitions, fire walls, smoke partitions, or floors, install a fire stop that provides an effective barrier against the spread of fire, smoke and gases as specified in Section 07 84 00, FIRESTOPPING.
- C. Waterproofing: At floor, exterior wall, and roof conduit penetrations, completely seal the gap around conduit to render it watertight, as specified in Section 07 92 00, JOINT SEALANTS.

# 3.2 INSTALLATION, GENERAL

- A. In accordance with NEC, NEMA, UL, as shown on drawings, and as specified herein.
- B. Raceway systems used for Essential Electrical Systems (EES) shall be entirely independent of other raceway systems.
- C. Install conduit as follows:

CONDUIT COLORS:

DATA - BLUE

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

FIRE - RED

CONTROLS - GREEN

SECURITY - YELLOW

- 1. In complete mechanically and electrically continuous runs before pulling in cables or wires.
- Unless otherwise indicated on the drawings or specified herein, installation of all conduits shall be concealed within finished walls, floors, and ceilings.
- 3. Flattened, dented, or deformed conduit is not permitted. Remove and replace the damaged conduits with new conduits.
- 4. Assure conduit installation does not encroach into the ceiling height head room, walkways, or doorways.
- 5. Cut conduits square, ream, remove burrs, and draw up tight.
- 6. Independently support conduit at 2.4 M (8 feet) on centers with specified materials and as shown on drawings.
- 7. Do not use suspended ceilings, suspended ceiling supporting members, lighting fixtures, other conduits, cable tray, boxes, piping, or ducts to support conduits and conduit runs.
- 8. Support within 300 mm (12 inches) of changes of direction, and within 300 mm (12 inches) of each enclosure to which connected.
- 9. Close ends of empty conduits with plugs or caps at the rough-in stage until wires are pulled in, to prevent entry of debris.
- 10. Conduit installations under fume and vent hoods are prohibited.
- 11. Secure conduits to cabinets, junction boxes, pull-boxes, and outlet boxes with bonding type locknuts. For rigid steel and IMC conduit installations, provide a locknut on the inside of the enclosure, made up wrench tight. Do not make conduit connections to junction box covers.
- 12. Flashing of penetrations of the roof membrane is specified in Section 07 60 00, FLASHING AND SHEET METAL.
- 13. Conduit bodies shall only be used for changes in direction, and shall not contain splices.

# D. Conduit Bends:

1. Make bends with standard conduit bending machines.

Contract No. 36C26319D0044 Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121 01-01-18

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

- 2. Conduit hickey may be used for slight offsets and for straightening stubbed out conduits.
- 3. Bending of conduits with a pipe tee or vise is prohibited.

# E. Layout and Homeruns:

- Install conduit with wiring, including homeruns, as shown on drawings.
- 2. Deviations: Make only where necessary to avoid interferences and only after drawings showing the proposed deviations have been submitted and approved by the COR.

#### 3.3 CONCEALED WORK INSTALLATION

#### A. In Concrete:

- 1. Conduit: Rigid steel, IMC, or EMT. Do not install EMT in concrete slabs that are in contact with soil, gravel, or vapor barriers.
- 2. Align and run conduit in direct lines.
- 3. Install conduit through concrete beams only:
  - a. Where shown on the structural drawings.
  - b. As approved by the COR prior to construction, and after submittal of drawing showing location, size, and position of each penetration.
- 4. Installation of conduit in concrete that is less than 75 mm (3 inches) thick is prohibited.
  - a. Conduit outside diameter larger than one-third of the slab thickness is prohibited.
  - b. Space between conduits in slabs: Approximately six conduit diameters apart, and one conduit diameter at conduit crossings.
  - c. Install conduits approximately in the center of the slab so that there will be a minimum of 19 mm (0.75-inch) of concrete around the conduits.
- 5. Make couplings and connections watertight. Use thread compounds that are UL approved conductive type to ensure low resistance ground continuity through the conduits. Tightening setscrews with pliers is prohibited.
- B. Above Furred or Suspended Ceilings and in Walls:
  - 1. Conduit for Conductors Above 600 V: Rigid steel. Mixing different types of conduits in the same system is prohibited.

# ${\tt EHRM} \ \ {\tt Infrastructure} \ \ {\tt UpgradesEHRM} \ \ {\tt Infrastructure} \ \ {\tt Upgrades}$

Bancroft Architects + Engineers

01-01-18

- 2. Conduit for Conductors 600 V and Below: Rigid steel, IMC, or EMT.

  Mixing different types of conduits in the same system is prohibited.
- Align and run conduit parallel or perpendicular to the building lines.
- 4. Connect recessed lighting fixtures to conduit runs with maximum 1.8 M (6 feet) of flexible metal conduit extending from a junction box to the fixture.
- 5. Tightening set screws with pliers is prohibited.
- 6. For conduits running through metal studs, limit field cut holes to no more than 70% of web depth. Spacing between holes shall be at least 457 mm (18 inches). Cuts or notches in flanges or return lips shall not be permitted.

#### 3.4 EXPOSED WORK INSTALLATION

- A. Unless otherwise indicated on drawings, exposed conduit is only permitted in mechanical and electrical rooms.
- B. Conduit for Conductors Above 600 V: Rigid steelMixing different types of conduits in the system is prohibited.
- C. Conduit for Conductors 600 V and Below: Rigid steel, IMC, or EMT. Mixing different types of conduits in the system is prohibited.
- D. Align and run conduit parallel or perpendicular to the building lines.
- E. Install horizontal runs close to the ceiling or beams and secure with conduit straps.
- F. Support horizontal or vertical runs at not over 2.4 M (8 feet) intervals.
- G. Surface Metal Raceways: Use only where shown on drawings.
- H. Painting:
  - 1. Paint exposed conduit as specified in Section 09 91 00, PAINTING.
  - 2. Paint all conduits containing cables rated over 600 V safety orange. Refer to Section 09 91 00, PAINTING for preparation, paint type, and exact color. In addition, paint legends, using 50 mm (2 inch) high black numerals and letters, showing the cable voltage rating. Provide legends where conduits pass through walls and floors and at maximum 6 M (20 feet) intervals in between.

# 3.5 DIRECT BURIAL INSTALLATION

Refer to Section 26 05 41, UNDERGROUND ELECTRICAL CONSTRUCTION.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

#### 3.6 HAZARDOUS LOCATIONS

- A. Use rigid steel conduit only.
- B. Install UL approved sealing fittings that prevent passage of explosive vapors in hazardous areas equipped with explosion-proof lighting fixtures, switches, and receptacles, as required by the NEC.

#### 3.7 WET OR DAMP LOCATIONS

- A. Use rigid steel or IMC conduits unless as shown on drawings.
- B. Provide sealing fittings to prevent passage of water vapor where conduits pass from warm to cold locations, i.e., refrigerated spaces, constant-temperature rooms, air-conditioned spaces, building exterior walls, roofs, or similar spaces.
- C. Use rigid steel or IMC conduit within 1.5 M (5 feet) of the exterior and below concrete building slabs in contact with soil, gravel, or vapor barriers, unless as shown on drawings. Conduit shall be half-lapped with 10 mil PVC tape before installation. After installation, completely recoat or retape any damaged areas of coating.
- D. Conduits run on roof shall be supported with integral galvanized lipped steel channel, attached to UV-inhibited polycarbonate or polypropylene blocks every 2.4 M (8 feet) with 9 mm (3/8-inch) galvanized threaded rods, square washer and locknut. Conduits shall be attached to steel channel with conduit clamps.

#### 3.8 MOTORS AND VIBRATING EQUIPMENT

- A. Use flexible metal conduit for connections to motors and other electrical equipment subject to movement, vibration, misalignment, cramped quarters, or noise transmission.
- B. Use liquid-tight flexible metal conduit for installation in exterior locations, moisture or humidity laden atmosphere, corrosive atmosphere, water or spray wash-down operations, inside airstream of HVAC units, and locations subject to seepage or dripping of oil, grease, or water.
- C. Provide a green equipment grounding conductor with flexible and liquidtight flexible metal conduit.

#### 3.9 EXPANSION JOINTS

A. Conduits 75 mm (3 inch) and larger that are secured to the building structure on opposite sides of a building expansion joint require expansion and deflection couplings. Install the couplings in accordance with the manufacturer's recommendations.

# ${\tt EHRM} \ \ {\tt Infrastructure} \ \ {\tt UpgradesEHRM} \ \ {\tt Infrastructure} \ \ {\tt Upgrades}$

Bancroft Architects + Engineers

01-01-18

- B. Provide conduits smaller than 75 mm (3 inch) with junction boxes on both sides of the expansion joint. Connect flexible metal conduits to junction boxes with sufficient slack to produce a 125 mm (5 inch) vertical drop midway between the ends of the flexible metal conduit. Flexible metal conduit shall have a green insulated copper bonding jumper installed. In lieu of this flexible metal conduit, expansion and deflection couplings as specified above are acceptable.
- C. Install expansion and deflection couplings where shown.

#### 3.10 CONDUIT SUPPORTS

- A. Safe working load shall not exceed one-quarter of proof test load of fastening devices.
- B. Use pipe straps or individual conduit hangers for supporting individual conduits.
- C. Support multiple conduit runs with trapeze hangers. Use trapeze hangers that are designed to support a load equal to or greater than the sum of the weights of the conduits, wires, hanger itself, and an additional 90 kg (200 lbs). Attach each conduit with U-bolts or other approved fasteners.
- D. Support conduit independently of junction boxes, pull-boxes, fixtures, suspended ceiling T-bars, angle supports, and similar items.
- E. Fasteners and Supports in Solid Masonry and Concrete:
  - 1. New Construction: Use steel or malleable iron concrete inserts set in place prior to placing the concrete.
  - 2. Existing Construction:
    - a. Steel expansion anchors not less than 6 mm (0.25-inch) bolt size and not less than 28 mm  $(1.125\ inch)$  in embedment.
    - b. Power set fasteners not less than 6 mm (0.25-inch) diameter with depth of penetration not less than 75 mm (3 inch).
    - c. Use vibration and shock-resistant anchors and fasteners for attaching to concrete ceilings.
- F. Hollow Masonry: Toggle bolts.
- G. Bolts supported only by plaster or gypsum wallboard are not acceptable.
- H. Metal Structures: Use machine screw fasteners or other devices specifically designed and approved for the application.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

- I. Attachment by wood plugs, rawl plug, plastic, lead or soft metal anchors, or wood blocking and bolts supported only by plaster is prohibited.
- J. Chain, wire, or perforated strap shall not be used to support or fasten
- K. Spring steel type supports or fasteners are prohibited for all uses except horizontal and vertical supports/fasteners within walls.
- L. Vertical Supports: Vertical conduit runs shall have riser clamps and supports in accordance with the NEC and as shown. Provide supports for cable and wire with fittings that include internal wedges and retaining collars.

#### 3.11 BOX INSTALLATION

- A. Boxes for Concealed Conduits:
  - 1. Flush-mounted.
  - 2. Provide raised covers for boxes to suit the wall or ceiling, construction, and finish.
- B. In addition to boxes shown, install additional boxes where needed to prevent damage to cables and wires during pulling-in operations or where more than the equivalent of 4-90 degree bends are necessary.
- C. Locate pullboxes so that covers are accessible and easily removed. Coordinate locations with piping and ductwork where installed above ceilings.
- D. Remove only knockouts as required. Plug unused openings. Use threaded plugs for cast metal boxes and snap-in metal covers for sheet metal boxes.
- E. Outlet boxes mounted back-to-back in the same wall are prohibited. A minimum 600 mm (24 inch) center-to-center lateral spacing shall be maintained between boxes.
- F. Flush-mounted wall or ceiling boxes shall be installed with raised covers so that the front face of raised cover is flush with the wall. Surface-mounted wall or ceiling boxes shall be installed with surface-style flat or raised covers.
- G. Minimum size of outlet boxes for ground fault circuit interrupter (GFCI) receptacles is 100 mm (4 inches) square x 55 mm (2.125 inches) deep, with device covers for the wall material and thickness involved.

# ${\tt EHRM} \ \ {\tt Infrastructure} \ \ {\tt UpgradesEHRM} \ \ {\tt Infrastructure} \ \ {\tt Upgrades}$

Bancroft Architects + Engineers

01-01-18

- H. Stencil or install phenolic nameplates on covers of the boxes identified on riser diagrams; for example "SIG-FA JB No. 1."
- I. On all branch circuit junction box covers, identify the circuits with black marker.

- - - E N D - - -

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

# SECTION 26 05 41 UNDERGROUND ELECTRICAL CONSTRUCTION

# PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section specifies the furnishing, installation, and connection of underground ducts and raceways, and precast manholes and pullboxes to form a complete underground electrical raceway system.
- B. The terms "duct" and "conduit" are used interchangeably in this section.

#### 1.2 RELATED WORK

- A. Section 07 92 00, JOINT SEALANTS: Sealing of conduit penetrations.
- B. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: Requirements that apply to all sections of Division 26.
- C. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS: Requirements for personnel safety and to provide a low impedance path for possible ground fault currents.
- D. Section 31 20 11, EARTH MOVING (SHORT FORM)//: Trenching, backfill, and compaction.

## 1.3 QUALITY ASSURANCE

- A. Quality Assurance shall be in accordance with Paragraph, QUALIFICATIONS (PRODUCTS AND SERVICES) in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.
- B. Coordinate layout and installation of ducts, manholes, and pullboxes with final arrangement of other utilities, site grading, and surface features.

#### 1.4 SUBMITTALS

- A. Submit in accordance with Paragraph, SUBMITTALS in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, and the following requirements:
  - 1. Shop Drawings:
    - a. Submit sufficient information to demonstrate compliance with drawings and specifications.
    - b. Submit information on manholes, pullboxes, ducts, and hardware. Submit manhole plan and elevation drawings, showing openings,

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

- pulling irons, cable supports, cover, ladder, sump, and other accessories.
- c. Proposed deviations from the drawings shall be clearly marked on the submittals. If it is necessary to locate manholes, pullboxes, or duct banks at locations other than shown on the drawings, show the proposed locations accurately on scaled site drawings, and submit to the COR for approval prior to construction.
- 2. Certifications: Two weeks prior to the final inspection, submit the following.
  - a. Certification by the manufacturer that the materials conform to the requirements of the drawings and specifications.
  - b. Certification by the Contractor that the materials have been properly installed, connected, and tested.

#### 1.5 APPLICABLE PUBLICATIONS

- A. Publications listed below (including amendments, addenda, revisions, supplements, and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by designation only.
- B. American Concrete Institute (ACI):

  Building Code Requirements for Structural Concrete

  318-14/318M-14.....Building Code Requirements for Structural

  Concrete & Commentary

  SP-66-04.....ACI Detailing Manual

  C. American National Standards Institute (ANSI):

  77-14......Underground Enclosure Integrity
- D. American Society for Testing and Materials (ASTM):

  C478 REV A-15......Standard Specification for Precast Reinforced

  Concrete Manhole Sections

  C858-10......Underground Precast Concrete Utility Structures

  C990-09......Joints for Concrete Pipe, Manholes and Precast
  - C990-09......Joints for Concrete Pipe, Manholes and Precast

    Box Sections Using Preformed Flexible Joint

    Sealants.
- E. National Electrical Manufacturers Association (NEMA):

  TC 2-13.....Electrical Polyvinyl Chloride (PVC) Conduit

#### EHRM Infrastructure Upgrades

	Bancroft Architects + Engineers
	01-01-17
	TC 3-15Polyvinyl Chloride (PVC) Fittings for Use With
	Rigid PVC Conduit And Tubing
	TC 6 & 8-13Polyvinyl Chloride (PVC) Plastic Utilities Duct
	For Underground Installations
	TC 9-04Fittings For Polyvinyl Chloride (PVC) Plastic
	Utilities Duct For Underground Installation
F.	National Fire Protection Association (NFPA):
	70-17National Electrical Code (NEC)
	70E-15National Electrical Safety Code
G.	Underwriters Laboratories, Inc. (UL):
	6-07Electrical Rigid Metal Conduit-Steel
	467-13Grounding and Bonding Equipment
	651-11Schedule 40, 80, Type EB and A Rigid PVC
	Conduit and Fittings
	651A-11Schedule 40 and 80 High Density Polyethylene
	(HDPE) Conduit

# PART 2 - PRODUCTS

# 2.1 PRE-CAST CONCRETE MANHOLES AND HARDWARE

- A. Structure: Factory-fabricated, reinforced-concrete, monolithically-poured walls and bottom. Frame and cover shall form top of manhole.
- B. Cable Supports:
  - 1. Cable stanchions shall be hot-rolled, heavy duty, hot-dipped galvanized "T" section steel, 56 mm (2.25 inches) x 6 mm (0.25 inch) in size, and punched with 14 holes on 38 mm (1.5 inches) centers for attaching cable arms.
  - 2. Cable arms shall be 5 mm (0.1875 inch) gauge, hot-rolled, hot-dipped galvanized sheet steel, pressed to channel shape. Arms shall be approximately 63 mm (2.5 inches) wide x 350 mm (14 inches) long.
  - 3. Insulators for cable supports shall be porcelain, and shall be saddle type or type that completely encircles the cable.
  - 4. Equip each cable stanchion with one spare cable arm, with three spare insulators for future use.
- C. Ladder: Fiberglass with 400 mm (16 inches) rung spacing. Provide securely-mounted ladder for every manhole over 1.2 M (4 feet) deep.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

- D. Ground Rod Sleeve: Provide a 75 mm (3 inches) PVC sleeve in manhole floors so that a driven ground rod may be installed.
- E. Sump: Provide 305 mm  $\times$  305 mm (12 inches  $\times$  12 inches) covered sump frame and grated cover.

#### 2.2 PULLBOXES

- A. General: Size as indicated on the drawings. Provide pullboxes with weatherproof, non-skid covers with recessed hook eyes, secured with corrosion- and tamper-resistant hardware. Cover material shall be identical to pullbox material. Covers shall have molded lettering, ELECTRIC or SIGNAL as applicable. Pullboxes shall comply with the requirements of ANSI 77 Tier 5 loading. Provide pulling irons, 22 mm (0.875 inch) diameter galvanized steel bar with exposed triangular-shaped opening.
- B. Polymer Concrete Pullboxes: Shall be molded of sand, aggregate, and polymer resin, and reinforced with steel, fiberglass, or both. Pullbox shall have open bottom.

#### 2.3 DUCTS

- A. Number and sizes shall be as shown on the drawings.
- B. Ducts (concrete-encased):
  - 1. Plastic Duct:
    - a. NEMA TC6 & 8 and TC9 plastic utilities duct // // UL 651 and 651A Schedule 40 PVC conduit.
    - b. Duct shall be suitable for use with 90°C (194°F) rated conductors.
  - 2. Conduit Spacers: Prefabricated plastic.
- C. Ducts (direct-burial): NOT USED

## 2.4 GROUNDING

A. Ground Rods and Ground Wire: Per Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS.

#### 2.5 WARNING TAPE

A. 4-mil polyethylene 75 mm (3 inches) wide detectable tape, red with black letters, imprinted with "CAUTION - BURIED ELECTRIC CABLE BELOW" or similar.

# 2.6 PULL ROPE FOR SPARE DUCTS

A. Plastic with 890 N (200 lb) minimum tensile strength.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

#### PART 3 - EXECUTION

# 3.1 MANHOLE AND PULLBOX INSTALLATION

- A. Assembly and installation shall be per the requirements of the manufacturer.
  - 1. Install manholes and pullboxes level and plumb.
  - 2. Units shall be installed on a 300 mm (12 inches) thick level bed of 90% compacted granular fill, well-graded from the 25 mm (1 inch) sieve to the No. 4 sieve. Granular fill shall be compacted with a minimum of four passes with a plate compactor.
- B. Access: Ensure the top of frames and covers are flush with finished grade.
- C. Grounding in Manholes:
  - 1. Ground Rods in Manholes: Drive a ground rod into the earth, through the floor sleeve, after the manhole is set in place. Fill the sleeve with sealant to make a watertight seal. Rods shall protrude approximately 100 mm (4 inches) above the manhole floor.
  - 2. Install a No. 3/0 AWG bare copper ring grounding conductor around the inside perimeter of the manhole and anchor to the walls with metallic cable clips.
  - 3. Connect the ring grounding conductor to the ground rod by an exothermic welding process.
  - 4. Bond the ring grounding conductor to the duct bank equipment grounding conductors, the exposed non-current carrying metal parts of racks, sump covers, and like items in the manholes with a minimum No. 6 AWG bare copper jumper using an exothermic welding process.

# 3.2 TRENCHING

- A. Refer to Section 31 20 11 EARTH MOVING (SHORT FORM) for trenching, backfilling, and compaction.
- B. Before performing trenching work at existing facilities, a Ground Penetrating Radar Survey shall be carefully performed by a certified technician to reveal all existing underground ducts, conduits, cables, and other utility systems.
- C. Work with extreme care near existing ducts, conduits, and other utilities to avoid damaging them.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

- D. Cut the trenches neatly and uniformly.
- E. For Concrete-Encased Ducts:
  - 1. After excavation of the trench, stakes shall be driven in the bottom of the trench at 1.2 M (4 feet) intervals to establish the grade and route of the duct bank.
  - 2. Pitch the trenches uniformly toward manholes or both ways from high points between manholes for the required duct line drainage. Avoid pitching the ducts toward buildings wherever possible.
  - 3. The walls of the trench may be used to form the side walls of the duct bank, provided that the soil is self-supporting and that the concrete envelope can be poured without soil inclusions. Forms are required where the soil is not self-supporting.
  - 4. After the concrete-encased duct has sufficiently cured, the trench shall be backfilled to grade with earth, and appropriate warning tape installed.
- F. Individual conduits to be installed under existing paved areas and roads that cannot be disturbed shall be jacked into place using rigid metal conduit, or bored using plastic utilities duct or PVC conduit, as approved by the COR.

### 3.3 DUCT INSTALLATION

- A. General Requirements:
  - 1. Ducts shall be in accordance with the NEC, as shown on the drawings, and as specified.
  - 2. Join and terminate ducts with fittings recommended by the manufacturer.
  - 3. Slope ducts to drain towards manholes and pullboxes, and away from building and equipment entrances. Pitch not less than 100 mm (4 inches) in 30 M (100 feet).
  - 4. Underground conduit stub-ups and sweeps to equipment inside of buildings shall be galvanized rigid metal conduit half-lap wrapped with PVC tape, and shall extend a minimum of 1.5 M (5 feet) outside the building foundation. Tops of conduits below building slab shall be minimum 610 mm (24 inches) below bottom of slab.
  - 5. Stub-ups and sweeps to equipment mounted on outdoor concrete slabs shall be galvanized rigid metal conduit half-lap wrapped with PVC

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

- tape, and shall extend a minimum of 1.5 M (5 feet) away from the edge of slab.
- 6. Install insulated grounding bushings on the conduit terminations.
- 7. Radius for sweeps shall be sufficient to accomplish pulls without damage. Minimum radius shall be six times conduit diameter.
- 8. All multiple conduit runs shall have conduit spacers. Spacers shall securely support and maintain uniform spacing of the duct assembly a minimum of 75 mm (3 inches) above the bottom of the trench during the concrete pour. Spacer spacing shall not exceed 1.5 M (5 feet). Secure spacers to ducts and earth to prevent floating during concrete pour. Provide nonferrous tie wires to prevent displacement of the ducts during concrete pour. Tie wires shall not act as substitute for spacers.
- 9. Duct lines shall be installed no less than 300 mm (12 inches) from other utility systems, such as water, sewer, chilled water.
- 10. Clearances between individual ducts:
  - a. For similar services, not less than 75 mm (3 inches).
  - b. For power and signal services, not less than 150 mm (6 inches).
- 11. Duct lines shall terminate at window openings in manhole walls as shown on the drawings. All ducts shall be fitted with end bells.
- 12. Couple the ducts with proper couplings. Stagger couplings in rows and layers to ensure maximum strength and rigidity of the duct bank.
- 13. Keep ducts clean of earth, sand, or gravel, and seal with tapered plugs upon completion of each portion of the work.
- 14. Spare Ducts: Where spare ducts are shown, they shall have a nylon pull rope installed. They shall be capped at each end and labeled as to location of the other end.
- 15. Duct Identification: Place continuous strip of warning tape approximately 300 mm (12 inches) above ducts before backfilling trenches. Warning tape shall be preprinted with proper identification.
- 16. Duct Sealing: Seal ducts, including spare ducts, at building entrances and at outdoor terminations for equipment, with a suitable non-hardening compound to prevent the entrance of foreign objects and material, moisture, and gases.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

17. Use plastic ties to secure cables to insulators on cable arms. Use minimum two ties per cable per insulator.

#### B. Concrete-Encased Ducts:

- Install concrete-encased ducts for medium-voltage systems, lowvoltage systems, and signal systems, unless otherwise shown on the drawings.
- 2. Duct banks shall be single or multiple duct assemblies encased in concrete. Ducts shall be uniform in size and material throughout the installation.
- 3. Tops of concrete-encased ducts shall be:
  - a. Not less than 600 mm (24 inches) and not less than shown on the drawings, below finished grade.
  - b. Not less than 750 mm (30 inches) and not less than shown on the drawings, below roads and other paved surfaces.
  - c. Additional burial depth shall be required in order to accomplish NEC-required minimum bend radius of ducts.
  - d. Conduits crossing under grade slab construction joints shall be installed a minimum of 1.2 M (4 feet) below slab.
- 4. Extend the concrete envelope encasing the ducts not less than 75 mm (3 inches) beyond the outside walls of the outer ducts.
- 5. Within 3 M (10 feet) of building and manhole wall penetrations, install reinforcing steel bars at the top and bottom of each concrete envelope to provide protection against vertical shearing.
- Install reinforcing steel bars at the top and bottom of each concrete envelope of all ducts underneath roadways and parking areas
- 7. Where new ducts and concrete envelopes are to be joined to existing manholes, pullboxes, ducts, and concrete envelopes, make the joints with the proper fittings and fabricate the concrete envelopes to ensure smooth durable transitions.
- 8. Duct joints in concrete may be placed side by side horizontally, but shall be staggered at least 150 mm (6 inches) vertically.
- 9. Pour each run of concrete envelope between manholes or other terminations in one continuous pour. If more than one pour is necessary, terminate each pour in a vertical plane and install 19 mm

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

- (0.75 inch) reinforcing rod dowels extending 450 mm (18 inches) into concrete on both sides of joint near corners of envelope.
- 10. Pour concrete so that open spaces are uniformly filled. Do not agitate with power equipment unless approved by COR.
- D. Connections to Manholes: Ducts connecting to manholes shall be flared to have an enlarged cross-section to provide additional shear strength. Dimensions of the flared cross-section shall be larger than the corresponding manhole opening dimensions by no less than 300 mm (12 inches) in each direction. Perimeter of the duct bank opening in the manhole shall be flared toward the inside or keyed to provide a positive interlock between the duct and the wall of the manhole. Use vibrators when this portion of the encasement is poured to ensure a seal between the envelope and the wall of the structure.
- E. Connections to Existing Manholes: For duct connections to existing manholes, break the structure wall out to the dimensions required and preserve the steel in the structure wall. Cut steel and extend into the duct bank envelope. Chip the perimeter surface of the duct bank opening to form a key or flared surface, providing a positive connection with the duct bank envelope.
- F. Connections to Existing Ducts: Where connections to existing ducts are indicated, excavate around the ducts as necessary. Cut off the ducts and remove loose concrete from inside before installing new ducts.

  Provide a reinforced-concrete collar, poured monolithically with the new ducts, to take the shear at the joint of the duct banks.
- G. Partially-Completed Ducts: During construction, wherever a construction joint is necessary in a duct bank, prevent debris such as mud and dirt from entering ducts by providing suitable plugs. Fit concrete envelope of a partially completed ducts with reinforcing steel extending a minimum of 600 mm (2 feet) back into the envelope and a minimum of 600 mm (2 feet) beyond the end of the envelope. Provide one No. 4 bar in each corner, 75 mm (3 inches) from the edge of the envelope. Secure corner bars with two No. 3 ties, spaced approximately 300 mm (12 inches) apart. Restrain reinforcing assembly from moving during pouring of concrete.

#### EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

#### 3.4 ACCEPTANCE CHECKS AND TESTS

- A. Duct Testing and Cleaning:
  - Upon completion of the duct installation, a standard flexible mandrel shall be pulled through each duct to loosen particles of earth, sand, or foreign material left in the duct, and to test for out-of-round conditions.
  - 2. The mandrel shall be not less than 300 mm (12 inches) long, and shall have a diameter not less than 13 mm (0.5 inch) less than the inside diameter of the duct. A brush with stiff bristles shall then be pulled through each duct to remove the loosened particles. The diameter of the brush shall be the same as, or slightly larger than, the diameter of the duct.
  - 3. If testing reveals obstructions or out-of-round conditions, the Contractor shall replace affected section(s) of duct and retest to the satisfaction of the COR.
  - 4. Mandrel pulls shall be witnessed by the COR.

---END---

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

# SECTION 26 24 16 PANELBOARDS

# PART 1 - GENERAL

#### 1.1 DESCRIPTION

A. This section specifies the furnishing, installation, and connection of panelboards.

#### 1.2 RELATED WORK

- A. Section 09 91 00, PAINTING: Painting of panelboards.
- C. Section 25 10 10, ADVANCED UTILITY METERING: Requirements for electrical metering.
- D. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: Requirements that apply to all sections of Division 26.
- E. Section 26 05 19, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES: Low-voltage conductors.
- F. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS:

  Requirements for personnel safety and to provide a low impedance path
  for possible ground fault currents.
- G. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS: Conduits.
- J. Section 26 43 13, SURGE PROTECTIVE DEVICES: Surge protective devices integral to panelboards.

# 1.3 QUALITY ASSURANCE

A. Quality Assurance shall be in accordance with Paragraph, QUALIFICATIONS (PRODUCTS AND SERVICES) in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

### 1.4 SUBMITTALS

- A. Submit in accordance with Paragraph, SUBMITTALS in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, and the following requirements:
  - 1. Shop Drawings:
    - a. Submit sufficient information to demonstrate compliance with drawings and specifications.
    - b. Include electrical ratings, dimensions, mounting details, materials, required clearances, terminations, weight, circuit breakers, wiring and connection diagrams, accessories, and nameplate data.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-18

#### 2. Manuals:

- a. Submit, simultaneously with the shop drawings, complete maintenance and operating manuals including technical data sheets, wiring diagrams, and information for ordering circuit breakers and replacement parts.
  - 1) Include schematic diagrams, with all terminals identified, matching terminal identification in the panelboards.
  - Include information for testing, repair, troubleshooting, assembly, and disassembly.
- b. If changes have been made to the maintenance and operating manuals originally submitted, submit updated maintenance and operating manuals two weeks prior to the final inspection.
- 3. Certifications: Two weeks prior to final inspection, submit the following.
  - a. Certification by the manufacturer that the panelboards conform to the requirements of the drawings and specifications.
  - b. Certification by the Contractor that the panelboards have been properly installed, adjusted, and tested.

#### 1.5 APPLICABLE PUBLICATIONS

- A. Publications listed below (including amendments, addenda, revisions, supplements, and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by designation only.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

489-16..... Molded Case Circuit Breakers and Circuit

Breaker Enclosures

#### PART 2 - PRODUCTS

### 2.1 GENERAL REQUIREMENTS

- A. Panelboards shall be in accordance with NEC, NEMA, UL, as specified, and as shown on the drawings.
- B. Panelboards shall have main breaker or main lugs, bus size, voltage, phases, number of circuit breaker mounting spaces, top or bottom feed, flush or surface mounting, branch circuit breakers, and accessories as shown on the drawings.
- C. Panelboards shall be completely factory-assembled with molded case circuit breakers and integral accessories as shown on the drawings or specified herein.
- D. Non-reduced size copper bus bars, rigidly supported on molded insulators, and fabricated for bolt-on type circuit breakers.
- E. Bus bar connections to the branch circuit breakers shall be the "distributed phase" or "phase sequence" type.
- F. Mechanical lugs furnished with panelboards shall be cast, stamped, or machined metal alloys listed for use with the conductors to which they will be connected.
- G. Neutral bus shall be 100rated, mounted on insulated supports.
- H. Grounding bus bar shall be equipped with screws or lugs for the connection of equipment grounding conductors.
- I. Bus bars shall be braced for the available short-circuit current as shown on the drawings, but not be less than 10,000 A symmetrical for 120/208 V and 120/240 V panelboards, and 14,000 A symmetrical for 277/480 V panelboards.
- J. In two-section panelboards, the main bus in each section shall be full size. The first section shall be furnished with subfeed lugs on the line side of main lugs only, or through-feed lugs for main breaker type panelboards, and have field-installed cable connections to the second section as shown on the drawings. Panelboard sections with tapped bus or crossover bus are not acceptable.
- K. Series-rated panelboards are not permitted.

# 2.2 ENCLOSURES AND TRIMS

A. Enclosures:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

- 1. Provide galvanized steel enclosures, with NEMA rating as shown on the drawings or as required for the environmental conditions in which installed.
- 2. Enclosures shall not have ventilating openings.
- 3. Enclosures may be of one-piece formed steel or of formed sheet steel with end and side panels welded, riveted, or bolted as required.
- 4. Provide manufacturer's standard option for prepunched knockouts on top and bottom end walls.
- 5. Include removable inner dead front cover, independent of the panelboard cover.

#### B. Trims:

- 1. Hinged "door-in-door" type.
- 2. Interior hinged door with hand-operated latch or latches, as required to provide access only to circuit breaker operating handles, not to energized parts.
- 3. Outer hinged door shall be securely mounted to the panelboard enclosure with factory bolts, screws, clips, or other fasteners, requiring a key or tool for entry. Hand-operated latches are not acceptable.
- 4. Inner and outer doors shall open left to right.
- 5. Trims shall be flush or surface type as shown on the drawings.

# 2.3 MOLDED CASE CIRCUIT BREAKERS

- A. Circuit breakers shall be per UL, NEC, as shown on the drawings, and as specified.
- B. Circuit breakers shall be bolt-on type.
- C. Circuit breakers shall have minimum interrupting rating as required to withstand the available fault current, as noted on drawings and equipment schedules, but not less than:
  - 1. 120/208 V Panelboard: 10,000 A symmetrical.
  - 2. 120/240 V Panelboard: 10,000 A symmetrical.
  - 3. 277/480 V Panelboard: 14,000 A symmetrical.
- D. Circuit breakers shall have automatic, trip free, non-adjustable, inverse time, and instantaneous magnetic trips for less than 400 A frame. Circuit breakers with 400 A frames and above shall have magnetic trip, adjustable from 5x to 10x. Service Entrance Disconnects and Fuses shall be sized as noted on drawings. .

Contract No. 36C26319D0044

Station Project No. 568A4-21-703

Bancroft-AE Project No. 18-121

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

- E. Circuit breaker features shall be as follows:
  - 1. A rugged, integral housing of molded insulating material.
  - 2. Silver alloy contacts.
  - 3. Arc quenchers and phase barriers for each pole.
  - 4. Quick-make, quick-break, operating mechanisms.
  - 5. A trip element for each pole, thermal magnetic type with long time delay and instantaneous characteristics, a common trip bar for all poles and a single operator.
  - 6. Electrically and mechanically trip free.
  - 7. An operating handle which indicates closed, tripped, and open positions.
  - 8. An overload on one pole of a multi-pole breaker shall automatically cause all the poles of the breaker to open.
  - 9. Ground fault current interrupting breakers, shunt trip breakers, lighting control breakers (including accessories to switch line currents), or other accessory devices or functions shall be provided where shown on the drawings.
- 10. For circuit breakers being added to existing panelboards, coordinate the breaker type with existing panelboards. Modify the panel directory accordingly.

#### 2.4 SURGE PROTECTIVE DEVICES

A. Where shown on the drawings, furnish panelboards with surge protective devices mounted on the outside. Refer to Section 26 43 13, SURGE PROTECTIVE DEVICES.

#### PART 3 - EXECUTION

# 3.1 INSTALLATION

- A. Installation shall be in accordance with the manufacturer's instructions, the NEC, as shown on the drawings, and as specified.
- B. Locate panelboards so that the present and future conduits can be conveniently connected.
- D. Install a printed schedule of circuits in each panelboard after approval by the COR. Schedules shall reflect final load descriptions, room numbers, and room names connected to each circuit breaker. Schedules shall be printed on the panelboard directory cards and be installed in the appropriate panelboards

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

- E. Mount panelboards such that the maximum height of the top circuit breaker above the finished floor shall not exceed 1980 mm (78 inches).
- F. Provide blank cover for each unused circuit breaker mounting space.
- I. Panelboard enclosures shall not be used for conductors feeding through, spliced, or tapping off to other enclosures or devices.

### 3.2 ACCEPTANCE CHECKS AND TESTS

- A. Perform in accordance with the manufacturer's recommendations. In addition, include the following:
  - 1. Visual Inspection and Tests:
    - a. Compare equipment nameplate data with specifications and approved shop drawings.
    - b. Inspect physical, electrical, and mechanical condition.
    - c. Verify appropriate anchorage and required area clearances.
    - d. Verify that circuit breaker sizes and types correspond to approved shop drawings.
    - e. To verify tightness of accessible bolted electrical connections, use the calibrated torque-wrench method or perform thermographic survey after energization.
    - f. Vacuum-clean enclosure interior. Clean enclosure exterior.

## 3.3 FOLLOW-UP VERIFICATION

A. Upon completion of acceptance checks, settings, and tests, the Contractor shall demonstrate that the panelboards are in good operating condition and properly performing the intended function.

---END---

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

# SECTION 26 27 26 WIRING DEVICES

### PART 1 - GENERAL

#### 1.1 DESCRIPTION

A. This section specifies the furnishing, installation, connection, and testing of wiring devices.

#### 1.2 RELATED WORK

- A. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: General electrical requirements that are common to more than one section of Division 26.
- B. Section 26 05 19, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES: Cables and wiring.
- C. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS:

  Requirements for personnel safety and to provide a low impedance path to ground for possible ground fault currents.
- D. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS: Conduit and boxes.
- E. Section 26 51 00, INTERIOR LIGHTING: Fluorescent ballasts and LED drivers for use with manual dimming controls.

#### 1.3 QUALITY ASSURANCE

A. Quality Assurance shall be in accordance with Paragraph, QUALIFICATIONS (PRODUCTS AND SERVICES) in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

#### 1.4 SUBMITTALS

- A. Submit in accordance with Paragraph, SUBMITTALS in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, and the following requirements:
  - 1. Shop Drawings:
    - a. Submit sufficient information to demonstrate compliance with drawings and specifications.
    - b. Include electrical ratings, dimensions, mounting details, construction materials, grade, and termination information.

# 2. Manuals:

a. Submit, simultaneously with the shop drawings, companion copies of complete maintenance and operating manuals, including

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-18

technical data sheets and information for ordering replacement parts.

- b. If changes have been made to the maintenance and operating manuals originally submitted, submit updated maintenance and operating manuals two weeks prior to the final inspection.
- 3. Certifications: Two weeks prior to final inspection, submit the following.
  - a. Certification by the manufacturer that the wiring devices conform to the requirements of the drawings and specifications.
  - b. Certification by the Contractor that the wiring devices have been properly installed and adjusted.

#### 1.5 APPLICABLE PUBLICATIONS

- A. Publications listed below (including amendments, addenda, revisions, supplements and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by basic designation only.
- B. National Electrical Manufacturers Association (NEMA):

WD 1-99(R2015)......General Color Requirements for Wiring Devices
WD 6-16 ......Wiring Devices - Dimensional Specifications

C. National Fire Protection Association (NFPA):

70-17......National Electrical Code (NEC)

99-18.....Health Care Facilities

D. Underwriter's Laboratories, Inc. (UL):

5-16.....Surface Metal Raceways and Fittings

20-10.....General-Use Snap Switches

231-16.....Power Outlets

467-13..... Grounding and Bonding Equipment

498-17.....Attachment Plugs and Receptacles

943-16.....Ground-Fault Circuit-Interrupters

1449-14.....Surge Protective Devices

1472-15.....Solid State Dimming Controls

#### PART 2 - PRODUCTS

### 2.1 RECEPTACLES

A. General: All receptacles shall comply with NEMA, NFPA, UL, and as shown on the drawings.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-18

- 1. Mounting straps shall be nickel plated brass, brass, nickel plated steel or galvanize steel with break-off plaster ears, and shall include a self-grounding feature. Terminal screws shall be brass, brass plated or a copper alloy metal.
- 2. Receptacles shall have provisions for back wiring with separate metal clamp type terminals (four minimum) and side wiring from four captively held binding screws.
- B. Duplex Receptacles Hospital-grade: shall be listed for hospital grade, single phase, 20 ampere, 120 volts, 2-pole, 3-wire, NEMA 5-20R, with break-off feature for two-circuit operation.
  - 1. Bodies shall be ivoryin color.
  - 2. Switched duplex receptacles shall be wired so that only the top receptacle is switched. The lower receptacle shall be unswitched.
  - 3. Duplex Receptacles on Emergency Circuit:
    - a. In rooms without emergency powered general lighting, the emergency receptacles shall be of the self-illuminated type.
  - 4. Ground Fault Current Interrupter (GFCI) Duplex Receptacles: Shall be an integral unit, hospital-grade, suitable for mounting in a standard outlet box, with end-of-life indication and provisions to isolate the face due to improper wiring. GFCI receptacles shall be self-test receptacles in accordance with UL 943.
    - a. Ground fault interrupter shall consist of a differential current transformer, self-test, solid state sensing circuitry and a circuit interrupter switch. Device shall have nominal sensitivity to ground leakage current of 4-6 milliamperes and shall function to interrupt the current supply for any value of ground leakage current above five milliamperes (+ or 1 milliampere) on the load side of the device. Device shall have a minimum nominal tripping time of 0.025 second.
    - b. Self-test function shall be automatically initiated within 5 seconds after power is activated to the receptacles. Self-test function shall be periodically and automatically performed every 3 hours or less.
    - c. End-of-life indicator light shall be a persistent flashing or blinking light to indicate that the GFCI receptacle is no longer in service.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

- 5. Tamper-Resistant Duplex Receptacles:
  - a. Bodies shall be grayin color.
    - 1) Shall permit current to flow only while a standard plug is in the proper position in the receptacle.
    - 2) Screws exposed while the wall plates are in place shall be the tamperproof type.
- C. Duplex Receptacles Non-hospital Grade: shall be the same as duplex receptacles - hospital grade in accordance with sections 2.1A and 2.1B of this specification, except for the hospital grade listing.
  - 1. Bodies shall be brownnylon.
- D. Receptacles 20, 30, and 50 ampere, 250 Volts: Shall be complete with appropriate cord grip plug.
- E. Weatherproof Receptacles: Shall consist of a duplex receptacle, mounted in box with a gasketed, weatherproof, cast metal cover plate and cap over each receptacle opening. The cap shall be permanently attached to the cover plate by a spring-hinged flap. The weatherproof integrity shall not be affected when heavy duty specification or hospital grade attachment plug caps are inserted. Cover plates on outlet boxes mounted flush in the wall shall be gasketed to the wall in a watertight manner.
- F. Surge Protective (TVSS) Receptacles shall have integral surge suppression in line to ground, line to neutral, and neutral to ground modes.
  - 1. TVSS Components: Multiple metal-oxide varistors; with a nominal clamp-level rating of 400 Volts, and minimum single transient pulse energy dissipation of 210 Joules.
  - 2. Active TVSS Indication: LED, visible in face of device to indicate device is active or no longer in service.
- G. Cable Reel Receptacles: (not used)

#### 2.2 TOGGLE SWITCHES

- A. Toggle switches shall be totally enclosed tumbler type with nylon bodies. Handles shall be ivoryin color unless otherwise specified or shown on the drawings.
  - 1. Switches installed in hazardous areas shall be explosion-proof type in accordance with the NEC and as shown on the drawings.
- 2. Shall be single unit toggle, butt contact, quiet AC type, heavy-duty general-purpose use with an integral self grounding mounting strap Contract No. 36C26319D0044

Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

# ${\tt EHRM\ Infrastructure\ UpgradesEHRM\ Infrastructure\ Upgrades}$

Bancroft Architects + Engineers

01-01-18

with break-off plasters ears and provisions for back wiring with separate metal wiring clamps and side wiring with captively held binding screws.

3. Switches shall be rated 20 amperes at 120-277 Volts AC.

### 2.3 MANUAL DIMMING CONTROL (NOT USED)

Α

#### 2.4 WALL PLATES

- A. Wall plates for switches and receptacles shall be type 302 stainless steel Oversize plates are not acceptable.
- B. Color shall be ivory unless otherwise specified.
  - C. For receptacles or switches mounted adjacent to each other, wall plates shall be common for each group of receptacles or switches.
  - D. In areas requiring tamperproof wiring devices, wall plates shall be type 302 stainless steel, and shall have tamperproof screws and beveled edges.
  - E. Duplex Receptacles on Emergency Circuit: Wall plates shall be red nylon with the word "EMERGENCY" engraved in 6 mm (1/4 inch) white lettersWall plates shall be type 302 stainless steel, with the word "EMERGENCY" engraved in 6 mm (1/4 inch) red letters.

## 2.5 SURFACE MULTIPLE-OUTLET ASSEMBLIES

- A. Shall have the following features:
  - 1. Enclosures:
    - a. Thickness of steel shall be not less than 1 mm (0.040 inch) for base and cover. Nominal dimensions shall be 40 mm x 70 mm (1-1/2 inches by 2-3/4 inches) with inside cross sectional area not less than 2250 square mm (3-1/2 square inches). The enclosures shall be thoroughly cleaned, phosphatized, and painted at the factory with primer and the manufacturer's standard baked enamel finish.
  - 2. Receptacles shall be duplex, hospital gradeSee paragraph 'RECEPTACLES' in this Section. Device cover plates shall be the manufacturer's standard corrosion resistant finish and shall not exceed the dimensions of the enclosure.
  - 3. Unless otherwise shown on drawings, receptacle spacing shall be 600 mm (24 inches) on centers.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-18

- 4. Conductors shall be as specified in Section 26 05 19, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLE.
- 5. Installation fittings shall be the manufacturer's standard bends, offsets, device brackets, inside couplings, wire clips, elbows, and other components as required for a complete system.
- 6. Bond the assemblies to the branch circuit conduit system.

#### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Installation shall be in accordance with the NEC and as shown as on the drawings.
- B. Install wiring devices after wall construction and painting is complete.
- C. The ground terminal of each wiring device shall be bonded to the outlet box with an approved green bonding jumper, and also connected to the branch circuit equipment grounding conductor.
- D. Outlet boxes for toggle switches and manual dimming controls shall be mounted on the strike side of doors.
- E. Provide barriers in multi-gang outlet boxes to comply with the NEC.
- F. Coordinate the electrical work with the work of other trades to ensure that wiring device flush outlets are positioned with box openings aligned with the face of the surrounding finish material. Pay special attention to installations in cabinet work, and in connection with laboratory equipment.
- G. Exact field locations of floors, walls, partitions, doors, windows, and equipment may vary from locations shown on the drawings. Prior to locating sleeves, boxes and chases for roughing-in of conduit and equipment, the Contractor shall coordinate exact field location of the above items with other trades.
- H. Install wall switches 1.2 M (48 inches) above floor, with the toggle OFF position down.
- I. Install wall dimmers 1.2 M (48 inches) above floor.
- J. Install receptacles 450 mm (18 inches) above floor, and 152 mm (6 inches) above counter backsplash or workbenches. Install specific-use receptacles at heights shown on the drawings.
- K. Install horizontally mounted receptacles with the ground pin to the right.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-18

- L. When required or recommended by the manufacturer, use a torque screwdriver. Tighten unused terminal screws.
- M. Label device plates with a permanent adhesive label listing panel and circuit feeding the wiring device.

### 3.2 ACCEPTANCE CHECKS AND TESTS

- A. Perform manufacturer's required field checks in accordance with the manufacturer's recommendations, and the latest NFPA 99. In addition, include the following:
  - 1. Visual Inspection and Tests:
    - a. Inspect physical and electrical conditions.
    - b. Vacuum-clean surface metal raceway interior. Clean metal raceway exterior.
    - c. Test wiring devices for damaged conductors, high circuit resistance, poor connections, inadequate fault current path, defective devices, or similar problems using a portable receptacle tester. Correct circuit conditions, remove malfunctioning units and replace with new, and retest as specified above.
    - d. Test GFCI receptacles.
  - 2. Receptacle testing in the Patient Care Spaces, such as retention force of the grounding blade of each receptacle, shall comply with the latest NFPA 99.

---END---

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

# SECTION 26 33 53 STATIC UNINTERRUPTIBLE POWER SUPPLY

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section specifies the furnishing, installation, connection, and testing of the static uninterruptible power supply, indicated in this section as UPS.
- B. When ordering this equipment contractor to clarify that the power input is from a 120/240V, single phase source.

#### 1.2 RELATED WORK

- B. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: Requirements that apply to all sections of Division 26.
- C. Section 26 05 19, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES: Low-voltage conductors.
- D. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS:

  Requirements for personnel safety and to provide a low impedance path for possible fault currents.
- E. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS: Conduits.
- G. Section 26 24 13, DISTRIBUTION SWITCHBOARDS: For low-voltage switchboard required for maintenance bypass of multiple module UPS.
- H. Section 26 26 00, POWER DISTRIBUTION UNITS FOR STATIC UNINTERRUPTIBLE POWER SYSTEMS: Power distribution units connected to the output of a UPS.

#### 1.3 QUALITY ASSURANCE

A. Quality Assurance shall be in accordance with Paragraph, QUALIFICATIONS (PRODUCTS AND SERVICES) in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

#### 1.4 FACTORY TESTS

- A. UPS shall be thoroughly tested at the factory to assure that there are no electrical or mechanical defects.
- B. Factory Tests shall be in accordance with Paragraph, MANUFACTURED PRODUCTS in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, and the following requirements:
  - 1. UPS shall be factory full-load tested to meet the requirements specified using a test battery (not the battery to be supplied with

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

the system) with AC input power and with battery power for a minimum of 8 hours, with meter readings taken every 30 minutes. Should a malfunction occur, the problem shall be corrected and the test shall be repeated. The tests shall encompass all aspects of operation, such as module failure, static bypass operation, battery failure, input power failure and overload ratings.

# 1.5 SUBMITTALS

A. Submit in accordance with Paragraph, SUBMITTALS in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, and the following requirements:

#### 1. Shop Drawings:

- a. Submit sufficient information to demonstrate compliance with drawings and specifications.
- b. Include electrical ratings, dimensions, mounting details, materials, required clearances, terminations, weight, plan, front, side, and rear elevations, accessories, and device nameplate data.
- c. Provide detailed and project-specific system diagram, showing maintenance bypass, UPS module(s), battery cabinet(s) and batteries, major circuit protective devices, interconnecting power and control wiring, key-type mechanical interlocks, and connections to power sources and loads, as applicable. Indicate whether interconnections are factory-provided/factory-installed, factory-provided/field-installed, or field-provided/field installed.

#### 2. Manuals:

- a. Submit, simultaneously with the shop drawings, companion copies of complete maintenance and operating manuals including technical data sheets, wiring diagrams, and information for ordering replacement parts.
  - 1) Wiring diagrams shall have their terminals identified to facilitate installation, maintenance, and operation.
  - 2) Wiring diagrams shall indicate internal wiring for each item of equipment and the interconnection between the items of equipment.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

- 3) Provide a clear and concise description of operation, which gives, in detail, the information required to properly operate the UPS, including but not limited to bypass switchboard, UPS, key-type mechanical interlocks, remote devices, emergency power off buttons, fire alarm interface, and other components as applicable.
- b. If changes have been made to the maintenance and operating manuals originally submitted, submit updated maintenance and operating manuals two weeks prior to the final inspection.
  - 1) Include complete "As Installed" diagrams that indicate all pieces of equipment and their interconnecting wiring.
  - 2) Include complete diagrams of the internal wiring for each piece of equipment, including "As Installed" revisions of the diagrams.
  - 3) The wiring diagrams shall identify the terminals to facilitate installation, maintenance, operation, and testing.

#### 3. Test Reports:

- a. Submit certified factory design and production test reports for approval.
- b. Two weeks prior to the final inspection, submit certified field test reports and data sheets to the COR.
- 4. Certifications: Two weeks prior to final inspection, submit the following.
  - a. Certification by the manufacturer that the UPS conforms to the requirements of the drawings and specifications.
  - b. Certification by the Contractor that the UPS has been properly installed, adjusted, and tested.

## 1.6 APPLICABLE PUBLICATIONS

- A. Publications listed below (including amendments, addenda, revisions, supplements, and errata), form a part of this specification to the extent referenced. Publications are referenced in the text by basic designation only.
- B. Institute of Engineering and Electronic Engineers (IEEE):

  C57.110-08......Recommended Practice for Establishing

  Transformer Capability When Supplying

  Nonsinusoidal Load Currents

# ${\tt EHRM} \ \ {\tt Infrastructure} \ \ {\tt UpgradesEHRM} \ \ {\tt Infrastructure} \ \ {\tt Upgrades}$

Bancroft Architects + Engineers

	01-01-17
	C62.41.1-02Surge Environment in Low-Voltage (1000 V and
	Less) AC Power Circuits
	C62.41.2-02Characterization of Surges in Low-Voltage (1000
	V and Less) AC Power Circuits
	450-10Maintenance, Testing, and Replacement of Vented
	Lead-Acid Batteries for Stationary Applications
	485-10Sizing Lead-Acid Batteries for Stationary
	Applications
C.	International Code Council (ICC):
	IBC-15International Building Code
D.	National Electrical Manufacturers Association (NEMA):
	PE 1-12Uninterruptible Power Systems - Specification
	and Performance Verification
Ε.	National Fire Protection Association (NFPA):

### PART 2 - PRODUCTS

# 2.1 GENERAL REQUIREMENTS

A. System Capacity: Unless stated otherwise, the parameters listed are under full rated output load at a minimum of 0.9 power factor, with batteries fully charged and floating on the DC bus and with nominal input voltage. Overall kVAredundant, at 40 °C.

70-17......National Electrical Code (NEC)

- B. Battery Capacity: Discharge time to end voltage: 240 minutes, at 25 °C (77 °F). Battery shall be capable of delivering 125 percent of full rated output load at initial start-up. Purchase battery to be 20% larger in Amp-Hours than calculation for 4 hour discharge.
- C. System Bus Bracing: Braced for amperes symmetrical interrupting capacity as shown on drawings.
- D. AC Input:
  - 1. Voltage 240V volts line-to-line.
  - 2. Number of phases: 1-phase, 2-wire, plus ground.
  - 3. Voltage Range: Plus 10 percent, minus 15 percent, without affecting battery float voltage or output voltage.
  - 4. Frequency: 60 Hz, plus or minus 5 percent.
  - 5. Total harmonic current distortion (THD) reflected into the primary line: 5 10percent maximum.
- E. AC Output

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

- 1. Voltage 208volts line-to-line, 120volts line-to-neutral.
- 2. Number of phases: 3-phase, 4-wire, plus ground.
- 3. Voltage regulation:
  - a. Balanced load: Plus or minus 1.0 percent.
  - b. 100 percent load imbalance, phase-to-phase: Plus or minus 3 percent.
- 4. Frequency: 60 Hz.
- 5. Frequency regulation: Plus or minus 0.05 percent.
- 6. Harmonic content (RMS voltage): 5 percent maximum total harmonic distortion with 100% nonlinear load.
- 7. Load power factor operating range: 1.0 to 0.8 lagging.
- 8. Phase displacement:
  - a. Balanced load: Plus or minus 1 degree of bypass input.
- 9. Overload capability (at full voltage) (excluding battery):
  - a. 125 percent load for 10 minutes.
  - b. 150 percent load for 1 minute.
- F. Voltage Transient Response:
  - 1. 100 percent load step: Plus or minus 5 percent.

#### 2.2 UPS

- A. General Description: UPS module shall consist of a rectifier/charger unit and a 3-phase inverter module unit with their associated transformers, synchronizing equipment, input and output circuit breakers, and accessories as required for operation.
- B. Rectifier/Charger Unit: Rectifier/charger unit shall be solid state and shall provide direct current to the DC bus.
  - Input Circuit Breaker: Rectifier/charger unit shall be provided with an input circuit breaker. The circuit breaker shall be sized to accept simultaneously the full-rated load and the battery recharge current.
  - 2. Sizing: Rectifier/charger unit shall be sized for the following two simultaneous operating conditions:
    - a. Supplying the full rated load current to the inverter.
    - b. Recharging a fully-discharged battery to 95 percent of rated ampere-hour capacity within ten times the discharge time after normal AC power is restored, with the input protective device closed.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

- C. Inverter Unit: Inverter unit shall be a solid-state device capable of accepting power from the DC bus and providing AC power within specified limits.
  - 1. Output Overload: The inverter shall be able to sustain an overload as specified across its output terminals.
  - 2. Synchronism: The inverter shall normally operate in phase-lock and synchronism with the bypass source.
  - 3. Modular Construction: Each control logic printed circuit board shall be electrically and physically packaged on an individual plug-in module with separate indication and adjustments.
  - 4. Output Circuit Breaker: The output circuit breaker shall be capable of shunt tripping and shall have interrupting capacity as specified. Circuit breaker shall have provision for locking in the "off" position.
- D. External Protection: UPS module shall have built-in self-protection against undervoltage, overvoltage, overcurrent and surges introduced on the AC input source and/or the bypass source. The UPS system shall sustain input surges without damage in accordance with IEEE C62.41.1 and IEEE C62.41.2. The UPS shall also have built-in self-protection against overvoltage and voltage surges introduced at the output terminals by paralleled sources, load switching, or circuit breaker operation in the critical load distribution system.
- E. Internal Protection: UPS module shall be self-protected against overcurrent, sudden changes in output load and short circuits at the output terminals. UPS module shall be provided with output reverse power detection which shall cause that module to be disconnected from the critical load bus when output reverse power is present. UPS module shall have built-in protection against permanent damage to itself and the connected load for predictable types of failure within itself and the connected load. At the end of battery discharge limit, the module shall shut down without damage to internal components.

#### 2.3 STATIC BYPASS TRANSFER SWITCH (NOT USED)

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

#### 2.9 BATTERY SYSTEM

- A. General: Specify Lithium batteries. Battery should be dated within three months of installation. Reason being that sealed battery life is about 5 years, so we do not want an old battery. A storage battery with sufficient ampere-hour rating to maintain UPS output at full capacity for the specified duration shall be provided for each UPS module.
- B. Battery Type: Lead calcium.
- C. Battery Construction: The battery shall be of the valve-regulated, sealed, non-gassing, recombinant type.
- F. Battery Cables: Battery-to-battery connections shall be stranded cable with proper cable supports.

#### PART 3 - EXECUTION

### 3.1 INSTALLATION

A. The UPS shall be set in place, wired, and connected in accordance with the approved shop drawings and manufacturer's instructions.

#### 3.2 ACCEPTANCE CHECKS AND TESTS

- A. An authorized representative of the UPS manufacturer shall technically supervise and participate during all of the field adjustments and tests. Major adjustments and field tests shall be witnessed by the COR. The manufacturer's representative shall certify in writing that the equipment has been installed, adjusted, and tested in accordance with the manufacturer's recommendations.
- B. Perform manufacturer's required field tests in accordance with the manufacturer's recommendations. In addition, include the following:
  - 1. Visual Inspection and Tests:
    - a. Compare equipment nameplate data with specifications and approved shop drawings.
    - b. Inspect physical, electrical, and mechanical condition.
    - c. Verify appropriate anchorage, required area clearances, and correct alignment.
    - d. Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method, or performing thermographic survey after energization.
    - e. Verify grounding connections.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

- f. Vacuum-clean enclosure interior. Clean enclosure exterior.
- g. Verify the correct operation of all alarms and indicating devices.
- h. Attach a phase rotation meter to the UPS input, output, and bypass buses, and observe proper phase sequences.
- i. Check and test controls for proper operation.
- j. Check doors for proper alignment and operation.
- k. Check and test each protective device for proper mechanical and electrical operation.
- 2. Load Test: The UPS shall be load tested for a continuous 24 hour period by means of resistive load banks, sized for full rated output load and provided by the UPS manufacturer. The UPS shall be continuously tested at 1/2 load for 8 hours, 3/4 load for 8 hours and full load for 8 hours. If a failure occurs during the burn-in period, the tests shall be repeated. Instrument readings shall be recorded every half hour for the following:
  - a. Input voltage and current (all three phases, for each module).
  - b. Input and output frequency.
  - c. Battery voltage for each module.
  - d. Output voltage and current (all three phases, for each module).
  - e. Output kilowatts for each module.
  - f. Output voltage and current (all three phases).
  - q. Output kilowatts.
- 3. Full Load Burn In Test: The UPS shall undergo an additional full load burn-in period of 24 continuous hours by means of resistive load banks, sized for full rated output load and provided by the UPS manufacturer. If a failure occurs during the burn-in period, the tests shall be repeated. Instrument readings shall be recorded every half hour as above. The following tests shall be performed:
  - a. With the UPS carrying full rated output load and supplied from the normal source, switch 100 percentof load bank capacity on and off a minimum of five times within the burn-in period.

#### 3.3 FOLLOW-UP VERIFICATION

A. After completion of acceptance checks and tests, the Contractor shall show by demonstration in service that the UPS is in good operating condition and properly performing the intended function.

Contract No. 36C26319D0044

Station Project No. 568A4-21-703 Bancroft-AE Project No. 18-121

### EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

#### 3.4 ONE LINE DIAGRAM AND SEQUENCE OF OPERATION

- A. At final inspection, an as-built one line diagram shall be laminated or mounted under acrylic glass, and installed in a frame mounted near the UPS.
- B. Furnish a written sequence of operation for the UPS and connected line side/load side electrical distribution equipment. The sequence of operation shall be laminated or mounted under acrylic glass, and installed in a frame mounted near the UPS.
- C. Deliver an additional four copies of the as-built one line diagram and sequence of operation to the COR.

#### 3.5 INSTRUCTION

A. Furnish the services of a factory-trained technician for one 4-hour training period for instructing personnel in the maintenance and operation of the UPS, on the dates requested by the COR.

---END---

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

# SECTION 26 43 13 SURGE PROTECTIVE DEVICES

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

A. This section specifies the furnishing, installation, and connection of Type 2 Surge Protective Devices, as defined in NFPA 70, and indicated as SPD in this section.

#### 1.2 RELATED WORK

- A. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: Requirements that apply to all sections of Division 26.
- B. Section 26 23 00, LOW-VOLTAGE SWITCHGEAR: For factory-installed or external SPD.
- C. Section 26 24 13, DISTRIBUTION SWITCHBOARDS: For factory-installed or external SPD.
- D. Section 26 24 16, PANELBOARDS: For factory-installed or external SPD.
- E. Section 26 26 00, POWER DISTRIBUTION UNITS FOR STATIC UNINTERRUPTIBLE POWER SYSTEMS: For factory-installed or external SPD.

#### 1.3 QUALITY ASSURANCE

A. Quality Assurance shall be in accordance with Paragraph, QUALIFICATIONS (PRODUCTS AND SERVICES) in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

#### 1.4 SUBMITTALS

- A. Submit in accordance with Paragraph, SUBMITTALS in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, and the following requirements:
  - 1. Shop Drawings:
    - a. Submit sufficient information to demonstrate compliance with drawings and specifications.
    - b. Include electrical ratings and device nameplate data.

### 2. Manuals:

a. Submit, simultaneously with the shop drawings, companion copies of complete maintenance and operating manuals including technical data sheets, wiring diagrams, and information for ordering replacement parts.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-17

- b. If changes have been made to the maintenance and operating manuals originally submitted, submit updated maintenance and operating manuals two weeks prior to the final inspection.
- 3. Certifications: Two weeks prior to final inspection, submit the following.
  - a. Certification by the manufacturer that the SPD conforms to the requirements of the drawings and specifications.
  - b. Certification by the Contractor that the SPD has been properly installed.

#### 1.5 APPLICABLE PUBLICATIONS

- A. Publications listed below (including amendments, addenda, revisions, supplement and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by the basic designation only.
- B. Institute of Engineering and Electronic Engineers (IEEE):
  - IEEE C62.41.2-02.......Characterization of Surges in Low-Voltage (1000 V and Less) AC Power Circuits
  - IEEE C62.45-08......Surge Testing for Equipment Connected to Low-Voltage (1000 V and Less) AC Power Circuits
- C. National Fire Protection Association (NFPA):
  - 70-17.....National Electrical Code (NEC)
- D. Underwriters Laboratories, Inc. (UL):
  - UL 1283-15..... Electromagnetic Interference Filters
  - UL 1449-14.....Surge Protective Devices

## PART 2 - PRODUCTS

#### 2.1 SWITCHGEAR/SWITCHBOARD SPD

- A. General Requirements:
  - 1. Comply with IEEE and UL.
  - 2. Modular design with field-replaceable modules, or non-modular design.
  - 3. Fuses, rated at 200 kA interrupting capacity.
  - 4. Bolted compression lugs for internal wiring.
  - 5. Integral disconnect switch.
  - 6. Redundant suppression circuits.
  - 7. LED indicator lights for power and protection status.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

- 8. Audible alarm, with silencing switch, to indicate when protection has failed.
- 9. Form-C contacts rated at 5 A and 250-V ac, one normally open and one normally closed, for remote monitoring of protection status.
  Contacts shall reverse on failure of any surge diversion module or on opening of any current-limiting device.
- 10. Four-digit transient-event counter.
- B. Surge Current per Phase: Minimum 240kA per phase.

#### 2.2 PANELBOARD SPD

- A. General Requirements:
  - 1. Comply with UL 1449 and IEEE C62.41.2.
  - 2. Modular design with field-replaceable modules, or non-modular design.
  - 3. Fuses, rated at 200 kA interrupting capacity.
  - 4. Bolted compression lugs for internal wiring.
  - 5. Integral disconnect switch.
  - 6. Redundant suppression circuits.
  - 7. LED indicator lights for power and protection status.
  - 8. Audible alarm, with silencing switch, to indicate when protection has failed.
  - 9. Form-C contacts rated at 5 A and 250-V ac, one normally open and one normally closed, for remote monitoring of protection status. Contacts shall reverse on failure of any surge diversion module or on opening of any current-limiting device.
  - 10. Four-digit transient-event counter.
- B. Surge Current per Phase: Minimum 120kA per phase.

#### 2.3 ENCLOSURES

A. Enclosures: NEMA 1

#### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Install the SPD on dedicated breaker, on outside of panel.

  Installation shall be in accordance with the NEC, as shown on the drawings, and manufacturer's instructions.
- B. Factory-installed SPD: Switchgear, switchboard, or panelboard manufacturer shall install SPD at the factory.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-17

- C. Field-installed SPD: Contractor shall install SPD with conductors or buses between SPD and points of attachment as short and straight as possible. Do not exceed manufacturer's recommended lead length. Do not bond neutral and ground.
  - 1. Provide a circuit breaker as a dedicated disconnecting means for TVSS as shown on drawings.
- D. Do not perform insulation resistance tests on switchgear, switchboards, panelboards, or feeders with the SPD connected. Disconnect SPD before conducting insulation resistance tests, and reconnect SPD immediately after insulation resistance tests are complete.

#### 3.2 ACCEPTANCE CHECKS AND TESTS

- A. Perform in accordance with the manufacturer's recommendations. In addition, include the following:
  - 1. Visual Inspection and Tests:
    - a. Compare equipment nameplate data with specifications and approved shop drawings.
    - b. Inspect physical, electrical, and mechanical condition.
    - c. Verify that disconnecting means and feeder size and maximum length to SPD corresponds to approved shop drawings.
    - d. Verifying tightness of accessible bolted electrical connections by calibrated torque-wrench method.
    - e. Vacuum-clean enclosure interior. Clean enclosure exterior.
    - f. Verify the correct operation of all sensing devices, alarms, and indicating devices.


#### 3.3 FOLLOW-UP VERIFICATION

A. After completion of acceptance checks and tests, the Contractor shall show by demonstration in service that SPD are in good operating condition and properly performing the intended function.

# 3.4 INSTRUCTION

A. Provide the services of a factory-trained technician for one 2-hour training period for instructing personnel in the maintenance and operation of the SPD, on the date requested by the COR.

`---END---



# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

# SECTION 27 05 11 REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS

### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section includes common requirements to communications installations and applies to all sections of Division 27 and Division 28.
- B. Provide completely functioning communications systems.
- C. Comply with VAAR 852.236.91 and FAR clause 52.236-21 in circumstance of a need for additional detail or conflict between drawings, specifications, reference standards or code.
- D. In the clinic project contractor is to assure that there are no cross connections between the VA Nework and the "Bedroom" network. Wiring can run in common pathways, but the two systems use separate switches in separate locations. The outputs of both networks are individually fed into the Golden West Demarc switch.

## 1.2 REFERENCES

- A. Abbreviations and Acronyms
  - Refer to http://www.cfm.va.gov/til/sdetail.asp for Division 00, ARCHITECTURAL ABBREVIATIONS.
  - 2. Additional Abbreviations and Acronyms:

А	Ampere		
AC	Alternating Current		
AE	Architect and Engineer		
AFF	Above Finished Floor		
AHJ	Authority Having Jurisdiction		
ANSI American National Standards Institute			
AWG American Wire Gauge (refer to STP and UTP)			
AWS	Advanced Wireless Services		
BCT Bonding Conductor for Telecommunications (also			
	Telecommunications Bonding Conductor (TBC))		
BDA	Bi-Directional Amplifier		
BICSI	Building Industry Consulting Service International		

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

BIM	Building Information Modeling		
BOM	M Bill of Materials		
BTU	U British Thermal Units		
BUCR Back-up Computer Room			
BTS	Base Transceiver Station		
CAD	AutoCAD		
CBOPC	Community Based Out Patient Clinic		
CBC	Coupled Bonding Conductor		
CBOC	Community Based Out Patient Clinic (refer to CBOPC,		
	OPC, VAMC)		
CCS	TIP's Cross Connection System (refer to VCCS and		
	HCCS)		
CFE	Contractor Furnished Equipment		
CFM US Department of Veterans Affairs Office of			
	Construction and Facilities Management		
CFR	FR Consolidated Federal Regulations		
CIO Communication Information Officer (Facility, VI			
	Region)		
cm	Centimeters		
CO	Central Office		
COR	Contracting Officer Representative		
CPU	Central Processing Unit		
CSU	Customer Service Unit		
CUP	Conditional Use Permit(s) - Federal/GSA for VA		
dB	Decibel		
dBm	dBm Decibel Measured		
dBmV	Decibel per milli-Volt		
DC	Direct Current		
DEA	United States Drug Enforcement Administration		
DSU	Data Service Unit		
EBC	Equipment Bonding Conductor		

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

EDGE Enhanced Data (Rates) for GSM Evolution  EDM Electrical Design Manual  EMCR Emergency Management Control Room (refer to DCR, ECC)  EMI Electromagnetic Interference (refer to RFI)  EMS Emergency Medical Service  EMT Electrical Metallic Tubing or thin wall conduit  ENTR Utilities Entrance Location (refer to DEMARC, POTS, LEC)  EPBX Electronic Digital Private Branch Exchange  ESR Vendor's Engineering Service Report  FA Fire Alarm  FAR Federal Acquisition Regulations in Chapter 1 of Title 48 of Code of Federal Regulations  FMS VA's Headquarters or Medical Center Facility's Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)  HSPA High Speed Packet Access	ECC	Engineering Control Center (refer to DCR, EMCR)		
EMCR Emergency Management Control Room (refer to DCR, ECC)  EMI Electromagnetic Interference (refer to RFI)  EMS Emergency Medical Service  EMT Electrical Metallic Tubing or thin wall conduit  ENTR Utilities Entrance Location (refer to DEMARC, POTS, LEC)  EPBX Electronic Digital Private Branch Exchange  ESR Vendor's Engineering Service Report  FA Fire Alarm  FAR Federal Acquisition Regulations in Chapter 1 of Title 48 of Code of Federal Regulations  FMS VA's Headquarters or Medical Center Facility's Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  High Frequency (Radio Band; Re FR, RF, VHF & UHF)	EDGE	Enhanced Data (Rates) for GSM Evolution		
EMS Emergency Medical Service  EMT Electrical Metallic Tubing or thin wall conduit  ENTR Utilities Entrance Location (refer to DEMARC, POTS, LEC)  EPBX Electronic Digital Private Branch Exchange  ESR Vendor's Engineering Service Report  FA Fire Alarm  FAR Federal Acquisition Regulations in Chapter 1 of Title 48 of Code of Federal Regulations  FMS VA's Headquarters or Medical Center Facility's Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  High Frequency (Radio Band; Re FR, RF, VHF & UHF)	EDM	Electrical Design Manual		
EMS Emergency Medical Service  EMT Electrical Metallic Tubing or thin wall conduit  ENTR Utilities Entrance Location (refer to DEMARC, POTS, LEC)  EPBX Electronic Digital Private Branch Exchange  ESR Vendor's Engineering Service Report  FA Fire Alarm  FAR Federal Acquisition Regulations in Chapter 1 of Title 48 of Code of Federal Regulations  FMS VA's Headquarters or Medical Center Facility's Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  High Frequency (Radio Band; Re FR, RF, VHF & UHF)	EMCR Emergency Management Control Room (refer to DCR, E			
EMT Electrical Metallic Tubing or thin wall conduit  ENTR Utilities Entrance Location (refer to DEMARC, POTS, LEC)  EPBX Electronic Digital Private Branch Exchange  ESR Vendor's Engineering Service Report  FA Fire Alarm  FAR Federal Acquisition Regulations in Chapter 1 of Title 48 of Code of Federal Regulations  FMS VA's Headquarters or Medical Center Facility's Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HHIC Head End Interface Cabinets(refer to HEC, PA)  High Frequency (Radio Band; Re FR, RF, VHF & UHF)	EMI	### Electromagnetic Interference (refer to RFI)		
Utilities Entrance Location (refer to DEMARC, POTS, LEC)  EPBX Electronic Digital Private Branch Exchange  ESR Vendor's Engineering Service Report  FA Fire Alarm  FAR Federal Acquisition Regulations in Chapter 1 of Title 48 of Code of Federal Regulations  VA's Headquarters or Medical Center Facility's Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  High Frequency (Radio Band; Re FR, RF, VHF & UHF)	EMS	Emergency Medical Service		
EPBX Electronic Digital Private Branch Exchange  ESR Vendor's Engineering Service Report  FA Fire Alarm  FAR Federal Acquisition Regulations in Chapter 1 of Title  48 of Code of Federal Regulations  FMS VA's Headquarters or Medical Center Facility's  Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	EMT	Electrical Metallic Tubing or thin wall conduit		
EPBX Electronic Digital Private Branch Exchange  ESR Vendor's Engineering Service Report  FA Fire Alarm  FAR Federal Acquisition Regulations in Chapter 1 of Title 48 of Code of Federal Regulations  FMS VA's Headquarters or Medical Center Facility's Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  High Frequency (Radio Band; Re FR, RF, VHF & UHF)	ENTR	Utilities Entrance Location (refer to DEMARC, POTS,		
FA Fire Alarm  FAR Federal Acquisition Regulations in Chapter 1 of Title 48 of Code of Federal Regulations  FMS VA's Headquarters or Medical Center Facility's Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)		LEC)		
FA Fire Alarm  FAR Federal Acquisition Regulations in Chapter 1 of Title  48 of Code of Federal Regulations  FMS VA's Headquarters or Medical Center Facility's  Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High- Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	EPBX	Electronic Digital Private Branch Exchange		
FAR Federal Acquisition Regulations in Chapter 1 of Title 48 of Code of Federal Regulations  FMS VA's Headquarters or Medical Center Facility's Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High- Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	ESR	Vendor's Engineering Service Report		
48 of Code of Federal Regulations  FMS VA's Headquarters or Medical Center Facility's Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  High Frequency (Radio Band; Re FR, RF, VHF & UHF)	FA	Fire Alarm		
FMS VA's Headquarters or Medical Center Facility's Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  High Frequency (Radio Band; Re FR, RF, VHF & UHF)	FAR	Federal Acquisition Regulations in Chapter 1 of Title		
Management Service  FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)		48 of Code of Federal Regulations		
FR Frequency (refer to RF)  FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	FMS	VA's Headquarters or Medical Center Facility's		
FTS Federal Telephone Service  GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)		Management Service		
GFE Government Furnished Equipment  GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	FR	Frequency (refer to RF)		
GPS Global Positioning System  GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	FTS	Federal Telephone Service		
GRC Galvanized Rigid Metal Conduit  GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	GFE	Government Furnished Equipment		
GSM Global System (Station) for Mobile  HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	GPS	Global Positioning System		
HCCS TIP's Horizontal Cross Connection System (refer to CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High-Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	GRC	Galvanized Rigid Metal Conduit		
CCS & VCCS)  HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High- Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	GSM	Global System (Station) for Mobile		
HDPE High Density Polyethylene Conduit  HDTV Advanced Television Standards Committee High- Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	HCCS	TIP's Horizontal Cross Connection System (refer to		
HDTV Advanced Television Standards Committee High- Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)		CCS & VCCS)		
Definition Digital Television  HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	HDPE High Density Polyethylene Conduit			
HEC Head End Cabinets(refer to HEIC, PA)  HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	HDTV	Advanced Television Standards Committee High-		
HEIC Head End Interface Cabinets(refer to HEC, PA)  HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)		Definition Digital Television		
HF High Frequency (Radio Band; Re FR, RF, VHF & UHF)	HEC	Head End Cabinets(refer to HEIC, PA)		
	HEIC	Head End Interface Cabinets(refer to HEC, PA)		
HSPA High Speed Packet Access	HF	High Frequency (Radio Band; Re FR, RF, VHF & UHF)		
	HSPA	High Speed Packet Access		

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

HZ	Hertz 09-01		
IBT	Intersystem Bonding Termination (NEC 250.94)		
IC	Intercom		
ICRA	Infectious Control Risk Assessment		
IDEN	Integrated Digital Enhanced Network		
IDC	DC Insulation Displacement Contact		
IDF	Intermediate Distribution Frame		
ILSM	Interim Life Safety Measures		
IMC	Rigid Intermediate Steel Conduit		
IRM	Department of Veterans Affairs Office of Information		
	Resources Management		
ISDN	Integrated Services Digital Network		
ISM	Industrial, Scientific, Medical		
IWS	Intra-Building Wireless System		
LAN	Local Area Network		
LBS	Location Based Services, Leased Based Systems		
LEC	Local Exchange Carrier (refer to DEMARC, PBX & POTS)		
LED	Light Emitting Diode		
LMR	Land Mobile Radio		
LTE	Long Term Evolution, or 4G Standard for Wireless Data		
	Communications Technology		
M	Meter		
MAS	Medical Administration Service		
MATV	Master Antenna Television		
MCR	Main Computer Room		
MCOR	Main Computer Operators Room		
MDF	Main Distribution Frame		
MH	Manholes or Maintenance Holes		
MHz	Megaherts (10 <sup>6</sup> Hz)		
mm	m Millimeter		
MOU	Memorandum of Understanding		

# 

09-01-19

	09-01-		
MW	Microwave (RF Band, Equipment or Services)		
NID	Network Interface Device (refer to DEMARC)		
NEC National Electric Code			
NOR Network Operations Room			
NRTL	NRTL OSHA Nationally Recognized Testing Laboratory		
NS	Nurse Stations		
NTIA	U.S. Department of Commerce National		
	Telecommunications and Information Administration		
OEM	Original Equipment Manufacturer		
T&IO	Office of Information and Technology		
OPC	VA's Outpatient Clinic (refer to CBOC, VAMC)		
OSH	Department of Veterans Affairs Office of Occupational		
	Safety and Health		
OSHA United States Department of Labor Occupational			
	and Health Administration		
OTDR Optical Time-Domain Reflectometer			
PA	Public Address System (refer to HE, HEIC, RPEC)		
PBX	Private Branch Exchange (refer to DEMARC, LEC, POTS)		
PCR	Police Control Room (refer to SPCC, could be		
	designated SCC)		
PCS	Personal Communications Service (refer to UPCS)		
PE	Professional Engineer		
PM	Project Manager		
PoE	Power over Ethernet		
POTS	Plain Old Telephone Service (refer to DEMARC, LEC,		
	PBX)		
PSTN Public Switched Telephone Network			
PSRAS	Public Safety Radio Amplification Systems		
PTS	Pay Telephone Station		
PVC	Poly-Vinyl Chloride		
PWR	Power (in Watts)		

# 

09-01-19

	09-01-		
RAN	Radio Access Network		
RBB	Rack Bonding Busbar		
RE	Resident Engineer or Senior Resident Engineer		
RF	Radio Frequency (refer to FR)		
RFI	Radio Frequency Interference (refer to EMI)		
RFID	RF Identification (Equipment, System or Personnel)		
RMC	Rigid Metal Conduit		
RMU	Rack Mounting Unit		
RPEC	Radio Paging Equipment Cabinets(refer to HEC, HEIC,		
	PA)		
RTLS	Real Time Location Service or System		
RUS	Rural Utilities Service		
SCC	Security Control Console (refer to PCR, SPCC)		
SMCS Spectrum Management and Communications Security			
	(COMSEC)		
SFO Solicitation for Offers			
SME	Subject Matter Experts (refer to AHJ)		
SMR	Specialized Mobile Radio		
SMS	Security Management System		
SNMP	Simple Network Management Protocol		
SPCC	Security Police Control Center (refer to PCR, SMS)		
STP	Shielded Balanced Twisted Pair (refer to UTP)		
STR	Stacked Telecommunications Room		
TAC	VA's Technology Acquisition Center, Austin, Texas		
TCO	Telecommunications Outlet		
TER	Telephone Equipment Room		
TGB Telecommunications Grounding Busbar (also Secondary			
Bonding Busbar (SBB))			
TIP	Telecommunications Infrastructure Plant		
TMGB	Telecommunications Main Grounding Busbar (also		
	Primary Bonding Busbar (PBB))		
L			

# 

09-01-19

	09-01-		
TMS	Traffic Management System		
TOR	Telephone Operators Room		
TP	TP Balanced Twisted Pair (refer to STP and UTP)		
TR Telecommunications Room (refer to STR)			
TWP	TWP Twisted Pair		
UHF	Ultra High Frequency (Radio)		
UMTS	Universal Mobile Telecommunications System		
UPCS	Unlicensed Personal Communications Service (refer to PCS)		
UPS	Uninterruptible Power Supply		
USC	United States Code		
UTP	Unshielded Balanced Twisted Pair (refer to TP and		
	STP)		
UV	Ultraviolet		
V	Volts		
VAAR	Veterans Affairs Acquisition Regulation		
VACO	Veterans Affairs Central Office		
VAMC	VA Medical Center (refer to CBOC, OPC, VACO)		
VCCS	TIP's Vertical Cross Connection System (refer to CCS and HCCS)		
VHF	Very High Frequency (Radio)		
VISN	Veterans Integrated Services Network (refers to		
	geographical region)		
VSWR	Voltage Standing Wave Radio		
W	Watts		
WEB	World Electronic Broadcast		
WiMAX	Worldwide Interoperability (for MW Access)		
WI-FI	Wireless Fidelity		
WMTS	Wireless Medical Telemetry Service		
WSP	Wireless Service Providers		
- 61 1.1			

# B. Definitions:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

- 1. Access Floor: Pathway system of removable floor panels supported on adjustable pedestals to allow cable placement in area below.
- 2. BNC Connector (BNC): United States Military Standard MIL-C-39012/21 bayonet-type coaxial connector with quick twist mating/unmating, and two lugs preventing accidental disconnection from pulling forces on cable.
- 3. Bond: Permanent joining of metallic parts to form an electrically conductive path to ensure electrical continuity and capacity to safely conduct any currents likely to be imposed to earth ground.
- 4. Bundled Microducts: All forms of jacketed microducts.
- 5. Conduit: Includes all raceway types specified.
- 6. Conveniently Accessible: Capable of being reached without use of ladders, or without climbing or crawling under or over obstacles such as, motors, pumps, belt guards, transformers, piping, ductwork, conduit and raceways.
- 7. Distributed (in house) Antenna System (DAS): An Emergency Radio Communications System installed for Emergency Responder (or first responders and Government personnel) use while inside facility to maintain contact with each respective control point; refer to Section 27 53 19, DISTRIBUTED RADIO ANTENNA (WITHIN BUILDING) EQUIPMENT AND SYSTEMS.
- 8. DEMARC, Extended DMARC or ENTR: Service provider's main point of demarcation owned by LEC or service provider and establishes a physical point where service provider's responsibilities for service and maintenance end. This point is called NID, in data networks.
- 9. Effectively Grounded: Intentionally bonded to earth through connections of low impedance having current carrying capacity to prevent buildup of currents and voltages resulting in hazard to equipment or persons.
- 10. Electrical Supervision: Analyzing a system's function and components (i.e. cable breaks / shorts, inoperative stations, lights, LEDs and states of change, from primary to backup) on a 24/7/365 basis; provide aural and visual emergency notification signals to minimum two remote designated or accepted monitoring stations.
- 11. Electrostatic Interference (ESI) or Electrostatic Discharge Interference: Refer to EMI and RFI.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

- 12. Emergency Call Systems: Wall units (in parking garages and stairwells) and pedestal mounts (in parking lots) typically provided with a strobe, camera and two-way audio communication functions.

  Additional units are typically provided in facility's emergency room, designated nurses stations, director's office, Disaster Control Center, SCC, ECC.
- 13. Project 25 (2014) (P25 (TIA-102 Series)): Set of standards for local, state and Federal public safety organizations and agencies digital LMR services. P25 is applicable to LMR equipment authorized or licensed under the US Department of Commerce National Telecommunications and Information Administration or FCC rules and regulations, and is a required standard capability for all LMR equipment and systems.
- 14. Grounding Electrode Conductor: (GEC) Conductor connected to earth grounding electrode.
- 15. Grounding Electrode System: Electrodes through which an effective connection to earth is established, including supplementary, communications system grounding electrodes and GEC.
- 16. Grounding Equalizer or Backbone Bonding Conductor (BBC): Conductor that interconnects elements of telecommunications grounding infrastructure.
- 17. Head End (HE): Equipment, hardware and software, or a master facility at originating point in a communications system designed for centralized communications control, signal processing, and distribution that acts as a common point of connection between equipment and devices connected to a network of interconnected equipment, possessing greatest authority for allowing information to be exchanged, with whom other equipment is subordinate.
- 18. Microducts: All forms of air blown fiber pathways.
- 19. Ohm: A unit of restive measurement.
- 20. Received Signal Strength Indication (RSSI): A measurement of power present in a received RF signal.
- 21. Service Provider Demarcation Point (SPDP): Not owned by LEC or service provider, but designated by Government as point within facility considered the DEMARC.

# 

09-01-19

- 22. Sound (SND): Changing air pressure to audible signals over given time span.
- 23. System: Specific hardware, firmware, and software, functioning together as a unit, performing task for which it was designed.
- 24. Telecommunications Bonding Backbone (TBB): Conductors of appropriate size (minimum 53.49 mm2 [1/0 AWG]) stranded copper wire, that connect to Grounding Electrode System and route to telecommunications main grounding busbar (TMGB) and circulate to interconnect various TGBs and other locations shown on drawings.
- 25. Voice over Internet Protocol (VoIP): A telephone system in which voice signals are converted to packets and transmitted over LAN network using Transmission Control Protocol (TCP)/Internet Protocol (IP). VA'S VoIP is not listed or coded for life and public safety, critical, emergency or other protection functions. When VoIP system or equipment is provided instead of PBX system or equipment, each TR (STR) and DEMARC requires increased AC power provided to compensate for loss of PBX's telephone instrument line power; and, to compensate for absence of PBX's UPS capability.
- 26. Wide Area Network (WAN): A digital network that transcends localized LANs within a given geographic location. VA'S WAN/LAN is not nationally listed or coded for life and public safety, critical, emergency or other safety functions.

### 1.3 APPLICABLE PUBLICATIONS

- A. Applicability of Standards: Unless documents include more stringent requirements, applicable construction industry standards have same force and effect as if bound or copied directly into the documents to extent referenced. Such standards are made a part of these documents by reference.
  - 1. Each entity engaged in construction must be familiar with industry standards applicable to its construction activity.
  - 2. Obtain standards directly from publication source, where copies of standards are needed to perform a required construction activity.
- B. Government Codes, Standards and Executive Orders: Refer to
  http://www.cfm.va.gov/TIL/cPro.asp:
  - 1. Federal Communications Commission, (FCC) CFR, Title 47:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

<b>PART 1 -</b> Bancroft Architects + Engineers 09-01-1			
Part 15	Restrictions of use for Part 15 listed RF		
	Equipment in Safety of Life Emergency Functions		
	and Equipment Locations		
Part 47	Chapter A, Paragraphs 6.1-6.23, Access to		
	Telecommunications Service, Telecommunications		
	Equipment and Customer Premises Equipment		
Part 58	Television Broadcast Service		
Part 73	Radio and Television Broadcast Rules		
Part 90	Rules and Regulations, Appendix C		
Form 854	Antenna Structure Registration		
Chapter XXIII	National Telecommunications and Information		
	Administration (NTIA, P/O Commerce, Chapter		
	XXIII) the 'Red Book'- Chapters 7, 8 & 9		
	compliments CFR, Title 47, FCC Part 15, RF		
	Restriction of Use and Compliance in "Safety of		
	Life" Functions & Locations		
2. US Department of Agr	riculture, (Title 7, USC, Chapter 55, Sections		
2201, 2202 & 2203:RI	US 1755 Telecommunications Standards and		
Specifications for I	Materials, Equipment and Construction:		
RUS Bull 1751F-630	Design of Aerial Cable Plants		
RUS Bull 1751F-640	Design of Buried Cable Plant, Physical		
	Considerations		
RUS Bull 1751F-643	Underground Plant Design		
RUS Bull 1751F-815	Electrical Protection of Outside Plants,		
RUS Bull 1753F-201	Acceptance Tests of Telecommunications Plants		
	(PC-4)		
RUS Bull 1753F-401	Splicing Copper and Fiber Optic Cables (PC-2)		
RUS Bull 345-50	Trunk Carrier Systems (PE-60)		
RUS Bull 345-65	Shield Bonding Connectors (PE-65)		
RUS Bull 345-72	Filled Splice Closures (PE-74)		
RUS Bull 345-83	Gas Tube Surge Arrestors (PE-80)		
3. US Department of Con	mmerce/National Institute of Standards		
Technology,(NIST):			
FIPS PUB 1-1	Telecommunications Information Exchange		
FIPS PUB 100/1	Interface between Data Terminal Equipment (DTE)		
	Circuit Terminating Equipment for operation		

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

Network Security

09-01-19 with Packet Switched Networks, or Between Two DTEs, by Dedicated Circuit FIPS PUB 140/2 Telecommunications Information Security Algorithms General Purpose 37 Position Interface between DTE and Data Circuit Terminating Equipment Electronic Data Interchange (EDI), Federal Building Standard for Telecommunications Pathway and Spaces

Guideline for the Analysis of Local Area

Standards for Security Categorization of

Advanced Encryption Standard (AES)

Federal Information and Information Systems

4. US Department of Defense, (DoD):

FIPS PUB 143

FIPS 160/2

FIPS 175

FIPS 191

FIPS 197

FIPS 199

MIL-STD-188-110	Interoperability and Performance Standards for
	Data Modems
MIL-STD-188-114	Electrical Characteristics of Digital Interface
	Circuits
MIL-STD-188-115	Communications Timing and Synchronizations
	Subsystems
MIL-C-28883	Advanced Narrowband Digital Voice Terminals
MIL-C-39012/21	Connectors, Receptacle, Electrical, Coaxial,
	Radio Frequency, (Series BNC (Uncabled), Socket
	Contact, Jam Nut Mounted, Class 2)

- 5. US Department of Health and Human Services: The Health Insurance Portability and Accountability Act of 1996 (HIPAA) Privacy, Security and Breach Notification Rules
- 6. US Department of Justice: 2010 Americans with Disabilities Act Standards for Accessible Design (ADAAD).
- 7. US Department of Labor, (DoL) Public Law 426-62 CFR, Title 29, Part 1910, Chapter XVII - Occupational Safety and Health Administration (OSHA), Occupational Safety and Health Standards):

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

		09-01-19
Subpart	7	Approved NRTLs; obtain a copy at
		https://www.osha.gov/dts/otpca/nrtl/nrtllist.ht
		<u>ml</u>
Subpart	35	Compliance with NFPA 101, Life Safety Code
Subpart	36	Design and Construction Requirements for Exit
		Routes
Subpart	268	Telecommunications
Subpart	305	Wiring Methods, Components, and Equipment for
		General Use
Subpart	508	Americans with Disabilities Act Accessibility
		Guidelines; technical requirement for
		accessibility to buildings and facilities by
		individuals with disabilities

- 8. US Department of Transportation, (DoT):
  - a. Public Law 85-625, CFR, Title 49, Part 1, Subpart C Federal Aviation Administration (FAA):AC 110/460-ID & AC 707 / 460-2E Advisory Circulars Standards for Construction of Antenna Towers, and 7450 and 7460-2 Antenna Construction Registration Forms.
- 9. US Department of Veterans Affairs (VA): Office of Telecommunications (OI&T), MP-6, PART VIII, TELECOMMUNICATIONS, CHAPTER 5, AUDIO, RADIO AND TELEVISION (and COMSEC) COMMUNICATIONS SYSTEMS: Spectrum Management and COMSEC Service (SMCS), AHJ for:
  - a. CoG, "Continuance of Government" communications guidelines and compliance.
  - b. COMSEC, "VA wide coordination and control of security classified communication assets."
  - c. COOP, "Continuance of Operations" emergency communications guidelines and compliance.
  - d. FAA, FCC, and US Department of Commerce National Telecommunications and Information Administration, "VA wide RF Co-ordination, Compliance and Licensing."
  - e. Handbook 6100 Telecommunications: Cyber and Information Security Office of Cyber and Information Security, and Handbook 6500 - Information Security Program.
  - f. Low Voltage Special Communications Systems "Design, Engineering, Construction Contract Specifications and Drawings Conformity,

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

Proof of Performance Testing, VA Compliance and Life Safety Certifications for CFM and VA Facility Low Voltage Special Communications Projects (except Fire Alarm, Telephone and Data Systems)."

- g. SATCOM, "Satellite Communications" guidelines and compliance, and Security and Law Enforcement Systems "Coordinates the Design, Engineering, Construction Contract Specifications and Drawings Conformity, Proof of Performance Testing, VA Compliance, DEA and Public Safety Certification(s) for CFM and VA Facility Security Low Voltage Special Communications and Physical Security Projects.
- h. VHA's National Center for Patient Safety Veterans Health Administration (VHA) Warning System, Failure of Medical Alarm Systems using Paging Technology to Notify Clinical Staff, July 2004.
- i. VA's CEOSH, concurrence with warning identified in VA Directive 7700.
- j. Wireless and Handheld Devices, "Guidelines and Compliance,"
- k. Office of Security and Law Enforcement: VA Directive 0730 and Health Special Presidential Directive (HSPD)-12.
- C. NRTL Standards: Refer to https://www.osha.gov/laws-regs/regulations/standardnumber/1926
  - 1. Canadian Standards Association (CSA); same tests as presented by UL
  - 2. Communications Certifications Laboratory (CEL); same tests as presented by UL.
  - 3. Intertek Testing Services NA, Inc., (ITSNA), formerly Edison Testing Laboratory (ETL) same tests as presented by UL).
  - 4. Underwriters Laboratory (UL):

1-2005	Flexible Metal Conduit
5-2011	Surface Metal Raceway and Fittings
6-2007	Rigid Metal Conduit
44-010	Thermoset-Insulated Wires and Cables
50-1995	Enclosures for Electrical Equipment
65-2010	Wired Cabinets
83-2008	Thermoplastic-Insulated Wires and Cables
96-2005	Lightning Protection Components

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

PART 1 - 1	Bancroft Architects + Engineers 09-01-19
96A-2007	Installation Requirements for Lightning
	Protection Systems
360-2013	Liquid-Tight Flexible Steel Conduit
444-2008	Communications Cables
467-2013	Grounding and Bonding Equipment
486A-486B-2013	Wire Connectors
486C-2013	Splicing Wire Connectors
486D-2005	Sealed Wire Connector Systems
486E-2009	Standard for Equipment Wiring Terminals for Use
	with Aluminum and/or Copper Conductors
493-2007	Thermoplastic-Insulated Underground Feeder and
	Branch Circuit Cable
497/497A/497B/497C	
497D/497E	Protectors for Paired Conductors/Communications
	Circuits/Data Communications and Fire Alarm
	Circuits/coaxial circuits/voltage
	protections/Antenna Lead In
510-2005	Polyvinyl Chloride, Polyethylene and Rubber
	Insulating Tape
514A-2013	Metallic Outlet Boxes
514B-2012	Fittings for Cable and Conduit
514C-1996	Nonmetallic Outlet Boxes, Flush-Device Boxes
	and Covers
651-2011	Schedule 40 and 80 Rigid PVC Conduit
651A-2011	Type EB and A Rigid PVC Conduit and HDPE
	Conduit
797-2007	Electrical Metallic Tubing
884-2011	Underfloor Raceways and Fittings
1069-2007	Hospital Signaling and Nurse Call Equipment
1242-2006	Intermediate Metal Conduit
1449-2006	Standard for Transient Voltage Surge
	Suppressors
1479-2003	Fire Tests of Through-Penetration Fire Stops
1480-2003	Speaker Standards for Fire Alarm, Emergency,
	Commercial and Professional use

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

	<b>PART 1 -</b> E	Bancroft Architects + Engineers 09-01-19
	1666-2007	Standard for Wire/Cable Vertical (Riser) Tray
		Flame Tests
	1685-2007	Vertical Tray Fire Protection and Smoke Release
		Test for Electrical and Fiber Optic Cables
	1861-2012	Communication Circuit Accessories
	1863-2013	Standard for Safety, communications Circuits
		Accessories
	1865-2007	Standard for Safety for Vertical-Tray Fire
		Protection and Smoke-Release Test for
		Electrical and Optical-Fiber Cables
	2024-2011	Standard for Optical Fiber Raceways
	2024-2014	Standard for Cable Routing Assemblies and
		Communications Raceways
	2196-2001	Standard for Test of Fire Resistive Cable
	60950-1 ed. 2-2014	Information Technology Equipment Safety
D. In	dustry Standards:	
1.	Advanced Television	Systems Committee (ATSC):
	A/53 Part 1: 2013	ATSC Digital Television Standard, Part 1,
		Digital Television System
	A/53 Part 2: 2011	ATSC Digital Television Standard, Part 2,
		RF/Transmission System Characteristics
	A/53 Part 3: 2013	ATSC Digital Television Standard, Part 3,
		Service Multiplex and Transport System
		Characteristics
	A/53 Part 4: 2009	ATSC Digital Television Standard, Part 4, MPEG-
		2 Video System Characteristics
	A/53 Part 5: 2014	ATSC Digital Television Standard, Part 5, AC-3
		Audio System Characteristics
	A/53 Part 6: 2014	ATSC digital Television Standard, Part 6,
		Enhanced AC-3 Audio System Characteristics
2.	American Institute o	of Architects (AIA): 2006 Guidelines for Design &
	Construction of Heal	th Care Facilities.
3.	American Society of	Mechanical Engineers (ASME):
	A17.1 (2013)	Safety Code for Elevators and Escalators
		Includes Requirements for Elevators,
		Escalators, Dumbwaiters, Moving Walks, Material

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

		09-01-19
		Lifts, and Dumbwaiters with Automatic Transfer
		Devices
	17.3 (2011)	Safety Code for Existing Elevators and
		Escalators
	17.4 (2009)	Guide for Emergency Personnel
	17.5 (2011)	Elevator and Escalator Electrical Equipment
4.	American Society for	Testing and Materials (ASTM):
	B1 (2001)	Standard Specification for Hard-Drawn Copper
		Wire
	B8 (2004)	Standard Specification for Concentric-Lay-
		Stranded Copper Conductors, Hard, Medium-Hard,
		or Soft
	D1557 (2012)	Standard Test Methods for Laboratory Compaction
		Characteristics of Soil Using Modified Effort
		56,000 ft-lbf/ft3 (2,700 kN- $m/m3$ )
	D2301 (2004)	Standard Specification for Vinyl Chloride
		Plastic Pressure Sensitive Electrical
		Insulating Tape
	B258-02 (2008)	Standard Specification for Standard Nominal
		Diameters and Cross-Sectional Areas of AWG
		Sizes of Solid Round Wires Used as Electrical
		Conductors
	D709-01(2007)	Standard Specification for Laminated
		Thermosetting Materials
	D4566 (2008)	Standard Test Methods for Electrical
		Performance Properties of Insulations and
		Jackets for Telecommunications Wire and Cable
5.	American Telephone as	nd Telegraph Corporation (AT&T) - Obtain
	following AT&T Public	cations at https://ebiznet.sbc.com/sbcnebs/
	ATT-TP-76200 (2013)	Network Equipment and Power Grounding,
		Environmental, and Physical Design Requirements
	ATT-TP-76300(2012)	Merged AT&T Affiliate Companies Installation
		Requirements
	ATT-TP-76305 (2013)	Common Systems Cable and Wire Installation and
		Removal Requirements - Cable Racks and Raceways
	ATT-TP-76306 (2009)	Electrostatic Discharge Control

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

	PART I - B	ancroit Architects + Engineers
	ATT-TP-76400 (2012)	09-01-19 Detail Engineering Requirements
	ATT-TP-76402 (2013)	AT&T Raised Access Floor Engineering and
		Installation Requirements
	ATT-TP-76405 (2011)	Technical Requirements for Supplemental Cooling
		Systems in Network Equipment Environments
	ATT-TP-76416 (2011)	Grounding and Bonding Requirements for Network
		Facilities
	ATT-TP-76440 (2005)	Ethernet Specification
	ATT-TP-76450 (2013)	Common Systems Equipment Interconnection
		Standards for AT&T Network Equipment Spaces
	ATT-TP-76461 (2008)	Fiber Optic Cleaning
	ATT-TP-76900 (2010)	AT&T Installation Testing Requirement
	ATT-TP-76911 (1999)	AT&T LEC Technical Publication Notice
6.	British Standards In	stitution (BSI):
	BS EN 50109-2	Hand Crimping Tools - Tools for The Crimp
		Termination of Electric Cables and Wires for
		Low Frequency and Radio Frequency Applications
		- All Parts & Sections. October 1997
7.	Building Industry Co	nsulting Service International(BICSI):
	ANSI/BICSI 002-2011	Data Center Design and Implementation Best
		Practices
	ANSI/BICSI 004-2012	Information Technology Systems Design and
		Implementation Best Practices for Healthcare
		Institutions and Facilities
	ANSI/NECA/BICSI	
	568-2006	Standard for Installing Commercial Building
		Telecommunications Cabling
	NECA/BICSI 607-2011	Standard for Telecommunications Bonding and
		Grounding Planning and Installation Methods for
		Commercial Buildings

8. Electronic Components Assemblies and Materials Association, (ECA). ECA EIA/RS-270 (1973)Tools, Crimping, Solderless Wiring Devices -Recommended Procedures for User Certification EIA/ECA 310-E (2005) Cabinets, and Associated Equipment

ANSI/BICSI 005-2013 Electronic Safety and Security (ESS) System

Design and Implementation Best Practices

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

9.	Facility Guid	delines	Institut	e: 2010	Guidelines	for	Design	and
	Construction	of Heal	Lth Care	Faciliti	ies.			

10.	Insulated	Cable	Engineers	Association	(ICEA):
-----	-----------	-------	-----------	-------------	---------

ANSI/ICEA	
S-80-576-2002	Category 1 & 2 Individually Unshielded Twisted
	Pair Indoor Cables for Use in Communications
	Wiring Systems
ANSI/ICEA	
S-84-608-2010	Telecommunications Cable, Filled Polyolefin

000 2010	
	<pre>Insulated Copper Conductor, S-87-640(2011)</pre>
	Optical Fiber Outside Plant Communications
	Cable

ANSI/ICEA	
S-90-661-2012	Category 3, 5, & 5e Individually Unshielded
	Twisted-Pair Indoor Cable for Use in General
	Purpose and LAN Communication Wiring Systems
S-98-688 (2012)	Broadband Twisted Pair Cable Aircore,
	Polyolefin Insulated, Copper Conductors
S-99-689 (2012)	Broadband Twisted Pair Cable Filled, Polyolefin

	Insulated, Copper Conductors
ICEA S-102-700	
(2004)	Category 6 Individually Unshielded Twisted Pair
	Indoor Cables (With or Without an Overall
	Shield) for use in Communications Wiring

Systems Technical Requirements

11. Institute of Electrical and Electronics Engineers (IEEE):	11.	Institute	of	Electrical	and	Electronics	Engineers	(IEEE):
---	-----	-----------	----	------------	-----	-------------	-----------	---------

ISSN 0739-5175	March-April 2008 Engineering in Medicine and
	Biology Magazine, IEEE (Volume: 27, Issue:2)
	Medical Grade-Mission Critical-Wireless
	Networks
IEEE C2-2012	National Electrical Safety Code (NESC)
C62.41.2-2002/	
Cor 1-2012 IEEE	Recommended Practice on Characterization of
	Surges in Low-Voltage (1000 V and Less) AC
	Power Circuits 4)

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

PART 1 - Bancroft Architects + Engineers	
C62.45-2002	09-01-19 IEEE Recommended Practice on Surge Testing for
	Equipment Connected to Low-Voltage (1000 V and
	Less) AC Power Circuits
81-2012 IEEE	Guide for Measuring Earth Resistivity, Ground
	Impedance, and Earth Surface Potentials of a
	Grounding System
100-1992	IEEE the New IEEE Standards Dictionary of
	Electrical and Electronics Terms
602-2007	IEEE Recommended Practice for Electric Systems
	in Health Care Facilities
1100-2005	IEEE Recommended Practice for Powering and
	Grounding Electronic Equipment
12. International Code Council:	
AC193 (2014)	Mechanical Anchors in Concrete Elements
13. International Organization for Standardization (ISO):	
ISO/TR 21730 (2007)	Use of Mobile Wireless Communication and
	Computing Technology in Healthcare Facilities -
	Recommendations for Electromagnetic
	Compatibility (Management of Unintentional
	Electromagnetic Interference) with Medical
	Devices
14. National Electrical	Manufacturers Association (NEMA):
NEMA 250 (2008)	Enclosures for Electrical Equipment (1,000V
	Maximum)
ANSI C62.61 (1993)	
	Arresters on Wire Line Telephone Circuits
ANSI/NEMA FB 1 (201	2)Fittings, Cast Metal Boxes and Conduit Bodies
	for Conduit, Electrical Metallic Tubing EMT)
	and Cable
ANSI/NEMA OS 1 (200	9)Sheet-Steel Outlet Boxes, Device Boxes, Covers,
	and Box Supports
NEMA SB 19 (R2007)	NEMA Installation Guide for Nurse Call Systems
TC 3 (2004)	Polyvinyl Chloride (PVC) Fittings for Use with
	Rigid PVC Conduit and Tubing
NEMA VE 2 (2006)	Cable Tray Installation Guidelines

15. National Fire Protection Association (NFPA):

## 

	PART I - B	ancroit Architects + Engineers
	70E-2015	09-01-19 Standard for Electrical Safety in the Workplace
	70-2014	National Electrical Code (NEC)
	72-2013	National Fire Alarm Code
	75-2013	Standard for the Fire Protection of Information
		Technological Equipment
	76-2012	Recommended Practice for the Fire Protection of
		Telecommunications Facilities
	77-2014	Recommended Practice on Static Electricity
	90A-2015	Standard for the Installation of Air
		Conditioning and Ventilating Systems
	99-2015	Health Care Facilities Code
	101-2015	Life Safety Code
	241	Safeguarding construction, alternation and
		Demolition Operations
	255-2006	Standard Method of Test of Surface Burning
		Characteristics of Building Materials
	262 - 2011	Standard Method of Test for Flame Travel and
		Smoke of Wires and Cables for Use in Air-
		Handling Spaces
	780-2014	Standard for the Installation of Lightning
		Protection Systems
	1221-2013	Standard for the Installation, Maintenance, and
		Use of Emergency Services Communications
		Systems
	5000-2015	Building Construction and Safety Code
16.	Society for Protecti	ve Coatings (SSPC):
	SSPC SP 6/NACE No.3	(2007) Commercial Blast Cleaning
17.	Society of Cable Tel	ecommunications Engineers (SCTE):
	ANSI/SCTE 15 2006	Specification for Trunk, Feeder and
		Distribution Coaxial Cable
18.	Telecommunications I	ndustry Association (TIA):
	TIA-120 Series	Telecommunications Land Mobile communications
		(APCO/Project 25) (January 2014)
	TIA TSB-140	Additional Guidelines for Field-Testing Length,
		Loss and Polarity of Optical Fiber Cabling
		Systems (2004)

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

<pre>PART 1 - Bancroft Architects + Engineers</pre>		
TIA-155	Guidelines for the Assessment and Mitigation of	
	Installed Category 6 Cabling to Support	
	10GBASE-T (2010)	
TIA TSB-162-A	Telecommunications Cabling Guidelines for	
	Wireless Access Points (2013)	
TIA-222-G	Structural Standard for Antenna Supporting	
	Structures and Antennas (2014)	
TIA/EIA-423-B	Electrical Characteristics of Unbalanced	
	Voltage Digital Interface Circuits (2012)	
TIA-455-C	General Requirements for Standard Test	
	Procedures for Optical Fibers, Cables,	
	Transducers, Sensors, Connecting and	
	Terminating Devices, and other Fiber Optic	
	Components (August 2014)	
TIA-455-53-A	FOTP-53 Attenuation by Substitution	
	Measurements for Multimode Graded-Index Optical	
	Fibers in Fiber Assemblies (Long Length)	
	(September 2001)	
TIA-455-61-A	FOTP-61 Measurement of Fiber of Cable	
	Attenuation Using an OTDR (July 2003)	
TIA-472D000-B	Fiber Optic Communications Cable for Outside	
	Plant Use (July 2007)	
ANSI/TIA-492-B	$62.5-\mu$ Core Diameter/125-um Cladding Diameter	
	Class la Graded-Index Multimode Optical Fibers	
	(November 2009)	
ANSI/TIA-492AAAB-A	50-um Core Diameter/125-um Cladding Diameter	
	Class IA Graded-Index Multimode Optically	
	Optimized American Standard Fibers (November	
	2009	
TIA-492CAAA	Detail Specification for Class IVa Dispersion-	
	Unshifted Single-Mode Optical Fibers (September	
	2002)	
TIA-492E000	Sectional Specification for Class IVd Nonzero-	
	Dispersion Single-Mode Optical Fibers for the	
	1,550 nm Window (September 2002)	

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

<b>PART 1 -</b> I	Bancroft Architects + Engineers 09-01-19
TIA-526-7-B	Measurement of Optical Power Loss of Installed
	Single-Mode Fiber Cable Plant - OFSTP-7
	(December 2008)
TIA-526.14-A	Optical Power Loss Measurements of Installed
	Multimode Fiber Cable Plant - SFSTP-14 (August
	1998)
TIA-568	Revision/Edition: C Commercial Building
	Telecommunications Cabling Standard Set: (TIA-
	568-C.0-2 Generic Telecommunications Cabling
	for Customer Premises (2012), TIA-568-C.1-1
	Commercial Building Telecommunications Cabling
	Standard Part 1: General Requirements (2012),
	TIA-568-C.2 Commercial Building
	Telecommunications Cabling Standard-Part 2:
	Balanced Twisted Pair Cabling Components
	(2009), TIA-568-C.3-1 Optical Fiber Cabling
	Components Standard, (2011) AND TIA-568-C.4
	Broadband Coaxial Cabling and Components
	Standard (2011) with addendums and erratas
TIA-569	Revision/Edition C Telecommunications Pathways
	and Spaces (March 2013)
TIA-574	Position Non-Synchronous Interface between Data
	Terminal equipment and Data Circuit Terminating
	Equipment Employing Serial Binary Interchange
	(May 2003)
TIA/EIA-590-A	Standard for Physical Location and Protection
	of Below Ground Fiber Optic Cable Plant (July
	2001)
TIA-598-D	Optical Fiber Cable Color Coding (January 2005)
TIA-604-10-B	Fiber Optic Connector Intermateablility
	Standard (August 2008)
ANSI/TIA-606-B	Administration Standard for Telecommunications
	Infrastructure (2012)
TIA-607-B	Generic Telecommunications Bonding and
	Grounding (Earthing) For Customer Premises
	(January 2013)

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

	09-01-19
TIA-613	High Speed Serial Interface for Data Terminal
	Equipment and Data Circuit Terminal Equipment
	(September 2005)
ANSI/TIA-758-B	Customer-owned Outside Plant Telecommunications
	Infrastructure Standard (April 2012)
ANSI/TIA-854	A Full Duplex Ethernet Specification for 1000
	Mb/s (1000BASE-TX) Operating over Category 6
	Balanced Twisted-Pair Cabling (2001)
ANSI/TIA-862-A	Building Automation Systems Cabling Standard
	(April 2011)
TIA-942-A	Telecommunications Infrastructure Standard for
	Data Centers (March 2014)
TIA-1152	Requirements for Field Testing Instruments and
	Measurements for Balanced Twisted Pair Cabling
	(September 2009)
TIA-1179	Healthcare Facility Telecommunications
	Infrastructure Standard (July 2010)

#### 1.4 SINGULAR NUMBER

A. Where any device or part of equipment is referred in singular number (such as "rack"), reference applies to as many such devices as are required to complete installation.

## 1.5 RELATED WORK

- A. Specification Order of Precedence: FAR Clause 52.236-21, VAAR Clause 852.236-71.
  - 1. Field Cutting and Patching: Section 09 91 00, PAINTING.
  - 2. Additional submittal requirements: Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.
  - 3. Availability and source of references and standards specified in applicable publications: Section 01 42 19, REFERENCE STANDARDS.
  - 4. Control of environmental pollution and damage for air, water, and land resources: Section 01 57 19, TEMPORARY ENVIRONMENTAL CONTROLS.
  - 5. Requirements for non-hazardous building construction and demolition waste: Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT.
  - 6. General requirements and procedures to comply with various federal mandates and U.S. Department of Veterans Affairs (VA) policies for

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

sustainable design: Section 01 81 13, SUSTAINABLE DESIGN REQUIREMENTS.

- 7. Closures of openings in walls, floors, and roof decks against penetration of flame, heat, and smoke or gases in fire resistant rated construction: Section 07 84 00, FIRESTOPPING.
- 8. Sealant and caulking materials and their application: Section 07 92 00, JOINT SEALANTS.
- 9. General electrical requirements that are common to more than one section of Division 26: Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.
- 10. Electrical conductors and cables in electrical systems rated 600 V and below: Section 26 05 21, LOW VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES (600 VOLTS AND BELOW).
- 11. Requirements for personnel safety and to provide a low impedance path to ground for possible ground fault currents: Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS.
- 12. Conduit and boxes: Section 26 05 33, RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS.
- 13. Wiring devices: Section 26 27 26, WIRING DEVICES.
- 14. Underground ducts, raceways, precast manholes and pull boxes: Section 26 05 41, UNDERGROUND ELECTRICAL CONSTRUCTION.
- 15. Lightning protection: Section 26 41 00, FACILITY LIGHTNING PROTECTION.
- 16. General requirements common to more than one section in Division 28: Section 28 05 00, COMMON WORK RESULTS FOR ELECTRONIC SAFETY AND SECURITY.
- 17. Conductors and cables for electronic safety and security systems:

  Section 28 05 13, CONDUCTORS AND CABLES FOR ELECTRONIC SAFETY AND

  SECURITY.
- 18. Low impedance path to ground for electronic safety and security system ground fault currents: Section 28 05 26, GROUNDING AND BONDING FOR SECURITY SYSTEMS.
- 19. Conduits and partitioned telecommunications raceways for Electronic Safety and Security systems: Section 28 05 28.33, CONDUITS AND BACK BOXES FOR ELECTRONIC SAFETY AND SECURITY.

## 

09-01-19

- 20. Physical Access Control System field-installed controllers connected by data transmission network: Section 28 13 00, PHYSICAL ACCESS DETECTION.
- 21. Detection and screening systems: Section 28 13 53, SECURITY ACCESS DETECTION.
- 22. Intrusion sensors and detection devices, and communication links to perform monitoring, alarm, and control functions: Section 28 16 11, INTRUSION DETECTION EQUIPMENT AND SYSTEMS.
- 23. Video surveillance system cameras, data transmission wiring, and control stations with associated equipment: Section 28 23 00, VIDEO SURVEILLANCE EQUIPMENT AND SYSTEMS.
- 24. Duress-panic alarms, emergency phones or call boxes, intercom systems, data transmission wiring and associated equipment: Section 28 26 00, ELECTRONIC PERSONAL PROTECTION EQUIPMENT AND SYSTEMS.
- 25. Alarm initiating devices, alarm notification appliances, control units, fire safety control devices, annunciators, power supplies, and wiring: Section 28 31 00, FIRE DETECTION AND ALARM.
- 26. Emergency Call telephones, intercom systems, with blue strobe light and equipment: Section 28 52 31, SECURITY EMERGENCY CALL/DURESS ALARM/COMMUNICATIONS SYSTEM AND EQUIPMENT.

## 1.6 ADMINISTRATIVE REQUIREMENTS

- A. Assign a single communications project manager to serve as point of contact for Government, contractor, and design professional.
- B. Be proactive in scheduling work.
  - 1. Use of premises is restricted at times directed by COR.
  - 2. Movement of materials: Unload materials and equipment delivered to site. Pay costs for rigging, hoisting, lowering and moving equipment on and around site, in building or on roof.
  - 3. Coordinate installation of required supporting devices and sleeves to be set in poured-in-place concrete and other structural components, as they are constructed.
  - 4. Sequence, coordinate, and integrate installations of materials and equipment for efficient flow of Work.
  - 5. Coordinate connection of materials, equipment, and systems with exterior underground and overhead utilities and services. Comply with requirements of governing regulations, franchised service

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

- companies, and controlling agencies; provide required connection for each service.
- 6. Initiate and maintain discussion regarding schedule for ceiling construction and install cables to meet that schedule.
- C. Contact the Office of Telecommunications, Special Communications Team (0050P2H3) (202)461-5310 to have a Government-accepted Telecommunications COR assigned to project for telecommunications review, equipment and system approval and coordination with other VA personnel.
- D. Communications Project Manager Responsibilities:
  - Assume responsibility for overall telecommunications system integration and coordination of work among trades, subcontractors, and authorized system installers.
  - 2. Coordinate with related work indicated on drawings or specified.
  - 3. Manage work related to telecommunications system installation in a manner approved by manufacturer.

#### 1.7 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Provide parts list including quantity of spare parts.
- C. Provide manufacturer product information. Government reserves the right to require a list of installations where products have been in operation.
- D. Provide Source Quality Control Submittal:
  - Submit written certification from OEM indicating that proposed supervisor of installation and proposed provider of warranty maintenance are authorized representatives of OEM. Include individual's legal name, contact information and OEM credentials in certification.
  - 2. Submit written certification from OEM that wiring and connection diagrams meet Government Life Safety Guidelines, NFPA, NEC, NRTL, these specifications, and Joint Commission requirements and instructions, requirements, recommendations, and guidance set forth by OEM for the proper performance of system.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

- 3. Pre-acceptance Certification: Certification in accordance with procedure outlined in Section 01 00 00, GENERAL REQUIREMENTS and specific Division 27 qualification documentation.
- E. Installer Qualifications: Submit three installations of similar size and complexity furnished and installed by installer; include:
  - 1. Installation location and name.
  - 2. Owner's name and contact information including, address, telephone and email.
  - 3. Date of project start and date of final acceptance.
  - 4. System project number.
  - 5. Three paragraph description of each system related to this project; include function, operation, and installation.
- F. Provide delegated design submittals (e.g. seismic support design).
- G. Submittals are required for all equipment anchors and supports. Include weights, dimensions, center of gravity, standard connections, manufacturer's recommendations and behavior problems (e.g., vibration, thermal expansion,) associated with equipment or conduit. Anchors and supports to resist seismic load based on seismic design categories per section 4.0 of VA seismic design requirements H-18-8 dated August, 2013.
- H. Test Equipment List:
  - 1. Supply test equipment of accuracy better than parameters to be tested.
  - 2. Submit test equipment list including make and model number:
    - a. ANSI/TIA-1152 Level IIIe testing to 500MHZ twisted pair cabling test instrument.
    - b. Fiber optic insertion loss power meter with light source.
    - c. Optical time domain reflectometer (OTDR).
    - d. Volt-Ohm meter.
    - e. Digital camera.
    - f. Bit Error Test Set (BERT).
    - g. Signal level meter.
    - h.
    - i.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

- 3. Supply only test equipment with a calibration tag from Government-accepted calibration service dated not more than 12 months prior to test.
- 4. Provide sample test and evaluation reports.

#### I. Submittal Drawings:

- 1. Telecommunications Space Plans/Elevations: Provide enlarged floor plans of telecommunication spaces indicating layout of equipment and devices, including receptacles and grounding provisions. Submit detailed plan views and elevations of telecommunication spaces showing racks, termination blocks, and cable paths. Include following rooms:
  - a. Telecommunications rooms.
  - b. Building Entrance Facility/Demarcation rooms.
  - c. Server rooms/Data Center.
  - d. Equipment rooms.
  - e. Antenna Head End rooms.
- 2. Logical Drawings: Provide logical riser or schematic drawings for all systems.
  - a. Provide riser diagrams systems and interconnection drawings for equipment assemblies; show termination points and identify wiring connections.
- 3. Access Panel Schedule on Submittal Drawings: Coordinate and prepare a location, size, and function schedule of access panels required to fully service equipment.
- J. Provide sustainable design submittals.
- K. Furnish electronic certified test reports to COR prior to final inspection and not more than 90 days after completion of tests.

## 1.8 CLOSEOUT SUBMITTALS

- A. Provide following closeout submittals prior to project closeout date:
  - 1. Warranty certificate.
  - 2. Evidence of compliance with requirements such as low voltage certificate of inspection.
  - 3. Project record documents.
  - 4. Instruction manuals and software that are a part of system.
- B. Maintenance and Operation Manuals: Submit in accordance with Section 01 00 00, GENERAL REQUIREMENTS.

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

- 1. Prepare a manual for each system and equipment specified.
- 2. Furnish on portable storage drive in PDF format or equivalent accepted by COR.
- 3. Furnish complete manual as specified in specification section, fifteen days prior to performance of systems or equipment test.
- 4. Furnish remaining manuals prior to final completion.
- 5. Identify storage drive "MAINTENANCE AND OPERATION MANUAL" and system name.
- 6. Include name, contact information and emergency service numbers of each subcontractor installing system or equipment and local representatives for system or equipment.
- 7. Provide a Table of Contents and assemble files to conform to Table of Contents.
- 8. Operation and Maintenance Data includes:
  - a. Approved shop drawing for each item of equipment.
  - b. Internal and interconnecting wiring and control diagrams with data to explain detailed operation and control of equipment.
  - c. A control sequence describing start-up, operation, and shutdown.
  - d. Description of function of each principal item of equipment.
  - e. Installation and maintenance instructions.
  - f. Safety precautions.
  - g. Diagrams and illustrations.
  - h. Test Results and testing methods.
  - i. Performance data.
  - j. Pictorial "exploded" parts list with part numbers. Emphasis to be placed on use of special tools and instruments. Indicate sources of supply, recommended spare parts, and name of servicing organization.
  - k. Warranty documentation indicating end date and equipment protected under warranty.
  - 1. Appendix; list qualified permanent servicing organizations for support of equipment, including addresses and certified personnel qualifications.
- C. Record Wiring Diagrams:
  - 1. Red Line Drawings: Keep one E size 91.44 cm x 121.92 cm (36 inches x 48 inches) set of floor plans, on site during work hours, showing

## 

09-01-19

installation progress marked and backbone cable labels noted. Make these drawings available for examination during construction meetings or field inspections.

- 2. General Drawing Specifications: Detail and elevation drawings to be
  D size 61 cm x 91.44 cm (24 inches x 36 inches) with a minimum scale
  of 0.635 cm = 30.48 cm (1/4 inch = 12 inches). ER, TR and other
  enlarged detail floor plan drawings to be D size 61 cm x 91.44 cm
  (24" x 36") with a minimum scale of 0.635 cm = 30.48 cm (1/4 inch =
  12 inches). Building composite floor plan drawings to be D size 61
  cm x 91.44 cm (24 inches x 36 inches) with a minimum scale of 3.175
  mm = 30.48 cm (1/8 inch = 1' 0 inch).
- 3. Building Composite Floor Plans: Provide building floor plans showing work area outlet locations and configuration, types of jacks, distance for each cable, and cable routing locations.
- 4. Floor plans to include:
  - a. Final room numbers and actual backbone cabling and pathway locations and labeling.
  - b. Inputs and outputs of equipment identified according to labels installed on cables and equipment
  - c. Device locations with labels.
  - d. Conduit.
  - e. Head-end equipment.
  - f. Wiring diagram.
  - g. Labeling and administration documentation.
- 5. Submit Record Wiring Diagrams within five business days after final cable testing.
- 6. Deliver Record Wiring Diagrams as CAD files in.rvt formats as determined by COR.
- 7. Deliver four complete sets of electronic record wiring diagrams to COR on portable storage drive.
- D. Service Qualifications: Submit name and contact information of service organizations providing service to this installation within four hours of receipt of notification service is needed.

## 1.9 MAINTENANCE MATERIAL SUBMITTALS

A. After approval and prior to installation, furnish COR with the following:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

- 1. A 300 mm (12 inch) length of each type and size of wire and cable along with tag from coils of reels from which samples were taken.
- 2. One coupling, bushing and termination fitting for each type of conduit.
- 3. Samples of each hanger, clamp and supports for conduit and pathways.
- 4. Duct sealing compound.

### 1.10 QUALITY ASSURANCE

- A. Manufacturer's Qualifications: Manufacturer must produce, as a principal product, the equipment and material specified for this project, and have manufactured item for at least three years.
- B. Product and System Qualification:
  - 1. OEM must have three installations of equipment submitted presently in operation of similar size and type as this project, that have continuously operated for a minimum of three years.
  - 2. Government reserves the right to require a list of installations where products have been in operation before approval.
  - 3. Authorized representative of OEM must be responsible for design, satisfactory operation of installed system, and certification.
- C. Trade Contractor Qualifications: Trade contractor must have completed three or more installations of similar systems of comparable size and complexity with regards to coordinating, engineering, testing, certifying, supervising, training, and documentation. Identify these installations as a part of submittal.
- D. System Supplier Qualifications: System supplier must be authorized by OEM to warranty installed equipment.
- E. Telecommunications technicians assigned to system must be trained, and certified by OEM on installation and testing of system; provide written evidence of current OEM certifications for installers.
- F. Manufactured Products:
  - 1. Comply with FAR clause 52.236-5 for material and workmanship.
  - 2. When more than one unit of same class of equipment is required, units must be product of a single manufacturer.
  - 3. Equipment Assemblies and Components:
    - a. Components of an assembled unit need not be products of same manufacturer.

## 

09-01-19

- b. Manufacturers of equipment assemblies, which include components made by others, to assume complete responsibility for final assembled unit.
- c. Provide compatible components for assembly and intended service.
- d. Constituent parts which are similar must be product of a single manufacturer.
- 4. Identify factory wiring on equipment being furnished and on wiring diagrams.
- G. Testing Agencies: Government reserves the option of witnessing factory tests. Notify COR minimum 15 working days prior to manufacturer performing the factory tests.
  - 1. When equipment fails to meet factory test and re-inspection is required, contractor is liable for additional expenses, including expenses of Government.

## 1.11 DELIVERY, STORAGE, AND HANDLING

- A. Delivery and Acceptance Requirements:
  - 1. Government's approval of submittals must be obtained for equipment and material before delivery to job site.
  - 2. Deliver and store materials to job site in OEM's original unopened containers, clearly labeled with OEM's name and equipment catalog numbers, model and serial identification numbers for COR to inventory cable, patch panels, and related equipment.
- B. Storage and Handling Requirements:
  - 1. Equipment and materials must be protected during shipment and storage against physical damage, dirt, moisture, cold and rain:
    - a. Store and protect equipment in a manner that precludes damage or loss, including theft.
    - b. Protect painted surfaces with factory installed removable heavy kraft paper, sheet vinyl or equivalent.
    - c. Protect enclosures, equipment, controls, controllers, circuit protective devices, and other like items, against entry of foreign matter during installation; vacuum clean both inside and outside before testing and operating.
- C. Coordinate storage.

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

#### 1.12 FIELD CONDITIONS

- A. Where variations from documents are requested in accordance with GENERAL CONDITIONS and Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES, connecting work and related components must include additions or changes to branch circuits, circuit protective devices, conduits, wire, feeders, controls, panels and installation methods.
- B. A contract adjustment or additional time will not be granted because of field conditions pursuant to FAR 52.236-2 and FAR 52.236-3; a contract adjustment or additional time will not be granted for additional work required for complete and usable construction and systems pursuant to FAR 52.246-12.

#### 1.13 WARRANTY

- A. Comply with FAR clause 52.246-21:
  - Warranty material and equipment to be free from defects, workmanship, and remain so for a period of one year for Emergency Systems from date of final acceptance of system by Government; provide OEM's equipment warranty document to COR.
  - 2. Government maintenance personnel must have ability to contact OEM for emergency maintenance and logistic assistance, remote diagnostic testing, and assistance in resolving technical problems at any time; contractor and OEM must provide this capability.

#### PART 2 - PRODUCTS

## 2.1 PERFORMANCE AND DESIGN CRITERIA

A. Provide communications spaces and pathways conforming to TIA 569, at a minimum.

## 2.2 EQUIPMENT IDENTIFICATION

- A. Provide laminated black phenolic resin with a white core nameplates with minimum 6 mm (1/4 inch) high engraved lettering.
- B. Nameplates furnished by manufacturer as standard catalog items, unless other method of identification is indicated.

## 2.3 UNDERGROUND WARNING TAPE (NOT USED)

#### 2.4 WIRE LUBRICATING COMPOUND

A. Provide non-hardening or forming adhesive coating cable lubricants suitable for cable jacket material and raceway.

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

#### 2.5 FIREPROOFING TAPE

- A. Provide flexible, conformable fabric tape of organic composition and coated one side with flame-retardant elastomer.
- B. Tape must be self-extinguishing and cannot support combustion; arcproof and fireproof.
- C. Tape cannot deteriorate when subjected to water, gases, salt water, sewage, or fungus; and tape must be resistant to sunlight and ultraviolet light.
- D. Application must withstand a 200-ampere arc for minimum 30 seconds.
- E. Securing Tape: Glass cloth electrical tape minimum 0.18 mm (7 mils) thick and 19 mm (3/4 inch) wide.

#### 2.6 UNDERGROUND CABLES (NOT USED)

## 2.7 AERIAL (ABOVEGROUND) ENCLOSURES (NOT USED)

## 2.8 TEMPORARY (NOT USED)//\_\_\_\_// TIP PATHS (OVERHEAD TRACKS, ROAD/PATH BRIDGES, ETC.)

#### 2.9 ACCESS PANELS

- A. Panels: 304 mm x 304 mm (12 inches by 12 inchesor size allowed by location to provide optimum access to equipment for maintenance and service.
- B. Provide access panels and doors as required to allow service of materials and equipment that require inspection, replacement, repair or service.
- C. Provide access panels where items installed require access and are concealed in floor, wall, furred space or above ceiling; ceilings consisting of lay-in or removable splined tiles do not require access panels.
- D. Provide access panels with same fire rating classification as surface penetrated.

#### PART 3 - EXECUTION

#### 3.1 PREPARATION

- A. Penetrations and Sleeves:
  - 1. Lay out penetration and sleeve openings in advance, to permit provision in work.
  - 2. Set sleeves in forms before concrete is poured.
  - 3. Set sleeves prior to installation of structure for passage of pipes, conduit, ducts, etc.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

- 4. Provide sleeves and packing materials at penetrations of foundations, walls, slabs, partitions, and floors.
- Make sleeves that penetrate outside walls, basement slabs, footings, and beams waterproof.
- 6. Fill slots, sleeves and other openings in floors or walls if not
  - a. Fill spaces in openings after installation of conduit or cable.
  - b. Provide fill for floor penetrations to prevent passage of water, smoke, fire, and fumes.
  - c. Provide fire resistant fill in rated floors and walls, to prevent passage of air, smoke and fumes.
- 7. Install sleeves through floors watertight and extend minimum 50.8 mm (2 inches) above floor surface.
- 8. Match and set sleeves flush with adjoining floor, ceiling, and wall finishes where raceways passing through openings are exposed in finished rooms.
- 9. Annular space between conduit and sleeve must be minimum 6 mm (1/4 inch).
- 10. Do not provide sleeves for slabs-on-grade, unless specified or indicated otherwise.
- 11. Comply with requirements for firestopping, for sleeves through rated fire walls and smoke partitions.
- 12. Do not support piping risers or conduit on sleeves.
- 13. Identify unused sleeves and slots for future installation.
- 14. Provide core drilling if walls are poured or otherwise constructed without sleeves and wall penetration is required; do not penetrate structural members.

#### B. Core Drilling:

- 1. Avoid core drilling whenever possible.
- 2. Coordinate openings with other trades and utilities, and prevent damage to structural reinforcement.
- 3. Investigate existing conditions in vicinity of required opening prior to coring, including an x-ray of floor if determined necessary by competent person or COR.
- 4. Protect areas from damage.
- C. Verification of In-Place Conditions:

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

- Verify location, use and status of all material, equipment, and utilities that are specified, indicated, or determined necessary for removal.
  - a. Verify materials, equipment, and utilities to be removed are inactive, not required, or in use after completion of project.
  - b. Replace with equivalent any material, equipment and utilities that were removed by contractor that are required to be left in place.
- 2. Existing Utilities: Do not interrupt utilities serving facilities occupied by Government or others unless permitted under following conditions and then only after arranging to provide temporary utility services, according to requirements indicated:
  - a. Notify COR in writing at least 14 days in advance of proposed utility interruptions.
  - b. Do not proceed with utility interruptions without Government's written permission.
- D. Provide suspended platforms, strap hangers, brackets, shelves, stands or legs for floor, wall and ceiling mounting of equipment as required.
- E. Provide steel supports and hardware for installation of hangers, anchors, guides, and other support hardware.
- F. Obtain and analyze catalog data, weights, and other pertinent data required for coordination of equipment support provisions and installation.
- G. Verify site conditions and dimensions of equipment to ensure access for proper installation of equipment without disassembly that would void warranty.

## 3.2 INSTALLATION - GENERAL

- A. Coordinate systems, equipment, and materials installation with other building components.
- B. Install systems, materials, and equipment to conform with approved submittal data, including coordination drawings.
- C. Conform to VAAR 852.236.91 arrangements indicated, recognizing that work may be shown in diagrammatic form or have been impracticable to detail all items because of variances in manufacturers' methods of achieving specified results.

## 

09-01-19

- D. Install systems, materials, and equipment level and plumb, parallel and perpendicular to other building systems and components, where installed in both exposed and un-exposed spaces.
- E. Install equipment according to manufacturers' written instructions.
- F. Install wiring and cabling between equipment and related devices.
- G. Install cabling, wiring, and equipment to facilitate servicing, maintenance, and repair or replacement of equipment components. Connect equipment for ease of disconnecting, with minimum interference of adjacent other installations.
- H. Provide access panel or doors where units are concealed behind finished surfaces.
- I. Arrange for chases, slots, and openings in other building components during progress of construction, to allow for wiring, cabling, and equipment installations.
- J. Where mounting heights are not detailed or dimensioned, install systems, materials, and equipment to provide maximum headroom and access for service and maintenance as possible.
- K. Install systems, materials, and equipment giving priority to systems required to be installed at a specified slope.
- L. Avoid interference with structure and with work or other trades, preserving adequate headroom and clearing doors and passageways to satisfaction of COR and code requirements.
- M. Install equipment and cabling to distribute equipment loads on building structural members provided for equipment support under other sections; install and support roof-mounted equipment on structural steel or roof curbs as appropriate.
- N. Provide supplementary or miscellaneous items, appurtenances, devices and materials for a complete installation.

#### 3.3 EQUIPMENT INSTALLATION

- A. Locate equipment as close as practical to locations shown on drawings.
- B. Note locations of equipment requiring access on record drawings.
- C. Access and Access Panels: Verify access panel locations and construction with COR.
- D. Inaccessible Equipment:
  - 1. Where Government determines that contractor has installed equipment not conveniently accessible for operation and maintenance, equipment

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

must be removed and reinstalled as directed and without additional cost to Government.

- 2. Refer to Section 27 11 00, TELECOMMUNICATIONS ROOM FITTINGS for communication equipment cabinet assembly.
- 3. Refer to Section 27 11 00, TELECOMMUNICATIONS ROOM FITTINGS for equipment labeling.

### 3.4 EQUIPMENT IDENTIFICATION

- A. Install an identification sign which clearly indicates information required for use and maintenance of equipment.
- B. Secure identification signs with screws.

#### 3.5 CUTTING AND PATCHING

- A. Perform cutting and patching according to contract general requirements and as follows:
  - 1. Remove samples of installed work as specified for testing.
  - 2. Remove and replace defective work.
  - 3. Remove and replace non-conforming work.
- B. Cut, remove, and legally dispose of selected equipment, components, and materials, including removal of material, equipment, devices, and other items indicated to be removed and items made obsolete by new work.
- C. Provide and maintain temporary partitions or dust barriers adequate to prevent spread of dust and dirt to adjacent areas.
- D. Protect adjacent installations during cutting and patching operations.
- E. Protect structure, furnishings, finishes, and adjacent materials not indicated or scheduled to be removed.
- F. Patch finished surfaces and building components using new materials specified for original installation and experienced installers.

## 3.6 FIELD QUALITY CONTROL

- A. Provide work according to VAAR 852.236.91 and FAR clause 52.236-5.
- B. Provide minimum clearances and work required for compliance with NFPA 70, National Electrical Code (NEC), and manufacturers' instructions; comply with additional requirements indicated for access and clearances.
- C. Verify all field conditions and dimensions that affect selection and provision of materials and equipment, and provide any disassembly, reassembly, relocation, demolition, cutting and patching required to

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

09-01-19

provide work specified or indicated, including relocation and reinstallation of existing wiring and equipment.

- 1. Protect facility, equipment, and wiring from damage.
- D. Submit written notice that:
  - 1. Project has been inspected for compliance with documents.
  - 2. Work has been completed in accordance with documents.
- E. Non-Conforming Work: Conduct project acceptance inspections, final completion inspections, substantial completion inspections, and acceptance testing and demonstrations after verification of system operation and completeness by Contractor.
- F. For project acceptance inspections, final completion inspections, substantial completion inspections, and testing/demonstrations that require more than one site visit by COR or design professional to verify project compliance for same material or equipment, Government reserves right to obtain compensation from contractor to defray cost of additional site visits that result from project construction or testing deficiencies and incompleteness, incorrect information, or non-compliance with project provisions.
  - COR will notify contractor, of hourly rates and travel expenses for additional site visits, and will issue an invoice to Contractor for additional site visits.
  - 2. Contractor is not be eligible for extensions of project schedule or additional charges resulting from additional site visits that result from project construction or testing deficiencies/incompleteness, incorrect information, or non-compliance with Project provisions.

#### G. Tests:

- 1. Interim inspection is required at approximately 50 percent of installation.
- 2. Request inspection ten working days prior to interim inspection start date by notifying COR in writing; this inspection must verify equipment and system being provided adheres to installation, mechanical and technical requirements of construction documents.
- 3. Inspection to be conducted by OEM and factory-certified contractor representative, and witnessed by COR, facility and SMCS 0050P2H3 representatives.

## 

09-01-19

- 4. Check each item of installed equipment to ensure appropriate NRTL listing labels and markings are fixed in place.
- 5. Verify cabling terminations in DEMARC, MCR, TER, SCC, ECC, TRs and head end rooms, workstation locations and TCO adhere to color code for // T568B // T568A // pin assignments and cabling connections are in compliance with TIA standards.
- 6. Visually confirm minimum Category 6A cable marking at TCOs, CCSs locations, patch cords and origination locations.
- 7. Review entire communications circulating ground system, each TGB and grounding connection, grounding electrode and outside lightning protection system.
- 8. Review cable tray, conduit and path/wire way installation practice.
- 9. OEM and contractor to perform:
  - a. (NOT USED)
  - b. Baseband cable field inspection tests via attenuation measurements on factory reels and provide results along with OEM certification for factory reel tests.
- 10. Relocate failed cable reels to a secured location for inventory, as directed by COR, and then remove from project site within two working days; provide COR with written confirmation of defective cable reels removal from project site.
- 11. Provide results of interim inspections to COR.
- 12. If major or multiple deficiencies are discovered, additional interim inspections could be required until deficiencies are corrected, before permitting further system installation.
  - a. Additional inspections are scheduled at direction of COR.
  - b. Re-inspection of deficiencies noted during interim inspections, must be part of system's Final Acceptance Proof of Performance Test.
  - c. The interim inspection cannot affect the system's completion date unless directed by COR.
- 13. Facility COR will ensure test documents become a part of system's official documentation package.
- H. Pretesting: Re-align, re-balance, sweep, re-adjust and clean entire system and leave system working for a "break-in" period, upon completing installation of system and prior to Final Acceptance Proof

## 

09-01-19

of Performance Test. System RF transmitting equipment must not be connected to keying or control lines during "break-in" period.

- 1. Pretesting Procedure:
  - a. Verify systems are fully operational and meet performance requirements, utilizing accepted test equipment and spectrum analyzer.
  - b. Pretest and verify system functions and performance requirements conform to construction documents and, that no unwanted physical, aural and electronic effects, such as signal distortion, noise pulses, glitches, audio hum, poling noise are present.
- 2. (NOT USED)

#### I. Acceptance Test:

- 1. Schedule an acceptance test date after system has been pretested, and pretest results and certification submitted to COR.
- 2. Give COR fifteen working days written notice prior to date test is expected to begin; include expected duration of time for test in notification.
- 3. Test in the presence of the following:
  - a. COR.
  - b. OEM representatives.
  - c. VACO:
    - 1) CFM representative.
    - 2) AHJ-SMCS 0050P2H3, (202)461-5310.
  - d. VISN-CIO, Network Officer and VISN representatives.
  - e. Facility:
    - 1) FMS Service Chief, Bio-Medical Engineering and facility representatives.
    - 2) OI&T Service Chief and OI&T representatives.
    - 3) Safety Officer, Police Chief and facility safety representatives.
- 4. Test system utilizing accepted test equipment to certify proof of performance and Life and Public Safety compliance, FCC, NRTL, NFPA and OSHA compliance.
  - a. Rate system as acceptable or unacceptable at conclusion of test; make only minor adjustments and connections required to show proof of performance.

## 

09-01-19

- 1) Demonstrate and verify that system complies with performance requirements under operating conditions.
- 2) Failure of any part of system that precludes completion of system testing, and which cannot be repaired within four hours, terminates acceptance test of that portion of system.
- 3) Repeated failures that result in a cumulative time of eight hours to affect repairs is cause for entire system to be declared unacceptable.
- 4) If system is declared unacceptable, retesting must be rescheduled at convenience of Government and costs borne by the contractor.

### J. Acceptance Test Procedure:

- Physical and Mechanical Inspection: The test team representatives must tour major areas to determine system and sub-systems are completely and properly installed and are ready for acceptance testing.
- 2. A system inventory including available spare parts must be taken at this time.
- 3. Each item of installed equipment must be re-checked to ensure appropriate NRTL (i.e. UL) certification listing labels are affixed.
- 4. Confirm that deficiencies reported during Interim Inspections and Pretesting are corrected prior to start of Acceptance Test.
- 5. Inventory system diagrams, record drawings, equipment manuals, pretest results.
- Failure of system to meet installation requirements of specifications is grounds for terminating testing and to schedule re-testing.

#### K. Operational Test:

- 1. Individual Item Test: VACO AHJ representative (SMCS 0050P2H3) may select individual items of equipment for detailed proof of performance testing until 100 percent of system has been tested and found to meet requirements of the construction documents.
- 2. Government's Condition of Acceptance of System Language:
  - a. Without Acceptance: Until system fully meets conditions of construction documents, system's ownership, use, operation and warranty commences at Government's final acceptance date.

## 

09-01-19

- b. With Conditional Acceptance: Stating conditions that need to be addressed by contractor or OEM and stating system's use and operation to commence immediately while its warranty commences only at Government's agreed final extended acceptance date.
- c. With Full Acceptance: Stating system's ownership, use, operation and warranty to immediately commence at Government's agreed to date of final acceptance.
- L. Acceptance Test Conclusion: Reschedule testing on deficiencies and shortages with COR, after COR and SMCS AHJ jointly agree to results of the test, using the generated punch list or discrepancy list. Perform retesting to comply with these specifications at contractor's expense.
- M. Proof of Performance Certification:
  - 1. If system is declared acceptable, AHJ (SMCS 0050P2H3) provides COR notice stating system processes to required operating standards and functions and is Government accepted for use by facility.
  - 2. Validate items with COR needing to be provided to complete project contract (i.e. charts & diagrams, manuals, spare parts, system warranty documents executed, etc.). Once items have been provided, COR contacts FMS service chief to turn over system from CFM oversight for beneficial use by facility.
  - 3. If system is declared unacceptable without conditions, rescheduled testing expenses are to be borne by contractor.

## 3.7 CLEANING

- A. Remove debris, rubbish, waste material, tools, construction equipment, machinery and surplus materials from project site and clean work area, prior to final inspection and acceptance of work.
- B. Put building and premises in neat and clean condition.
- C. Remove debris on a daily basis.
- D. Remove unused material, during progress of work.
- E. Perform cleaning and washing required to provide acceptable appearance and operation of equipment to satisfaction of COR.
- F. Clean exterior surface of all equipment, including concrete residue, dirt, and paint residue, after completion of project.
- G. Perform final cleaning prior to project acceptance by COR.
- H. Remove paint splatters and other spots, dirt, and debris; touch up scratches and mars of finish to match original finish.

## 

09-01-19

- I. Clean devices internally using methods and materials recommended by manufacturer.
- J. Tighten wiring connectors, terminals, bus joints, and mountings, to include lugs, screws and bolts according to equipment manufacturer's published torque tightening values for equipment connectors. In absence of published connection or terminal torque values, comply with torque values specified in UL 486A-486B.

#### 3.8 TRAINING

- A. Provide training in accordance with subsection, INSTRUCTIONS, of Section 01 00 00, GENERAL REQUIREMENTS.
- B. Provide training for equipment or system as required in each associated specification.
- C. Develop and submit training schedule for approval by COR, at least 30 days prior to planned training.

#### 3.9 PROTECTION

- A. Protection of Fireproofing:
  - 1. Install clips, hangers, clamps, supports and other attachments to surfaces to be fireproofed, if possible, prior to start of spray fireproofing work.
  - 2. Install conduits and other items that would interfere with proper application of fireproofing after completion of spray fire proofing work.
  - 3. Patch and repair fireproofing damaged due to cutting or course of work must be performed by installer of fireproofing and paid for by trade responsible for damage.
- B. Maintain equipment and systems until final acceptance.
- C. Ensure adequate protection of equipment and material during installation and shutdown and during delays pending final test of systems and equipment because of seasonal conditions.

- - - E N D - - -

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

06-01-15

## SECTION 27 05 26 GROUNDING AND BONDING FOR COMMUNICATIONS SYSTEMS

## PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section identifies common and general grounding and bonding requirements of communication installations and applies to all sections of Divisions 27 and 28.
- B. Contractor to install a new Telecommunications Grounding System consisting of a grounding triad and Telecommunications Ground Bar (TMGB). Additionally all telecommunications grounds presently connected to the "Electrical Ground" in Electric Panel 1 must all be removed to avoid damage to IT equipment.
- C. Contractor to also coordinate with ADT and Golden West to perform their portion of the EHRM upgrade, and also direct these groups to relocate their Telecommunications Grounds to the new TMGB.

#### 1.2 RELATED WORK

- A. Requirements for a lightning protection system: Section 26 41 00, FACILITY LIGHTNING PROTECTION.
- B. Low voltage wiring: Section 27 10 00, STRUCTURED CABLING.

#### 1.3 SUBMITTALS

- A. Submit in accordance with Section 27 05 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS.
- B. Provide plan indicating location of system grounding electrode connections and routing of aboveground and underground grounding electrode conductors.
- C. Closeout Submittals: In addition to Section 27 05 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS provide the following:
  - 1. Certified test reports of ground resistance.
  - 2. Certifications: Two weeks prior to final inspection, submit following to COR:
    - a. Certification materials and installation is in accordance with construction documents.
    - b. Certification complete installation has been installed and tested.

## PART 2 - PRODUCTS

## EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

06-01-15

#### 2.1 COMPONENTS

- A. Grounding and Bonding Conductors:
  - Provide UL 83 insulated stranded copper equipment grounding conductors, with the exception of solid copper conductors for sizes 6 mm² (10 AWG) and smaller. Identify all grounding conductors with continuous green insulation color, except identify wire sizes 25 mm² (4 AWG) and larger per NEC.
  - Provide ASTM B8 bare stranded copper bonding conductors, with the exception of ASTM B1 solid bare copper for wire sizes 6 mm<sup>2</sup> (10 AWG) and smaller.

#### B. Ground Rods:

- 1. Copper clad steel, 19 mm (3/4-inch) diameter by 3000 mm (10 feet) long, conforming to UL 467.
- 2. Provide quantity of rods required to obtain specified ground resistance.
- C. Splices and Termination Components: Provide components meeting or exceeding UL 467 and clearly marked with manufacturer's name, catalog number, and permitted conductor sizes.
- D. Telecommunication System Ground Busbars:
  - 1. Telecommunications Main Grounding Busbar (TMGB):
    - a. 6.4 mm (1/4 inch) thick solid copper bar.
    - b. Minimum 100 mm (4 inches) high and length sized in accordance application requirements and future growth of minimum 510 mm (20 inches) long.
    - c. Minimum thirty predrilled attachment points (two rows of fifteen each) for attaching standard sized two-hole grounding lugs.
      - 1) 27 lugs with 15.8 mm (5/8 inch) hole centers.
      - 2) 3 lugs with 25.4 mm (1 inch) hole centers.
    - d. Wall-mount stand-off brackets, assembly screws and insulators for 100 mm (4 inches) standoff from wall.
    - e. Listed as grounding and bonding equipment.
  - 2. Telecommunications Grounding Busbar (TGB):
    - a. 6.4 mm (1/4 inch) thick solid copper bar.
    - b. Minimum 50 mm (2 inches) high and length sized in accordance application requirements and future growth of minimum 300 mm long (12 inches) long.

## 

06-01-15

- c. Minimum nine predrilled attachment points (one row) for attaching standard sized two-hole grounding lugs.
  - 1) 6 lugs with 15.8 mm (5/8 inch) hole centers.
  - 2) 3 lugs with 25.4 mm (1 inch) hole centers.
- d. Wall-mount stand-off brackets, assembly screws and insulators for 100 mm (4 inches) standoff from wall.
- e. Listed as grounding and bonding equipment.
- E. Equipment Rack and Cabinet Ground Bars:
  - 1. Solid copper ground bars designed for horizontal mounting to framework of open racks or enclosed equipment cabinets:
    - a. 4.7 mm (3/16 inch) thick by 19.1 mm (3/4 inch) high hard-drawn electrolytic tough pitch 110 alloy copper bar.
    - b. 482 mm (19 inches) or 584 mm (23 inches) EIA/ECA-310-E rack mounting width (as required) for mounting on racks or cabinets.
    - c. Eight 6-32 tapped ground mounting holes on 25.4 mm (1 inch) intervals.
    - d. Four 7.1 mm (0.281 inch) holes for attachment of two-hole grounding lugs.
    - e. Copper splice bar of same material to transition between adjoining racks.
    - f. Two each  $12-24 \times 19.1 \text{ mm}$  (3/4 inch) copper-plated steel screws and flat washers for attachment to rack or cabinet.
    - g. Listed as grounding and bonding equipment.
  - 2. Solid copper ground bars designed for vertical mounting to framework of open racks or enclosed equipment cabinets:
    - a. 1.3 mm (0.05 inch) thick by 17 mm (0.68 inch) wide tinned copper strip.
    - b. 1997 mm (78 inches) high for mounting vertically on full height racks.
    - c. Holes punched on 15.875 mm-15.875 mm-12.7 mm (5/8"-5/8"-1/2") alternating vertical centers to match EIA/ECA-310-E Universal Hole Pattern for a 45 RMU rack.
    - d. Three #12-24 zinc-plated thread forming hex washer head installation screws, an abrasive pad and antioxidant joint compound.
    - e. NRTL listed as grounding and bonding equipment.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

06-01-15

- F. Ground Terminal Blocks: Provide screw lug-type terminal blocks at equipment mounting location (e.g. backboards and hinged cover enclosures) where rack-type ground bars cannot be mounted.
  - 1. Electroplated tin aluminum extrusion.
  - 2. Accept conductors ranging from #14 AWG through 2/0.
  - 3. Hold conductors in place by two stainless steel set screws.
  - 4. Two 6 mm (1/4 inch) holes spaced on 15.8 mm (5/8 inch) centers to allow secure two-bolt attachment.
  - 5. Listed as a wire connector.
- G. Splice Case Ground Accessories: Provide splice case grounding and bonding accessories manufactured by splice case manufacturer when available. Otherwise, use 16 mm<sup>2</sup> (6 AWG) insulated ground wire with shield bonding connectors.
- H. Irreversible Compression Lugs:
  - 1. Electroplated tinned copper.
  - 2. Two holes spaced on 15.8 mm (5/8 inch) or 25.4 mm (1 inch) centers.
  - 3. Sized to fit the specific size conductor.
  - 4. Listed as wire connectors.
- I. Antioxidant Joint Compound: Oxide inhibiting joint compound for copper-to-copper, aluminum-to-aluminum or aluminum-to-copper connections.

#### PART 3 - EXECUTION

## 3.1 EQUIPMENT INSTALLATION AND REQUIREMENTS

- A. Exterior Equipment Grounding: Bond exterior metallic components (including masts and cabinets), antennas, satellite dishes, towers, raceways, primary telecommunications protector/arresters, secondary surge protection, waveguides, cable shields, down conductors and other conductive items to directly to Intersystem Bonding Termination.
- B. Install telecommunications bonding backbone conductor throughout building via telecommunications backbone pathways effectively bonding all interior telecommunications grounding busbars in telecommunications rooms, to telecommunications main grounding busbar in Demarc room after testing bond to verify bonding conductor for telecommunications from grounding electrode conductor is installed per NEC. Size telecommunications bonding backbone conductor as specified in TIA-607-B.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

- C. Inaccessible Grounding Connections: Utilize exothermic welding for bonding of buried or otherwise inaccessible connections with the exception of connections requiring periodic testing.
- D. Conduit Systems:
  - 1. Bond ferrous metallic conduit to ground.
  - 2. Bond grounding conductors installed in ferrous metallic conduit at both ends of conduit using grounding bushing with #6 AWG conductor.
- E. Boxes, Cabinets, and Enclosures:
  - Bond each pull box, splice box, equipment cabinet, and other enclosures through which conductors pass (except for special grounding systems for intensive care units and other critical units shown) to ground.
  - 2. Raised Floors: Bonding raised floor components to ground.
- F. Corrosion Inhibitors: Apply corrosion inhibitor for protecting connection between metals used to contact surfaces, when making ground and ground bonding connections.
- G. Telecommunications Grounding System:
  - Bond telecommunications grounding systems and equipment to facility's electrical grounding electrode at Intersystem Bonding Termination.
  - Provide hardware as required to effectively bond metallic cable shields communications pathways, cable runway, and equipment chassis to ground.
  - 3. Install bonding conductors without splices using shortest length of conductor possible to maintain clearances required by NEC.
  - 4. Provide paths to ground that are permanent and continuous with a resistance of 1 ohm or less from each raceway, cable tray, and equipment connection to telecommunications grounding busbar.
  - 5. Below-Grade Connections: When making exothermic welds, wire brush or file the point of contact to a bare metal surface. Use exothermic welding cartridges and molds in accordance with manufacturer's recommendations. After welds have been made and cooled, brush slag from weld area and thoroughly clean joint areas. Notify COR prior to backfilling at ground connections.
  - 6. Above-Grade Bolted or Screwed Grounding Connections:
    - a. Remove paint to expose entire contact surface by grinding.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

06-01-15

- b. Clean all connector, plate and contact surfaces.
- c. Apply corrosion inhibitor to surfaces before joining.

# 7. Bonding Jumpers:

- a. Assemble bonding jumpers using insulated ground wire of size and type shown on drawings or use a minimum of 16 mm<sup>2</sup> (6 AWG) insulated copper wire terminated with compression connectors of proper size for conductors.
- b. Use connector manufacturer's compression tool.

### 8. Bonding Jumper Fasteners:

- a. Conduit: Connect bonding jumpers using lugs on grounding bushings or clamp pads on push-type conduit fasteners. Where appropriate, use zinc-plated external tooth lockwashers or Belleville Washers.
- b. Wireway and Cable Tray: Fasten bonding jumpers using zinc-plated bolts, external tooth lock washers or Belleville washers and nuts. Install protective cover, e.g., zinc-plated acorn nuts, on bolts extending into wireway or cable tray to prevent cable damage.
- c. Grounding Busbars: Fasten bonding conductors using two-hole compression lugs. Use 300 series stainless steel bolts, Belleville Washers, and nuts.
- d. Slotted Channel Framing and Raised Floor Stringers: Fasten bonding jumpers using zinc-plated, self-drill screws and Belleville washers or external tooth lock washers.

# H. Telecommunications Room Bonding:

- 1. Telecommunications Grounding Busbars:
  - a. Install busbar hardware no less than 950 mm (18 inches) A.F.F.
  - b. Where other grounding busbars are located in same room, e.g. electrical panelboard for telecommunications equipment, bond busbars together as indicated on grounding riser diagrams.
  - c. Make conductor connections with two-hole compression lugs sized to fit busbar and conductors.
  - d. Attach lugs with stainless steel hardware after preparing bond according to manufacturer recommendations and treating bonding surface on busbar with anti-oxidant to help prevent corrosion.
- 2. Telephone-Type Cable Rack Systems:

# 

- a. Aluminum pan installed on telephone-type cable rack serves as primary ground conductor within communications room.
- b. Make ground connections by installing bonding jumpers:
  - Install minimum 16 mm² (6 AWG) bonding between telecommunications ground busbars and the aluminum pan installed on cable rack.
  - 2) Install 16  $\mathrm{mm^2}$  (6 AWG) bonding jumpers across aluminum pan junctions.
- I. Self-Supporting and Cabinet-Mounted Equipment Rack Ground Bars:
  - 1. Install rack-mount horizontal busbar or vertical busbar to provide multiple bonding points,
  - 2. At each rack or cabinet containing active equipment or shielded cable terminations:
    - a. Bond busbar to ground as part of overall telecommunications bonding and grounding system.
    - b. Bond copper ground bars together using solid copper splice plates manufactured by same ground bar manufacturer, when ground bars are provided at rear of lineup of bolted together equipment racks.
    - c. Bond non-adjacent ground bars on equipment racks and cabinets with 16 mm<sup>2</sup> (6 AWG) insulated copper wire bonding jumpers attached at each end with compression-type connectors and mounting bolts.
    - d. Provide 16  $mm^2$  (6 AWG) bonding jumpers between rack and cabinet ground busbars and overhead cable runway or raised floor stringers, as appropriate.
- J. Backboards: Provide a screw lug-type terminal block or drilled and tapped copper strip near top of backboards used for communications cross-connect systems. Connect backboard ground terminals to cable runway using an insulated 16 mm<sup>2</sup> (6 AWG) bonding jumper.
- K. Other Communication Room Ground Systems: Ground metallic conduit, wireways, and other metallic equipment located away from equipment racks or cabinets to cable tray or telecommunications ground busbar, whichever is closer, using insulated 16 mm² (6 AWG) ground wire bonding jumpers.
- L. Communications Cable Grounding:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

06-01-15

- Bond all metallic cable sheaths in multi-pair communications cables together at each splicing or terminating location to provide 100 percent metallic sheath continuity throughout communications distribution system.
- Install a cable shield bonding connector with a screw stud connection for ground wire, at terminal points. Bond cable shield connector to ground.
- 3. Bond all metallic cable shields together within splice closures using cable shield bonding connectors or splice case manufacturer's splice case grounding and bonding accessories. When an external ground connection is provided as part of splice closure, connect to an effective ground source and bond all other metallic components and equipment at that location.

#### M. Communications Cable Tray Systems:

- 1. Bond metallic structures of cable tray to provide 100 percent electrical continuity throughout cable tray systems.
- 2. Where metallic cable tray systems are mechanically discontinuous:
  - a. Install splice plates provided by cable tray manufacturer between cable tray sections so resistance across a bolted connection is 0.010 ohms or less, as verified by measuring across splice plate connection.
  - b. Install 16 mm<sup>2</sup> (6 AWG) bonding jumpers across each cable tray splice or junction where splice plates cannot be used.
- 3. Bond cable tray installed in same room as telecommunications grounding busbar to busbar.

### N. Communications Raceway Grounding:

- 1. Conduit: Use insulated 16 mm<sup>2</sup> (6 AWG) bonding jumpers to bond metallic conduit at both ends and intermediate metallic enclosures to ground.
- 2. Cable Tray Systems: Use insulated 16 mm<sup>2</sup> (6 AWG) grounding jumpers to bond cable tray to column-mounted building ground plates (pads) at both ends and approximately 16 meters (50 feet) on centers.

#### O. Ground Resistance:

1. Install telecommunications grounding system so resistance to grounding electrode system measures 5 ohms or less.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

06-01-15

- 2. Measure grounding electrode system resistance using an earth test meter, clamp-on ground tester, or computer-based ground meter as defined in IEEE 81. Record ground resistance measurements before electrical distribution system is energized.
- 3. Backfill only after below-grade connection have been visually inspected by COR. Notify COR twenty-four hours before below-grade connections are ready for inspection.

#### 3.2 FIELD QUALITY CONTROL

- A. Verify that all old Telecommunications Grounds have been removed from the old electrical ground in Electrical Panel 1.
- B. Perform tests per BICSI's Information Technology Systems Installation Methods Manual (ITSIMM), Recommended Testing Procedures and Criteria.
- C. Perform two-point bond test using trained installers qualified to use test equipment.
- D. Conduct continuity test to verify that metallic pathways in telecommunications spaces are bonded to TGB or TMGB.
- E. Conduct electrical continuity test to verify that TMGB is effectively bonded to grounding electrode conductor.
- F. Visually inspect to verify that screened and shielded cables are bonded to TGB or TMGB.
- G. Perform a resistance test to ensure patch panel, rack and cabinet bonding connection resistance measures less than 5 Ohms to TGB or TMGB.

- - - E N D - - -

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

10-01-18

# SECTION 27 05 33 RACEWAYS AND BOXES FOR COMMUNICATIONS SYSTEMS

### PART 1 - GENERAL

#### 1.1 DESCRIPTION

A. This section specifies conduit, fittings, and boxes to form complete, coordinated, raceway systems. Raceways are required for communications cabling unless shown or specified otherwise.

#### B. CONDUIT COLORS

SYSTEM	CABLE JACKET
VOICE	WHITE
DATA	YELLOW
DATA	GREEN
DATA	GREY
WIRELESS	ORANGE
VIDEO	VIOLET
SURVEILLANCE	
NURSE CALL	BLUE
FIRE ALARM	RED
BAS & DAS	BLACK

# 1.2 RELATED WORK

- A. Bedding of conduits: Section 31 20 00, EARTH MOVING.
- B. Mounting board for Telecommunication Rooms: Section 06 10 00, ROUGH CARPENTRY.
- C. Sealing around penetrations to maintain integrity of fire rated construction: Section 07 84 00, FIRESTOPPING.
- D. Fabrications for deflection of water away from building envelope at penetrations: Section 07 60 00, FLASHING AND SHEET METAL.
- E. Sealing around conduit penetrations through building envelope to prevent moisture migration into building: Section 07 92 00, JOINT SEALANTS.
- F. Identification and painting of conduit and other devices: Section 09 91 00, PAINTING.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

10-01-18

G. Requirements for personnel safety and to provide a low impedance path for possible ground fault currents: Section 27 05 26, GROUNDING AND BONDING FOR COMMUNICATIONS SYSTEMS.

#### 1.3 SUBMITTALS

- A. In accordance with Section 27 50 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS, submit the following:
  - 1. Size and location of cabinets, splice boxes and pull boxes.
  - 2. Layout of required conduit penetrations through structural elements.
  - 3. Catalog cuts marked with specific item proposed and area of application identified.
- B. Certification: Provide letter prior to final inspection, certifying material is in accordance with construction documents and properly installed.

#### PART 2 - PRODUCTS

### 2.1 MATERIAL

- A. Minimum Conduit Size: 19 mm (3/4 inch).
- B. Conduit:
  - 1. Rigid Galvanized Steel: Conform to UL 6, ANSI C80.1.
  - 2. Rigid Intermediate Steel Conduit (IMC): Conform to UL 1242, ANSI C80.6.
  - 3. Electrical Metallic Tubing (EMT):
    - a. Maximum Size: 105 mm (4 inches).
    - b. Install only for cable rated 600 volts or less.
    - c. Conform to UL 797, ANSI C80.3.
  - 4. Flexible Galvanized Steel Conduit: Conform to UL 1.
  - 5. Liquid-tight Flexible Metal Conduit: Conform to UL 360.
  - 6. Surface Metal Raceway: Conform to UL 5.
  - 7. Wireway, Approved "Basket": Provide "Telecommunications Service" rated with approved length way partitions and cable straps to prevent wires and cables from changing from one partitioned pathway to another.
- C. Conduit Fittings:
  - 1. Rigid Galvanized Steel and Rigid Intermediate Steel Conduit Fittings:
    - a. Provide fittings meeting requirements of UL 514B and ANSI/  $\ensuremath{\mathsf{NEMA}}$  FB 1.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

- b. Sealing: Provide threaded cast iron type. Use continuous drain type sealing fittings to prevent passage of water and vapor. In concealed work, install sealing fittings in flush steel boxes with blank cover plates having same finishes as other electrical plates in room.
- c. Standard Threaded Couplings, Locknuts, Bushings, and Elbows: Only steel or malleable iron materials are acceptable. Integral retractable type IMC couplings are also acceptable.
- d. Locknuts: Bonding type with sharp edges for digging into metal wall of an enclosure.
- e. Bushings: Metallic insulating type, consisting of an insulating insert molded or locked into metallic body of fitting. Bushings made entirely of metal or nonmetallic material are not permitted.
- f. Erickson (union-type) and Set Screw Type Couplings:
  - 1) Couplings listed for use in concrete are permitted for use to complete a conduit run where conduit is installed in concrete.
  - 2) Use set screws of case hardened steel with hex head and cup point to seat in conduit wall for positive ground. Tightening of set screws with pliers is prohibited.
- g. Provide OEM approved fittings.
- 2. Rigid Aluminum Conduit Fittings (NOT USED)
  - a. NOT USED)
- 3. Electrical Metallic Tubing Fittings:
  - a. Conform to UL 514B and ANSI/ NEMA FB1; only steel or malleable iron materials are acceptable.
  - b. Couplings and Connectors: Concrete tight and rain tight, with connectors having insulated throats.
    - 1) Use gland and ring compression type couplings and connectors for conduit sizes 50 mm (2 inches) and smaller.
    - 2) Use set screw type couplings with four set screws each for conduit sizes over 50 mm (2 inches).
    - 3) Use set screws of case-hardened steel with hex head and cup point to seat in wall of conduit for positive grounding.
  - c. Indent type connectors or couplings are not permitted.
  - d. Die-cast or pressure-cast zinc-alloy fittings or fittings made of "pot metal" are not permitted.

# 

- e. Provide OEM approved fittings.
- 4. Flexible Steel Conduit Fittings:
  - a. Conform to UL 514B; only steel or malleable iron materials are acceptable.
  - b. Provide clamp type, with insulated throat.
  - c. Provide OEM approved fittings.
- 5. Liquid-tight Flexible Metal Conduit Fittings:
  - a. Conform to UL 514B and ANSI/ NEMA FB1; only steel or malleable iron materials are acceptable.
  - b. Fittings must incorporate a threaded grounding cone, a steel or plastic compression ring, and a gland for tightening.
  - c. Provide connectors with insulated throats to prevent damage to cable jacket.
  - d. Provide OEM approved fittings.
- 6. Direct Burial Plastic Conduit Fittings: Provide fittings meeting requirements of UL 514C and NEMA TC3, and as recommended by conduit manufacturer.
- 7. Surface Metal Raceway: Conform to UL 5 and "telecommunications service" rated with approved length-way partitions and cable straps to prevent wires and cables from changing from one partitioned pathway to another.
- 8. Surface Metal Raceway Fittings: As recommended by raceway manufacturer.
- 9. Expansion and Deflection Couplings:
  - a. Conform to UL 467 and UL 514B.
  - b. Accommodate 19 mm (3/4 inch) deflection, expansion, or contraction in any direction, and allow 30 degree angular deflections.
  - c. Include internal flexible metal braid sized to ensure conduit ground continuity and fault currents in accordance with UL 467, and NEC code tables for ground conductors.
  - d. Jacket: Flexible, corrosion-resistant, watertight, moisture and heat resistant molded rubber material with stainless steel jacket clamps.
- 10. Rigid Aluminum Fittings (NOT USED)
  - a. NOT USED)

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

- 11. Wireway Fittings: As recommended by wireway OEM.
- D. Conduit Supports:
  - 1. Parts and Hardware: Provide zinc-coat or equivalent corrosion protection.
  - Individual Conduit Hangers: Designed for the purpose, having a preassembled closure bolt and nut, and provisions for receiving a hanger rod.
  - 3. Multiple Conduit (Trapeze) Hangers: Minimum 38 mm by 38 mm (1-1/2 by 1-1/2 inch), 2.78 mm (12 gage) steel, cold formed, lipped channels; with minimum 9 mm (3/8 inch) diameter steel hanger rods.
  - 4. Solid Masonry and Concrete Anchors: Self-drilling expansion shields, or machine bolt expansion.
- E. Outlet, Splice, and Pull Boxes:
  - 1. Conform to UL-50 and UL-514A.
  - 2. Cast metal where required by NEC or shown, and equipped with rustproof boxes.
  - 3. Sheet Metal Boxes: Galvanized steel, except where otherwise shown.
  - 4. Install flush mounted wall or ceiling boxes with raised covers so that front face of raised cover is flush with wall.
  - 5. Install surface mounted wall or ceiling boxes with surface style flat or raised covers.
- F. Wireways: Equip with hinged covers, except where removable covers are shown.
- G. Warning Tape: Standard, 4-Mil polyethylene 76 mm (3 inch) wide tape detectable type, red with black letters, and imprinted with "CAUTION BURIED COMMUNICATIONS CABLE BELOW".
- H. Flexible Nonmetallic Communications Raceway (Innerduct) and Fittings:
  - 1. General: Provide UL 910 listed plenum, riser, and general purpose corrugated pliable communications raceway for optical fiber cables and communications cable applications; select in accordance with provisions of NEC Articles 770 and 800.
  - 2. Provide Communications Raceway with a factory installed 567 kg (1250 lb.) tensile pre-lubricated pull tape.
  - 3. Use only metallic straps, hangers and fittings to support raceway from building structure. Cable ties are not permitted for securing raceway to building structure.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

- 4. Provide fittings to be installed in spaces used for environmental air made of materials that do not exceed flammability, smoke generation, ignitibility, and toxicity requirements of environmental air space.
- 5. Size: Metric Designator 53 (trade size 2) or smaller.
- 6. Outside Plant: Plenum-rated where each interduct is 75 mm (3 inches) and larger.
- 7. Inside Plant: Listed and marked for installation in plenum airspaces and minimum 25 mm (1 inch) inside diameter.
- 8. Plenum: Non-metallic communications raceway.
  - a. Constructed of low smoke emission, flame retardant PVC with corrugated construction.
  - b. UL 94 V-O rating for flame spreading limitation.
- 9. Provide innerduct reel lengths as necessary to ensure ducts are continuous; one piece runs from ENTR to MH; MH to MH; DEMARC to MCR/TER; TR to TR. Innerduct connectors are not permitted between rooms.
- 10. Provide pulling accessories used for innerduct including but not limited to, inner duct lubricants, spreaders, applicators, grips, swivels, harnesses, and line missiles (blown air) compatible with materials being pulled.
- I. Outlet Boxes Contractor to select appropriate box:
  - 1. Flush wall mounted minimum 11.9 cm (4-11/16 inches) square, 9.2 cm (3-5/8 inches) deep pressed galvanized steel.
  - 2. 2-Gang Tile Box:
    - a. Flush backbox type for installation in block walls.
    - b. Minimum 92 mm (3-5/8 inches) deep.
- J. Weatherproof Outlet Boxes: Surface mount two gang, 67 mm (2-5/8 inches) deep weatherproof cast aluminum with powder coated finish internal threads on hubs 19 mm (3/4 inch) minimum.
- K. Cable Tray:
  - 1. Provide wire basket type of sizes indicated; with all required splicing and mounting hardware.
  - 2. Materials and Finishes:
    - a. Electro-plated zinc galvanized (post plated) made from carbon steel and plated to ASTM B 633, Type III, SC-1.

# 

10-01-18

- b. Remove soot, manufacturing residue/oils, or metallic particles after fabrication.
- c. Rounded edges and smooth surfaces.
- 3. Provide continuous welded top side wire to protect cable insulation and installers.
- 4. High strength steel wires formed into a  $50 \times 100$  mm (2 inches by 4 inches) wire mesh pattern with intersecting wires welded together.
- 5. Wire Basket Sizes:
  - a. Wire Diameter: 5 mm (0.195 inch) minimum on all mesh sections.
  - b. Usable Loading Depth: 105 mm (4 inch).
  - c. Width: 300 mm (12 inches).
- 6. Fittings: Field-formed, from straight sections, in accordance with manufacturer's instructions.
- 7. Provide accessories to protect, support and install wire basket tray system.
- L. Cable Duct: Equip with hinged covers, except where removable covers are accepted by COR.
- M. Cable Duct Fittings: As recommended by cable duct OEM.

### PART 3 - EXECUTION

#### 3.1 EQUIPMENT INSTALLATION AND REQUIREMENTS

A. Raceways typically required for cabling systems unless otherwise indicated:

System	Specification Section	Installed Method
Grounding	27 05 26	Conduit Not Required
Control, Communication and Signal Wiring	27 10 00	Complete Conduit Allowed in Non-Partitioned Cable Tray or Cable Ladders
Communications Structured Cabling	27 15 00	Conduit to Cable Tray Partitioned Cable Tray
Security Emergency Call, , and Telecommunications	27 52 31	Conduit to Cable Tray, Partitioned Cable Tray
Miscellaneous Medical Systems	27 52 41	Complete Conduit

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

10-01-18

System	Specification Section	Installed Method
Grounding and Bonding for Electronic Safety and Security	28 05 26	Conduit Not Required Unless Required by Code
Security Access Detection	28 13 53	Complete Conduit
Intrusion Detection System	28 16 00	Conduit to Cable Tray, Partitioned Cable Tray
Fire Detection and Alarm	28 31 00	Complete Conduit

#### B. Penetrations:

- 1. Cutting or Holes:
  - a. Locate holes in advance of installation. Where they are proposed in structural sections, obtain approval of structural engineer and COR prior to drilling through structural sections.
  - b. All openings are in plaster walls. Cutting through masonry is not required. Pneumatic hammer, impact electric, hand or manual hammer type drills are not permitted; COR may grant limited permission by request, in condition of limited working space.
  - c. Fire Stop: Where conduits, wireways, and other communications raceways pass through fire partitions, fire walls, smoke partitions, or floors, install a fire stop that provides an effective barrier against spread of fire, smoke and gases as specified in Section 07 84 00, FIRESTOPPING.
    - 1) Fill and seal clearances between raceways and openings with fire stop material.
    - 2) Install only retrofittable, non-hardening, and reusable firestop material that can be removed and reinstalled to seal around cables inside conduits.
  - - 1) NOT USED)

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

10-01-18

#### C. Conduit Installation:

- 1. Minimum conduit size of 19 mm (3/4 inch), but not less than size required for 40 percent fill.
- 2. Install insulated bushings on all conduit ends.
- 3. Install pull boxes after every 180 degrees of bends (two 90 degree bends). Size boxes per TIA 569.
- 4. Extend vertical conduits/sleeves through floors minimum 75 mm (3 inches) above floor and minimum 75 mm (3 inches) below ceiling of floor below.
- 5. Terminate conduit runs to and from a backboard in a closet or interstitial space at top or bottom of backboard. Install conduits to enter telecommunication rooms next to wall and flush with backboard.
- 6. Where drilling is necessary for vertical conduits, locate holes so as not to affect structural sections.
- 7. Seal empty conduits located in telecommunications rooms or on backboards with a standard non-hardening putty compound to prevent entrance of moisture and gases and to meet fire resistance requirements.
- 8. Minimum radius of communication conduit bends:

Sizes of Conduit Trade Size	Radius of Conduit Bends mm, Inches
3/4	150 (6)
1	230 (9)
1-1/4	350 (14)
1-1/2	430 (17)
2	525 (21)
2-1/2	635 (25)
3	775 (31)
3-1/2	900 (36)
4	1125 (45)

9. Provide 19 mm (3/4 inch) thick fire retardant plywood specified in Section 06 10 00, ROUGH CARPENTRY on wall of communication closets where shown on drawings. Mount plywood with bottom edge 300 mm (12 inches) above finished floor and top edge 2.74 m (9 feet) A.F.F.

# 

- 10. Provide pull wire in all empty conduits; sleeves through floor are exceptions.
- 11. Complete each entire conduit run installation before pulling in cables.
- 12. Flattened, dented, or deformed conduit is not permitted.
- 13. Ensure conduit installation does not encroach into ceiling height head room, walkways, or doorways.
- 14. Cut conduit square with a hacksaw, ream, remove burrs, and draw tight.
- 15. Install conduit mechanically continuous.
- 16. Independently support conduit at 2.44 m (8 feet) on center; do not use other supports (i.e., suspended ceilings, suspended ceiling supporting members, luminaires, conduits, mechanical piping, or mechanical ducts).
- 17. Support conduit within 300 mm (1 foot) of changes of direction, and within 300 mm (1 foot) of each enclosure to which connected.
- 18. Close ends of empty conduit with plugs or caps to prevent entry of debris, until cables are pulled in.
- 19. Attach conduits to cabinets, splice cases, pull boxes and outlet boxes with bonding type locknuts. For rigid and IMC conduit installations, provide a locknut on inside of enclosure, made up wrench tight. Do not make conduit connections to box covers.
- 20. Do not use aluminum conduits in wet locations.
- 21. Unless otherwise indicated on drawings or specified herein, conceal conduits within finished walls, floors and ceilings.
- 22. Conduit Bends:
  - a. Make bends with standard conduit bending machines; observe minimum bend radius for cable type and outside diameter.
  - b. Conduit hickey is permitted only for slight offsets, and for straightening stubbed conduits.
  - c. Bending of conduits with a pipe tee or vise is not permitted.
- 23. Layout and Homeruns Deviations: Make only where necessary to avoid interferences and only after drawings showing proposed deviations have been submitted and approved by COR.
- D. Concealed Work Installation:
  - 1. In Concrete:

# 

- a. Conduit: Rigid steel or IMC.
- b. Align and run conduit in direct lines.
- c. Install conduit through concrete beams only when the following occurs:
  - 1) Where shown on structural drawings.
  - 2) As accepted by COR prior to construction, and after submittal of drawing showing location, size, and position of each penetration.
- d. Installation of conduit in concrete that is less than 75 mm (3 inches) thick is prohibited.
  - 1) Conduit outside diameter larger than 1/3 of slab thickness is prohibited.
  - 2) Space between Conduits in Slabs: Approximately six conduit diameters apart, except one conduit diameter at conduit crossings.
  - 3) Install conduits approximately in center of slab to ensure a minimum of 19 mm (3/4 inch) of concrete around conduits.
- e. Make couplings and connections watertight. Use thread compounds that are NRTL listed conductive type to ensure low resistance ground continuity through conduits. Tightening set screws with pliers is not permitted.
- E. Furred or Suspended Ceilings and in Walls:
  - 1. Rigid steel, IMC. Different type conduits mixed indiscriminately in same system is not permitted.
  - 2. Align and run conduit parallel or perpendicular to building lines.
  - 3. Tightening set screws with pliers is not permitted.
- F. Exposed Work Installation:
  - 1. Unless otherwise indicated on drawings, exposed conduit is only permitted in telecommunications rooms.
    - a. Provide rigid steel, IMC or rigid aluminum.
    - b. Different type of conduits mixed indiscriminately in system is not permitted.
  - 2. Align and run conduit parallel or perpendicular to building lines.
  - 3. Install horizontal runs close to ceiling or beams and secure with conduit straps.

# 

10-01-18

- 4. Support horizontal or vertical runs at not over 2400 mm (96 inches) intervals.
- 5. Surface Metal Raceways: Use only where shown on drawings.
- 6. Painting:
  - a. Paint exposed conduit as specified in Section 09 91 00, PAINTING.
  - b. Refer to Section 09 91 00, PAINTING for preparation, paint type, and exact color.
  - c. Provide labels where conduits pass through walls and floors and at maximum 6000 mm (20 foot) intervals in between.

### G. Expansion Joints:

- 1. Conduits 75 mm (3 inches) and larger, that are secured to building structure on opposite sides of a building expansion joint, require expansion and deflection couplings. Install couplings in accordance with manufacturer's recommendations.
- 2. Provide conduits smaller than 75 mm (3 inches) with pull boxes on both sides of expansion joint. Connect conduits to expansion and deflection couplings as specified.
- 3. Install expansion and deflection couplings where shown.
- H. Seismic Areas (NOT USED)
- I. Conduit Supports, Installation:
  - 1. Select AC193 code listed mechanical anchors or fastening devices with safe working load not to exceed 1/4 of proof test load.
  - 2. Use pipe straps or individual conduit hangers for supporting individual conduits. Maximum distance between supports is  $2.5\ m$  (8 foot) on center.
  - 3. Support multiple conduit runs with trapeze hangers. Use trapeze hangers designed to support a load equal or greater than sum of the weights of the conduits, wires, hanger itself, and 90 kg (200 pounds). Attach each conduit with U-bolts or other accepted fasteners.
  - 4. Support conduit independent of pull boxes, luminaires, suspended ceiling components, angle supports, duct work, and similar items.
  - 5. Fastenings and Supports in Solid Masonry and Concrete:
    - a. New Construction: Use steel or malleable iron concrete inserts set in place prior to placing concrete.
    - b. Existing Construction:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

10-01-18

- 1) Code AC193 listed wedge type steel expansion anchors minimum 6 mm (1/4 inch) bolt size and minimum 28 mm (1-1/8 inch) embedment.
- 2) Power set fasteners minimum 6 mm (1/4 inch) diameter with depth of penetration minimum 75 mm (3 inches).
- 3) Use vibration and shock resistant anchors and fasteners for attaching to concrete ceilings.
- 6. Fastening to Hollow Masonry: Toggle bolts are permitted.
- 7. Fastening to Metal Structures: Use machine screw fasteners or other devices designed and accepted for application.
- 8. Bolts supported only by plaster or gypsum wallboard are not acceptable.
- 9. Attachment by wood plugs, rawl plug, plastic, lead or soft metal anchors, or wood blocking and bolts supported only by plaster is prohibited.
- 10. Do not support conduit from chain, wire, or perforated strap.
- 11. Spring steel type supports or fasteners are not permitted except horizontal and vertical supports/fasteners within walls.
- 12. Vertical Supports:
  - a. Install riser clamps and supports for vertical conduit runs in accordance with NEC.
  - b. Provide supports for cable and wire with fittings that include internal wedges and retaining collars.

# J. Box Installation:

- 1. Boxes for Concealed Conduits:
  - a. Flush mounted.
  - b. Provide raised covers for boxes to suit wall or ceiling, construction and finish.
- 2. In addition to boxes shown, install additional boxes where needed to prevent damage to cables during pulling.
- 3. Remove only knockouts as required and plug unused openings. Use threaded plugs for cast metal boxes and snap-in metal covers for sheet metal boxes.
- 4. Stencil or install phenolic nameplates on covers of boxes identified on riser diagrams; for example "SIG-FA JB No. 1".

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

10-01-18

- 5. Outlet boxes mounted back-to-back in same wall are not permitted. A minimum 600 mm (24 inches) center-to-center lateral spacing must be maintained between boxes.
- K. Flexible Nonmetallic Communications Raceway (Innerduct), Installation:
  - 1. Install supports from building structure for horizontal runs at intervals not to exceed 900 mm (3 feet) and at each end.
  - 2. Install supports from building structure for vertical runs at intervals not to exceed 1.2 m (4 feet) and at each side of joints.
  - 3. Install only in accessible spaces not subject to physical damage or corrosive influences.
  - 4. Make bends manually to assure internal diameter of tubing is not effectively reduced.
  - 5. Extend each segment of innerduct minimum 300 mm (12 inches) beyond end of service conduit tie or cable tray. Restrain innerduct ends with wall mount clamps and seal when cable is installed.

#### 3.2 TESTING

- A. Examine fittings and locknuts for secureness.
- B. Test RMC, IMC and EMT systems for electrical continuity.
- C. Perform simple continuity test after cable installation.

- - - E N D - - -

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

11/02/2021

# SECTION 27 08 00 COMMISSIONING OF COMMUNICATIONS SYSTEMS

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section includes requirements for commissioning facility communications systems, related subsystems and related equipment. This Section supplements general requirements specified in Section 01 91 00, GENERAL COMMISSIONING REQUIREMENTS.
- B. Complete list of equipment and systems to be commissioned is specified in Section 01 91 00, GENERAL COMMISSIONING REQUIREMENTS and Specification 27 05 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS.

### C. Commissioned Systems:

- 1. Commissioning of systems specified in Division 27 is part of project's construction process including documentation and proof of performance testing of these systems, as well as training of VA's Operation and Maintenance personnel in accordance with requirements of Section 01 91 00, GENERAL COMMISSIONING REQUIREMENTS and Division 27, in cooperation with Government and Commissioning Agent.
- 2. The facility exterior closure systems commissioning includes communications systems listed in Section 01 91 00 GENERAL COMMISSIONING REQUIRMENTS and 27 05 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS.

### 1.2 RELATED WORK

- A. System tests: Section 01 00 00, GENERAL REQUIREMENTS.
- B. Commissioning process requires review of selected submittals that pertain to systems to be commissioned: Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

11/02/2021

C. Construction phase commissioning process and procedures including roles and responsibilities of commissioning team members and user training: Section 01 91 00, GENERAL COMMISSIONING REQUIREMENTS.

### 1.3 COORDINATION

- A. Commissioning Agent will provide a list of submittals that must be reviewed by Commissioning Agent simultaneously with engineering review; do not proceed with work of sections identified without engineering and Commissioning Agent's review completed.
- B. Commissioning of communications systems require inspection of individual elements of communications system construction throughout construction period. Coordinate with Commissioning Agent in accordance with Section 01 91 00, GENERAL COMMISSIONING REQUIREMENTS and commissioning plan to schedule communications systems inspections as required to support the commissioning process.

# 1.4 CLOSEOUT SUBMITTALS

- A. Refer to Section 01 91 00, GENERAL COMMISSIONING REQUIREMENTS for submittal requirements for pre-functional checklists, equipment startup reports, and other commissioning documents.
- B. Pre-Functional Checklists:
  - 1. Complete pre-functional checklists provided by commissioning agent to verify systems, subsystems, and equipment installation is complete and systems are ready for Systems Functional Performance Testing.
  - 2. Submit completed checklists to COR and to Commissioning Agent.

    Commissioning Agent can spot check a sample of completed

    checklists. If Commissioning Agent determines that information

    provided on the checklist is not accurate, Commissioning Agent

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

11/02/2021

then returns the marked-up checklist to Contractor for correction and resubmission.

- 3. If Commissioning Agent determines that a significant number of completed checklists for similar equipment are not accurate, Commissioning Agent can select a broader sample of checklists for review.
- 4. If Commissioning Agent determines that a significant number of broader sample of checklists is also inaccurate, all checklists for the type of equipment will be returned to Contractor for correction and resubmission.
- C. Submit training agendas and trainer resumes in accordance with requirements of Section 01 91 00, GENERAL COMMISSIONING REQUIREMENTS.

PART 2 - PRODUCTS - NOT USED

#### PART 3 - EXECUTION

# 3.1 FIELD QUALITY CONTROL

- A. Contractor's Tests:
  - Scheduled tests required by other sections of Division 27 must be documented in accordance with Section 01 00 00, GENERAL REQUIREMENTS.
  - 2. Incorporate all testing into project schedule. Provide minimum seven calendar days' notice of testing for Commissioning Agent to witness selected Contractor tests at sole discretion of Commissioning Agent.
  - 3. Complete tests prior to scheduling Systems Functional Performance Testing.
- B. Systems Functional Performance Testing:
  - Commissioning process includes Systems Functional Performance Testing that is intended to test systems functional performance under steady state conditions, to test system

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

11/02/2021

reaction to changes in operating conditions, and system performance under emergency conditions.

- 2. Commissioning Agent prepares detailed Systems Functional
  Performance Test procedures for review and acceptance by COR.
- Provide required labor, materials, and test equipment identified in test procedure to perform tests.
- 4. Commissioning Agent must witness and document the testing.
  - a. Provide test reports to Commissioning Agent. Commissioning Agent will sign test reports to verify tests were performed.

#### 3.2 TRAINING

- A. Training of Government's operation and maintenance personnel is required in cooperation with COR and Commissioning Agent.
- B. Provide competent, factory authorized personnel to provide instruction to operation and maintenance personnel concerning location, operation, and troubleshooting of installed systems.
- C. Schedule instruction in coordination with COR after submission and approval of formal training plans.

- - - E N D - - -

# EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

**PART 1 -** Bancroft Architects + Engineers

06-01-15

# SECTION 27 10 00 CONTROL, COMMUNICATION AND SIGNAL WIRING

### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section includes control, communication and signal wiring for a comprehensive systems infrastructure.
- B. This section applies to all sections of Divisions 27 and 28.
- C. CABLE AND WIRE COLORS

SYSTEM	CABLE JACKET
VOICE	WHITE
DATA	YELLOW
DATA	GREEN
DATA	GREY
WIRELESS	ORANGE
VIDEO	VIOLET
SURVEILLANCE	
NURSE CALL	BLUE
FIRE ALARM	RED
BAS & DAS	BLACK

D.

### 1.2 RELATED WORK

- A. Excavation and backfill for cables that are installed in conduit: Section 31 20 00, EARTH MOVING.
- B. Sealing around penetrations to maintain integrity of time rated construction: Section 07 84 00, FIRESTOPPING.
- C. General electrical requirements that are common to more than one section in Division 27: Section 27 05 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS.
- D. Conduits for cables and wiring: Section 27 05 33, RACEWAYS AND BOXES FOR COMMUNICATIONS SYSTEMS.
- E. Requirements for personnel safety and to provide a low impedance path for possible ground fault currents: Section 27 05 26, GROUNDING AND BONDING FOR COMMUNICATIONS SYSTEMS.

### 1.3 SUBMITTALS

A. Submit in accordance with Section 27 05 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

06-01-15

- B. Submit written certification from OEM:
  - Indicate wiring and connection diagrams meet National and Government Life Safety Guidelines, NFPA, NEC, NRTL, Joint Commission, OEM, this section and Section 27 05 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS.
  - 2. Include instructions, requirements, recommendations, and guidance for proper performance of system as described herein.
  - 3. Government will not approve any submittal without this certification.
- C. Identify environmental specifications on technical submittals; identify requirements for installation.
  - 1. Minimum floor space and ceiling heights.
  - 2. Minimum size of doors for cable reel passage.
- D. Power: Provide specific voltage, amperage, phases, and quantities of circuits.
- E. Provide conduit size requirements. Utilize Cat6a, Conduit Fill Schedule on drawings.
- F. Closeout Submittals:
  - Provide contact information for maintenance personnel to contact contractor for emergency maintenance and logistic assistance, and assistance in resolving technical problems at any time during warranty period.
  - 2. Provide certified OEM sweep test tags from each cable reel to COR.
  - 3. Furnish spare or unused wire and cable with appropriate connectors (female types) for installation in appropriate punch blocks, barrier strips, patch, or bulkhead connector panels.
  - 4. Turn over unused and opened installation kit boxes, coaxial, fiber optic, and twisted pair cable reels, conduit, cable tray, cable duct bundles, wire rolls, physical installation hardware to COR.
  - 5. Documentation: Include any item or quantity of items, as installed drawings, equipment, maintenance, and operation manuals, and OEM materials needed to completely and correctly provide system documentation required herein.

# PART 2 - PRODUCTS

### 2.1 CONTROL WIRING (NOT USED)

A. Distribution System Signal Wires and Cables:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

06-01-15

- Provide in same manner, and use construction practices, as Fire Protective and other Emergency Systems identified and defined in NFPA 101, Life Safety Code, Chapters 7, 12, and 13, NFPA 70, National Electrical Code, Chapter 7, Special Conditions.
- 2. Provide system able to withstand adverse environmental conditions without deterioration, in their respective location.
- 3. Provide entering of each equipment enclosure, console, cabinet or rack in such a manner that all doors or access panels can be opened and closed without removal or disruption of cables.
- 4. Terminate on an item of equipment by direct connection.

#### 2.2 COMMUNICATION AND SIGNAL WIRING

- A. Provide communications and signal wiring conforming to recommendations of manufacturers of EHRM systems 500MHZ; provide not less than TIA Performance Category 6a .
- B. Wiring shown is for typical systems; provide wiring as required for systems being provided.
- C. Provide color-coded conductor insulation for multi-conductor cables.

#### D. Connectors:

- 1. Provide connectors for transmission lines, and signal extensions to maintain uninterupted continuity, ensure effective connection, and preserve uniform polarity between all points in system.
  - a. Provide AC barrier strips with a protective cover to prevent accidental contact with wires carrying live AC current.
  - b. Provide punch blocks for signal connection, not AC power. AC power twist-on wire connectors are not permitted for signal wire terminations.
- 2. Cables: Provide connectors designed for specific size cable and conductors being installed with OEM's approved installation tool. Typical system cable connectors include:
  - a. Audio spade lug.
  - b. Punch block.
  - c. Wirewrap.

### 2.3 INSTALLATION KIT

A. Include connectors and terminals, labeling systems, audio spade lugs, barrier strips, punch blocks or wire wrap terminals, heat shrink tubing,

# 

06-01-15

cable ties, solder, hangers, clamps, bolts, conduit, cable duct, cable tray, etc., required to accomplish a neat and secure installation.

- B. Terminate conductors in a spade lug and barrier strip, wire wrap terminal or punch block, so there are no unfinished or unlabeled wire connections.
- C. Minimum required installation sub-kits:
  - 1. System Grounding:
    - a. Provide required cable and installation hardware for effective ground path, including the following:
      - 1) Control Cable Shields.
      - 2) Data Cable Shields.
      - 3) Equipment Racks.
      - 4) Equipment Cabinets.
      - 5) Conduits.
      - 6) Ducts.
      - 7) Cable Trays.
      - 8) Power Panels.
      - 9) Connector Panels.
      - 10) Grounding Blocks.
    - b. Bond radio equipment to earth ground via internal building wiring, according to NEC.
  - 2. Wire and Cable: Provide connectors and terminals, punch blocks, tie wraps, hangers, clamps, labels, etc. required to accomplish termination in an orderly installation.
  - 3. Conduit, Cable Duct, and Cable Tray: Provide conduit, duct, trays, junction boxes, back boxes, cover plates, feed through nipples, hangers, clamps, other hardware required to accomplish a neat and secure conduit, cable duct, cable tray installation in accordance with NEC and documents.
  - 4. Equipment Interface: Provide any items or quantity of equipment, cable, mounting hardware and materials to interface systems with identified sub-systems, according to OEM requirements and construction documents.
  - 5. Labels: Provide any item or quantity of labels, tools, stencils, and materials to label each subsystem according to OEM requirements, asinstalled drawings, and construction documents.

# 

- D. Cross-Connection System (CCS) Equipment Breakout, Termination Connector (or Bulkhead), and Patch Panels:
  - 1. Connector Panels: Flat smooth 3.175 mm (1/8 inch) thick solid aluminum, custom designed, fitted and installed in cabinet. Install bulkhead equipment connectors on panel to enable cabinet equipment's signal, control, and coaxial cables to be connected through panel. Match panel color to cabinet installed.
    - a. Voice (or Telephone):
      - 1) Provide industry standard Type 110 (minimum) punch blocks for voice or telephone, and control wiring instead of patch panels, each being certified for category 6a.
      - 2) IDC punch blocks (with internal RJ45 jacks) are acceptable for use in CCS when designed for Category 6a and the size and type of cable used.
      - 3) Secure punch block strips to OEM designed physical anchoring unit on a wall location in TRS; console, cabinet, rail, panel, etc. mounting is permitted at OEM recommendation and as accepted by COR. Punch blocks are not permitted for Class II or 120 VAC power wiring.
      - 4) Technical Characteristics:
        - a) Number of Horizontal Rows: Minimum 100.
        - b) Number of Terminals per Row: Minimum 4.
        - c) Terminal Protector: Required for each used or unused terminal.
        - d) Insulation Splicing: Required between each row of terminals.
    - b. Digital or High Speed Data:
      - 1) Provide 480 mm (19 inches) horizontal EIA/ECA 310 rack mountable patch panel with EIA/ECA 310 standard spaced vertical mounting holes for digital or high-speed data service CSS, with modular female Category 5E (or on a case by case basis Category 6A for specialized powered systems accepted by SMCS 0050P2H3, (202) 461-5310, OI&T and FMS Services, and COR) RJ45 jacks designed for size and type of UTP or F/UTP cable installed in rows.
      - 2) Technical Characteristics:

# EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

PART 1 - Bancroft Architects + Engineers

06-01-15

- a) Number of Horizontal Rows: Minimum 2.
- b) Number of Jacks Per Row: Minimum 24.
- c) Type of Jacks: RJ45.
- d) Terminal Protector: Required for each used or unused jack.
- e) Insulation: Required between each row of jacks.

#### 2.4 EXISTING WIRING

A. Do not reuse existing wiring. .

#### PART 3 - EXECUTION

### 3.1 INSTALLATION

### A. General:

- 1. Install wiring in cable tray or raceway.
- Seal cable entering a building from underground, between wire and conduit where cable exits conduit, with non-hardening approved compound.
- 3. Wire Pulling:
  - a. Provide installation equipment that prevents cutting or abrasion of insulation during pulling of cables.
  - b. Use ropes made of nonmetallic material for pulling feeders.
  - c. Attach pulling lines for feeders by means of either woven basket grips or pulling eyes attached to conductors, as accepted by COR.
  - d. Pull multiple cables into a single conduit together.
- B. Installation in Maintenance or Man holes (NOT USED):
- C. Control, Communication and Signal Wiring Installation:
  - Unless otherwise specified in other sections, provide wiring and connect to equipment/devices to perform required functions as indicated.
  - Install separate cables for each system so that malfunctions in any system does not affect other systems, except where otherwise required.
  - 3. Group wires and cables according to service (i.e. AC, grounds, signal, DC, control, etc.); DC, control and signal cables can be included with any group.
  - 4. Form wires and cables to not change position in group throughout the conduit run. Bundle wires and cables in accepted signal duct, conduit, cable ducts, or cable trays neatly formed, tied off in 600

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

06-01-15

mm to 900 mm (24 inch to 36 inch) lengths to not change position in group throughout run.

- 5. Concealed splices are not allowed.
- 6. Separate, organize, bundle, and route wires or cables to restrict EMI, channel crosstalk, or feedback oscillation inside any enclosure.
- 7. Looking at any enclosure from the rear (wall mounted enclosures, junction, pull or interface boxes from the front), locate AC power, DC and speaker wires or cables on the left; coaxial, control, microphone and line level audio and data wires or cables, on the right.
- 8. Provide ties and fasteners that do not damage or distort wires or cables. Limit spacing between tied points to maximum 150 mm (6 inches).
- 9. Install wires or cables outside of buildings in conduit, secured to solid building structures.
- 10. Wires or cables must be specifically accepted, on a case by case basis, to be installed outside of conduit. Bundled wires or cables must be tied at minimum 460 mm (18 inches) intervals to a solid building structure; bundled wires or cables must have ultra violet protection and be waterproof (including all connections).
- 11. Laying wires or cables directly on roof tops, ladders, drooping down walls, walkways, floors, etc. is not permitted.
- 12. Wires or cables installed outside of conduit, cable trays, wireways, cable duct, etc.:
  - a. Only when authorized, can wires or cables be identified and approved to be installed outside of conduit.
  - b. Provide wire or cable rated plenum and OEM certified for use in air plenums.
  - c. Provide wires and cables hidden, protected, fastened and tied at maximum 600 mm (24 inches) intervals, to building structure.
  - d. Provide closer wire or cable fastening intervals to prevent sagging, maintain clearance above suspended ceilings.
  - e. Remove unsightly wiring and cabling from view, and discourage tampering and vandalism.

# 

06-01-15

f. Sleeve and seal wire or cable runs, not installed in conduit, that penetrate outside building walls, supporting walls, and two hour fire barriers, with an approved fire retardant sealant.

#### D. AC Power:

- Bond to ground contractor-installed equipment and identified Government-furnished equipment, to eliminate shock hazards and to minimize ground loops, common mode returns, noise pickup, crosstalk, etc. for total ground resistance of 0.1 Ohm or less.
- 2. Use of conduit, signal duct or cable trays as system or electrical ground is not permitted; use these items only for dissipation of internally generated static charges (not to be confused with externally generated lightning) that can be applied or generated outside mechanical and physical confines of system to earth ground. Discovery of improper system grounding is grounds to declare system unacceptable and termination of all system acceptance testing.
- 3. Cabinet Bus: Extend a common ground bus of at least #10 AWG solid copper wire throughout each equipment cabinet and bond to system ground. Provide a separate isolated ground connection from each equipment cabinet ground bus to system ground. Do not tie equipment ground busses together.
- 4. Equipment: Bond equipment to cabinet bus with copper braid equivalent to at least #12 AWG. Self-grounding equipment enclosures, racks or cabinets, that provide OEM certified functional ground connections through physical contact with installed equipment, are acceptable alternatives.

# 3.2 EQUIPMENT IDENTIFICATION

- A. Control, Communication and Signal System Identification:
  - 1. Install a permanent wire marker on each wire at each termination.
  - 2. Identify cables with numbers and letters on the labels corresponding to those on wiring diagrams used for installing systems.
  - 3. Install labels retaining their markings after cleaning.
  - 4. In each maintenance hole (manhole) and handhole, install embossed brass tags to identify system served and function.

### B. Labeling:

1. Industry Standard: ANSI/TIA-606-B.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades PART 1 - Bancroft Architects + Engineers

06-01-15

- 2. Print lettering for voice and data circuits using Brady or equal labels that will not degrade handwritten labels are not acceptable.
- 3. Cable and Wires (hereinafter referred to as "cable"): Label cables at both ends in accordance with industry standard. Provide permanent labels in contrasting colors. Identify cables matching system Record Wiring Diagrams.
- 4. Equipment: Permanently labeled system equipment with contrasting plastic laminate or bakelite material. Label system equipment on face of unit corresponding to its source.
- 5. Conduit, Cable Duct, and Cable Tray: Label conduit, duct and tray, including utilized GFE, with permanent marking devices or spray painted stenciling a minimum of 3 meters (10 ft.) identifying system. Label each enclosure according to this standard.
- 6. Termination Hardware: Label workstation outlets and patch panel connections using color coded labels with identifiers in accordance with industry standard and Record Wiring Diagrams.

#### 3.3 TESTING

- A. Minimum test requirements are for impedance compliance, inductance, capacitance, signal level compliance, opens, shorts, cross talk, noise, and distortion, and split pairs on cables in frequency ranges specified.
- B. Tests required for data cable must be made to confirm operation of this cable at minimum 10 Mega (M) Hertz (Hz) full bandwidth, fully channel loaded and a Bit Error Rate of a minimum of 10-6 at maximum rate of speed.
- C. Provide cable installation and test records at acceptance testing to COR and thereafter maintain in facility's telephone switch room.
- D. Record changes (used pair, failed pair, etc.) in these records as change occurs.
- E. Test cables after installation and replace any defective cables.

- - - E N D - - -

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-16

# SECTION 27 15 00 COMMUNICATIONS STRUCTURED CABLING

### PART 1 - GENERAL

#### 1.1 DESCRIPTION

A. This section specifies a complete and operating voice and digital structured cabling distribution system and associated equipment and hardware to be installed in VA Medical Centerhere-in-after referred to as the "facility".

#### 1.2 RELATED WORK

- A. Wiring devices: Section 26 27 26, WIRING DEVICES.
- B. Lightning protection system: Section 26 41 00, FACILITY LIGHTNING PROTECTION.
- C. General electrical requirements that are common to more than one section in Division 27: Section 27 05 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS.
- D. Requirements for personnel safety and to provide a low impedance path for possible ground fault currents: Section 27 05 26, GROUNDING AND BONDING FOR COMMUNICATIONS SYSTEMS.
- E. Conduits for cables and wiring: Section 27 05 33, RACEWAYS AND BOXES FOR COMMUNICATIONS SYSTEMS.
- F. Low voltage cabling system infrastructure: Section 27 10 00, CONTROL, COMMUNICATION AND SIGNAL WIRING.
- G. Voice communication switching and routing equipment: Section 27 31 00, VOICE COMMUNICATIONS SWITCHING AND ROUTING EQUIPMENT.
- H. Extension of a voice communication switching and routing system: Section 27 31 31, VOICE COMMUNICATIONS SWITCHING AND ROUTING EQUIPMENT EXTENSION
- I. Emergency radio equipment: Section 27 32 41, TWO-WAY RADIO EQUIPMENT AND SYSTEMS.
- J. High Definition (HDTV) Master Antenna Television (MATV) system and associated equipment: Section 27 41 31, MASTER ANTENNA TELEVISION EQUIPMENT AND SYSTEMS.
- K. Emergency Service Public Address System (PAS) and associated equipment: Section 27 51 16, PUBLIC ADDRESS AND MASS NOTIFICATION SYSTEMS.

# ${\tt EHRM} \ \ {\tt Infrastructure} \ \ {\tt UpgradesEHRM} \ \ {\tt Infrastructure} \ \ {\tt Upgrades}$

Bancroft Architects + Engineers

01-01-16

#### 1.3 SUBMITTALS

- A. In addition to requirements of Section 27 05 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS provide:
  - 1. Pictorial layout drawing of facility and routing to each end point, showing termination cabinets, each distribution cabinet and rack, as each is expected to be installed and configured.
  - 2. List of test equipment as per 27 05 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS.

#### B. Certifications:

- Submit written certification from OEM indicating that proposed supervisor of installation and proposed provider of contract maintenance are authorized representatives of OEM. Include individual's legal name and address and OEM warranty credentials in the certification.
- 2. Pre-acceptance Certification: Submit in accordance with test procedures.
- 3. Test system cables and certify to COR before proof of performance testing can be conducted. Identify each cable as labeled on asinstalled drawings.
- 4. Provide current and qualified test equipment OEM training certificates and product OEM installation certification for contractor installation, maintenance, and supervisory personnel.
- C. Closeout Submittal: Provide document from OEM certifying that each item of equipment installed conforms to OEM published specifications.

### 1.4 WARRANTY

A. Work subject to terms of Article "Warranty of Construction," FAR clause 52.246-21.

### PART 2 - PRODUCTS

# 2.1 PERFORMANCE AND DESIGN CRITERIA

- A. Provide complete system including "punch down" and cross-connector blocks voice and data distribution sub-systems, and associated hardware including telecommunications outlets (TCO); copper and fiber optic distribution cables, connectors, "patch" cables, "break out" devices and equipment cabinets, interface cabinets, and radio relay equipment rack.
- B. Industry Standards:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

- 1. Cable distribution systems provided under this section are connected to systems identified as critical care performing life support functions.
- 2. Conform to National and Local Life Safety Codes (whichever are more stringent), NFPA, NEC, this section, Joint Commission Life Safety Accreditation requirements, and OEM recommendations, instructions, and guidelines.
- 3. Provide supplies and materials listed by a nationally recognized testing laboratory where such standards are established for supplies, materials or equipment.
- 4. Refer to industry standards and minimum requirements of Section 27 05 11, REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS and guidelines listed.
- 5. Active and passive equipment required by system design and approved technical submittal; must conform to each UL standard in effect for equipment, when technical submittal was reviewed and approved by Government or date when COR accepted system equipment to be replaced. Where a UL standard is in existence for equipment to be used in completion of this contract, equipment must bear approved NRTL label.
- C. System Performance: Provide complete system structured wiring to meet or exceed TIA Category 6A requirements.
- D. Provide continuous inter- and/or intra-facility voice, data, and analog service.
  - 1. For VA Systems, provide voice and data cable distribution system based on a physical "Star" topology, as shown on drawing network diagram..
  - 2. For Bedroom Communications, provide separate cable distribution system.
  - 3. Contact SMCS 0050P2H3 (202-462-5310) for specific technical assistance and approvals.
- E. Specific Subsystem Requirements: Provide products necessary for a complete and functional voice, data, analog and videotelephone communications cabling system, including backbone cabling system, patch

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-16

- panels and cross-connections, horizontal cabling systems, jacks, faceplates, and patch cords.
- F. Coordinate size and type of conduit, pathways and firestopping for maximum 40 percent cable fill with subcontractors.
- G. Terminate all interconnecting twisted pair, fiber-optic or coaxial cables on patch panels or punch blocks. Terminate unused or spare conductors and fiber strands. Do not leave unused or spare twisted pair wire, fiber-optic or coaxial cable unterminated, unconnected, loose or unsecured.
- H. Color code distribution wiring to conform to ANSI/TIA 606-B and construction documents, whichever is more stringent. Label all equipment, conduit, enclosures, jacks, and cables on record drawings, to facilitate installation and maintenance.
- I. In addition to requirements in Section 27 05 11, REQUIREMENTS FOR COMMUNICATION INSTALLATIONS, provide stainless steel faceplates with plastic covers over labels.

### 2.2 EQUIPMENT AND MATERIALS

- A. Where system connects to an existing or future voice (telephone) system, refer to Section 27 31 00, VOICE COMMUNICATIONS SWITCHING AND ROUTING EQUIPMENT for specific voice (telephone) equipment and system operational performance standards.
- B. Cable Systems Twisted Pair, Fiber optic, Coaxial and Analog:

### 1. General:

- a. Provide cable (i.e. backbone, outside plant, and horizontal cabling) conforming to accepted industry standards with regards to size, color code, and insulation.
- b. Some areas can be considered "plenum". Comply with all codes pertaining to plenum environments. It is contractor's responsibility to review the VA's cable requirements with COR and OI&T Service prior to installation to confirm type of environment present at each location.
- c. Provide proper test equipment to confirm that cable pairs meet each OEM's standard transmission requirements, and ensure cable carries data transmissions at required speeds, frequencies, and fully loaded bandwidth.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- 2. Telecommunications Rooms (TR):
  - a. In TR's served with UTP fiber optic, coaxial and analog backbone cables, terminate UTP cable on RJ-45, 8-pin connectors of separate 48-port modular patch panels,
  - b. NOT USED
  - c. Provide connecting cables required to extend backbone cables (i.e. patch cords, twenty-five pair, etc.), to ensure complete and operational distribution systems.
  - d. In TR's, which are only served by a UTP backbone cable, terminate cable on separate modular connecting devices, Type 110A punch down blocks (or equivalent), dedicated to data applications.
- 3. Backbone Copper Cables:
  - a. Riser Cable:
    - Provide communication riser cables listed in NEC Table 800,
       154(a) for the purpose and suited for electrical connection to a communication network.
    - 2) Provide STP or Unshielded Twisted Pair (UTP), minimum 24
      American Wire Gauge (AWG) solid, thermoplastic insulated
      conductors for communication (analog RF coaxial cable is not
      to be provided in riser systems) riser cables with a
      thermoplastic outer jacket.
    - 3) Label and test complete riser cabling system.
- 4. Horizontal Cable: Installed from TCO jack to the TR patch panel.
  - a. Tested to ANSI/TIA-568-C.2 Category 6A requirements including NEXT, ELFEXT (Pair-to-Pair and Power Sum), Insertion Loss (attenuation), Return Loss, and Delay Skew.
  - b. Minimum Transmission Parameters: 500 MHz.
  - c. Provide four pair 0.326 mm2 (22 AWG) cable
  - d. Terminate all four pairs on same port at patch panel in TR.
  - e. Terminate all four pairs on same jack, at work area Telecommunication Outlets (TCO):
    - 1) Jacks: Minimum three eight-pin RJ-45 ANSI/TIA-568-C.2 Category Type jacks at TCO.
      - a) Top Port: RJ-45 jack compatible with RJ-11 plug for voice.
      - b) Bottom Two Ports: Unkeyed RJ-45 jacks for data.
- 5. Patient Bedside Prefabricated Units (PBPU):NOT USED

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- 6. Fiber Optics Backbone Cable:NOT USED
- C. Cross-Connect Systems (CCS):NOT USED
- D. Telecommunication Room (TR):
  - 1. Terminate backbone and horizontal, copper, fiber optic, coaxial and analog cables on appropriate cross-connection systems (CCS) containing patch panels, punch blocks, and breakout devices provided in enclosures and tested, regardless of installation method, mounting, termination, or cross-connecting used. Provide cable management system as a part of each CCS.
  - Coordinate location in TR with FMS equipment (i.e. fire alarm, nurse call, code blue, video, public address, radio entertainment, intercom, and radio paging equipment).
- E. Coaxial and Analog Cables are not in this project:
- F. Main Cross-connection Subsystem (MCCS): MCCS is common point of distribution for inter- and intra-building copper and fiber optic backbone system cables, and connections to the voice (telephone) and data cable systems.
- G. Voice (or Telephone) Cable Cross-Connection Subsystem:
  - 1. Provide Insulation Displacement Connection (IDC) hardware.
  - 2. Provide the following for each Category Category 6A for specialized powered systems technically accepted by SMCS 0050P2H3, (202) 461-5310, OI&T and FMS Services and COR) Cabling System termination; RJ-45 patch cord connector to RJ-45 patch cord connector.
    - a. Provide terminations to be accessible without need for disassembly of IDC wafer. Provide IDC wafers removable from their mounts to facilitate testing on either side of connector.
    - b. Provide removable designation strips or labels to allow for inspection of terminations.
    - c. Provide cable management system as a part of IDC.
  - Provide IDC connectors capable of re-terminations, without damage, a minimum of 200 IDC insertions or withdrawals on either side of connector panel.
  - 4. Install using only non-impact terminating tool having both a tactile and an audible feedback to indicate proper termination.
  - 5. Provide inputs from Local Voice (Telephone) System including alarms from Fire Alerm Control Panel, or diverse routed voice distribution

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- systems on left side of IDC (110A blocks with RJ45 connections are acceptable alternates to IDC) of MCCS.
- 6. Provide system outputs from MCCS to voice backbone cable distribution system on the right side of same IDC (or 110A blocks) of MCCS.
- 7. Do not split pairs within cables between different jacks or connections.
- 8. Provide UTP cross connect wire to connect each pair of terminals plus an additional 50 percent spare.
- H. Data Cross-Connection Subsystems:
  - Provide patch panels with modular RJ45 female to 110 connectors for cross-connection of copper data cable terminations and system ground with cable management system.
  - 2. Provide patch panels conforming to EIA/ECA 310-E dimensions and suitable for mounting in standard equipment racks, with 48 RJ45 jacks aligned in two horizontal rows per panel. Provide RJ45 jacks of modular design and capable of accepting and functioning with other modular (i.e. RJ11) plugs without damaging jack.
    - a. Provide system inputs from servers, data LAN, bridge, or interface distribution systems on top row of jacks of appropriate patch panel.
    - b. Provide backbone cable connections on bottom row of jacks of same patch panel.
    - c. Provide patch cords for each system pair of connection jacks with modular RJ45 connectors provided on each end to match panel's modular RJ45 female jack's being provided.
    - d. Provide Patch Cords in same color as source cables.
- I. Fiber-Optic Cross-Connection Subsystems: NOT USED The only fiber optic cable is from the Demarc Switch to the telephone company router..
- J. Horizontal Cabling (HC):
  - 1. Horizontal cable length to farthest system outlet to be maximum of  $80\ m\ (260\ ft)$ ;  $10\ M\ (32\ ft)$  is allowed at both ends of cables for terminations.
  - 2. Splitting of pairs within a cable between different jacks is not permitted.

### EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-16

- K. Air Blown Fiber: (NOT USED)
  - 1. Outside Microducts: NOT USED

#### 2.3 DISTRIBUTION EQUIPMENT AND SYSTEMS - SEE NETWORK DIAGRAM ON DRAWINGS

- A. Telecommunication Outlet:NOT IN PROJECT
  - 1.
  - 2. Provide wall outlet with a stainless steel face plate and sufficient ports to fit data multi- pin jacks and plastic covers for labels when mounted on outlet box provided (minimum 100mm (4 inches) x 100mm (4 inches) for single and 100mm (4 inches) x 200mm (8 inches) for dual outlet box applications.
- B. Backbone Distribution Cables (NOT USED):
  - 1. Data Multi-Conductor:
    - a. Unshielded UTP cable with solid conductors.
    - b. Able to handle the power and voltage used over the distance required.
    - c. Meets TIA transmission performance requirements of Category 6A.
    - d. Technical Characteristics:
      - 1) 0.205 mm2 (24 AWG) for data only 0.326 mm2 (22 AWG) cable for POE ports.
      - 2) Bend Radius: 10 times cable outside diameter.
      - 3) Impedance: 100 Ohms + 15%, BAL.
      - 4) Bandwidth: 500 MHz.
      - 5) DC Resistance: Maximum 9.38 Ohms/100m (328 ft.) at 20 degrees C.
      - 6) Maximum Mutual Capacitance: 5.6 nF per 100 m (328 ft.).
      - 7) Shield Coverage: NOT USED
        - a) Overall Outside (if OEM specified): 100 percent.
        - b) Individual Pairs (if OEM specified): 100 percent.
      - 8) Maximum attenuation for 100m (328 ft.) at 20° C:

500		45.3

- 2. Fiber Optic: NOT USED
- C. Outlet Connection Cables:
  - 1. Voice (Telephone): USE VOIP / POE TELEPHONES DATA CABLE for data ports.
  - 2. Data:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- a. Provide a connection cable for each TCO data jack in system with 10 percent spares to connect a data instrument to TCO data jack.Do not provide data terminals/equipment.
- b. Technical Characteristics:
  - 1) Length: Minimum 1.8 m (6 feet).
  - 2) Cable: Data grade Category 5E or on a case-by-case basis
    Category 6A for specialized powered systems accepted by SMCS
    0050P2H3 (202) 461-5310, IT and FMS Services and COR.
  - 3) Connector: RJ-45 male on each end.
  - 4) Color Coding: Required, data industry standard.
  - 5) Size: Minimum 24 AWG for data only and 22 AWG for POE ports.
- 3. Fiber Optic: NOT USED
- D. System Connectors:
  - 1. Modular (RJ-45/11 and RJ-45): Provide voice and high speed data transmission applications type modular plugs compatible with voice (telephone) instruments, computer terminals, and other type devices requiring linking through modular telecommunications outlet to the system compatible with UTP cables.
    - a. Technical Characteristics:
      - 1) Number of Pins:
        - a) RJ-45: Eight.
        - b) RJ-11/45: Compatible with RJ-45.
      - 2) Dielectric: Surge.
      - 3) Voltage: Minimum 1,000V RMS, 60 Hz at one minute.
      - 4) Current: 2.2A RMS at 30 minutes or 7.0A RMS at 5.0 seconds.
      - 5) Leakage: Maximum 100 μA.
      - 6) Connections:
        - a) Initial contact resistance: Maximum 20 milli-Ohms.
        - b) Insulation displacement: Maximum 10 milli-Ohms.
        - c) Interface: Must interface with modular jacks from a variety of OEMs. RJ-11/45 plugs provide connection when used in RJ-45 jacks.
        - d) Durability: Minimum 200 insertions/withdrawals.
- E. Fiber Optic Terminators (NOT USED):
- F. Conduit and Signal Ducts:
  - 1. Conduit:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-16

- a. Size conduit for network cables per Conduit Fill Schedule on drawing.
- b. Provide conduit or sleeves for cables penetrating walls, ceilings, floors, interstitial space, fire barriers, etc.
- c. Minimum Conduit Size: 19 mm (3/4 inch).
- d. Provide separate conduit and signal ducts for each cable type installation.
- e. When metal (plastic covered, flexible cable protective armor, etc.) systems are authorized to be provided for use in system, follow installation guidelines and standard specified in Section 27 05 33, RACEWAYS AND BOXES FOR COMMUNICATIONS SYSTEMS and NEC.
- f. Maximum conduit fill per Conduit Fill Schedule on drawing, for cable installation.
- 2. Signal Duct, Cable Duct, or Cable Tray: Use existing signal duct, cable duct, and cable tray, when identified and accepted by COR.

#### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Install for ease of operation, maintenance, and testing.
- B. Install system to comply with NFPA 70 National Electrical Code, NFPA 99 Health Care Facilities, NFPA 101 Life Safety Code, Joint Commission Manual for Health Care Facilities, and original equipment manufacturers' (OEM) installation instructions.
- C. Cable Systems Installation:
  - Install system cables in cable duct, cable tray, cable runway, conduit or when specifically approved, flexible NEC Article 800 communications raceway. Confirm drawings show sufficient quantity and size of cable pathways. If flexible communications raceway is used, install in same manner as conduit.
  - 2. Coordinate outside plant and backbone cables to furnish number of cable pairs for system requirements and obtain approval of COR and IT Service prior to installation.
  - 3. Bond to ground metallic cable sheaths, etc. (i.e. risers, underground, horizontal, etc.).
  - 4. Install temporary cable to not present a pedestrian safety hazard and be responsible for all work associated with removal. Temporary

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-16

cable installations are not required to meet Industry Standards; but, must be reviewed and accepted by COR, IT Service, FMS and SMCS 0050P2H3 (202-461-5310) prior to installation.

- D. Patient Bedside Prefabricated Units (PBPU) Installation: NOT USED
- E. Labeling:
  - 1. Industry Standard: Provide labeling in accordance with ANSI/TIA-606-B
  - 2. Print lettering of labels with laser printers; handwritten labels are not acceptable.
  - 3. Label both ends of all cables in accordance with industry standard. Provide permanent Labels in contrasting colors and identify according to system "Record Wiring Diagrams".
  - 4. Termination Hardware: Label workstation outlets and patch panel connections using color coded labels with identifiers in accordance with industry standard and record on "Record Wiring Diagrams".

#### 3.2 FIELD QUALITY CONTROL

- A. Interim Inspection:
  - Verify that equipment provided adheres to installation requirements of this section. Interim inspection must be conducted by a factorycertified representative and witnessed by COR.
  - 2. Check each item of installed equipment to ensure appropriate NRTL label.
  - 3. Verify cabling terminations in telecommunications rooms and at workstations adhere to color code for T568A pin assignments and cabling connections comply with TIA standards.
  - 4. Visually confirm marking of cables, faceplates, patch panel connectors and patch cords.
  - 5. Perform fiber optical field inspection tests via attenuation measurements on factory reels and provide results along with manufacturer certification for factory reel tests. Remove failed cable reels from project site upon attenuation test failure.
  - 6. Notify COR of the estimated date the contractor expects to be ready for interim inspection, at least 20 working days before requested inspection date, so interim inspection does not affect systems' completion date.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-16

- 7. Provide results of interim inspection to COR. If major or multiple deficiencies are discovered, COR can require a second interim inspection before permitting contractor to continue with system installation.
- 8. Do not proceed with installation until COR determines if an additional inspection is required. In either case, re-inspection of deficiencies noted during interim inspections must be part of the proof of performance test.

#### B. Pretesting:

- 1. Pretest entire system upon completion of system installation.
- 2. Verify during system pretest, utilizing the accepted equipment, that system is fully operational and meets system performance requirements of this section.
- 3. Provide COR four copies of recorded system pretest measurements and the written certification that system is ready for formal acceptance test.
- C. Microduct Tests: NOT USED
- D. Acceptance Test:
  - 1. After system has been pretested and the contractor has submitted pretest results and certification to COR, then schedule an acceptance test date and give COR 30 days' written notice prior to date acceptance test is expected to begin.
  - 2. Test only in presence of a COR.
  - 3. Test utilizing approved test equipment to certify proof of performance.
  - 4. Verify that total system meets the requirements of this section.
  - 5. Include expected duration oftest time, with notification of the acceptance test.

#### E. Verification Tests:

- Test UTP copper cabling for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors, and between conductors and shield, if cable has an overall shield. Test cables after termination and prior to cross-connection.
- 2. Multi-mode Fiber Optic Cable: NOT USED
- 3. Single mode Fiber Optic Cable: NOT USED
- F. Performance Testing:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

01-01-16

- 1. Perform Category 6A for specialized powered systems accepted by SMCS 0050P2H3, (202) 461-5310, IT and FMS Services and COR) tests in accordance with TIA-568-B.1 and TIA-568-B.2. Include the following tests - wire map, length, insertion loss, return loss, NEXT, PSNEXT, ELFEXT, PSELFEXT, propagation delay and delay skew.
- 2. Fiber Optic Links (NOT USED):
- G. Total System Acceptance Test: Perform verification tests for UTP copper cabling systems cabling systems after complete telecommunication distribution system and workstation outlets are installed.

#### 3.3 MAINTENANCE

- A. Accomplish the following minimum requirements during one year warranty period:
  - 1. Respond and correct on-site trouble calls, during standard work week:
    - a. A routine trouble call within one working day of its report. A routine trouble is considered a trouble which causes a system outlet, station, or patch cord to be inoperable.
    - b. Standard work week is considered 8:00 A.M. to 5:00 P.M., Monday through Friday exclusive of Federal holidays.
  - 2. Respond to an emergency trouble call within six hours of its report.


    An emergency trouble is considered a trouble which causes a subsystem or distribution point to be inoperable at any time.
  - 3. Respond on-site to a catastrophic trouble call within four hours of its report. A catastrophic trouble call is considered total system failure.
    - a. If a system failure cannot be corrected within four hours (exclusive of standard work time limits), provide alternate equipment, or cables within four hours after four hour trouble shooting time.
    - b. Routine or emergency trouble calls in critical emergency health care facilities (i.e., cardiac arrest, intensive care units, etc.) are also be deemed as a catastrophic trouble.
  - 4. Provide COR written report itemizing each deficiency found and the corrective action performed during each official reported trouble call. Provide COR with sample copies of reports for review and approval at beginning of total system acceptance test.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

01-01-16

- - - E N D - - -



### EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

09-11

# SECTION 28 13 53 SECURITY ACCESS DETECTION

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. Security access detection to Room 112 will be provided by ADT.
  - 1. Wiring from detector to ADT panel shall be in conduit,
  - Conductors from detector to ADT panel shall be per ADT specification,
  - 3. ADT tamper switches shall be installed on Room 112 door a,d on the two doors of the Computer Cabinet.
  - 4. Follow Division 27 wiring and raceway requirements.
  - 5. Contractor shall perform a full test of all doors after installation:
    - a. Contact COR to determine ADT response requirements,
    - b. Test each door individually,
    - c. Verify that ADT responds to test,
    - d. Verify ADT notifies proper individuals.
    - e. Provide Test Report to COR.
  - 6. THE REMAINDER OF THIS SPECIFICATION DOES NOT APPLY TO THIS PROJECT.

#### 3.9 COMMISSIONING (NOT REQUIRED)

----END----

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

10-11

# SECTION 28 31 00 FIRE DETECTION AND ALARM

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This project involves relocating the existing Fire Alarm Control Panel (FACP) from one side of the wall in Room 112, to the other side of the wall into the Waiting Area.
  - 1. Contractor to obtain services of the Certified Maintenance
    Contractor that presently performs system maintenance to perform
    all work related to relocating the Fire Alarm Control panel.
  - 2. Certified Fire Protection contractor shall test system prior to relocating the FACP,
  - 3. Notify COR of planned test three weeks prior to test.
  - 4. After relocating the panel, contractor to verify that by extending the wiring, the system shall still function properly. Provide a report to COR certifying the functionality.
  - Perform a full functional test of detection and alarming capabilities, including remote alarming. Provide test report to COR.
- B. Fire alarm systems modifications shall comply with requirements of the most recent VA FIRE PROTECTION DESIGN MANUAL and NFPA 72 unless variations to NFPA 72 are specifically identified within these contract documents by the following notation: "variation". The design, system layout, document submittal preparation, and supervision of installation and testing shall be provided by a technician that is certified NICET level III or a registered fire protection engineer. The NICET certified technician shall be on site for the supervision and testing of the system. Factory engineers from the equipment manufacturer, thoroughly familiar and knowledgeable with all equipment utilized, shall provide additional technical support at the site as required by the COR or his authorized representative. Installers shall have a minimum of 2 years of experience installing fire alarm systems.
- C. Fire alarm signals:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades

Bancroft Architects + Engineers

10-11

1. The existing facility fire alarm signaling sequence of operation shall be maintained.

#### 1.2 SCOPE

- 1. A. The existing facility fire alarm system is a SILENT KNIGHT SK-5208 fire emergency voice/alarm communication system. Device and appliance locations shown on the drawings are for reference only unless specifically dimensioned. Actual locations shall be in accordance with NFPA 72 and this specification.
- B. All existing fire alarm conduit not reused shall be removed.

#### C. Basic Performance:

- The existing fire alarm sequence of operation for trouble, supervisory, alarm and building safety functions shall remain the same as currently programmed.
- 2. Modified initiating device circuits (IDC) shall be wired in accordance with the existing system circuit class and NFPA 72..
- Modified Signaling line circuits (SLC) within buildings shall be wired in accordance with the existing system circuit class and NFPA
   72.
- 4. Modified notification appliance circuits (NAC) shall be wired in accordance with the existing system circuit class and NFPA 72.

#### 1.3 RELATED WORK

- A. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.

  Requirements for procedures for submittals.
- B. Section 07 84 00 FIRESTOPPING. Requirements for fire proofing wall penetrations.
- C. Section 21 13 13 WET-PIPE SPRINKLER SYSTEMS. Requirements for sprinkler systems.
- D. Section 28 05 00 COMMON WORK RESULTS FOR ELECTRONIC SAFETY AND SECURITY. Requirements for general requirements that are common to more than one section in Division 28.
- E. Section 28 05 13 CONDUCTORS AND CABLES FOR ELECTRONIC SAFETY AND SECURITY. Requirements for conductors and cables.
- F. Section 28 05 26 GROUNDING AND BONDING FOR ELECTRONIC SAFETY AND SECURITY. Requirements for grounding of equipment.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

10-11

- G. Section 28 05 28.33 CONDUITS AND BACKBOXES FOR ELECTRONIC SAFETY AND SECURITY. Requirements for infrastructure.
- H. Section 28 05 13 CONDUCTORS AND CABLES FOR ELECTRONIC SAFETY AND SECURITY. Requirements for conductors and cables.
- I. Section 28 08 00, COMMISIONING OF ELECTRONIC SAFETY AND SECURITY SYSTEMS. Requirements for commissioning - systems readiness checklists, and training.

#### 1.4 SUBMITTALS - SEE PART 1

#### B. Drawings:

- 1. Prepare drawings using AutoCAD Release 14 software and include all contractors information. Layering shall be by VA criteria as provided by the Contracting Officer's Technical Representative (COTR). Bid drawing files on AutoCAD will be provided to the Contractor at the pre-construction meeting. The contractor shall be responsible for verifying all critical dimensions shown on the drawings provided by VA.
- 2. Floor plans: For the areas of work: Provide locations of all devices (with device number at each addressable device corresponding to control unit programming), appliances, panels, equipment, junction/terminal cabinets/boxes, risers, electrical power connections, individual circuits and raceway routing, system zoning; number, size, and type of raceways and conductors in each raceway; conduit fill calculations with cross section area percent fill for each type and size of conductor and raceway. Only those devices connected and incorporated into the final system shall be on these floor plans. Do not show any removed devices on the floor plans. Show all interfaces for all fire safety functions.
- 3. Riser diagrams: Provide, for the scope of work, the number, size and type of riser raceways and conductors in each riser raceway and number of each type device. Show HVAC shutdown interface, fire extinguishing system interface, and all other fire safety interfaces related to the scope of work. Show wiring Styles on the riser diagram for all circuits. Provide diagrams both on a per building and campus wide basis.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

10-11

- 4. Detailed wiring diagrams: Provide for modified control panels, modules, power supplies, electrical power connections, auxiliary relays and annunciators showing termination identifications, size and type conductors, circuit boards, LED lamps, indicators, adjustable controls, switches, ribbon connectors, wiring harnesses, terminal strips and connectors, spare zones/circuits. Diagrams shall be drawn to a scale sufficient to show spatial relationships between components, enclosures and equipment configuration.
- 5. Two weeks prior to final inspection, the Contractor shall deliver to the COTR 3 sets of as-built drawings and one set of the as-built drawing computer files(using AutoCAD 2007 or later). As-built drawings (floor plans) shall show all new and/or existing conduit used for the fire alarm system.

#### C. Manuals:

- Submit simultaneously with the shop drawings, companion copies of complete maintenance and operating manuals including technical data sheets for all items used in the system, power requirements, device wiring diagrams, dimensions, and information for ordering replacement parts.
  - a. Wiring diagrams shall have their terminals identified to facilitate installation, operation, expansion and maintenance.
  - b. Wiring diagrams shall indicate internal wiring for each item of equipment and the interconnections between the items of equipment.
  - c. Include complete listing of all software used and installation and operation instructions including the input/output matrix chart.
  - d. Provide a clear and concise description of operation that gives, in detail, the information required to properly operate, inspect, test and maintain the equipment and system. Provide all manufacturer's installation limitations including but not limited to circuit length limitations.
  - e. Complete listing of all digitized voice messages.
  - f. Provide standby battery calculations under normal operating and alarm modes. Battery calculations shall include the magnets for holding the doors open for one minute.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

10 - 11

- g. Include information indicating who will provide emergency service and perform post contract maintenance.
- h. Provide a replacement parts list with current prices. Include a list of recommended spare parts, tools, and instruments for testing and maintenance purposes.
- i. A computerized preventive maintenance schedule for all equipment. The schedule shall be provided on disk in a computer format acceptable to the VAMC and shall describe the protocol for preventive maintenance of all equipment. The schedule shall include the required times for systematic examination, adjustment and cleaning of all equipment. A print out of the schedule shall also be provided in the manual. Provide the disk in a pocket within the manual.
- j. Furnish manuals in 3 ring loose-leaf binder or manufacturer's standard binder.
- k. A print out for all devices proposed on each signaling line circuit with spare capacity indicated.
- 2. Two weeks prior to final inspection, deliver 4 copies of the final updated maintenance and operating manual to the COTR.
  - a. The manual shall be updated to include any information necessitated by the maintenance and operating manual approval.
  - b. Complete "As installed" wiring and schematic diagrams shall be included that shows all items of equipment and their interconnecting wiring. Show all final terminal identifications.
  - c. Complete listing of all programming information, including all control events per device including an updated input/output matrix.
  - d. Certificate of Installation as required by NFPA 72 for each building. The certificate shall identify any variations from the National Fire Alarm Code.
  - e. Certificate from equipment manufacturer assuring compliance with all manufacturers installation requirements and satisfactory system operation.

#### D. Certifications:

1. Together with the shop drawing submittal, submit the technician's NICET level III fire alarm certification as well as certification

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

10-11

from the control unit manufacturer that the proposed performer of contract maintenance is an authorized representative of the major equipment manufacturer. Include in the certification the names and addresses of the proposed supervisor of installation and the proposed performer of contract maintenance. Also include the name and title of the manufacturer's representative who makes the certification.

- 2. Together with the shop drawing submittal, submit a certification from either the control unit manufacturer or the manufacturer of each component (e.g., smoke detector) that the components being furnished are compatible with the control unit.
- 3. Together with the shop drawing submittal, submit a certification from the major equipment manufacturer that the wiring and connection diagrams meet this specification, UL and NFPA 72 requirements.

#### 1.5 WARRANTY

All work performed and all material and equipment furnished under this contract shall be free from defects and shall remain so for a period of one year from the date of acceptance of the entire installation by the Contracting Officer.

# 1.6 GUARANTY PERIOD SERVICES NOT USED - (N/A)

#### 1.7 APPLICABLE PUBLICATIONS

A. The publications listed below (including amendments, addenda, revisions, supplements and errata) form a part of this specification to the extent referenced. The publications are referenced in text by the

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

10-11

basic designation only and the latest editions of these publications shall be applicable.

- B. National Fire Protection Association (NFPA):
  - NFPA 13 ......Standard for the Installation of Sprinkler
    Systems, 2019 edition
  - NFPA 14 ...... Standard for the Installation of Standpipes and
    Hose Systems, 2019 edition
  - NFPA 20 ...... Standard for the Installation of Stationary

    Pumps for Fire Protection, 2013 edition
  - NFPA 70......National Electrical Code (NEC), 2020 edition
  - NFPA 72......National Fire Alarm Code, 2019 edition
  - NFPA 90A.....Standard for the Installation of Air

    Conditioning and Ventilating Systems, 2019

    edition
  - NFPA 101.....Life Safety Code, 2021 edition
- C. Underwriters Laboratories, Inc. (UL): Fire Protection Equipment Directory
- D. Factory Mutual Research Corp (FM): Approval Guide, 2014
- E. American National Standards Institute (ANSI):
  - S3.41......Audible Emergency Evacuation Signal, 1990 edition, reaffirmed 2008
- F. International Code Council, International Building Code (IBC), 2009 edition

# PART 2 - PRODUCTS

# 2.1 EQUIPMENT AND MATERIALS, GENERAL

A. All equipment and components shall be new and the manufacturer's current model. All equipment shall be tested and listed by Underwriters Laboratories, Inc. or Factory Mutual Research Corporation for use as part of a fire alarm system. The authorized representative of the manufacturer of the major equipment shall certify that the installation complies with all manufacturers' requirements and that satisfactory total system operation has been achieved.

## 2.2 CONDUIT, BOXES, AND WIRE

- A. Conduit shall be in accordance with Section 28 05 28.33 CONDUIT AND BACKBOXES FOR ELECTRONIC SAFETY AND SECURITY and as follows:
  - 1. All new conduits shall be installed in accordance with NFPA 70.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

10 - 11

- 2. Conduit fill shall not exceed 40 percent of interior cross sectional area.
- 3. All new conduits shall be 3/4 inch (19 mm) minimum.

#### B. Wire:

- 1. Wiring shall be in accordance with NEC article 760, Section 28 05 13, CONDUCTORS AND CABLES FOR ELECTRONIC SAFETY AND SECURITY, and as recommended by the manufacturer of the fire alarm system. All wires shall be color coded. Number and size of conductors shall be as recommended by the fire alarm system manufacturer, but not less than 18 AWG for initiating device circuits and 14 AWG for notification device circuits.
- 2. Addressable circuits and wiring shall be twisted and shielded unless specifically excepted by the fire alarm equipment manufacturer in writing.
- 3. All fire alarm system wiring shall be solid copper, unless specifically noted otherwise.
- 4. Any fire alarm system wiring that extends outside of a building shall have additional power surge protection to protect equipment from physical damage and false signals due to lightning, voltage and current induced transients. Protection devices shall be shown on the submittal drawings and shall be UL listed or in accordance with written manufacturer's requirements.
- 5. All wire or cable used in underground conduits including those in concrete shall be listed for wet locations.
- C. Terminal Boxes, Junction Boxes, and Cabinets:
  - 1. Shall be galvanized steel in accordance with UL requirements.
  - 2. All boxes shall be sized and installed in accordance with NFPA 70.
  - 3. covers shall be repainted red in accordance with Section 09 91 00, PAINTING and shall be identified with white markings as "FA" for junction boxes and as "FIRE ALARM SYSTEM" for cabinets and terminal boxes. Lettering shall be a minimum of 3/4 inch (19 mm) high.
  - 4. Terminal boxes and cabinets shall have a volume 50 percent greater than required by the NFPA 70. Minimum sized wire shall be considered as 14 AWG for calculation purposes.
  - 5. Terminal boxes and cabinets shall have identified pressure type terminal strips and shall be located at the base of each riser.

# ${\tt EHRM} \ \ {\tt Infrastructure} \ \ {\tt UpgradesEHRM} \ \ {\tt Infrastructure} \ \ {\tt Upgrades}$

Bancroft Architects + Engineers

10-11

Terminal strips shall be labeled as specified or as approved by the COTR.

#### 2.3 ALARM NOTIFICATION APPLIANCES

#### A. Speakers:

- 1. Speakers shall be compatible for use with the existing Silent Knight fire alarm control units and shall operate on the existing fire alarm system voltage with field selectable output taps from 0.5 to 2.0W and originally installed at the 1/2 watt tap. Speakers shall provide a minimum sound output of 80 dBA at 10 feet (3,000 mm) with the 1/2 watt tap.
- 2. Frequency response shall be a minimum of 400 HZ to 4,000 HZ.
- 3. Four inches (100 mm) or 8 inches (200 mm) cone type speakers ceiling mounted with white colored baffles in areas with suspended ceilings and wall mounted in areas without ceilings.

#### C. Strobes:

- 1. Strobes shall be compatible for use with the existing Silent Knight fire alarm control units. Xenon flash tube type minimum 15 candela in toilet rooms and 75 candela in all other areas with a flash rate of 1 HZ. Strobes shall be synchronized where required by the National Fire Alarm Code (NFPA 72).
- 2. Backplate shall be red with 1/2 inch (13 mm) permanent red letters. Lettering to read "Fire", be oriented on the wall or ceiling properly, and be visible from all viewing directions.
- 3. Each new or modified strobe circuit shall have a minimum of 20 percent spare capacity.
- 4. Strobes may be combined with the audible notification appliances specified herein.

#### 2.4 ALARM INITIATING DEVICES

- A. Projected Beam-type Smoke Detectors:
  - Devices shall be shall be compatible for use with the existing Gamewell fire alarm control units. Detectors shall receive power from the fire alarm control unit and be with a remote, self-test feature.

#### 2.5 SUPERVISORY DEVICES

A. Duct Smoke Detectors:

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

10-11

- 1. Duct smoke detectors shall be maintained provided and connected by way of an address reporting interface device. Detectors shall be provided with an approved duct housing mounted exterior to the duct, and shall have perforated sampling tubes extending across the full width of the duct (wall to wall). Detector placement shall be such that there is uniform airflow in the cross section of the duct.
- 2. Interlocking with fans shall be provided in accordance with NFPA 90A and as specified hereinafter under Part 3.2, "TYPICAL OPERATION".
- 3. Provide remote indicator lamps, key test stations and identification nameplates (e.g. "DUCT SMOKE DETECTOR AHU-X") for all duct detectors. Locate key test stations in plain view on walls or ceilings so that they can be observed and operated from a normal standing position.
- B. Sprinkler and Standpipe System Supervisory Switches:

1..

2. Valve supervisory switches shall be connected to the fire alarm system by way of address reporting interface device. See Section 21 13 13, WET-PIPE SPRINKLER SYSTEMS for new switches to be added. Connect tamper switches for all control valves shown on the approved shop drawings.

#### 2.6 ADDRESS REPORTING INTERFACE DEVICE

- A. Shall have unique addresses that reports directly to the building fire alarm panel.
- B. Shall be configurable to monitor normally open or normally closed devices for both alarm and trouble conditions.
- C. Shall have terminal designations clearly differentiating between the circuit to which they are reporting from and the device that they are monitoring.
- D. Shall be UL listed for fire alarm use and compatibility with the panel to which they are connected.
- E. Shall be mounted in weatherproof housings if mounted exterior to a building.

#### 2.7 SPARE AND REPLACEMENT PARTS

- A. 1. Fire alarm strobes (wall mounted) 2
- 2. 2

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

10-11

B. Spare and replacement parts shall be in original packaging and submitted to the COTR.

#### PART 3 - EXECUTION

#### 3.1 INSTALLATION:

- A. Installation shall be in accordance with NFPA 70, 72, 90A, and 101 as shown on the drawings, and as recommended by the major equipment manufacturer. Fire alarm wiring shall be installed in conduit. All conduit and wire shall be installed in accordance with, Section 28 05 13 CONDUCTORS AND CABLES FOR ELECTRONIC SAFETY AND SECURITY, Section 28 05 26 GROUNDING AND BONDING FOR ELECTRONIC SAFETY AND SECURITY, Section 28 05 28.33 CONDUIT AND BACKBOXES FOR ELECTRONIC SAFETY AND SECURITY, and all penetrations of smoke and fire barriers shall be protected as required by Section 07 84 00, FIRESTOPPING.
- B. All conduits, junction boxes, conduit supports and hangers shall be concealed in finished areas and may be exposed in unfinished areas.
- C. All new and reused exposed conduits shall be painted in accordance with Section 09 91 00, PAINTING to match surrounding finished areas and red in unfinished areas.
- D. All existing accessible fire alarm conduit not reused shall be removed.
- E. Existing devices that are reused shall be properly mounted and installed. Where devices are installed on existing shallow backboxes, extension rings of the same material, color and texture of the new fire alarm devices shall be used. Mounting surfaces shall be cut and patched in accordance with Section 01 00 00, GENERAL REQUIREMENTS, Restoration, and be re-painted in accordance with Section 09 91 00, PAINTING as necessary to match existing.
- F. All fire detection and alarm system devices, control units and remote annunciators shall be flush mounted when located in finished areas and may be surface mounted when located in unfinished areas. Exact locations are to be approved by the COTR.
- G. Speakers shall be ceiling mounted as indicated on the drawings and fully recessed in areas with suspended ceilings. Speakers shall be wall mounted and recessed in finished areas without suspended ceilings. Speakers may be surface mounted in unfinished areas.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

10-11

- H. Strobes and speaker/strobes shall be flush wall mounted with the bottom of the unit located 80 inches (2,000 mm) above the floor or 6 inches (150 mm) below ceiling, whichever is lower. Locate and mount to maintain a minimum 36 inches (900 mm) clearance from side obstructions.
- I. Mount valve tamper switches so as not to interfere with the normal operation of the valve and adjust to operate within 2 revolutions toward the closed position of the valve control, or when the stem has moved no more than 1/5 of the distance from its normal position.
- L. Connect flow and tamper switches installed under Section 21 13 13, WET-PIPE SPRINKLER SYSTEMS.

#### 3.2 TYPICAL OPERATION

- A. Activation of any manual pull station, water flow or pressure switch, heat detector, kitchen hood suppression system, gaseous suppression system, or smoke detector shall cause the following operations to occur:
  - 1. Operate the emergency voice communication and visible notification system in accordance with the existing sequence of operation.
  - 3. Release only the magnetic door holders in the smoke zone on the floor from which alarm was initiated after the alert signal.
  - 4. Transmit a separate alarm signal, via the main fire alarm control unit to the fire department.
  - 5. Unlock the electrically locked exit doors within the zone of alarm.
- B. Operation of projected beam-type smoke detectors shall initiate the building atrium smoke exhaust system in accordance with the existing sequence of operation.
- C. Operation of duct smoke detectors shall cause a system supervisory condition and shut down the ventilation system and close the associated smoke dampers as appropriate.
- D. Operation of any sprinkler system valve supervisory switch, high/low air pressure switch shall cause a system supervisory condition.

#### 3.3 TESTS

A. Provide the service of a NICET level III, competent, factory-trained engineer or technician authorized by the manufacturer of the fire alarm equipment to technically supervise and participate during all of the adjustments and tests for the system. Make all adjustments and tests in the presence of the COTR.

# EHRM Infrastructure UpgradesEHRM Infrastructure Upgrades Bancroft Architects + Engineers

10-11

- B. When the systems have been completed and prior to the scheduling of the final inspection, furnish testing equipment and perform the following tests in the presence of the COTR. When any defects are detected, make repairs or install replacement components, and repeat the tests until such time that the complete fire alarm systems meets all contract requirements. After the system has passed the initial test and been approved by the COTR, the contractor may request a final inspection.
  - Before energizing the cables and wires, check for correct connections and test for short circuits, ground faults, continuity, and insulation.
  - 2. Test the insulation on all installed cable and wiring by standard methods as recommended by the equipment manufacturer.
  - 3. Run water through all flow switches on new sprinklers zones and existing sprinkler zones which are modified under Section 21 13 13. Check time delay on water flow switches. Submit a report listing all water flow switch operations and their retard time in seconds.
  - 4. Open each alarm initiating and notification circuit to see if trouble signal actuates.
  - 5. Ground each alarm initiation and notification circuit and verify response of trouble signals.

#### 3.4 FINAL INSPECTION AND ACCEPTANCE

- A. Prior to final acceptance a minimum 30 day "burn-in" period shall be provided. The purpose shall be to allow equipment to stabilize and potential installation and software problems and equipment malfunctions to be identified and corrected. During this diagnostic period, all system operations and malfunctions shall be recorded. Final acceptance will be made upon successful completion of the "burn-in" period and where the last 14 days is without a system or equipment malfunction.
- B. At the final inspection a factory trained representative of the manufacturer of the major equipment shall repeat the tests in Article 3.3 TESTS and those required by NFPA 72. In addition the representative shall demonstrate that the systems function properly in every respect. The demonstration shall be made in the presence of a VA representative.

# 3.5 INSTRUCTION

A. The manufacturer's authorized representative shall provide instruction and training to the VA as follows:


# ${\tt EHRM} \ \ {\tt Infrastructure} \ \ {\tt UpgradesEHRM} \ \ {\tt Infrastructure} \ \ {\tt Upgrades}$

Bancroft Architects + Engineers

10-11

1. One 2-hour session to engineering staff, security police and central attendant personnel for simple demonstration and operation of the system modifications performed under this contract.

- - END - -



Pine Ridge, SD 57770

#### EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

# SECTION 31 20 11 EARTHWORK (SHORT FORM)

#### PART 1 - GENERAL

# 1.1:DESCRIPTION:

This section specifies the requirements for furnishing all equipment, materials, labor and techniques for earthwork including excavation, fill, backfill and site restoration utilizing fertilizer, seed and/or sod.

#### 1.2 DEFINITIONS:

- A. Unsuitable Materials:
  - 1. Fills: Topsoil, frozen materials; construction materials and materials subject to decomposition; clods of clay and stones larger than 75 mm (3 inches); organic materials, including silts, which are unstable; and inorganic materials, including silts, too wet to be stable.
  - 2. Existing Subgrade (except footings): Same materials as above paragraph, that are not capable of direct support of slabs, pavement, and similar items, with the possible exception of improvement by compaction, proofrolling, or similar methods of improvement.
  - 3. Existing Subgrade (footings only): Same as Paragraph 1, but no fill or backfill. If materials differ from design requirements, excavate to acceptable strata subject to Resident Engineer's approval.
- B. Earthwork: Earthwork operations required within the new construction area. It also includes earthwork required for auxiliary structures and buildings and sewer and other trenchwork throughout the job site.
- C. Degree of Compaction: Degree of compaction is expressed as a percentage of maximum density obtained by the test procedure presented in the construction drawings.
- D. The term fill means fill or backfill as appropriate.

### 1.3 RELATED WORK:

A. Materials testing and inspection during construction: Section 01 45 29, TESTING LABORATORY SERVICES. NOT USED

Pine Ridge, SD 57770

## EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- B. Safety Requirements: Section 00 72 00, GENERAL CONDITIONS, Article, ACCIDENT PREVENTION. NOT USED
- C. Protection of existing utilities, fire protection services, existing equipment, roads, and pavements: Section 01 00 00, GENERAL REQUIREMENTS.
- D. Subsurface Investigation: Section 01 00 00, GENERAL REQUIREMENTS, Article, PHYSICAL DATA.

#### 1.4 CLASSIFICATION OF EXCAVATION:

- A. Unclassified Excavation: Removal and disposal of pavements and other man-made obstructions visible on the surface; utilities, and other items including underground structures indicated to be demolished and removed; together with any type of materials regardless of character of material and obstructions encountered.
- B. Classified Excavation: Removal and disposal of all material not defined as rock.
- C. Rock Excavation:
  - 1. Solid ledge rock (igneous, metamorphic, and sedimentary rock).
  - 2. Bedded or conglomerate deposits so cemented as to present characteristics of solid rock which cannot be excavated without blasting; or the use of a modern power excavator (shovel, backhoe, or similar power excavators) of no less than 0.75 m3 (1 cubic yard) capacity, properly used, having adequate power and in good running condition.
  - 3. Boulders or other detached stones each having a volume of  $0.4~\mathrm{m3}$  (1/2 cubic yard) or more.

# 1.5 MEASUREMENT AND PAYMENT FOR EXCAVATION:

Any material that cannot be reused to backfill the excavation shall be removed to a location designated by the COR. Measurement: The unit of measurement for excavation and borrow will be the cubic yard, computed by the average end area method from cross sections taken before and after the excavation and borrow operations, including the excavation for ditches, gutters, and channel changes, when the material is acceptably utilized or disposed of as herein specified. If required by

Pine Ridge, SD 57770

## EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

COR, quantities should be computed by a Registered Professional Land Surveyor or Registered Civil Engineer, specified in Section 01 00 00, GENERAL REQUIREMENTS. The measurement will not include the volume of subgrade material or other material used for purposes other than directed. The volume of overburden stripped from borrow pits and the volume of excavation for ditches to drain borrow its, unless used as borrow material, will not be measured for payment. The measurement will not include the volume of any excavation performed prior to taking of elevations and measurements of the undisturbed grade.

# 1.6 MEASUREMENT AND PAYMENT FOR ROCK EXCAVATION (NOT EXPECTED FOR THIS PROJECT):

- A. Measurement: Cross section and measure the uncovered and separated materials, and compute quantities by the Registered Professional Land Surveyor or Registered Civil Engineer, specified in Section 01 00 00, GENERAL REQUIREMENTS. Do not measure quantities beyond the following limits:
  - 1. 300 mm (12 inches) outside of the perimeter of formed footings.
  - 2. 600 mm (24 inches) outside the face of concrete work for which forms are required, except for footings.
  - 3. 150 mm (6 inches) below the bottom of pipe and not more than the pipe diameter plus 600 mm (24 inches) in width for pipe trenches.
  - 4. The outside dimensions of concrete work for which no forms are required (trenches, conduits, and similar items not requiring forms).
- B. Payment: No separate payment shall be made for rock excavation quantities shown. The contract price and time will be adjusted for overruns or underruns in accordance with Articles, DIFFERING SITE CONDITIONS, CHANGES and CHANGES-SUPPLEMENT of the GENERAL CONDITIONS as applicable.

#### 1.7 SUBMITTALS:

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Rock Excavation Report:

#### Pine Ridge, SD 57770

#### EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- 1. Certification of rock quantities excavated.
- 2. Excavation method.
- 3. Labor.
- 4. Equipment.
- 5. Land Surveyor's or Civil Engineer's name and official registration stamp.
- 6. Plot plan showing elevations.
- C. Contractor shall submit procedure and location for disposal of unused satisfactory material. Proposed source of borrow material. Notification of encountering rock in the project. Advance notice on the opening of excavation or borrow areas. Advance notice on shoulder construction for rigid pavements.
- D. Furnish to Resident Engineer, soil samples, suitable for laboratory tests, of proposed off site or on site fill material.
- E. Qualifications of the commercial testing laboratory or Contractor's Testing facility shall be submitted.

# 1.8 APPLICABLE PUBLICATIONS:

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in the text by the basic designation only.
- B. American Nursery and Landscape Association (ANLA):
  2004......American Standard for Nursery Stock
- C. American Association of State Highway and Transportation Officials (AASHTO):
  - T99-10......Moisture-Density Relations of Soils Using a 2.5 kg (5.5 lb) Rammer and a 305 mm (12 inch) Drop
  - T180-10......Standard Method of Test for Moisture-Density

    Relations of Soils Using a 4.54-kg [10 lb]

Rammer and a 457 mm (18 inch) Drop

D. American Society for Testing and Materials (ASTM):

C33-03.....Concrete Aggregate

Pine Ridge, SD 57770

## EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

D698-e1Laboratory Compaction Characteristics of Soil		
Using Standard Effort		
D1140-00Amount of Material in Soils Finer than the No.		
200 (75-micrometer) Sieve		
D1556-00Standard Test Method for Density and Unit		
Weight of Soil in Place by the Sand-Cone Method		
D1557-09Laboratory Compaction Characteristics of Soil		
Using Modified Effort		
D2167-94 (2001)Standard Test Method for Density and Unit		
Weight of Soil in Place by the Rubber Balloon		
Method		
D2487-06Standard Classification of Soil for Engineeri		
Purposes (Unified Soil Classification System)		
Purposes (Unified Soil Classification System) D6938-10Standard Test Methods for Density of Soil and		

E. Standard Specifications of South Dakota State

Department of Transportation, latest revision.

#### PART 2 - PRODUCTS

- 2.1 MATERIALS:A. Fills: Materials approved from on site and off site sources having a minimum dry density of 1760 kg/m3 (110 pcf), a maximum Plasticity Index of 6, and a maximum Liquid Limit of 30.
- B. Granular Fill:
  - 1. Under concrete slab, granular fill shall consist of clean, poorly graded crushed rock, crushed gravel, or uncrushed gravel placed beneath a building slab with or without a vapor barrier to cut off the capillary flow of pore water to the area immediately below. Fine aggregate grading shall conform to ASTM C33 with a maximum of 3 percent by weight passing ASTM D1140, as specified in the construction drawings..
  - 2. Bedding for duct work, , crushed stone or gravel graded from 13 mm (1/2 inch) to 4.75 mm (No. 4).

Pine Ridge, SD 57770

## EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- C. Fertilizer: (5-10-5) delivered to site in unopened containers that clearly display the manufacturer's label, indicating the analysis of the contents.
- D. Seed: Grass mixture comparable to existing turf delivered to site in unopened containers that clearly display the manufacturer's label, indicating the analysis of the contents.
- E. Sod: Comparable species with existing turf. Use State Certified or State Approved sod when available. Deliver sod to site immediately after cutting and in a moist condition. Thickness of cut must be 19 mm to 32 mm (3/4 inch to 1 1/4 inches) excluding top growth. There shall be no broken pads and torn or uneven ends
- F. Requirements For Offsite Soils: Offsite soils brought in for use as backfill shall be tested for TPH, BTEX and full TCLP including ignitability, corrosivity and reactivity. Backfill shall contain less than 100 parts per million (ppm) of total hydrocarbons (TPH) and less than 10 ppm of the sum of Benzene, Toleune, Ethyl Benzene, and Xylene (BTEX) and shall not fail the TCLP test. TPH concentrations shall be determined by using EPA 600/4-79/020 Method 418.1. BTEX concentrations shall be determined by using EPA SW-846.3-3a Method5030/8020. TCLP shall be performed in accordance with EPA SW-846.3-3a Method 1311. Provide Borrow Site Testing for TPH, BTEX and TCLP from a composite sample of material from the borrow site, with at least one test from each borrow site. Material shall not be brought on site until tests have been approved by the Resident Engineer.
- G. Buried Warning and Identification Tape: Polyethylene plastic, acid- and alkali-resistant polyethylene plastic Warning tape manufactured specifically for warning and identification of buried utility lines. Provide tape on rolls, 3 inch minimum width, color coded as specific below for the intended utility with warning and identification imprinted in bold black letters continuously over the entire tape length. Warning and identification to read, "CAUTION, BURIED

ELECTRIC DUCT LINE BELOW" or similar wording. Color and printing

Pine Ridge, SD 57770

## EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

shall be permanent, Unaffected by moisture or soil. Warning tape color codes shall be as specified on the construction drawings.

Red: Electric

Η.

- I. Detectable Warning Tape for Non-Metallic Piping: Polyethylene plastictape conforming to the width, color, and printing requirements specified above. Minimum thickness of the tape shall be 0.102 mm (0.004 inch). Tape shall have a minimum strength of 10.3 MPa (1500 psi) lengthwise and 8.6 MPa (1250 psi) crosswise. Tape shall be manufactured with integral wires, foil backing, or other means of enabling detection by a metal detector when tape is buried up to 0.9 m(3 feet) deep. Encase metallic element of the tape in a protective jacket or provide with other means of corrosion protection.
- J. Detection Wire For Non-Metallic Piping: Detection wire shall be Insulated single strand, solid copper with a minimum of 12 AWG.

### PART 3 - EXECUTION

- 3.1 SITE PREPARATION: A. Clearing: Clearing within the limits of earthwork operations as described or designated by the Resident Engineer. Work includes removal of trees, shrubs, fences, foundations, incidental structures, paving, debris, trash and any other obstructions. Remove materials from the Medical Center and Cemetery Property.
- B. Grubbing: Remove stumps and roots 75 mm (3 inches) and larger diameter. Undisturbed sound stumps, roots up to 75 mm (3 inches) diameter, and nonperishable solid objects which will be a minimum of 900 mm (3 feet) below subgrade or finished embankment may be left. Cemetery Projects: do not leave material within the burial profile up to 2400 mm (8 feet) below finished grade.
- C. Trees and Shrubs: Trees and shrubs, not shown for removal, may be removed from the areas within 4500 mm (15 feet) of new construction and 2250 mm (7'-6") of utility lines if such removal is approved in advance

#### Pine Ridge, SD 57770

#### EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

by the Resident Engineer. Remove materials from the Medical Center Cemetery Property. Box, and otherwise protect from damage, existing trees and shrubs which are not shown to be removed in the construction area. Repair immediately damage to existing trees and shrubs by trimming, cleaning and painting damaged areas, including the roots, in accordance with standard industry horticultural practice for the geographic area and plant species. Building materials shall not be stored closer to trees and shrubs that are to remain, than the farthest extension of their limbs.

- D. Stripping Topsoil: Unless otherwise indicated on the drawings, the limits of earthwork operations shall extend anywhere the existing grade is filled or cut or where construction operations have compacted or otherwise disturbed the existing grade or turf. Strip topsoil as defined herein, or as indicated in the geotechnical report, from within the limits of earthwork operations as specified above unless specifically indicated or specified elsewhere in the specifications or shown on the drawings. Topsoil shall be fertile, friable, natural topsoil of loamy character and characteristic of the locality. Topsoil shall be capable of growing healthy horticultural crops of grasses. Stockpile topsoil and protect as directed by the Resident Engineer. Eliminate foreign material, such as weeds, roots, stones, subsoil, frozen clods, and similar foreign materials, larger than  $0.014~\mathrm{m}3~(1/2~\mathrm{m})$ cubic foot) in volume, from soil as it is stockpiled. Retain topsoil on the station. Remove foreign materials larger than 50 mm (2 inches) in any dimension from topsoil used in final grading. Topsoil work, such as stripping, stockpiling, and similar topsoil work, shall not, under any circumstances, be carried out when the soil is wet so that the tilth of the soil will be destroyed.
  - 2. Concrete Slabs and Paving: Score deeply or saw cut to insure a neat, straight cut, sections of existing concrete slabs and paving to be removed where excavation or trenching occurs. Extend pavement section to be removed a minimum of 300 mm (12 inches) on each side of widest part of trench excavation and insure final score lines are

Pine Ridge, SD 57770

#### EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

approximately parallel unless otherwise indicated. Remove material from the Medical Center and Cemetery Property.

E. Disposal: All materials removed from the property shall be disposed of at a legally approved site, for the specific materials, and all removals shall be in accordance with all applicable Federal, State and local regulations. No burning of materials is permitted onsite.

#### 3.2 EXCAVATION:

- A. Shoring, Sheeting and Bracing: Shore, brace, or slope to it's angle of repose banks of excavations to protect workmen, banks, adjacent paving, structures, and utilities, in compliance with OSHA requirements.
  - 1. Extend shoring and bracing to the bottom of the excavation. Shore excavations that are carried below the elevations of adjacent existing foundations.
  - 2. If the bearing of any foundation is disturbed by excavating, improper shoring or removal of shoring, placing of backfill, and similar operations, provide a concrete fill support in compliance with Specification Section 31 23 23.33, FLOWABLE FILL, under disturbed foundations, as directed by Resident Engineer, at no additional cost to the Government. Do not remove shoring until permanent work in excavation has been inspected and approved by Resident Engineer.
- B. Excavation Drainage: Operate pumping equipment as required, to keep excavations free of water and subgrades dry, firm, and undisturbed until approval of permanent work has been received from Resident Engineer. Approval by the Resident Engineer is also required before placement of the permanent work on all subgrades. When subgrade for foundations has been disturbed by water, remove the disturbed material to firm undisturbed material after the water is brought under control. Replace disturbed subgrade in trenches by mechanically tamped sand or gravel. When removed disturbed material is located where it is not possible to install and properly compact disturbed subgrade material with mechanically compacted sand or gravel, the Resident Engineer should be contacted to consider the use of flowable fill. Groundwater

#### Pine Ridge, SD 57770

## EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

flowing toward or into excavations shall be controlled to prevent sloughing of excavation slopes and walls, boils, uplift and heave in the excavation and to eliminate interference with orderly progress of construction. French drains, sumps, ditches or trenches will not be permitted within 0.9 m (3 feet) of the foundation of any structure, except with specific written approval, and after specific contractual provisions for restoration of the foundation area have been made. Control measures shall be taken by the time the excavation reaches the water level in order to maintain the integrity of the in situ material. While the excavation is open, the water level shall be maintained continuously, as specified in the construction drawings. Operate dewatering system continuously until construction work below existing water levels is complete. Submit performance records weekly.

- C. Blasting: NOT USEDD. Building Earthwork⊗
  NOT USED)
- E. Trench Earthwork:
  - 1. Utility trenches (except sanitary and storm sewer):
    - a. Excavate to a width as necessary for sheeting and bracing and proper performance of the work.
    - b. Grade bottom of trenches with bell-holes, scooped-out to provide a uniform bearing.
    - c. Support piping on suitable undisturbed earth unless a mechanical support is shown. Unstable material removed from the bottom of the trench or excavation shall be replaced with select granular material placed in layers not exceeding 150 mm (6 inches) loose thickness.
    - d. The length of open trench in advance of pipe laying shall not be greater than is authorized by the Resident Engineer.
    - e. Provide buried utility lines with utility identification tape.

      Bury tape 300 mm (12 inches) below finished grade; under pavements and slabs, bury tape 150 mm (6 inches) below top of subgrade

#### Pine Ridge, SD 57770

## EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- f. Bury detection wire directly above non-metallic piping at a distance not to exceed 300 mm (12 inches) above the top of pipe. The wire shall extend continuously and unbroken, from manhole to manhole. The ends of the wire shall terminate inside the manholes at each end of the pipe, with a minimum of 0.9 m (3 feet) of wire, coiled, remaining accessible in each manhole. The wire shall remain insulated over it's entire length. The wire shall enter manholes between the top of the corbel and the frame, and extend up through the chimney seal between the frame and the chimney seal. For force mains, the wire shall terminate in the valve pit at the pump station end of the pipe.
- g. Bedding shall be of the type and thickness shown. Initial backfill material shall be placed and compacted with approved tampers to a height of at least one foot above the utility pipe or conduit. The backfill shall be brought up evenly on both sides of the pipe for the full length of the pipe. Care shall be taken to ensure thorough compaction of the fill under the haunches of the pipe. Except as specified otherwise in the individual piping section, provide bedding for buried piping in accordance with AWWA C600, Type 4, except as specified herein.

  Backfill to top of pipe shall be compacted to 95 percent of ASTM D 698maximum density. Plastic piping shall have bedding to spring line of pipe. Provide materials as follows:
  - 1) Class I: Angular, 6 to 40 mm (0.25 to 1.5 inches), graded stone, including a number of fill materials that have regional significance such as coral, slag, cinders, crushed stone, and crushed shells.
  - 2) Class II: Coarse sands and gravels with maximum particle size of 40 mm (1.5 inches), including various graded sands and gravels containing small percentages of fines, generally granular and noncohesive, either wet or dry. Soil Types GW, GP, SW, and SP are included in this class as specified in ASTM D 2487.

Pine Ridge, SD 57770

## EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- 3) Clean, coarse-grained sand classified as specified in the construction drawings.4) Clean, coarsely graded natural gravel, crushed stone or a combination thereof identified as specified in the construction drawings.
- 2. Sanitary and storm sewer trenches ③
- NOT USED) F. Site Earthwork: Excavation shall be accomplished as required by drawings and specifications. Remove subgrade materials that are determined by the Resident Engineer as unsuitable, and replace with acceptable material. If there is a question as to whether material is unsuitable or not, the Contractor shall obtain samples of the material, under the direction of the Resident Engineer, and the materials shall be examined by an independent testing laboratory for soil classification to determine whether it is unsuitable or not. Testing of the soil shall be performed by the VA Testing Laboratory. When unsuitable material is encountered and removed, the contract price and time will be adjusted in accordance with Articles, DIFFERING SITE CONDITIONS, CHANGES and CHANGES-SUPPLEMENT of the GENERAL CONDITIONS as applicable. Adjustments to be based on meters (yardage) in cut section only.
- G. Finished elevation of subgrade shall be as follows:
  - 1. Pavement Areas bottom of the pavement or base course as applicable.
  - 2. Planting and Lawn Areas 100 mm (4 inches) below the finished grade, unless otherwise specified or indicated on the drawings.

#### 3.3 FILLING AND BACKFILLING:

A. General: Do not fill or backfill until all debris, unsatisfactory soil materials, obstructions, and deleterious materials have been removed from the excavation. Proof-roll exposed subgrades with a fully loaded dump truck. Use excavated materials or borrow for fill and backfill, as applicable. Do not use unsuitable excavated materials. Do not backfill until foundation walls have been completed above grade and adequately braced, waterproofing or dampproofing applied, and pipes coming in

#### Pine Ridge, SD 57770

#### EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

contact with backfill have been installed, and inspected and approved by Resident Engineer.

- B. Proof-rolling Existing Subgrade: Proof rolling shall be done on an exposed subgrade free of surface water (wet conditions resulting from rainfall) which would promote degradation of an otherwise acceptable subgrade. Notify the Resident Engineer a minimum of 3 days prior to proof rolling. Proof rolling shall be performed in the presence of the Resident Engineer. Rutting or pumping of material shall be undercut as directed by the Resident Engineer. Bids shall be based on the construction drawings at various locations.
- C. Placing: Place material in horizontal layers not exceeding 200 mm (8 inches) in loose depth and then compacted. Do not place material on surfaces that are muddy, frozen, or contain frost.
- D. Compaction: Use approved equipment (hand or mechanical) well suited to the type of material being compacted. Do not operate mechanized vibratory compaction equipment within 3000 mm (10 feet) of new or existing building walls without the prior approval of the Resident Engineer. Moisten or aerate material as necessary to provide the moisture content that will readily facilitate obtaining the specified compaction with the equipment used. Compact each layer as specified in the construction drawings. Backfill adjacent to any and all types of structures shall be placed and compacted to at least 90 percent laboratory maximum density for cohesive materials or 95 percent laboratory maximum density for cohesionless materials to prevent wedging action or eccentric loading upon or against the structure.
- E. Borrow Material: Borrow material shall be selected to meet the requirements and conditions of the particular fill or embankment for which it is to be used. Borrow material shall be obtained from the borrow areas shown on drawings. Unless otherwise provided in the contract, the Contractor shall obtain from the owners the right to procure material, pay royalties and other charges involved, and bear the expense of developing the sources, including rights-of-way for hauling. Borrow material from approved sources on Government-

Pine Ridge, SD 57770

## EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

controlled land may be obtained without payment of royalties. Unless specifically provided, no borrow shall be obtained within the limits of the project site without prior written approval. Necessary clearing, grubbing, and satisfactory drainage of borrow pits and the disposal of debris thereon shall be considered related operations to the borrow excavation.

F. Opening and Drainage of Excavation and Borrow Pits: The Contractor shall notify the Resident Engineer sufficiently in advance of the opening of any excavation or borrow pit to permit elevations and measurements of the undisturbed ground surface to be taken. Except as otherwise permitted, borrow pits and other excavation areas shall be excavated providing adequate drainage. Overburden and other spoil material shall be transported to designated spoil areas or otherwise disposed of as directed. Borrow pits shall be neatly trimmed and drained after the excavation is completed. The Contractor shall ensure that excavation of any area, operation of borrow pits, or dumping of spoil material results in minimum detrimental effects on natural environmental conditions.

#### 3.4 GRADING:

- A. General: Uniformly grade the areas within the limits of this section, including adjacent transition areas. Smooth the finished surface within specified tolerance. Provide uniform levels or slopes between points where elevations are indicated, or between such points and existing finished grades. Provide a smooth transition between abrupt changes in slope.
- B. Cut rough or sloping rock to level beds for foundations. In unfinished areas fill low spots and level off with coarse sand or fine gravel.
- C. Slope backfill outside the building away from the building walls for a minimum distance of 3048 mm (10 feet) at a minimum five percent (5%) slope.
- D. The finished grade shall be 150 mm (6 inches) below bottom line of windows or other building wall openings unless greater depth is shown.

Pine Ridge, SD 57770

## EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- E. Place crushed stone or gravel fill under concrete slabs on grade tamped and leveled. The thickness of the fill shall be 150 mm (6 inches), unless otherwise indicated.
- F. Finish subgrade in a condition acceptable to the Resident Engineer at least one day in advance of the paving operations. Maintain finished subgrade in a smooth and compacted condition until the succeeding operation has been accomplished. Scarify, compact, and grade the subgrade prior to further construction when approved compacted subgrade is disturbed by contractor's subsequent operations or adverse weather.
- G. Grading for Paved Areas: Provide final grades for both subgrade and base course to +/- 6 mm (0.25 inches) of indicated grades.

#### 3.5 LAWN AREAS:

- A. General: Harrow and till to a depth of 100 mm (4 inches), new or existing lawn areas to remain, which are disturbed during construction. Establish existing or design grades by dragging or similar operations. Do not carry out lawn areas earthwork out when the soil is wet so that the tilth of the soil will be destroyed. Plant bed must be approved by Resident Engineer before seeding or sodding operation begins.
- B. Finished Grading: Begin finish grading after rough grading has had sufficient time for settlement. Scarify subgrade surface in lawn areas to a depth of 100 mm (4 inches). Apply topsoil so that after normal compaction, dragging and raking operations (to bring surface to indicated finish grades) there will be a minimum of 100 mm (4 inches) of topsoil over all lawn areas; make smooth, even surface and true grades, which will not allow water to stand at any point. Shape top and bottom of banks to form reverse curves in section; make junctions with undisturbed areas to conform to existing topography. Solid lines within grading limits indicate finished contours. Existing contours, indicated by broken lines are believed approximately correct but are not guaranteed.
- C. Fertilizing: Incorporate fertilizer into the soil to a depth of 100 mm (4 inches) at a rate of 12 kg/100 m2 (25 pounds per 1000 square feet).

#### Pine Ridge, SD 57770

#### EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

- D. Seeding: Seed at a rate of 2 kg/100 m2 (4 pounds per 1000 square feet) and accomplished only during periods when uniform distribution may be assured. Lightly rake seed into bed immediately after seeding. Roll seeded area immediately with a roller not to exceed 225 kg/m (150 pounds per foot) of roller width.
- E. Sodding: Topsoil shall be firmed by rolling and during periods of high temperature the topsoil shall be watered lightly immediately prior to laying sod. Sod strips shall be tightly butted at the ends and staggered in a running bond fashion. Placement on slopes shall be from the bottom to top of slope with sod strips running across slope. Secure sodded slopes by pegging or other approved methods. Roll sodded area with a roller not to exceed 225 kg/m (150 pounds per foot) of the roller width to improve contact of sod with the soil.
- F. Watering: The Resident Engineer is responsible for having adequate water available at the site. As sodding is completed in any one section, the entire sodded area shall be thoroughly irrigated by the contractor, to a sufficient depth, that the underside of the new sod pad and soil, immediately below sod, is thoroughly wet. Resident Engineer will be responsible for sod after installation and acceptance.

#### 3.6 DISPOSAL OF UNSUITABLE AND EXCESS EXCAVATED MATERIAL:

- A. Disposal: Remove surplus satisfactory soil and waste material, including unsatisfactory soil, trash, and debris, and legally dispose of it off Medical Center and Cemetery property.
- B. Place excess excavated materials suitable for fill and/or backfill on site where directed.
- C. Remove from site and dispose of any excess excavated materials after all fill and backfill operations have been completed.
- D. Segregate all excavated contaminated soil designated by the Resident Engineer from all other excavated soils, and stockpile on site on two 0.15 mm (6 mil) polyethylene sheets with a polyethylene cover. A designated area shall be selected for this purpose. Dispose of excavated contaminated material in accordance with State and Local requirements.

Pine Ridge, SD 57770

# EHRM Infrastructure Upgrades EHRM Infrastructure Upgrades

Bancroft Architects + Engineers

# 3.7 CLEAN-UP:

Upon completion of earthwork operations, clean areas within contract limits, remove tools, and equipment. Provide site clear, clean, free of debris, and suitable for subsequent construction operations. Remove debris, rubbish, and excess material from the Medical Center and Cemetery Property.

- - - E N D - - -