

SOLICITATION #: 36C77625B0014
PROJECT NAME: Fargo EHRM Tier 2
TECHNICAL QUESTIONS AND VA RESPONSE TRACKING SHEET

Item No.	QUESTION	GOVERNMENT RESPONSE
	ROUND 3 Q&A:	
152	<p>Amendment 2 Q&A #18 indicates to reuse existing doors and frames for opening BE-98A and BE-98B. New door frame for opening BE-98B requires a much larger door frame that needs to accommodate louvers, a blank off panel per keynote 3 and intake hood keynote 16 per drawing AS-B1-204 and AS-B1-301 therefore reusing the frame is not possible. Based on elevation drawing AS-B1-301 it appears operable windows are above the door and louver.</p> <p>Which is correct, glazing above the door and adjacent louver, or intake hood and blank off panel?</p> <p>Sizes are needed with a door/frame and hardware schedule for accurate pricing.</p>	<p>Note #3 also specifies “Blast Mitigation Components”. Therefore no Glazing in these openings.</p> <p>No additional Drawings or Schedules are currently available.</p>
153	<p>Also door BE-98A has the incorrect swing to reuse the door or the frame.</p> <p>Will a door frame and hardware schedule be provided for both openings?</p>	<p>Reversing Door BE-98A gives the new swing (interior door so swing direction doesn’t matter for safety).</p> <p>No additional Drawings or Schedules are currently available.</p>
154	<p>Ref drawing AS-601- Will hardware set numbers be provided for 6 of the 4th floor door openings that appear in the schedule without hardware set numbers?</p>	<p>Sargent 8251 Storeroom Deadbolt</p>