

BUILDING 115 - EHRM INFRASTRUCTURE UPGRADES

St. Cloud VA Health Care System Main Campus, St. Cloud, Minnesota





ROOM ICRA SCHEDULE CAI BLDG NAME / FUNCTION CONSTRUCTION PROJECT ACTIVITY INFECTION CONTROL RISK GROUP CONTROL PROCEDURE CLASS LEVEL NO. ROOM NAME FIRST FLOOR 107 TELECOM ROOM MENTAL HEALTH BEDS SEE GENERAL NOTES SHEET FOR CONSTRUCTION INFECTION CONTROL RISK ASSESSMENT (ICRA) DESCRIPTIONS. TYPE, GROUP AND CLASS SELECTED TO BEST OF DESIGN TEAM'S KNOWLEDGE. FINAL DETERMINATION BY THE VA WILL BE MADE AT A LATER DATE.

LOCATION, WHERE APPROVED BY THE VA FOR USE IN RISK TYPE B.


UPGRADE TO 1 HOUR RATED PARTITION WHEN DIRECTED BY THE VA

INFECTION CONTROL RISK ASSESSMENT (ICRA) LEGEND LIMITS OF CONSTRUCTION 1 HOUR FIRE RATED ICRA / CONSTRUCTION BARRIER LOCATION, AND DOOR, WHERE SHOWN TEMPORARY NON-RATED (PLASTIC SHEETING) CONSTRUCTION BARRIER


CONSULTANT REVISION DATE Omaha, NE 68134 www.specializedeng.com

ARCHITECT/ENGINEER OF RECORD ANDERSON 13605 1st Ave. N. #100 Plymouth, MN 55441 P 763.412.4000 | F 763.412.4090 | ae-mn.com

Anderson Engineering of Minnesota, LLC | Proj # 16305







VA MEDICAL CENTER ST.CLOUD, MN 56303

FULLY SPRINKLERED






DE1 PREPARE WALL FOR PLYWOOD BACKBOARD INSTALLATION AND EHRM REQUIREMENTS, SEE FLOOR PLAN AND TELECOM DRAWINGS

ALL FOUR PERIMETER WALL PARTITIONS APPLY 4' BY 8' AC GRADE 3/4" TRADE SIZE FIRE RATED PLYWOOD BACKBOARD FINISHED WITH HIGH-GLOSS WHITE PAINT OVER TWO COATS OF FIRE RESISTANT PAINT FOR SERVICE PROVIDER / SECURITY / VIDEO / ET CETERA. DO NOT PAINT


REFLECTED CEILING PLAN KEYED NOTES

RC1 LED LIGHTING, SEE ELECTRICAL. IN FRONT OF AND BEHIND CABINET ROWS PROVIDE 500 LUMENS IN HORIZONTAL AND 200 LUMENS IN THE VERTICAL AT 3 FT AFF. OPERATED BY MOTION SENSOR PER CABINET


- ALL EXISTING CONDITIONS MUST BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO DEMOLITION OR CONSTRUCTION. EXISTING CONDITIONS THAT DIFFER FROM THOSE SHOWN MUST BE BROUGHT TO THE ATTENTION OF THE C.O.R. TO INFORM THE ARCHITECTS AND
- THE INFORMATION SHOWN ON THE DRAWINGS IS BASED ON DRAWINGS AND PHOTOGRAPHS PROVIDED BY THE C.O.R. COMBINED WITH OBSERVATIONS AND SURVEYED DATA FROM THE ARCHITECTS AND
- SEE CIVIL, STRUCTURAL, TELECOM, ELECTRICAL, MECHANICAL, AND PLUMBING DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL
- PORTABLE FIRE EXTINGUISHERS (CO2 OR HALOGENATED TYPE AS DETERMINED BY THE VA) WITH WALL MOUNT BRACKET AND CODE REQUIRED SIGNAGE SHALL BE PROVIDED BY THE CONTRACTOR WITHIN

























FULLY SPRINKLERED

115

VA MEDICAL CENTER ST.CLOUD, MN 56303





5 9

A. REFER TO GENERAL DEMOLITION NOTES ON SHEET T000 FOR ADDITIONAL DEMOLITION SCOPE.

SHEET NOTES:

GENERAL NOTES:

1. EXISTING TELECOMMUNICATIONS CAGE AND RACK SHALL BE INCLUDED WITHIN THE SCOPE OF DEMOLITION. EXISTING CABLING AND ASSOCIATED OUTLETS SHALL BE REMOVED AND REPLACED 1 FOR 1 AND REFED FROM DISTRIBUTION EQUIPMENT LOCATED WITHIN THE NEW TELECOMMUNICATIONS ROOM. REFER TO GENERAL CABLING NOTES FOR APPROXIMATE QUANTITIES. REFER TO NEW WORK PLANS FOR SERVING COMMUNICATIONS ROOM LOCATION AND NEW CABLING ROUTES.

RELOCATION COUNT ARE THE NEW OR RELOCATED CABLES TO BE FED FROM THE SPACE. THE FINAL

CONSULTANT Omaha, NE 68134 www.specializedeng.com

REVISION

ARCHITECT/ENGINEER OF RECORD ANDERSON 13605 1st Ave. N. #100 Plymouth, MN 55441 P 763.412.4000 | F 763.412.4090 | ae-mn.com

Anderson Engineering of Minnesota, LLC | Proj # 16305







KSB

FULLY SPRINKLERED

115


VA MEDICAL CENTER ST.CLOUD, MN 56303





GENERAL NOTES: A. REFER TO GENERAL NOTES ON SHEET T000 FOR ADDITIONAL SCOPE.

> SHEET NOTES: PROVIDE JUNCTION BOX TO CONNECT EXISTING FIBER CONDUIT ENTRY TO EXTEND CONDUIT PATHWAY TO THE NEW TELECOM ROOM.



1 2 8

CONSULTANT

Omaha, NE 68134


REVISION

Phone: 402.991.5520

www.specializedeng.com

ARCHITECT/ENGINEER OF RECORD ANDERSON 13605 1st Ave. N. #100 Plymouth, MN 55441 P 763.412.4000 | F 763.412.4090 | ae-mn.com

Anderson Engineering of Minnesota, LLC | Proj # 16305



FIRST FLOOR PLAN -TELECOMMUNICATIONS

EHRM INFRASTRUCTURE

FULLY SPRINKLERED

BUILDING No 115


LOCATION

VA MEDICAL CENTER

ST.CLOUD, MN 56303

03/30/2022 KSB SSK 115-TN110





5 BICSI ID # 346555

Expires 12-31-23

Note an M. Timm

13605 1st Ave. N. #100 Plymouth, MN 55441

P 763.412.4000 | F 763.412.4090 | ae-mn.com

Anderson Engineering of Minnesota, LLC | Proj # 16305

10360 Ellison Circle Omaha, NE 68134 Phone: 402.991.5520

www.specializedeng.com

Administration

Health Care System

St. Cloud VA

BUILDING No 115


LOCATION
VA MEDICAL CENTER
ST.CLOUD, MN 56303


CHECKED BY DRAWN DRAWING NO. 115-TN210


FULLY
SPRINKLERED ______DWG. OF___

1 2 9 10


REVISION







1 2 8



GENERAL NOTES:

A. REFER TO GENERAL NOTES ON SHEET T000 FOR ADDITIONAL SCOPE.


SHEET NOTES:

1. IF NO ACCESS CONTROL PANEL IS PRESENT IN THE TR, PROVIDE A NEW ACCESS CONTROL PANEL TO BE INSTALLED IN THE TELECOM ROOM. THE CARD READER AND KEYPAD FOR THIS ROOM TO BE WIRED TO THE NEW ACCESS CONTROL PANEL. EXISTING CARD READERS AND KEYPADS WILL BE MOVED TO THE NEW CONTROL PANEL UNDER A DIFFERENT PROJECT.

CABLING NOTE:

CABLING NOTES: A. THE EXISTING CABLE COUNT ARE THE CABLES CURRENTLY PRESENT IN THE SPACE. THE CABLE RELOCATION COUNT ARE THE NEW OR RELOCATED CABLES TO BE FED FROM THE SPACE. THE FINAL CABLE COUNT ARE THE CABLES THAT WILL BE PRESENT IN THE SPACE AT THE COMPLETION OF THE PROJECT.

- DATA (CAT6): 0 DATA (CAT5e): 94
- DATA (CAT5): 0
- DATA (CAT3): 0
- CABLE RELOCATION COUNT DATA (CAT6): 0 DATA (CAT5e): 0
- DATA (CAT5): 0 DATA (CAT3): 0
- EXISTING CABLE TO REMAIN DATA (CAT6): 0
- DATA (CAT5e): 0 DATA (CAT5): 0
- DATA (CAT3): 0
- FINAL CABLE COUNT DATA (CAT6A): 94 DATA (CAT6): 0



REVISION


NOTES:

1. REFER TO NEW WORK PLAN FOR RACK LOCATIONS.

- 2. COORDINATE EXACT RACK COUNT AND LOCATION WITH OWNER PRIOR TO PERMANENT INSTALLATION. 3. SEE PROJECT SPECIFICATIONS FOR ADDITIONAL RACK COMPONENTS. 4. RACK ELEVATION SHOWS A FULLY CONFIGURED SAMPLE RACK. CONTRACTOR TO PROVIDE REQUIRED EQUIPMENT TO
- SUPPORT THE FINAL DATA COUNT FROM THE ENLARGED NEW SHEET. (NOT TO EXCEED 288 PORTS PER RACK). 5. COORDINATE FINAL RACK COMPONENT LAYOUT WITH OWNER'S IS/IT REPRESENTATIVE.
- 6. CONTRACTOR IS RESPONSIBLE FOR FINAL CABLE COUNT, QUANTITY OF PATCH PANELS, SWITCHES, FIBER ENCLOSURES, BLANKING PANELS, CABLE MANAGEMENT, AND MOUNTING HARDWARE NOT MARKED AS "OIT PROVIDED". 7. PUNCHDOWN COPPER BACKBONES ON RACK MOUNT PATCH PANELS. TERMINATE ONE (1) PAIR PER PATCH PANEL PORT.

COMMUNICATIONS - TYPICAL ONE RACK ELEVATION WITH RACK MOUNT UPS - TR 107

NOT TO SCALE



ENLARGED PLAN - TR 107 - TELECOM - CABLE TRAY AND DATA

ENLARGED PLANS -

TELECOMMUNICATIONS

STAMP

03/30/2022

SSK DRAWING NO. 115-TN400 KSB FULLY SPRINKLERED VA MEDICAL CENTER ST.CLOUD, MN 56303

PROJECT TITLE

EHRM INFRASTRUCTURE

UPGRADES

BUILDING No 115

U.S. Department of Veterans Affairs Veterans Health Administration St. Cloud VA Health Care System




ARCHITECT/ENGINEER OF RECORD ANDERSON 13605 1st Ave. N. #100 Plymouth, MN 55441

P 763.412.4000 | F 763.412.4090 | ae-mn.com

Anderson Engineering of Minnesota, LLC | Proj # 16305




KEYNOTES: # PROVIDE ELECTRICAL CONNECTION TO CONDENSING UNIT, AS REQUIRED. COORDINATE FINAL LOCATION AND CONNECTION REQUIREMENTS WITH MECHANICAL.




5 9

CONSULTANT 100% CD 03/30 Phone: 402.991.5520 DATE REVISION Omaha, NE 68134 www.specializedeng.com

ARCHITECT/ENGINEER OF RECORD ANDERSON 13605 1st Ave. N. #100 Plymouth, MN 55441 P 763.412.4000 | F 763.412.4090 | ae-mn.com Anderson Engineering of Minnesota, LLC | Proj # 16305







FULLY SPRINKLERED







KEYNOTES: # COORDINATE FINAL LOCATION OF RECEPTACLE L21-20R WITH TELECOM CONTRACTOR. PROVIDE 3/4"C-4#12, 1#12 GND TO PANEL FOR EACH RECEPTACLE. PROVIDE EATON BLADEUPS, 5KW, 120/208V, 3-PHASE,4-WIRE RACK MOUNTED UPS FOR EACH RACK TOWER. PROVIDE APC#AP8861 RPDU RACK PDU 2G WITH L21-20P CORD. (120/208V, 3-PHASE, 20A, ZERO U, 5.7 KW, 208V, (36) C13 (6) C19 (2) 5-20R OUTLETS. PROVIDE TWO PER RACK, MOUNTED PER MANUFACTURER'S REQUIREMENTS. INDOOR UNIT TO BE POWERED BY OUTDOOR UNIT. COORDINATE EXACT LOCATION WITH VERIFY EXACT BREAKER LOACTION WITH


SPACE IN PANEL.


5 9

EXISTING PANEL 115-EC1-1 MOUNTING: SURFACE MAIN: 100 A MCB **ENCLOSURE:** NEMA PB 1 **SOLID NEUTRAL VOLTS:** 120/208 Wye FED FROM: TF-115-EMC1-1 **GROUND BUS** PHASE: 3 WIRE: 4 LOCATION: SCCR: 65 kA ISC UNKNOWN 0.00 kA WIRE SIZE OCPD OCPD WIRE SIZE E CKT CKT E LOAD DESCRIPTION G N H P AMPS LOAD DESCRIPTION NO. Y 1.67 0 2 20 A CU-1 20 A 3 1.67 37 **L21-20R Total Load:** 1.67 kVA 1.67 kVA 1.67 kVA Total Amps: 13.89 13.89 13.89 LOAD SUMMARY CONNECTED LOAD | DEMAND FACTOR | ESTIMATED DEMAND LOAD CLASSIFICATION TOTALS* 100.00% TOTAL CONNECTED LOAD: TOTAL ESTIMATED DEMAND LOAD: 5 kVA TOTAL CONNECTED AMPS: TOTAL ESTIMATED DEMAND AMPS: 13.9 A *TOTAL DEMAND CALCS SUBTRACT ANY REDUNDANT LOAD AND THE SMALLER OF ANY NONCOINCIDENT HVAC LOADS. THIS CALC IS DONE AT EACH PANEL **CIRCUIT KEY NOTES:**











PROJECT TITLE

EHRM INFRASTRUCTURE
UPGRADES

DATE: 03/30
PLOT SCA
PROJECT TITLE


03/30
PLOT SCA

TBD GJL

FULLY SPRINKLERED

115

VA MEDICAL CENTER ST.CLOUD, MN 56303






FIELD VERIFICATION NOTES

- THE HVAC CONTRACTOR SHOULD VISIT THE SITE <u>PRIOR TO BID</u> TO FIELD VERIFY ALL EXISTING CONDITIONS WHICH MAY AFFECT THEIR BID. THE FOLLOWING ITEMS SHALL BE VERIFIED:
- A. EXACT PLACEMENT, SIZE, CAPACITY, MANUFACTURER AND AND CONDITION OF ALL EXISTING HVAC EQUIPMENT WITHIN SCOPE OF WORK, WHETHER EXPLICITLY SHOWN OR NOT.
- B. SIZE AND LOCATION OF ALL EXISTING DUCTWORK.
- C. SIZE AND LOCATION OF ALL EXISTING GRILLES, REGISTERS AND DIFFUSERS.
- D. SIZE AND LOCATION OF EXISTING THERMOSTATIC CONTROL DEVICES
- E. SIZE AND LOCATION OF EXISTING PLUMBING AND HYDRONIC PIPING.
- 2. ALL REFERENCES ON THESE DRAWINGS TO EXISTING EQUIPMENT, DUCTWORK, DIFFUSERS, THERMOSTATS, AND PIPING ARE FOR REFERENCE ONLY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY ALL THESE ITEMS PRIOR TO THEIR BID AND INCLUDE IN THEIR BID ANY AND ALL AMOUNTS REQUIRED TO ACCOMMODATE EXISTING CONDITIONS.
- 3. ANY DISCREPANCIES WHICH MAY AFFECT CONTRACTORS BID SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER AND ARCHITECT FOR DIRECTION


KEYNOTES 1/115-M101: #

- REMOVE AND DISPOSE OF EXISTING DRIP PANNED 3" HYDRONIC HEATING PIPE AS SHOWN. PREPARE FOR RECONNECTION.
- REMOVE AND DISPOSE OF EXISTING SUPPLY AIR DIFFUSER.
- REMOVE AND DISPOSE OF EXISTING RETURN AIR GRILLE. CAP DUCT.
- REMOVE AND DISPOSE OF EXISTING THERMOSTAT AND ASSOCIATED WIRING.
- REMOVE AND DISPOSE OF 3/4" DRAIN TO FLOOR.




1 FIRST FLOOR DEMOLITION - MECHANICAL - EXIST 107


1 2 8








License Number: MN#





FULLY SPRINKLERED



U.S. Department of Veterans Affairs Veterans Health Administration St. Cloud VA Health Care System

FIELD VERIFICATION NOTES

- 1. THE HVAC CONTRACTOR SHOULD VISIT THE SITE **PRIOR TO BID** TO FIELD VERIFY ALL EXISTING CONDITIONS WHICH MAY AFFECT T HEIR BID. THE FOLLOWING ITEMS SHALL BE VERIFIED:
- A. EXACT PLACEMENT, SIZE, CAPACITY, MANUFACTURER AND AND CONDITION OF ALL EXISTING HVAC EQUIPMENT WITHIN SCOPE OF WORK, WHETHER EXPLICITLY SHOWN OR NOT.
- B. SIZE AND LOCATION OF ALL EXISTING DUCTWORK.
- C. SIZE AND LOCATION OF ALL EXISTING GRILLES, REGISTERS AND DIFFUSERS.
- D. SIZE AND LOCATION OF EXISTING THERMOSTATIC CONTROL DEVICES
- E. SIZE AND LOCATION OF EXISTING PLUMBING AND HYDRONIC PIPING.
- 2. ALL REFERENCES ON THESE DRAWINGS TO EXISTING EQUIPMENT, DUCTWORK, DIFFUSERS, THERMOSTATS, AND PIPING ARE FOR REFERENCE ONLY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY ALL THESE ITEMS PRIOR TO THEIR BID AND INCLUDE IN THEIR BID ANY AND ALL AMOUNTS REQUIRED TO ACCOMMODATE EXISTING CONDITIONS.
- 3. ANY DISCREPANCIES WHICH MAY AFFECT CONTRACTORS BID SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER AND ARCHITECT FOR DIRECTION


KEYNOTES, 2/115-M201:

5 9

- ROUTE REFRIGERANT PIPING FROM AIR COOLED CONDENSING UNIT TO RM 108AC UNIT. FIELD COORDINATE EXACT ROUTING REQUIREMENTS.
- PROVIDE NEW CONDENSING UNIT ON GRADE. PROVIDE CONCRETE PAD. REFER TO REFRIGERANT PIPING DETAIL 1/0-GM400 AND PAD MOUNTING DETAIL

KEYNOTES, 1/115-M201:

- REROUTE AND RECONNECT EXISTING 3" F
- . REROUTE AND RECONNECT EXISTING 3" HYDRONIC HEATING PIPE FIELD VERIFY EXACT REQUIREMENTS.
- 2. PROVIDE NEW SPLIT SYSTEM AC UNIT.
- ROUTE REFRIGERANT PIPING TO NEW AIR-COOLED CONDENSING UNIT LOCATED AT EAST EXTERIOR OF BUILDING. SEE 2/115-M201.
- 4. ROUTE 1" PUMPED CONDENSATE PIPING TO FLOOR DRAIN IN MECHANICAL ROOM 159, APPROXIMATELY 30 FT NORTH. FIELD COORDINATE FINAL ROUTING.
- 5. PROVIDE NEW THERMOSTAT.
- PROVIDE NEW FIRE-SPRINKLER HEAD AND BRANCH PIPE. CONNECT TO SPRINKLER MAIN IN CORRIDOR. FIELD VERIFY REQUIREMENTS.



PORT PAN CONDENSATE PRING IN ROOM

DRIP PAN CONDENSATE PRING IN ROOM

CORRIDOR

107

CORRIDOR

107

CORRIDOR

107

CORRIDOR

104

1 FIRST FLOOR - MECHANICAL



115

VA MEDICAL CENTER ST.CLOUD, MN 56303

100% CD 03/30
No REVISION DATE

SPECIALIZED ENGINEERING SOLUTIONS

10360 Ellison Circle Omaha, NE 68134

Phone: 402.991.5520 www.specializedeng.com

ARCHITECT/ENGINEER OF RECORD

AND ERSON

13605 1st Ave. N. #100 Plymouth, MN 55441
P 763.412.4000 | F 763.412.4090 | ae-mn.com

Anderson Engineering of Minnesota, LLC | Proj # 16305

I hereby certify that this plan, specification or report was prepared by me or under my direct supervision and that I am a duly Licensed Engineer under the laws of the State of Minnesota.

Name:

Date: 03/30/2022

License Number: MN#

FIRST FLOOR - MECHANICAL

PROJECT TITLE

EHRM INFRASTRUCTURE
UPGRADES

PROJECT NO.
656-21-2

RDL DJC

FULLY SPRINKLERED



