

DRAWING INDEX

VOLUME 1

GENERAL

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 00-GI-000.1 through 00-GI-008.

CIVIL

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets C0001 through C0017.

STRUCTURAL

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 145-SF-100 and 296-SF-100.

ARCHITECTURAL - DEMOLITION

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 53-AD-201 through 296-AD-201.

ARCHITECTURAL - NEW CONSTRUCTION

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 40-AE-201 through 296-AE-501.

VOLUME 1, CONTINUED

MECHANICAL GENERAL

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets MG-001 through MG-004.

MECHANICAL DEMOLITION

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 053-MD-011 through T296-MD-011.

MECHANICAL

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 053-MH-011 through T296-MH-011.

END OF VOLUME 1

VOLUME 2

GENERAL

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 00-GI-000.2 and 00-GI-001.

TELECOMMUNICATIONS DEMOLITION

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 040-TD-011 through T296-TD-011.

END OF VOLUME 2

VOLUME 2, CONTINUED

TELECOMMUNICATIONS REMODEL

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 040-TN-011 through T296-TN-011.

GENERAL TELECOM NOTES

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets TK-001 through TS-001.

END OF VOLUME 2

VOLUME 3

GENERAL

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 00-GI-000.3 and 00-GI-001.

ELECTRICAL DEMOLITION

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 040-ED-011 through T296-ED-011.

ELECTRICAL REMODEL

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets EK-001 through EK-014.

Table with 2 columns: SHEET NO., SHEET NAME. Includes sheets 040-EP-011 through T296-EP-011.

END OF VOLUME 3

FLOOR PLAN NOTES

- 1. REFER TO STRUCTURAL, MECHANICAL, AND ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION...
2. PROVIDE ALL BACKING FOR MILLWORK, GRAB BARS, AND ANY AND ALL WALL MOUNTED EQUIPMENT OR ACCESSORIES...
3. ALL DIMENSIONS ARE FROM STRUCTURAL OR UNFINISHED FACE OF STUD, UNLESS OTHERWISE NOTED...
4. PROVIDE A SMOOTH AND LEVEL FINISH FLOOR, TYP. PATCH AND REPAIR ALL INCONSISTENCIES IN FLOOR ELEVATIONS...
5. PATCH AND REPAIR ANY / ALL WALL SURFACES AS REQUIRED TO PROVIDE SUITABLE SUBSTRATE FOR FINISHES...
6. REFER TO DOOR AND FRAME SCHEDULE FOR DOORS REQUIRING ADA ACCESS CONTROL...
7. PROVIDE ACOUSTICAL SEALANT AROUND WALL EDGES, TOP AND BOTTOM, AND PENETRATIONS, AND INSTALL PUTTY PADS AROUND ELECTRICAL BOXES WHERE PARTITION CONTAINS ACOUSTICAL INSULATION...
8. ALL TELECOMMUNICATION ROOMS ARE TO HAVE EXPOSED STRUCTURE UNLESS NOTED OTHERWISE, NO CEILINGS SPECIFIED.

DEMOLITION NOTES


- 1. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FAMILIARIZE HIMSELF/ HERSELF WITH THE SCOPE OF WORK.
2. THE DEMOLITION NOTES PROVIDE A GENERAL DESCRIPTION OF THE ITEMS AND AREAS REQUIRING REMOVAL. THE CONTRACTOR SHALL FIELD VERIFY ACTUAL QUANTITIES AND LOCATIONS OF ALL INDICATED ITEMS AS NECESSARY TO COMPLETE THE SCOPE OF WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
3. COORDINATE WITH OWNER FOR ANY EQUIPMENT TO BE SALVAGED, UNLESS SPECIFICALLY SCHEDULED FOR REUSE. DEMOLISHED MATERIALS SHALL BECOME THE POSSESSION OF THE CONTRACTOR AND SHALL BE IMMEDIATELY REMOVED FROM THE SITE.
4. REMOVE MATERIALS FROM SITE AND DISPOSE OF IN A LEGAL AND ENVIRONMENTALLY FRIENDLY MANNER PER VA GUIDELINES AT NO ADDITIONAL EXPENSE TO OWNER.
5. DEBRIS FROM THE DEMOLITION SHALL NOT BE ALLOWED TO ACCUMULATE WITHIN THE BUILDING OR ON THE SITE. ALL DEBRIS IS TO BE REMOVED, AT MINIMUM ONCE PER SHIFT DURING THE DESIGNATED TIMES.
6. REMOVE FROM SITE ANY CONTAMINATED, VERMIN INFESTED, OR DANGEROUS MATERIALS ENCOUNTERED AND DISPOSE OF BY SAFE MEANS SO AS NOT TO ENDANGER HEALTH OF WORKERS AND PUBLIC.
7. BURNING OF MATERIALS ON SITE IS NOT PERMITTED.
8. CLEAN-UP: MUST MEET GOVERNING DUST CONTROL CODES AND STANDARDS.
9. NOTIFY AFFECTED UTILITY COMPANIES BEFORE STARTING WORK AND COMPLY WITH THEIR REQUIREMENTS.
10. PREVENT MOVEMENT OR SETTLEMENT OF ADJACENT STRUCTURES. PROVIDE BRACING AND SHORING.
11. CARRY OUT DEMOLITION WORK TO CAUSE AS LITTLE INCONVENIENCE TO ANY ADJACENT OCCUPIED BUILDING OR SITE AS POSSIBLE AND WITH MINIMUM INTERFERENCE TO PUBLIC OR PRIVATE ACCESSES. MAINTAIN PROTECTED EGRESS AND ACCESS AT ALL TIMES.
12. CONTRACTOR SHALL PROVIDE TEMPORARY DUST AND CONSTRUCTION SEPARATION WALLS AS REQUIRED TO SHIELD THE PUBLIC FROM NOISE, DUST, WEATHER, AND OTHER HAZARDS THAT MAY BE EXPOSED AS A RESULT OF THE DEMOLITION WORK. SEE SPECIFICATION SECTION 01 35 26 FOR DETAILS AND DEMOLITION DRAWINGS FOR LOCATIONS.
13. PERFORM CUTTING OF EXISTING CONCRETE AND MASONRY WITH SAWS AND CORE DRILLS. DO NOT USE JACK-HAMMERS EXCEPT WHERE PERMITTED AND APPROVED BY C.O.R..
14. BREAK CONCRETE AND MASONRY INTO SECTIONS LESS THAN 3 FEET IN ANY DIMENSION.
15. CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO INSURE EXISTING STRUCTURAL ELEMENTS REMAIN UNDAMAGED THROUGHOUT CONSTRUCTION, UNLESS SPECIFICALLY NOTED ON DEMOLITION PLAN. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO IDENTIFY AND PROVIDE ANY SHORING, BRACING, OR TEMPORARY STRUCTURE, AND TO COORDINATE WITH STRUCTURAL ENGINEER AS REQUIRED.
16. ALL PUBLIC UTILITIES ARE TO REMAIN IN OPERATION THROUGHOUT CONSTRUCTION. CONTRACTOR TO COORDINATE ANY TEMPORARY SERVICES REQUIRED TO MAINTAIN BUSINESS OPERATIONS WITH THE C.O.R..
17. SEE ENGINEERING DRAWINGS FOR DUCTWORK, DIFFUSER, PLENUM BOX, ETC. DEMOLITION AND/OR PROTECTION. COORDINATE WITH MECHANICAL ENGINEER. ANY EARTHWORK REQUIRES A THIRD PARTY LOCATE.
18. FIRE SAFETY MUST BE MAINTAINED FOR ALL PERSONNEL WORKING ON THE FLOOR. ALL FIRE STAIRS, ALARMS, SPEAKERS, ETC. MUST REMAIN ACCESSIBLE AND OPERABLE AT ALL TIMES. CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT THIS EQUIPMENT. IMMEDIATELY NOTIFY C.O.R., BUILDING SECURITY, AND BUILDING MANAGER OF DAMAGED OR DISABLED SYSTEMS AND REPAIR OR REPLACE DAMAGED SYSTEMS IMMEDIATELY AS DIRECTED AND TO THE SATISFACTION OF THE C.O.R.. RELOCATION OF SMOKE DETECTORS, PUBLIC ADDRESS SPEAKERS AND FIRE ALARM EQUIPMENT, NECESSITATED BY NEW CONSTRUCTION, SHALL BE ACCOMPLISHED AS A FIRST PRIORITY, AND PER THE PLANS.
19. IF ANY QUESTIONS ARISE AS TO THE REMOVAL OF ANY MATERIAL, CLARIFY THE POINT IN QUESTION WITH THE C.O.R. BEFORE PROCEEDING. IMMEDIATELY STOP WORK IF HAZARDOUS MATERIALS ARE FOUND AND CONTACT THE C.O.R..
20. SEE TELECOMMUNICATION DRAWINGS FOR REMOVAL OF ANY EQUIPMENT, CABLING SWITCHES, AND CONDUIT PERTAINING TO DATA/COMMUNICATIONS AND TELEPHONE. VERIFY WITH TELEPHONE COMPANIES' SERVICE OWNER OR TENANT DATA/COMMUNICATIONS REPRESENTATIVE AS REQUIRED TO PREVENT NEW CONSTRUCTION DELAYS.
21. PROVIDE FIRE PROOFING REPAIR AS REQUIRED, TO THE ORIGINAL RATING WHERE CONSTRUCTION TRADED REMOVE EXISTING FIRE PROOFING. REPAIR ANY DAMAGE OR PENETRATIONS IN RATED ASSEMBLIES TO CONFORM TO THEIR ORIGINAL LISTING REQUIREMENTS AND TO MAINTAIN FIRE PROTECTION AND SEPARATION AS ORIGINALLY DESIGNED.
22. AT COMPLETION OF DEMOLITION WORK, THE CONSTRUCTION AREA(S) SHALL BE LEFT IN CLEAN AND ORDERLY CONDITION. ALL DEBRIS AND MISCELLANEOUS MATERIAL SHALL BE REMOVED.
23. CONTRACTOR SHALL BE RESPONSIBLE FOR PATCHING AND/OR REPAIRING ANY AND ALL DAMAGE CAUSED BY OR IN CONJUNCTION WITH THE "WORK". REFINISH TO MATCH EXISTING ADJACENT FINISH, OR AS NOTED HEREIN.
24. FOR AREAS NOT IN DEMOLITION SCOPE OF WORK, PROTECT AS REQUIRED. ALL SURFACES, EQUIPMENT, FIXTURES AND HARDWARE DURING DEMOLITION AND/OR CONSTRUCTION.
25. PRIOR TO DEMOLITION, INVESTIGATE WALLS FOR CONCEALED PIPING AND/OR OTHER UTILITIES OR SERVICES AND INFORM THE C.O.R. OF ANY CONDITION NOT DOCUMENTED IN CONTRACT DRAWINGS. DEMO DESIGNATED WALL BASES, WALL FRAMING, BATT INSULATION AND GYPSUM BOARD. DEMO CONDUITS AND RECEPTACLES. REFERENCE ELECTRICAL DEMO PLAN FOR ADDITIONAL INFORMATION.
26. ALL EXISTING DIRECTIONAL SIGNAGE TO BE REMOVED UNLESS NOTED OTHERWISE.
27. WHERE NOTED, REMOVE FLOORING DOWN TO TOP OF CONC. SLAB, INCLUDING ADHESIVES, TRANSITION STRIPS, AND OTHER ASSOCIATED ELEMENTS, TYP., UNLESS NOTED OTHERWISE. PREPARE REMAINING SURFACES TO RECEIVE NEW FINISHES.

INFECTION CONTROL NOTES

- 1. PRESSURE INDICATOR MUST BE AT -0.01 OR MORE NEGATIVE PRESSURE (VERIFY TWICE A DAY IN WRITING) AND SUBMIT TO C.O.R. IF NOT, VERIFY ALL OPENINGS (SUCH AS DOORS) ARE CLOSED AND/OR CHANGE OUT NEGATIVE AIR PRE-FILTER. METER MUST READ CONTINUOUSLY.
2. CONTRACTOR SHALL DEVELOPE A DAILY CHECK LIST FOR CONSTRUCTION OVERSIGHT TUNED TO THE QUALITY ASSURANCE PLAN WHICH CAPTURED MOST ERRORS. THIS MAY EVOLVE TO A LIVING DOCUMENT PENDING ISSUES ENCOUNTERED.
3. REFER TO SPEC SECTION 01 35 26 AND DEMOLITION DRAWINGS FOR ICRA REQUIREMENTS BASED ON DURATION / EXTENT OF WORK AND RISK FACTOR

HAZARDOUS MATERIALS NOTES

- 1. REMOVAL OF HAZARDOUS MATERIALS FROM THE BUILDING MUST FOLLOW STATE AND FEDERAL REGULATIONS, AS WELL AS LOCAL LAWS WHEN APPLICABLE. DRAWINGS DIAGRAM THE KNOWN ACM MATERIALS AFFECTED BY THE "WORK" AND THESE QUANTITIES FORM THE BASE BID OF THE CONTRACT. REFER TO MECHANICAL, ELECTRICAL, AND TELECOM DRAWINGS FOR SPECIFIC ROUTING, PENETRATIONS, ETC. COORDINATE ALL HAZMAT CONDITIONS WITH ARCHITECTURAL PLANS.
2. ASBESTOS TESTING OF ALL MATERIALS AFFECTED WITHIN PROJECT SCOPE PRIOR TO DEMOLITION UNLESS OTHERWISE NOTED IS REQUIRED. REFER TO SPECIFICATION SECTION 02 82 11 FOR MATERIAL PRE-TESTED, QUANTITIES, AND MECHANICAL DRAWINGS FOR SPECIFIC PENETRATIONS AND CABLE ROUTING TO DATA PORTS IN EACH ROOM.
3. AT COMPLETION OF TESTING CONTRACTOR WILL PROVIDE A REPORT WHICH WILL INCLUDE MATERIAL LOCATION, DESCRIPTION, AND QUANTITY.
4. REFER TO ACM REPORT TO BE PROVIDED BY THE VA



REFLECTED CEILING PLAN NOTES

- 1. REFER TO ELECTRICAL SHEETS FOR FIXTURE TYPES, SWITCHING, AND SPECIAL SYSTEMS.
2. REFER TO MECHANICAL SHEETS FOR DIFFUSER AND DUCTING LAYOUTS.
3. REFERENCE EXTERIOR FINISH LEGEND FOR EXTERIOR PAINT COLORS; REFERENCE FINISH SCHEDULE FOR INTERIOR PAINT COLORS AND FINISH.

CONSULTANT: A/E: GDM, 1000 W STEUBEN ST. UNIT 3, BINGEN, WA 98605, 541.436.4723, ADAM GODDIN, PE

ARCHITECT/ENGINEER OF RECORD: ARCHITECT: A&E DESIGN, 124 NORTH 29TH STREET, #100, BILLINGS, MONTANA 59101, 406.248.2633, T. MARCELLO PIERROTTET, AIA

STAMP: STATE OF MONTANA, BILLINGS, ERIC PIERROTTET, LICENSED ARCHITECT

PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC): U.S. Department of Veterans Affairs

DRAWING TITLE: DRAWING INDEX AND PROJECT GENERAL INFORMATION, APPROVED: Project Director

PHASE: 100% CONSTRUCTION DOCUMENTS, FLS, FULLY SPRINKLERED

PROJECT TITLE: EHRM INFRASTRUCTURE UPGRADES, LOCATION: FORT MEADE, SOUTH DAKOTA, ISSUE DATE: 04/15/2022, CHECKED BY: TMP, DRAWN BY: JPR

PROJECT NUMBER: 568-21-701, BUILDING NUMBER: GEN INFO, DRAWING NUMBER: 00-GI-001

2022-05-29 09:57:36, BIM 360://2112_VA_Medical_Center_F_Miscellaneous_S02112_General.rvt, VA FORM 08 - 6231

APPLICABLE CODES AND ORDINANCES

2021 NFPA 101, LIFE SAFETY CODE
 2022 NFPA 13, STANDARD FOR THE INSTALLATION OF SPRINKLER SYSTEMS
 2020 NFPA 25, STANDARD FOR THE INSPECTION, TESTING, AND MAINTENANCE OF WATER-BASED FIRE PROTECTION SYSTEMS
 2020 NFPA 70, NATIONAL ELECTRICAL CODE
 2022 NFPA 72, NATIONAL FIRE ALARM AND SIGNALING CODE
 2020 NFPA 75, STANDARD FOR THE FIRE PROTECTION OF INFORMATION TECHNOLOGY EQUIPMENT
 2021 INTERNATIONAL BUILDING CODE (IBC) WHERE NFPA 101 AND ASSOCIATED DOCUMENTS ARE SILENT
 2021 INTERNATIONAL ENERGY CONSERVATION CODE
 2021 INTERNATIONAL FIRE CODE (IFC), WHERE NFPA STANDARDS AND CODES ARE SILENT
 2021 INTERNATIONAL MECHANICAL CODE (IMC)
 2021 INTERNATIONAL FUEL GAS CODE (IFGC)
 2021 UNIFORM PLUMBING CODE
 2009 ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES (ICCANSI 117.1)

ENERGY CODE - BUILDING ENVELOPE

PER 2018 IECC TABLE C402.2:
 MONTANA, CLIMATE ZONE XX

BUILDING ELEMENT	REQUIRED	PROVIDED
ROOFS	R-30d	R-30g (MIN.)
WALLS, ABOVE GRADE	R-13 + R-7.5d	R-22 + R-7.5d
WALLS, BELOW GRADE	BELOW-GRADE WALL	R-7.5d
SLAB- ON- GRADE FLOORS	UNHEATED SLABS	R-10 FOR 24" BELOW R-15 TO T.O. FOUNDATION
OPAQUE DOORS	SWINGING	U-0.37 U-0.37
	ROLL- UP OR SLIDING	R-4.75 R-4.75
FIXED FENESTRATION	U-0.36; SHGC-0.40	U-0.33 MIN; GLAZING SHGC 0.27 MIN
OPERABLE FENESTRATION	U-0.43; SHGC-0.40	NA
ENTRANCE DOORS	U-0.77; SHGC-0.40	U-0.33 MIN; GLAZING SHGC 0.27 MIN

2018 INTERNATIONAL ENERGY CODE SUMMARIES AND REFERENCE SECTIONS BELOW ARE PROVIDED FOR CONVENIENCE ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO UNDERSTAND AND MEET THE REQUIREMENTS OF THE 2018 INTERNATIONAL ENERGY CODE

C402.4 AIR LEAKAGE (MANDATORY)
 THE THERMAL ENVELOPE OF BUILDINGS SHALL COMPLY WITH SECTIONS C402.4.1 THROUGH C402.4.8

C402.4.1 AIR BARRIERS

A CONTINUOUS AIR BARRIER SHALL BE PROVIDED THROUGHOUT THE BUILDING THERMAL ENVELOPE.

C402.4.1.1 AIR BARRIER CONSTRUCTION

1. THE AIR BARRIER SHALL BE CONTINUOUS FOR ALL ASSEMBLIES THAT ARE THE THERMAL ENVELOPE OF THE BUILDING AND ACROSS THE JOINTS AND ASSEMBLIES
 2. AIR BARRIER JOINTS AND SEAMS SHALL BE SEALED, INCLUDING SEALING TRANSITIONS IN PLACES AND CHANGES IN MATERIALS
 3. RECESSED LIGHTING FIXTURES AND OTHER SIMILAR INSTALLED OBJECTS WHICH PENETRATE THE AIR BARRIER SHALL COMPLY WITH SECTION C402.4.8
- EXCEPTION:** BUILDINGS THAT COMPLY WITH SECTION C402.4.1.2.3 ARE NOT REQUIRED TO COMPLY WITH ITEMS 1 AND 3

C402.4.1.2.3 BUILDING TEST

THE COMPLETED BUILDING SHALL BE TESTED AND THE AIR LEAKAGE RATE OF THE BUILDING ENVELOPE SHALL NOT EXCEED 0.40 cfm/ft² AT A PRESSURE DIFFERENTIAL OF 0.3 INCHES WATER GAUGE (2.0 in³/ft² AT 75 Pa) IN ACCORDANCE WITH ASTM E779 OR AN EQUIVALENT METHOD APPROVED BY THE CODE OFFICIAL.

C402.4.2 AIR BARRIER PENETRATIONS

A CONTINUOUS AIR BARRIER SHALL BE PROVIDED THROUGHOUT THE BUILDING THERMAL ENVELOPE.

ACCESSIBILITY

SECTION 1103 SCOPING REQUIREMENTS - 1103.1 WHERE REQUIRED.
 SITES, BUILDINGS, STRUCTURES, FACILITIES, ELEMENTS AND SPACES, TEMPORARY OR PERMANENT, SHALL BE ACCESSIBLE TO PERSONS WITH PHYSICAL DISABILITIES.

EXCEPTIONS:

1103.2.3 EMPLOYEE WORK AREAS: SPACES AND ELEMENTS WITHIN EMPLOYEE WORK AREAS SHALL ONLY BE REQUIRED TO COMPLY WITH SECTION 907.5.2.3.2, 1007, AND 1104.3.1 AND SHALL BE DESIGNED AND CONSTRUCTION SO THAT INDIVIDUALS WITH DISABILITIES CAN APPROACH, ENTER, AND EXIT THE WORK AREAS.

1103.2.8 LIMITED ACCESS SPACES: NONOCCUPIABLE SPACES ACCESSED ONLY BY LADDERS, CATWALKS, CRAWLSPACES, FREIGHT ELEVATORS OR VERY NARROW PASSAGEWAYS ARE NOT REQUIRED TO BE ACCESSIBLE.

1103.2.9 EQUIPMENT SPACES: SPACES FREQUENTED ONLY BY PERSONNEL FOR MAINTENANCE, REPAIR OR MONITORING OF EQUIPMENT ARE NOT REQUIRED TO BE ACCESSIBLE.

2203.2.15 WALK IN COOLERS AND FREEZERS: WALK IN COOLERS AND FREEZERS INTENDED FOR EMPLOYEE USE ONLY ARE NOT REQUIRED TO BE ACCESSIBLE.

SECTION 1104 ACCESSIBLE ROUTES - 1104.5 LOCATION.

ACCESSIBLE ROUTES SHALL COINCIDE WITH OR BE LOCATED IN THE SAME AREA AS A GENERAL CIRCULATION PATH. WHERE THE CIRCULATION PATH IS INTERIOR, THE ACCESSIBLE ROUTE SHALL ALSO BE INTERIOR. WHERE ONLY ONE ACCESSIBLE ROUTE IS PROVIDED, THE ACCESSIBLE ROUTE SHALL NOT PASS THROUGH KITCHENS, STORAGE ROOMS, RESTROOMS, CLOSETS, OR SIMILAR SPACES.

1105.1 PUBLIC ENTRANCES.

IN ADDITION TO ACCESSIBLE ENTRANCES REQUIRED BY SECTION 1105.1.1 THROUGH 1105.1.6, AT LEAST 60 PERCENT OF ALL PUBLIC ENTRANCES SHALL BE ACCESSIBLE.

EXCEPTIONS: LOADING AND SERVICE ENTRANCES THAT ARE NOT THE ONLY ENTRANCE TO A TENANT SPACE.

1105.1.6 TENANT SPACES.

AT LEAST ONE ACCESSIBLE ENTRANCE SHALL BE PROVIDED TO EACH TENANT.

SECTION 1106 PARKING AND PASSENGER LOADING FACILITIES - 1106.1 REQUIRED.

WHERE PARKING IS PROVIDED, ACCESSIBLE PARKING SPACES SHALL BE PROVIDED IN COMPLIANCE WITH TABLE 1106.1, EXCEPT AS REQUIRED BY SECTION 1106.2 THROUGH 1106.4.

1106.6 LOCATION.

ACCESSIBLE PARKING SPACES SHALL BE LOCATED ON THE SHORTEST ACCESSIBLE ROUTE OF TRAVEL FROM ADJACENT PARKING TO AN ACCESSIBLE BUILDING ENTRANCE.

SECTION 1108 SPECIAL OCCUPANCIES - 1108.2 ASSEMBLY AREA SEATING.

A BUILDING, ROOM OR SPACE USED FOR ASSEMBLY PURPOSES WITH FIXED SEATING SHALL COMPLY WITH SECTION 1108.2.1 THROUGH 1108.2.5. PER 1108.2.2.1 GENERAL SEATING, WHEELCHAIR SPACES SHALL BE PROVIDED IN ACCORDANCE WITH TABLE 1108.2.2.1.

SECTION 1110 SIGNAGE - 1110.1 SIGNS.

REQUIRED ACCESSIBLE ELEMENTS SHALL BE IDENTIFIED BY THE INTERNATIONAL SYMBOL OF ACCESSIBILITY AT THE FOLLOWING LOCATIONS: ACCESSIBLE PARKING SPACES, PASSENGER LOADING ZONES, ROOMS, ENTRANCES, CHECK-OUT AISLES, FAMILY OR ASSISTED-USE TOILET AND BATHING ROOMS, AREAS OF REFUGE, AND EXTERIOR AREAS. IN ADDITIONAL 1110.2 DIRECTIONAL SIGNAGE, DIRECTIONAL SIGNAGE INDICATING THE ROUTE TO THE NEAREST LIKE ACCESSIBLE ELEMENT SHALL BE PROVIDED AT THE FOLLOWING LOCATIONS STATED IN 1110.2 AND INCLUDE THE INTERNATIONAL SYMBOL OF ACCESSIBILITY.

1110.4 VARIABLE MESSAGE SIGNS - TRANSPORTATION FACILITIES.

WHERE PROVIDED IN TRANSPORTATION FACILITIES, VARIABLE MESSAGE SIGNS CONVEYING TRANSPORTATION-RELATED INFORMATION SHALL COMPLY WITH SECTION 1110.4

SUSTAINABILITY NOTES

1. REPETITIVE AND/OR INTERMITTENT HIGH-LEVEL NOISE PERMITTED ONLY DURING DAYTIME. AT 50'-0" FROM THE PROJECT BOUNDARY DO NOT EXCEED 70 DB(A) FOR MORE THAN 12 MINUTES IN ANY HOUR.
2. MAXIMUM AMBIENT NOISE LEVELS (DB) FOR NOISE AREA AT PROJECT BOUNDARY: DAYLIGHT HOURS 65 DB, NON-DAYLIGHT HOURS 45 DB.
3. DEVELOP A WASTE MANAGEMENT PLAN ACCORDING TO ASTM E 1609. PLAN SHALL CONSIST OF WASTE IDENTIFICATION, WASTE REDUCTION WORK PLAN, AND COST/REVENUE ANALYSIS. DISTINGUISH BETWEEN CONSTRUCTION WASTES. INDICATE QUANTITIES BY WEIGHT OR VOLUME, BUT USE SAME UNITS OF MEASURE THROUGHOUT WASTE MANAGEMENT PLAN.
4. DEVELOP A WASTE REDUCTION WORK PLAN. IDENTIFY NON-HAZARDOUS DEMOLITION AND CONSTRUCTION WASTE GENERATED BY THE PROJECT AND WHETHER IT WILL BE SALVAGED, RECYCLED, OR DISPOSED OF IN LANDFILL. INCLUDE QUANTITY OF EACH TYPE OF WASTE, QUANTITY FOR EACH MEANS OF RECOVERY, AND HANDLING AND TRANSPORTATION PROCEDURES.
5. RECYCLED MATERIALS: DIVERT, AT A MINIMUM, 50% OF RESULTING WASTE FROM A LANDFILL THROUGH SALVAGE AND RECYCLING. SEPARATE RECYCLABLE WASTE FROM OTHER WASTE MATERIALS, TRASH, AND DEBRIS.
6. DEVELOP A CONSTRUCTION IAQ MANAGEMENT PLAN. AT A MINIMUM, SCHEDULE OF INSTALLATION OF INTERIOR FINISHES, IDENTIFY SOURCES OF ODOR AND DUST, NOTE CONSTRUCTION VENTILATION PROVIDED INCLUDING USE OF PERMANENT HVAC SYSTEMS, TYPES OF FILTRATION AND SCHEDULE FOR REPLACEMENT OF FILTERS, CLEANING AND DUST CONTROL PROCEDURES, PRODUCTS REQUIRING MOISTURE PROTECTION, AND SCHEDULE FOR INSPECTION OF STORED MATERIALS.
7. DEVELOP A TEMPORARY SEDIMENTATION CONTROL PLAN. INDICATE DEVICES, MEASURES, AND LOCATIONS FOR SEDIMENT CONTROL DEVICES, DESCRIBE CONSTRUCTION ACTIVITIES EFFECTING EROSION, DESCRIBE MONITORING AND MEASURES FOR SEDIMENT CONTROL, DESCRIBE MITIGATION AND RESPONSE TO FAILED EROSION CONTROL MEASURES.
8. LOW EMITTING MATERIALS. PAINTS, COATINGS, ADHESIVES AND SEALANTS FOR FIELD APPLICATIONS INSIDE THE WEATHER PROOFING SYSTEM SHALL COMPLY WITH VOC CONTENT LIMITS OF AUTHORITIES HAVING JURISDICTIONS OR SCAQMD RULE 1168, WHICHEVER IS STRICTER.
9. NO SMOKING. SMOKING, VAPING, AND SMOKELESS TOBACCO USE IS NOT PERMITTED WITHIN THE BUILDING, OR WITHIN 25'-0" OF ENTRANCES, OPERABLE WINDOWS, OR OUTDOOR AIR INTAKES.
10. CAST-IN-PLACE CONCRETE. PROVIDE STEEL REINFORCING MATERIALS WITH MINIMUM 25% RECYCLED CONTENT. PROVIDE AGGREGATE AND CEMENT EXTRACTED AND/OR MANUFACTURED WITHIN 500 MILES OF PROJECT SITE.
11. UNIT MASONRY. PROVIDE BRICK, BLOCK, AGGREGATE, CEMENT, MORTAR, AND LIME EXTRACTED AND/OR MANUFACTURED WITHIN 500 MILES OF PROJECT SITE.
12. STRUCTURAL STEEL, STEEL DECKING, FORMED METAL FRAMING, METAL TOILET COMPARTMENTS, AND FORMED METAL WALL AND ROOF PANELS. PROVIDE MATERIALS WITH POST-CONSUMER RECYCLED CONTENT PLUS ONE-HALF OF PRE-CONSUMER RECYCLED CONTENT NOT LESS THAN 25%.
13. ALL COMPOSITE WOOD PRODUCTS SHALL BE MANUFACTURED WITHOUT ADDED UREA FORMALDEHYDE.
14. ALUMINUM ENTRANCE AND WINDOW SYSTEMS. PROVIDE ALUMINUM MATERIALS WITH POST-CONSUMER RECYCLED CONTENT PLUS ONE-HALF OF PRE-CONSUMER RECYCLED CONTENT NOT LESS THAN 50%.
15. PROVIDE GYPSUM BOARD WALL PANELS MANUFACTURED WITHIN 500 MILES OF THE PROJECT SITE.
16. RESILIENT HARD SURFACE FLOORING MATERIALS AND THEIR ADHESIVES SHALL BE FLOORSCORE CERTIFIED.
17. PLUMBING FIXTURES SHALL BE WATERSENSE CERTIFIED.

A

B

C

D

E

F

BIM 360://2112_VA Medical Center - F1 Meade SD21112_General.rvt
 2022-05-24 09:57:26

Revisions:	Date:


CONSULTANT

A/E:
 GDM
 1000 W STEUBEN ST. UNIT 3
 BINGEN, WA 98605
 541.436.4723
 ADAM GODDIN, PE




ARCHITECT/ENGINEER OF RECORD

ARCHITECT
 A&E DESIGN
 124 NORTH 29TH STREET, #100
 BILLINGS, MONTANA 59101
 406.248.2633
 T. MARCELLO PIERROTTET, AIA



STAMP



PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC)

VA U.S. Department of Veterans Affairs

DRAWING TITLE
 PROJECT CODE SUMMARY

APPROVED: Project Director

PHASE
 100% CONSTRUCTION DOCUMENTS

FLS
 FULLY SPRINKLERED

PROJECT TITLE
 EHRM INFRASTRUCTURE UPGRADES

LOCATION
 FORT MEADE, SOUTH DAKOTA


ISSUE DATE: 04/15/2022
 CHECKED BY: TMP
 DRAWN BY: JPR

PROJECT NUMBER
 568-21-701

BUILDING NUMBER
 GEN INFO

DRAWING NUMBER
 00-GI-002

SOUTH DAKOTA STATE MAP



PROJECT REGION MAP



PROJECT LOCATION MAP





PROJECT SITE MAP



PROJECT KEY PLAN

BLACK HILLS VA HEALTHCARE SYSTEM
BLACK HILLS NETWORK #
113 COMANCHE ROAD | FORT MEADE, SD 57741



PROJECT CAMPUS PLAN

N.T.S.

2022-05-24 09:57:37
B:\136012\112_VA Medical Center - Ft Meade SD\112_General_L201.rvt

Revisions:	Date:

CONSULTANT

A/E:
GDM
1000 W STEUBEN ST. UNIT 3
BINGEN, WA 98605
541.436.4723
ADAM GODDIN, PE

ARCHITECT/ENGINEER OF RECORD

ARCHITECT
A&E DESIGN
124 NORTH 29TH STREET, #100
BILLINGS, MONTANA 59101
406.248.2633
T. MARCELLO PIERROTTET, AIA

STAMP

PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC)

VA U.S. Department of Veterans Affairs

DRAWING TITLE
PROJECT LOCATION MAPS & CAMPUS PLAN

APPROVED: Project Director

PHASE
100% CONSTRUCTION DOCUMENTS

FLS
FULLY SPRINKLERED

PROJECT TITLE
EHRM INFRASTRUCTURE UPGRADES

LOCATION
FORT MEADE, SOUTH DAKOTA

ISSUE DATE: 04/15/2022
CHECKED BY: TMP
DRAWN BY: JPR

PROJECT NUMBER
568-21-701

BUILDING NUMBER
GEN INFO

DRAWING NUMBER
00-GI-003

NOTE: ALL WORK TO BE CONDUCTED IN DESIGNATED CLASS IV AND V AREAS AS INDICATED IN DRAWINGS, IS TO BE COORDINATED SEVEN (7) DAYS AHEAD OF SCHEDULE WORK WITH INFECTION PREVENTION STAFF AND C.O.R.

ASHE
Infection Control Risk Assessment 2.0
Matrix of Precautions for Construction, Renovation and Operations

Step One:
Using Table 1, identify the Construction Project Activity Type (A-D).

Table 1 - Construction Project Activity Type:

Type A	<p>Inspection and non-invasive activities. Includes but is not limited to:</p> <ul style="list-style-type: none"> Removal of ceiling tile for visual inspection-limited to 1 tile per 50 square feet with limited exposure time. Limited building system maintenance (e.g., pneumatic tube station, HVAC system, fire suppression system, electrical and carpentry work to include painting without sanding) that does not create dust or debris. Clean plumbing activity limited in nature.
Type B	<p>Small-scale, short duration activities that create minimal dust and debris. Includes but is not limited to:</p> <ul style="list-style-type: none"> Work conducted above the ceiling (e.g., prolonged inspection or repair of firewalls and barriers, installation of conduit and/or cabling, and access to mechanical and/or electrical chase spaces). Fan shutdown/startup. Installation of electrical devices or new flooring that produces minimal dust and debris. The removal of drywall where minimal dust and debris is created. Controlled sanding activities (e.g., wet or dry sanding) that produce minimal dust and debris.
Type C	<p>Large-scale, longer duration activities that create a moderate amount of dust and debris. Includes but is not limited to:</p> <ul style="list-style-type: none"> Perform noninvasive work actively as to not block or interrupt patient care. New drywall placement. Renovation work in a single room. Nonexisting cable pathway or invasive electrical work above ceilings. The removal of drywall where a moderate amount of dust and debris is created. Dry sanding where a moderate amount of dust and debris is created. Work creating significant vibration and/or noise. Any activity that cannot be completed in a single work shift.
Type D	<p>Major demolition and construction activities. Includes but is not limited to:</p> <ul style="list-style-type: none"> Removal or replacement of building system component(s). Removal/installation of drywall partitions. Invasive large-scale new building construction. Renovation work in two or more rooms.

©2021 American Society for Health Care Engineering of the American Hospital Association

ASHE
Infection Control Risk Assessment 2.0
Matrix of Precautions for Construction, Renovation and Operations

Step Two:
Using Table 2, identify the Patient Risk Group(s) that will be affected. If more than one risk group will be affected, select the higher risk group.

Table 2 - Patient Risk Group:

Low Risk	Medium Risk	High Risk	Highest Risk
<p>Non-patient care areas such as:</p> <ul style="list-style-type: none"> Public hallways and gathering areas not on clinical units. Office areas not on clinical units. Bathrooms or locker rooms not on clinical units. Mechanical rooms not on clinical units. EVS closets not on clinical units. 	<p>Patient care support areas such as:</p> <ul style="list-style-type: none"> Waiting areas. Clinical engineering. Materials management. Sterile processing department - dirty side. Kitchen, cafeteria, gift shop, coffee shop, and food kiosks. 	<p>Patient care areas such as:</p> <ul style="list-style-type: none"> All acute care units. Emergency department. Employee health. Pharmacy - general work zone. Medication rooms and clean utility rooms. Imaging suites: diagnostic imaging. Laboratory. 	<p>Procedural, invasive, sterile support and highly compromised patient care areas such as:</p> <ul style="list-style-type: none"> All transplant and intensive care units. All oncology units. OR theaters and restricted areas. Procedural suites. Pharmacy compounding. Sterile processing department - clean side. Transfusion services. Dedicated isolation wards/units. Imaging suites: invasive imaging.

Step Three:

Match the Patient Risk Group (Low, Medium, High, Highest) from Step Two with the planned Construction Activity Project Type (A, B, C, D) from Step One using Table 3 to find the Class of Precautions (I, II, III, IV or V) or level of infection control activities required. The activities are listed in Table 5 - Minimum Required Infection Control Precautions by Class.

Table 3 - Class of Precautions:

Patient Risk Group	Construction Project Type			
	TYPE A	TYPE B	TYPE C	TYPE D
LOW Risk Group	I	II	III	IV
MEDIUM Risk Group	I	II	III	IV
HIGH Risk Group	I	II	III	IV
HIGHEST Risk Group	III	IV	V	V

Infection control permit and approval will be required when Class of Precautions III (Type C) and all Class of Precautions IV or V are necessary.

Environmental conditions that could affect human health, such as sewage, mold, asbestos, gray water and black water will require Class of Precautions IV for LOW and MEDIUM Risk Groups and Class of Precautions V for HIGH and HIGHEST Risk Groups.

©2021 American Society for Health Care Engineering of the American Hospital Association

ASHE
Infection Control Risk Assessment 2.0
Matrix of Precautions for Construction, Renovation and Operations

Step Four:
Assess potential risk to areas surrounding the project. Using Table 4, identify the surrounding areas that will be affected and the type of impact that will occur. If more than one risk group will be affected, select the higher risk group using Table 2 - Patient Risk Group.

Table 4 - Surrounding Area Assessment

Unit Below:	Unit Above:	Unit Lateral:	Unit Behind:	Unit in Front:
Risk Group:	Risk Group:	Risk Group:	Risk Group:	Risk Group:
Contact:	Contact:	Contact:	Contact:	Contact:
Phone:	Phone:	Phone:	Phone:	Phone:
Additional Controls:	Additional Controls:	Additional Controls:	Additional Controls:	Additional Controls:
<input type="checkbox"/> Noise <input type="checkbox"/> Vibration <input type="checkbox"/> Dust control <input type="checkbox"/> Pressurization <input type="checkbox"/> Impact to other systems, such as: <input type="checkbox"/> Data <input type="checkbox"/> Mechanical <input type="checkbox"/> Med Gases	<input type="checkbox"/> Noise <input type="checkbox"/> Vibration <input type="checkbox"/> Dust control <input type="checkbox"/> Pressurization <input type="checkbox"/> Impact to other systems, such as: <input type="checkbox"/> Data <input type="checkbox"/> Mechanical <input type="checkbox"/> Med Gases	<input type="checkbox"/> Noise <input type="checkbox"/> Vibration <input type="checkbox"/> Dust control <input type="checkbox"/> Pressurization <input type="checkbox"/> Impact to other systems, such as: <input type="checkbox"/> Data <input type="checkbox"/> Mechanical <input type="checkbox"/> Med Gases	<input type="checkbox"/> Noise <input type="checkbox"/> Vibration <input type="checkbox"/> Dust control <input type="checkbox"/> Pressurization <input type="checkbox"/> Impact to other systems, such as: <input type="checkbox"/> Data <input type="checkbox"/> Mechanical <input type="checkbox"/> Med Gases	<input type="checkbox"/> Noise <input type="checkbox"/> Vibration <input type="checkbox"/> Dust control <input type="checkbox"/> Pressurization <input type="checkbox"/> Impact to other systems, such as: <input type="checkbox"/> Data <input type="checkbox"/> Mechanical <input type="checkbox"/> Med Gases
Noise & Vibration Mitigation Strategies				
<input type="checkbox"/> Use diamond drills instead of powder-actuated fasteners. <input type="checkbox"/> Schedule noise-making periods with adjacent spaces. <input type="checkbox"/> Use beam clamps instead of shot. <input type="checkbox"/> Prefab where possible. <input type="checkbox"/> Use lin snips to cut metal studs instead of using a chop saw. <input type="checkbox"/> Install metal decking with vent tabs, then use cellular floor deck hangers. <input type="checkbox"/> Consider pro-press instead of soldering, brazing or welding. <input type="checkbox"/> Wet core drill instead of dry core or percussion. <input type="checkbox"/> Instead of jackhammering concrete, use wet diamond saws. <input type="checkbox"/> Use HEPA vacuums instead of standard wet/dry vacuums. <input type="checkbox"/> Use mechanical joining system sprinkler fittings instead of threaded. <input type="checkbox"/> Where fumes are tolerated, use chemical adhesive remover (flooring glue) instead of mechanical. <input type="checkbox"/> To remove flooring, shot blast instead of using a floor scraper. <input type="checkbox"/> Use electric sheers instead of reciprocating saw for ductwork cutting. <input type="checkbox"/> Install exterior man/material lifts.				
Ventilation & Pressurization Mitigation Strategies				
<input type="checkbox"/> HEPA to exterior. <input type="checkbox"/> Install temporary ductwork. <input type="checkbox"/> Utilize temporary HVAC equipment. <input type="checkbox"/> Vacate the area. <input type="checkbox"/> Install temporary partitions. <input type="checkbox"/> Use carbon filtration to filter odors.				
Impact to Other Systems Mitigation Strategies				
<input type="checkbox"/> Schedule outages. <input type="checkbox"/> Provide temporary systems. <input type="checkbox"/> Back-feed electricity or medical gases.				

©2021 American Society for Health Care Engineering of the American Hospital Association

ASHE
Infection Control Risk Assessment 2.0
Matrix of Precautions for Construction, Renovation and Operations

Table 5 - Minimum Required Infection Control Precautions by Class | Before and During Work Activity

Class of Precautions	Mitigation Activities (Performed Before and During Work Activity)
Class I	<ol style="list-style-type: none"> Provide active means to prevent airborne dust dispersion into the occupied areas. Perform noninvasive work activities in areas that are not directly occupied with patients. Perform noninvasive work activity in a manner that does not create dust. Immediately replace any displaced ceiling tile before leaving the area and/or at end of noninvasive work activity.
Class II	<ol style="list-style-type: none"> Perform only limited dust work and/or activities designed for basic facilities and engineering work. Perform limited dust and invasive work following standing precautions procedures approved by the organization. This Class of Precautions must never be used for construction or renovation activities.
Class III	<ol style="list-style-type: none"> Means for controlling minimal dust dispersion may include hand-held HEPA vacuum devices, polyethylene plastic containment, or isolation of work area by closing room door. Remove or isolate return air diffusers to avoid dust from entering the HVAC system. Remove or isolate the supply air diffusers to avoid positive pressurization of the space. If work area is contained, then it must be neutrally to negatively pressurized at all times. Seal all doors with tape that will not leave residue. Contain all trash and debris in the work area. Nonporous/smooth and cleanable containers (with a hard lid) must be used to transport trash and debris from the construction areas. These containers must be damp-wiped cleaned and free of visible dust/debris before leaving the contained work area. Install a sticky (dust collection) mat at entrance of contained work area based on facility policy. Sticky mats must be changed routinely and when visibly soiled. Maintain clean surroundings when area is not contained by damp mopping or HEPA vacuuming surfaces.
Class IV	<ol style="list-style-type: none"> Construct and complete critical barriers meeting NFPA 241 requirements. Barriers must extend to the ceiling or if ceiling tile is removed, to the deck above. All (plastic or hard) barrier construction activities must be completed in a manner that prevents dust release. Plastic barriers must be effectively affixed to ground and ceiling and secure from movement or damage. Apply tape that will not leave a residue to seal gaps between barriers, ceiling or floor. Seal all penetrations in containment barriers, including floors and ceiling, using approved materials (UL schedule firestop if applicable for barrier type). Containment units or environmental containment units (ECUs) approved for Class IV precautions in small areas totally contained by the unit and that has HEPA-filtered exhaust air. Remove or isolate return air diffusers to avoid dust entering the HVAC system. Remove or isolate the supply air diffusers to avoid positive pressurization of the space. Negative airflow pattern must be maintained from the entry point to the anteroom and into the construction area. The airflow must cascade from outside to inside the construction area. The entire construction area must remain negatively pressurized. Maintain negative pressurization of the entire workspace by use of HEPA exhaust air systems directed outdoors. Exhaust discharged directly to the outdoors that is 25 feet or greater from entrances, air intakes and windows does not require HEPA-filtered air. If exhaust is directed indoors, then the system must be HEPA filtered. Prior to start of work, HEPA filtration must be verified by particulate measurement as no less than 99.97% efficiency and must not alter or change airflow/pressure relationships in other areas. Exhaust into shared or recirculating HVAC systems, or other shared exhaust systems (e.g., bathroom exhaust) is not acceptable. Install device (e.g., magnetic, manometer, or digital monitoring) on exterior of work containment to continually monitor negative pressurization. The "ball in the wall" or similar apparatus are not acceptable.

©2021 American Society for Health Care Engineering of the American Hospital Association

ASHE
Infection Control Risk Assessment 2.0
Matrix of Precautions for Construction, Renovation and Operations

Table 6 - Minimum Required Infection Control Precautions | Upon Completion of Work Activity

Class of Precautions	Mitigation Activities (Performed upon Completion of Work Activity)
Classes I, II and III	<p>Cleaning:</p> <ol style="list-style-type: none"> Clean work areas including all environmental surfaces, high horizontal surfaces and flooring materials. Check all supply and return air registers for dust accumulation on upper surfaces as well as air diffuser surfaces. <p>HVAC Systems:</p> <ol style="list-style-type: none"> Remove isolation of HVAC system in areas where work is being performed. Verify that HVAC systems are clean and operational. Verify the HVAC systems meet original airflow and air exchange design specifications. <p>Class III (Type C Activities only), IV, and V precautions require inspection and documentation for downgraded ICRA precautions.</p> <p>Construction areas must be inspected by an infection preventionist or designee and engineering representative for discontinuation or downgrading of ICRA precautions.</p> <p>Work Area Cleaning:</p> <ol style="list-style-type: none"> Clean work areas including all environmental surfaces, high horizontal surfaces and flooring materials. Check all supply and return air registers for dust accumulation on upper surfaces as well as air diffuser surfaces. <p>Removal of Critical Barriers:</p> <ol style="list-style-type: none"> Critical barriers must remain in place during all work involving drywall removal, creation of dust and activities beyond simple touch-up work. The barrier may NOT be removed until a work area cleaning has been performed. All (plastic or hard) barrier removal activities must be completed in a manner that prevents dust release. Use the following precautions when removing hard barriers: <ol style="list-style-type: none"> Carefully remove screws and painter tape. If dust will be generated during screw removal, use hand-held HEPA vacuum. Drywall cutting is prohibited during removal process. Clean all stud tracks with HEPA vacuum before removing outer hard barrier. Use a plastic barrier to enclose area if dust could be generated. <p>Negative Air Requirements:</p> <ol style="list-style-type: none"> The use of negative air must be designed to remove contaminants from the work area. Negative air devices must remain operational at all times and in place for a period after completion of dust creating activities to remove contaminants from the work area and before removal of critical barriers. <p>HVAC systems:</p> <ol style="list-style-type: none"> Upon removal of critical barriers, remove isolation of HVAC system in areas where work is being performed. Verify that HVAC systems are clean and operational. Verify the HVAC systems meet original airflow and air exchange design specifications.
Class IV and V	<ol style="list-style-type: none"> Construct and complete critical barriers meeting NFPA 241 requirements. Barriers must extend to the ceiling or if ceiling tile is removed, to the deck above. All (plastic or hard) barrier construction activities must be completed in a manner that prevents dust release. Plastic barriers must be effectively affixed to ground and ceiling and secure from movement or damage. Apply tape that will not leave a residue to seal gaps between barriers, ceiling or floor. Seal all penetrations in containment barriers, including floors and ceiling using approved materials (UL schedule firestop if applicable for barrier type). Construct anteroom large enough for equipment staging, cart cleaning, workers. The anteroom must be constructed adjacent to entrance of construction work area. Personnel will be required to wear coveralls at all times during Class V work activities. Coveralls must be removed before leaving the anteroom. Remove or isolate return air diffusers to avoid dust entering the HVAC system. Remove or isolate the supply air diffusers to avoid positive pressurization of the space. Negative airflow pattern must be maintained from the entry point to the anteroom and into the construction area. The airflow must cascade from outside to inside the construction area. The entire construction area must remain negatively pressurized. Maintain negative pressurization of the entire workspace using HEPA exhaust air systems directed outdoors. Exhaust discharged directly to the outdoors that is 25 feet or greater from entrances, air intakes and windows does not require HEPA-filtered air. If exhaust is directed indoors, then the system must be HEPA filtered. Prior to start of work, HEPA filtration must be verified by particulate measurement as no less than 99.97% efficiency and must not alter or change airflow/pressure relationships in other areas. Exhaust into shared or recirculating HVAC systems, or other shared exhaust systems (bathroom exhaust) is not acceptable. Install device (e.g., magnetic, manometer, or digital monitoring) on exterior of work containment to continually monitor negative pressurization. The "ball in the wall" or similar apparatus are not acceptable. Contain all trash and debris in the work area. Nonporous/smooth and cleanable containers (with a hard lid) must be used to transport trash and debris from the construction areas. These containers must be damp-wiped cleaned and free of visible dust/debris before leaving the contained work area. Worker clothing must be clean and free of visible dust before leaving the work area anteroom. Workers must wear shoe covers prior to entry into the work area. Shoe covers must be changed prior to exiting the anteroom to the occupied space (non-work area). Damaged shoe covers must be immediately changed. Install a sticky (dust collection) mat at entrance of contained work area based on facility policy. Sticky mats must be changed routinely and when visibly soiled. Consider collection of particulate data during work to monitor and ensure that contaminants do not enter the occupied spaces. Routine collection of particulate samples may be used to verify HEPA filtration efficiencies.

©2021 American Society for Health Care Engineering of the American Hospital Association

ASHE
Infection Control Risk Assessment 2.0
Matrix of Precautions for Construction, Renovation and Operations

Table 6 - Minimum Required Infection Control Precautions | Upon Completion of Work Activity

Class of Precautions	Mitigation Activities (Performed upon Completion of Work Activity)
Classes I, II and III	<p>Cleaning:</p> <ol style="list-style-type: none"> Clean work areas including all environmental surfaces, high horizontal surfaces and flooring materials. Check all supply and return air registers for dust accumulation on upper surfaces as well as air diffuser surfaces. <p>HVAC Systems:</p> <ol style="list-style-type: none"> Remove isolation of HVAC system in areas where work is being performed. Verify that HVAC systems are clean and operational. Verify the HVAC systems meet original airflow and air exchange design specifications. <p>Class III (Type C Activities only), IV, and V precautions require inspection and documentation for downgraded ICRA precautions.</p> <p>Construction areas must be inspected by an infection preventionist or designee and engineering representative for discontinuation or downgrading of ICRA precautions.</p> <p>Work Area Cleaning:</p> <ol style="list-style-type: none"> Clean work areas including all environmental surfaces, high horizontal surfaces and flooring materials. Check all supply and return air registers for dust accumulation on upper surfaces as well as air diffuser surfaces. <p>Removal of Critical Barriers:</p> <ol style="list-style-type: none"> Critical barriers must remain in place during all work involving drywall removal, creation of dust and activities beyond simple touch-up work. The barrier may NOT be removed until a work area cleaning has been performed. All (plastic or hard) barrier removal activities must be completed in a manner that prevents dust release. Use the following precautions when removing hard barriers: <ol style="list-style-type: none"> Carefully remove screws and painter tape. If dust will be generated during screw removal, use hand-held HEPA vacuum. Drywall cutting is prohibited during removal process. Clean all stud tracks with HEPA vacuum before removing outer hard barrier. Use a plastic barrier to enclose area if dust could be generated. <p>Negative Air Requirements:</p> <ol style="list-style-type: none"> The use of negative air must be designed to remove contaminants from the work area. Negative air devices must remain operational at all times and in place for a period after completion of dust creating activities to remove contaminants from the work area and before removal of critical barriers. <p>HVAC systems:</p> <ol style="list-style-type: none"> Upon removal of critical barriers, remove isolation of HVAC system in areas where work is being performed. Verify that HVAC systems are clean and operational. Verify the HVAC systems meet original airflow and air exchange design specifications.
Class IV and V	<ol style="list-style-type: none"> Construct and complete critical barriers meeting NFPA 241 requirements. Barriers must extend to the ceiling or if ceiling tile is removed, to the deck above. All (plastic or hard) barrier construction activities must be completed in a manner that prevents dust release. Plastic barriers must be effectively affixed to ground and ceiling and secure from movement or damage. Apply tape that will not leave a residue to seal gaps between barriers, ceiling or floor. Seal all penetrations in containment barriers, including floors and ceiling using approved materials (UL schedule firestop if applicable for barrier type). Construct anteroom large enough for equipment staging, cart cleaning, workers. The anteroom must be constructed adjacent to entrance of construction work area. Personnel will be required to wear coveralls at all times during Class V work activities. Coveralls must be removed before leaving the anteroom. Remove or isolate return air diffusers to avoid dust entering the HVAC system. Remove or isolate the supply air diffusers to avoid positive pressurization of the space. Negative airflow pattern must be maintained from the entry point to the anteroom and into the construction area. The airflow must cascade from outside to inside the construction area. The entire construction area must remain negatively pressurized. Maintain negative pressurization of the entire workspace using HEPA exhaust air systems directed outdoors. Exhaust discharged directly to the outdoors that is 25 feet or greater from entrances, air intakes and windows does not require HEPA-filtered air. If exhaust is directed indoors, then the system must be HEPA filtered. Prior to start of work, HEPA filtration must be verified by particulate measurement as no less than 99.97% efficiency and must not alter or change airflow/pressure relationships in other areas. Exhaust into shared or recirculating HVAC systems, or other shared exhaust systems (bathroom exhaust) is not acceptable. Install device (e.g., magnetic, manometer, or digital monitoring) on exterior of work containment to continually monitor negative pressurization. The "ball in the wall" or similar apparatus are not acceptable. Contain all trash and debris in the work area. Nonporous/smooth and cleanable containers (with a hard lid) must be used to transport trash and debris from the construction areas. These containers must be damp-wiped cleaned and free of visible dust/debris before leaving the contained work area. Worker clothing must be clean and free of visible dust before leaving the work area anteroom. Workers must wear shoe covers prior to entry into the work area. Shoe covers must be changed prior to exiting the anteroom to the occupied space (non-work area). Damaged shoe covers must be immediately changed. Install a sticky (dust collection) mat at entrance of contained work area based on facility policy. Sticky mats must be changed routinely and when visibly soiled. Consider collection of particulate data during work to monitor and ensure that contaminants do not enter the occupied spaces. Routine collection of particulate samples may be used to verify HEPA filtration efficiencies.

©2021 American Society for Health Care Engineering of the American Hospital Association

BIM 360://2112_VA_Medical_Center - F:\Missile SD2112_General.rvt
2022-05-24 09:57:37
F

Revisions:	Date:


CONSULTANT

A/E:
GDM
1000 W STEUBEN ST. UNIT 3
BINGEN, WA 98605
541.436.4723
ADAM GODDIN, PE




ARCHITECT/ENGINEER OF RECORD

ARCHITECT
A&E DESIGN
124 NORTH 29TH STREET, #100
BILLINGS, MONTANA 59101
406.248.2633
T. MARCELLO PIERROTTET, AIA



STAMP



PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC)

VA U.S. Department of Veterans Affairs

DRAWING TITLE
ICRA CLASSIFICATION PROCESS

APPROVED: Project Director

PHASE
100% CONSTRUCTION DOCUMENTS

FLS
FULLY SPRINKLERED

PROJECT TITLE
EHRM INFRASTRUCTURE UPGRADES

LOCATION
FORT MEADE, SOUTH DAKOTA

ISSUE DATE
04/15/2022

CHECKED BY
TMP




DRAWN BY
Author

PROJECT NUMBER
568-21-701


BUILDING NUMBER
GEN INFO

DRAWING NUMBER
00-GI-004

VERTICAL ASSEMBLIES











WALL TYPE TAG LEGEND



ADDITIONAL WALL COMPONENTS:
 L - LOW WALL
 P - PARTIAL HEIGHT
 S - SOUND BATTS
 T - TILE BACKER BOARD
 V - VAPOR PERMEABLE AIR BARRIER
 W - WET WALL

EXAMPLE: $\langle 2A-6T \rangle$ = 2-HOUR FIRE RATING (PER U.L. DESCRIPTION) TYPE 'A' WALL WITH 6\"/>

A SERIES PARTITION (GWB BOTH SIDES)



B SERIES PARTITION (GWB 1-SIDE)


C SERIES PARTITION (CONC)

D SERIES PARTITION (SHAFT)


M SERIES PARTITION (CMU)

E SERIES PARTITION

HORIZONTAL ASSEMBLIES



F1 FLOOR ASSEMBLY



R1 ROOF ASSEMBLY

2022-05-24 09:57:38
 BIM 360://2112_VA Medical Center - F1 Meads SD2112_General.rvt
 VA FORM 08 - 6231

Revisions:	Date:

CONSULTANT

A/E:
 GDM
 1000 W STEUBEN ST. UNIT 3
 BINGEN, WA 98605
 541.436.4723
 ADAM GODDIN, PE

ARCHITECT/ENGINEER OF RECORD

ARCHITECT
 A&E DESIGN
 124 NORTH 29TH STREET, #100
 BILLINGS, MONTANA 59101
 406.248.2633
 T. MARCELLO PIERROTTI, AIA

STAMP

PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC)

VA U.S. Department of Veterans Affairs

DRAWING TITLE
 PROJECT ASSEMBLY TYPES

APPROVED: Project Director

PHASE
 100% CONSTRUCTION DOCUMENTS

FLS
 FULLY SPRINKLERED

PROJECT TITLE
 EHRM INFRASTRUCTURE UPGRADES

LOCATION
 FORT MEADE, SOUTH DAKOTA

ISSUE DATE
 04/15/2022


CHECKED BY
 TMP

DRAWN BY
 JPR


PROJECT NUMBER
 568-21-701

BUILDING NUMBER
 GEN INFO


DRAWING NUMBER
 00-GI-005




5 INTERSECTION OF RATED WALLS
1 1/2" = 1'-0"




4 PARTITION HEAD DETAIL
1 1/2" = 1'-0"




9 PARTITIONS - PENETRATIONS
3" = 1'-0"




3 WALL BRACING - CROSS DECKING
1 1/2" = 1'-0"




8 CORNER GUARDS
1 1/2" = 1'-0"




7 ELEC BOXES IN RATED & ACOUSTICAL WALLS
1 1/2" = 1'-0"




2 ANGLED PIPE PENETRATION
1 1/2" = 1'-0"




6 RECESSED WALL CAB IN RATED WALL
1 1/2" = 1'-0"




14 GYP PARTITION - PERIMETER RELIEF
1 1/2" = 1'-0"




11 PARTITION INTERSECTION
1 1/2" = 1'-0"




16 WALL FRAMING AT OPENINGS
1 1/2" = 1'-0"




15 PART PENETRATION - ACOUSTIC SEALANT
1 1/2" = 1'-0"



13 GYP BD PARTITION CONTROL JOINTS
1 1/2" = 1'-0"



10 DUCT PENETRATION
1 1/2" = 1'-0"



12 TYP MTL STUD PARTITION HEAD DETAIL
1 1/2" = 1'-0"

- STRUCTURAL DECK
- RUNNER TRACK SECURED TO STRUCTURE
- METAL STUD FRAMING, SEE CODE TO PARTITION TYPES
- STUD CRIPPLES AT 16" O.C.
- WALL OPENING
- STUD CRIPPLES SECURED TO ADJACENT VERTICAL STUDS
- RUNNER TRACK AT SPANS TO 4' SEE ALT. FRAMING FOR ALTERNATE FRAMING OPENINGS FROM 4 TO 8 FT. SUPPORT RUNNER TRACK ON 2 HORIZONTAL 6" METAL STUDS (SHOWN WITH BROKEN LINES)
- BACKING PLATE - 6" RUNNER TRACK, NOTCH AND OPENING FLANGES AS SHOWN AT VERTICAL FRAMING MEMBERS
- SCREW ATTACH AT EACH STUD
- DOUBLE STUDS AT ALL FRAMING OPENINGS MORE THAN 24" WIDE TO EXTEND FROM FLOOR LINE TO BOTTOM OF METAL DECK AT INTERIOR PARTITIONS AND FLOOR LINE TO FLOOR LINE MINIMUM AT EXTERIOR WALLS
- PROVIDE 12 GA. BACKING PLATE WHERE SPECIFIED.

- PENETRATING PIPE, CONDUIT, ECT. CLOSER PERIMETER JOINT AROUND PENETRATING WORK. USE SOUND SEAL MASTIC AT NON-RATED PARTITIONS. FOR FIRE-SAFING REQUIREMENTS, SEE SPECIFICATIONS.
- PIPE SLEEVE. CLOSE PERIMETER JOINT WITH DRYWALL OPENING COMPOUND AT DRYWALL PARTITION. MORTAR AT MASONRY PARTITIONS. OFFSET BACK-TO-BACK BOXES. CONNECT WITH CONDUIT. PLUG CONDUIT AFTER WIRING IS PULLED THROUGH. USE SOUND SEAL MASTIC. WALL BOX FOR MECHANICAL OR ELECTRICAL EQUIPMENT. COAT OUTSIDE SURFACES TO CLOSE JOINTS AND GAPS AND SEAL HOLDS. USE SOUND SEAL MASTIC.
- PARTITION FACE FOR MATERIAL AND THICKNESS. SEE PARTITION TYPE REFERENCES.

2022-05-24 09:57:40
 BIM 360://2112_VA Medical Center - F:\Models SD2112_General.rvt
 VA FORM 08 - 6231

CONSULTANT
 A/E:
 GDM
 1000 W STEUBEN ST. UNIT 3
 BINGEN, WA 98605
 541.436.4723
 ADAM GODDIN, PE

ARCHITECT/ENGINEER OF RECORD
 ARCHITECT
 A&E DESIGN
 124 NORTH 29TH STREET, #100
 BILLINGS, MONTANA 59101
 406.248.2633
 T. MARCELLO PIERROTTET, AIA

STAMP

PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC)
 VA U.S. Department of Veterans Affairs

DRAWING TITLE
 PARTITION DETAILS

APPROVED: Project Director

PHASE
 100% CONSTRUCTION DOCUMENTS

FLS
 FULLY SPRINKLERED

PROJECT TITLE
 EHRM INFRASTRUCTURE UPGRADES

LOCATION
 FORT MEADE, SOUTH DAKOTA

ISSUE DATE: 04/15/2022
 CHECKED BY: TMP
 DRAWN BY: JPR

PROJECT NUMBER
 568-21-701

BUILDING NUMBER
 GEN INFO

DRAWING NUMBER
 00-GI-007

GENERAL

1. THE FOLLOWING PROVISIONS ARE TO BE USED IN CONJUNCTION WITH VA SPECIAL PROVISIONS, VA STANDARD SPECIFICATIONS, AND ALL OTHER APPLICABLE JURISDICTIONS.
2. ANY REVISIONS TO THESE PLANS MUST BE REVIEWED AND APPROVED BY THE APPROPRIATE JURISDICTIONS.
3. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH THE PROJECT SITE AND BRING ANY DISCREPANCIES TO THE ATTENTION OF THE ENGINEER PRIOR TO UNDERTAKING OF THE AFFECTED WORK.
4. ANY DISCREPANCIES IN THESE DRAWINGS, SPECIFICATIONS, NOTES, AND THE SITE CONDITIONS SHALL BE REPORTED TO THE ENGINEER, WHO SHALL CORRECT SUCH DISCREPANCIES IN WRITING AFTER THOROUGHLY REVIEWING ANY CHANGES. ANY WORK DONE BY THE CONTRACTOR AFTER THE DISCOVERY OF SUCH DISCREPANCIES SHALL BE DONE AT THE CONTRACTOR'S RISK. THE CONTRACTOR SHALL VERIFY AND COORDINATE THE DIMENSIONS AMONG ALL DRAWINGS PRIOR TO PROCEEDING WITH ANY WORK.
5. A PRE-CONSTRUCTION MEETING SHALL BE HELD AT THE VA FACILITIES WITH THE APPLICANT, CONTRACTOR, ENGINEER, AND ALL APPLICABLE INSPECTORS PRIOR TO BEGINNING WORK.

ADDITIONAL PERMITS

6. VA SPECIFIC PERMITS MAY BE REQUIRED FOR ON-SITE WORK INCLUDING ALL RETAINING WALLS, GRADING, AND EROSION CONTROL. ADHERENCE TO ALL CONDITIONS OF THESE PERMITS IS REQUIRED AS A PART OF THIS PLAN. COORDINATE WITH C.O.R.
7. VA SPECIFIC PERMITS MAY BE REQUIRED FOR SIDEWALK INSTALLATION AS WELL AS CURB AND GUTTER REMOVAL AND DRIVEWAY CONSTRUCTION WHEN CONSTRUCTED AT BUILDING PERMIT STAGE. COORDINATE WITH C.O.R.

UTILITIES

8. THE EXISTING UNDERGROUND UTILITIES SHOWN HEREON ARE BASED UPON EXISTING RECORD DRAWINGS AND ARE NOT GUARANTEED TO BE ACCURATE, NOR ALL INCLUSIVE.
9. ALL UTILITIES MUST BE VERIFIED PRIOR TO CONSTRUCTION. IF THE PROJECT REQUIRES ANY EXCAVATION, THE DEVELOPER/CONTRACTOR IS REQUIRED TO CALL THE UTILITY UNDERGROUND LOCATION CENTER AT 811 AT LEAST TWO DAYS BEFORE STARTING SUCH EXCAVATION.
10. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO PROTECT, IN PLACE, ALL UTILITIES AND/OR STRUCTURES WHETHER SHOWN OR NOT SHOWN ON THIS PLAN. PROVIDE FALSEWORK AS IS REQUIRED TO TEMPORARILY SUPPORT ALL MATERIAL. DAMAGE DUE TO THE CONTRACTORS OPERATIONS SHALL BE REPAIRED AT THE CONTRACTORS EXPENSE.
11. DO NOT CUT OR DAMAGE EXISTING UTILITIES, STRUCTURAL MEMBERS, OR BUILDING FOUNDATIONS. HAND EXCAVATE IN LOCATIONS WHERE EXISTING UTILITIES ARE SUBJECT TO DAMAGE.

EXCAVATION

12. IF WORKERS ENTER ANY TRENCH OR OTHER EXCAVATION FOUR FEET OR MORE IN DEPTH THAT DOES NOT MEET THE OPEN PIT REQUIREMENTS OF SECTION 2-09.3(3)B, IT SHALL BE SHORED AND CRIBBED. ALL TRENCH SAFETY SYSTEMS SHALL MEET THE REQUIREMENTS OF STATE INDUSTRIAL SAFETY AND HEALTH ACT. THE CONTRACTOR ALONE SHALL BE RESPONSIBLE FOR ALL WORKER SAFETY, THE ENGINEER, NOR THE VA ASSUMES ANY RESPONSIBILITY.

PAVEMENT PREPARATION/RESTORATION

13. ADDITIONAL REMOVAL AND REPLACEMENT OF PAVEMENT MAY BE REQUIRED TO PROVIDE PROPER TRANSITION/CROWN AS DIRECTED BY INSPECTOR IN FIELD.
14. THE SUBGRADE COMPACTION SHALL BE TESTED BY A PROFESSIONAL GEOTECHNICAL CONSULTANT PRIOR TO PLACING THE BASE MATERIAL.
15. PAVEMENT RESTORATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH VA RESTORATION POLICY AND APPLICABLE STANDARD PLANS.
16. FINAL RESTORATION LIMITS SHALL BE DETERMINED IN THE FIELD BY INSPECTOR.

CONCRETE

17. CONCRETE PAVEMENT MIX DESIGN SHALL BE BASED ON STANDARD PLAN PD-01-PAVEMENT DESIGN STANDARDS.
18. COLD WEATHER CONCRETE WORK. THE FOLLOWING REQUIREMENTS FOR PLACING CONCRETE SHALL BE IN EFFECT FROM NOVEMBER 1 TO APRIL 1:
 - a. THE ENGINEER SHALL BE NOTIFIED AT LEAST 24 HOURS PRIOR TO ANY CONCRETE PLACEMENT.
 - b. WEATHER PERMITTING, ALL CONCRETE PLACEMENT SHALL BE COMPLETED NO LATER THAN 2:00 PM EACH DAY.
 - c. WHERE FORMS HAVE BEEN PLACED AND THE SUBGRADE HAS BEEN SUBJECTED TO SEVERE FROST, NO CONCRETE SHALL BE PLACED UNTIL THE GROUND IS COMPLETELY THAWED. AT THAT TIME, THE FORMS SHALL BE ADJUSTED AND SUBGRADE REPAIRED AS DETERMINED BY THE ENGINEER.
19. THE SLUMP FOR STANDARD CONCRETE USED FOR SIDEWALKS SHALL NOT EXCEED FOUR INCHES +/- ONE INCH.
20. ALL SIDEWALKS AND CURB RAMPS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ADA STANDARDS FOR ACCESSIBLE DESIGN, 28 CFR, PART 35 AND AS SUPPLEMENTED BY THE PUBLIC WORKS RIGHT OF WAY ACCESSIBILITY GUIDELINES (PROWAG).

EROSION CONTROL NOTES

21. WHEN CONSTRUCTION OPERATIONS ARE SUCH THAT DEBRIS FROM THE WORK IS DEPOSITED ON THE STREETS, THE CONTRACTOR SHALL IMMEDIATELY REMOVE ANY DEPOSITS OR DEBRIS WHICH MAY ACCUMULATE ON THE ROADWAY SURFACE. IF THE CONTRACTOR FAILS TO KEEP THE STREETS FREE FROM DEPOSITS AND DEBRIS RESULTING FROM THE WORK, THE CONTRACTOR SHALL, UPON ORDER OF THE INSPECTOR, PROVIDE FACILITIES FOR, AND REMOVE ALL CLAY, DIRT, OR OTHER DEPOSITS FROM THE TIRES OR BETWEEN WHEELS BEFORE TRUCKS OR OTHER EQUIPMENT WILL BE ALLOWED TO TRAVEL OVER PAVED STREETS. SHOULD THE CONTRACTOR FAIL OR REFUSE TO CLEAN THE STREETS IN QUESTION, OR THE TRUCKS OR EQUIPMENT IN QUESTION, JURISDICTION INSPECTOR MAY ORDER THE WORK SUSPENDED AT THE CONTRACTORS RISK UNTIL COMPLIANCE WITH THE CONTRACTORS OBLIGATIONS IS ASSURED, OR THE JURISDICTION INSPECTOR MAY ORDER THE STREETS IN QUESTION CLEANED BY OTHERS AND SUCH COSTS INCURRED IN ACHIEVING COMPLIANCE WITH THESE REQUIREMENTS, INCLUDING CLEANING OF THE STREETS, SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
22. THE CONTRACTOR SHALL PROTECT EXISTING DRAINAGE STRUCTURES USING ACCEPTABLE METHODS AND MATERIALS AS SHOWN ON THIS PLAN. IF THE METHODS AND MATERIALS AS SHOWN ON THIS PLAN ARE NOT ADEQUATE, THE JURISDICTION INSPECTOR MAY REQUIRE ADDITIONAL/ALTERNATIVE METHODS FOR EROSION CONTROL AND/OR PROTECTION OF EXISTING DRAINAGE STRUCTURES. ADDITIONAL OR ALTERNATIVE METHODS SHALL BE SUBMITTED BY THE DESIGN ENGINEER AND ACCEPTED BY THE JURISDICTION INSPECTOR. ANY DAMAGE CAUSED TO THE JURISDICTION STORMWATER SYSTEM AS A RESULT OF THE WORK OUTLINED ON THIS PLAN SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. RESOLVING SAID DAMAGE MAY INCLUDE, BUT NOT BE LIMITED TO, THE CLEANING OF THE DRAINAGE SYSTEM IN QUESTION BY THE CONTRACTOR.
23. WATERING PROVISIONS WHEN APPLICABLE MUST BE IN PLACE TO PREVENT DUST FROM BECOMING AIR BORNE. VIOLATION OF THIS CONDITION WILL RESULT IN A STOP WORK ORDER UNTIL CORRECTED.
24. FILL THAT WILL SUPPORT A STREET SECTION OR OTHER STRUCTURES SHALL BE PLACED UNDER THE INSPECTION OF A STATE LICENSED GEOTECHNICAL ENGINEER. SOIL TO BE PLACED SHALL BE TESTED AND COMPACTED TO 95% OF ITS MAXIMUM DENSITY. ENGINEER SHALL DOCUMENT EXISTING SITE CONDITIONS, SOIL AND ITS PLACEMENT AND ALLOWABLE BEARING CAPACITY SUBMITTED.
25. A STORMWATER POLLUTION PREVENTION PLAN (SWPPP) IS NOT REQUIRED FOR THIS PROJECT, AS THE CONSTRUCTION ACTIVITY WILL DISTURB LESS THAN AN ACRE OF LAND.


EROSION CONTROL MEASURES

26. MINIMUM EROSION CONTROL MEASURES SHALL INCLUDE:
 - a. CONSTRUCTION ENTRANCE (WHEN APPLICABLE)
 - b. PERIMETER EROSION/SEDIMENTATION CONTROL
 - c. PROTECTION OF CATCH BASINS
 - d. STABILIZATION OF EXPOSED SOILS
27. ALL EROSION CONTROL SHALL BE IN PLACE PRIOR TO CLEARING. THE CONTRACTOR SHALL CALL THE JURISDICTION INSPECTOR FOR INITIAL EROSION CONTROL INSPECTION PRIOR TO START OF WORK, AS DESCRIBED BELOW.
28. EROSION CONTROL MEASURES SHALL BE MAINTAINED AT ALL TIMES TO THE APPROVAL OF THE INSPECTOR.
29. CALL FOR INSPECTION UPON COMPLETION OF:
 - a. STAKING OF CLEARING LIMITS
 - b. INSTALLATION OF EROSION CONTROL AND PRIOR TO SITE GRADING
 - c. PRIOR TO REMOVAL OF EROSION CONTROL DEVICES
30. ALL MATERIAL REMOVED FROM SITE SHALL BE PLACED ONLY AT A PERMITTED SITE. VERIFY LOCATION OF DESTINATION OF MATERIAL PRIOR TO EXPORTATION.
31. TRAFFIC CONTROL PROVISIONS AS APPROVED BY THE CITY TRAFFIC ENGINEER SHALL BE ADHERED TO AT ALL TIMES.
32. TREES TO BE REMOVED SHALL BE CLEARLY MARKED FOR REMOVAL. TREES TO BE SAVED SHALL BE FENCED WITH BARRICADE FENCE AT THE DRIP LINE (OUTER EDGE OF TREE BRANCHES) TO KEEP CONSTRUCTION VEHICLES FROM COMPACTING ROOT ZONE AND KILLING TREES. THIS FENCING SHALL BE MAINTAINED UNTIL CONSTRUCTION ENDS.
33. TREE PROTECTION MEASURES TO BE INSTALLED WITH INITIAL TESC MEASURES AND SHALL BE MAINTAINED THROUGHOUT THE DURATION OF SITE WORK. REFER TO JURISDICTION STANDARD PLANS.
34. ALL REVISIONS TO THE APPROVED PLANS MUST BE APPROVED BY THE DESIGN ENGINEER, THE VA, PRIOR TO IMPLEMENTATION OF THE CHANGES

A
B
C
D
E
F


A
B
C
D
E
F

		CONSULTANT		ARCHITECT/ENGINEER OF RECORD		STAMP		PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC)		Drawing Title CIVIL - GENERAL NOTES		Phase 100% CONSTRUCTION DOCUMENTS		Project Title EHRM INFRASTRUCTURE UPGRADES		Project Number 568-21-701	
				A/E: GDM 1000 W STEUBEN ST, UNIT 3 BINDGE, WA 98605 P: 541.436.4723 ADAM GOODIN, PE						Approved: Project Director		FLS FULLY SPRINKLERED		Location FORT MEADE, SOUTH DAKOTA		Drawing Number CI0001	
Revisions:		Date:										Issue Date 4-15-2022		Checked AJG		Drawn RDR	



1 SECONDARY FIBER OPTICS PLAN
 STA. 200+00 - 206+00
 SCALE: 1"=20'-0"
 NORTH

NOTES:
 1. THE CONTRACTOR IS TO PROVIDE LOCATES, TEMPORARY SHORING, FALSEWORK, DEWATERING, AND OTHER SERVICES, TOOLS, AND SUPPLIES AS IS NECESSARY TO PERFORM THE CIVIL RELATED PORTIONS OF THE WORK.




2 SECONDARY FIBER OPTICS PROFILE
 STA. 200+00 - 206+00
 SCALE: H: 1"=20'-0" V: 1"=5'-0"

Revisions:	Date:	CONSULTANT	ARCHITECT/ENGINEER OF RECORD	STAMP	PROGRAM CONTRACTING ACTIVITY	Drawing Title	Phase	Project Title	Project Number		
					CENTRAL (PCAC)	CIVIL - SECONDARY FIBER OPTICS PLAN AND PROFILE	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES	568-21-701		
			A/E: GDM 1000 W STEUBEN ST, UNIT 3 BINDGE, WA 98605 P: 541.436.4723 ADAM GOODIN, PE		VA U.S. Department of Veterans Affairs	Approved: Project Director	FLS	Location	Building Number		
							FULLY SPRINKLERED	FORT MEADE, SOUTH DAKOTA			
								Issue Date	Checked	Drawn	Drawing Number
								4-15-2022	AJG	RDR	CU0108




1 SECONDARY FIBER OPTICS PLAN
 STA. 206+00 - 211+38
 SCALE: 1"=20'-0"
 0 10 20 40'

NOTES:
 1. THE CONTRACTOR IS TO PROVIDE LOCATES, TEMPORARY SHORING, FALSEWORK, DEWATERING, AND OTHER SERVICES, TOOLS, AND SUPPLIES AS IS NECESSARY TO PERFORM THE CIVIL RELATED PORTIONS OF THE WORK.




2 SECONDARY FIBER OPTICS PROFILE
 STA. 206+00 - 211+38
 SCALE: H: 1"=20'-0" V: 1"=5'-0"

Revisions:	Date:	CONSULTANT	ARCHITECT/ENGINEER OF RECORD	STAMP	PROGRAM CONTRACTING ACTIVITY	Drawing Title	Phase	Project Title	Project Number
					CENTRAL (PCAC)	CIVIL - SECONDARY FIBER OPTICS PLAN AND PROFILE	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES	568-21-701
			GDM ARCHITECTS • ENGINEERS	Professional Engineer Seal: GELYN J. DEZMAN, No. 84232, STATE OF FLORIDA	VA U.S. Department of Veterans Affairs	Approved: Project Director	FLS FULLY SPRINKLERED	Location: FORT MEADE, SOUTH DAKOTA	Building Number
								Issue Date: 4-15-2022	Checked: AJG
								Drawn: RDR	Drawing Number: CU0109




1 SECONDARY FIBER OPTICS PLAN
 STA. 300+00 - 306+00
 SCALE: 1"=20'-0"
 NORTH

NOTES:
 1. THE CONTRACTOR IS TO PROVIDE LOCATES, TEMPORARY SHORING, FALSEWORK, DEWATERING, AND OTHER SERVICES, TOOLS, AND SUPPLIES AS IS NECESSARY TO PERFORM THE CIVIL RELATED PORTIONS OF THE WORK.




2 SECONDARY FIBER OPTICS PROFILE
 STA. 300+00 - 306+00
 SCALE: H: 1"=20'-0" V: 1"=5'-0"

Revisions:	Date:	CONSULTANT	ARCHITECT/ENGINEER OF RECORD	STAMP	PROGRAM CONTRACTING ACTIVITY	Drawing Title	Phase	Project Title	Project Number	
					CENTRAL (PCAC)	CIVIL - SECONDARY FIBER OPTICS PLAN AND PROFILE	100% CONSTRUCTION DOCUMENTS	EHRM INFRASTRUCTURE UPGRADES	568-21-701	
			GDM ARCHITECTS • ENGINEERS	Professional Engineer Seal	VA U.S. Department of Veterans Affairs	Approved: Project Director	FLS FULLY SPRINKLERED	Location	Drawing Number	
								FORT MEADE, SOUTH DAKOTA	CU0110	
								Issue Date	Checked	Drawn
								4-15-2022	AJG	RDR




1 SECONDARY FIBER OPTICS PLAN
 STA. 400+00 - 404+55
 SCALE: 1"=20'-0"
 0 10' 20' 40'

NOTES:
 1. THE CONTRACTOR IS TO PROVIDE LOCATES, TEMPORARY SHORING, FALSEWORK, DEWATERING, AND OTHER SERVICES, TOOLS, AND SUPPLIES AS IS NECESSARY TO PERFORM THE CIVIL RELATED PORTIONS OF THE WORK.




2 SECONDARY FIBER OPTICS PROFILE
 STA. 400+00 - 404+55
 SCALE: H: 1"=20'-0" V: 1"=5'-0"


Revisions:	Date:	CONSULTANT	ARCHITECT/ENGINEER OF RECORD	STAMP	PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC)	Drawing Title CIVIL - SECONDARY FIBER OPTICS PLAN AND PROFILE	Phase 100% CONSTRUCTION DOCUMENTS	Project Title EHRM INFRASTRUCTURE UPGRADES	Project Number 568-21-701		
						Approved: Project Director	FLS FULLY SPRINKLERED	Location FORT MEADE, SOUTH DAKOTA	Building Number		
			A/E: GDM 1000 W STEUBEN ST, UNIT 3 BINDGE, WA 98605 P: 541.436.4723 ADAM GOODIN, PE					Issue Date 4-15-2022	Checked AJG	Drawn RDR	Drawing Number CU0112




KEY PLAN
145-SF-100 1/16" = 1'-0"




1 SECTION
145-SF-100 3/4" = 1'-0"




2 SECTION
145-SF-100 1" = 1'-0"




3 SECTION
145-SF-100 1" = 1'-0"




FOUNDATION PLAN
145-SF-100 1/8" = 1'-0"



4 SECTION
145-SF-100 1" = 1'-0"




5 SECTION
145-SF-100 1" = 1'-0"




6 PARTIAL ELEVATION
145-SF-100 1/8" = 1'-0"


NOTES:
1. SEE ARCH DRAWINGS FOR SIZE & LOCATION OF NEW DOOR



7 PLAN SECTION
145-SF-100 1 1/2" = 1'-0"



8 HEADER ATTACHMENT SECTION
145-SF-100 1 1/2" = 1'-0"



9 PLAN SECTION
145-SF-100 3" = 1'-0"

Revisions:	Date:

CONSULTANT
ENGINEER
KRAMER GEHLEN & ASSOCIATES
400 COLUMBIA STREET, STE 240
VANCOUVER, WA 98660
360.693.1621

ARCHITECT/ENGINEER OF RECORD
A/E:
GDM
1000 W STEUBEN ST. UNIT 3
BINGEN, WA 98605
541.436.4723
ADAM GODDIN, PE

STAMP
PROFESSIONAL ENGINEER
REG. NO. 13889
EXPIRES 09/31/2022

PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC)
VA U.S. Department of Veterans Affairs


DRAWING TITLE
BUILDING 145 PLANS
APPROVED: Project Director

PHASE
100% CONSTRUCTION DOCUMENTS
FLS
FULLY SPRINKLERED


PROJECT TITLE
EHRM INFRASTRUCTURE UPGRADES
LOCATION
FORT MEADE, SOUTH DAKOTA
ISSUE DATE
05/25/2022
CHECKED BY
MH CNB
DRAWN BY
ATW

PROJECT NUMBER
568-21-701
BUILDING NUMBER
BLDG 145
DRAWING NUMBER
145-SF-100


A B C D E F




A PARTIAL PLAN
296-SF-100 1/8" = 1'-0"



1 SECTION
296-SF-100 1" = 1'-0"



2 SECTION
296-SF-100 1" = 1'-0"



3 SECTION
296-SF-100 1" = 1'-0"

4 SECTION
296-SF-100 3" = 1'-0"

DESIGN STANDARD
2021 INTERNATIONAL BUILDING CODE (IBC) WITH THE VA H-18-8 SEISMIC DESIGN STANDARD

DESIGN CRITERIA
1. DESIGN ALL LOADS FOR NEW CONSTRUCTION, UNLESS NOTED OTHERWISE.
2. LIVE LOADS
A. FLOOR LIVE LOADS: 100 PSF
3. SEISMIC DESIGN DATA
A. RISK CATEGORY: II
B. SEISMIC IMPORTANCE FACTOR: I_s = 1.0
C. MAPPED SPECTRAL RESPONSE ACCELERATION PARAMETERS: S₁ = 0.122 g S₂ = 0.039 g
D. SITE CLASSIFICATION: A
E. DESIGN SPECTRAL RESPONSE ACCELERATION PARAMETERS: S₁₀ = 0.130 g S₀₁ = 0.063 g
F. SEISMIC DESIGN CATEGORY: D

GENERAL
1. THESE STRUCTURAL NOTES ARE A SUPPLEMENT TO THE SPECIFICATIONS.
2. SPECIFICATIONS AND CODES REFERENCED IN THESE NOTES ARE THE VERSIONS MOST RECENTLY ADOPTED BY THE PERMITTING AUTHORITY.
3. VERIFY DIMENSIONS AND CONDITIONS WITH THE ARCHITECTURAL DRAWINGS. FIELD VERIFY DIMENSIONS AND ELEVATIONS RELATIVE TO THE EXISTING STRUCTURE PRIOR TO FABRICATION OF MATERIALS.
4. FOR FEATURES OF CONSTRUCTION NOT FULLY SHOWN, PROVIDE THE SAME TYPE AND CHARACTER AS SHOWN FOR SIMILAR CONDITIONS, SUBJECT TO REVIEW BY THE ARCHITECT AND STRUCTURAL ENGINEER OF RECORD.
5. APPLY, PLACE, ERECT OR INSTALL ALL PRODUCTS AND MATERIALS IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.
6. ADEQUATELY BRACE STRUCTURE AND ALL STRUCTURAL COMPONENTS AGAINST WIND, LATERAL EARTH AND SEISMIC FORCES UNTIL THE PERMANENT LATERAL-FORCE RESISTING SYSTEMS HAVE BEEN INSTALLED.
7. PERMANENTLY ATTACH FIRST FLOOR TO WALLS OR SHORE WALLS PRIOR TO BACK-FILLING AGAINST STRUCTURE.
8. SUBMITTALS:
A. SUBMIT SHOP DRAWINGS FOR:
a. REINFORCING STEEL
B. SUBMIT SHOP DRAWINGS PRIOR TO FABRICATION OF MATERIAL.

STRUCTURAL FILL OR BACK-FILL
1. STRUCTURAL FILL MATERIAL:
A. SAND AND GRAVEL MIXTURE OR CRUSHED ROCK.
B. WELL GRADED FROM COARSE-TO-FINE WITH LESS THAN 10% BY WEIGHT OF THE MINUS 3/4" FRACTION PASSING THE NO. 200 SIEVE.
C. FREE OF ORGANICS, RUBBISH, CLAY BALLS AND ROCKS LARGER THAN 4".
2. PLACE STRUCTURAL FILL IN LOOSE LIFTS, MAXIMUM OF 8" IN THICKNESS.
3. COMPACT STRUCTURAL FILL TO A MINIMUM DENSITY OF 95% OF MAXIMUM DRY DENSITY, AS DETERMINED BY ASTM D 1557.
4. VERIFY ADEQUACY OF STRUCTURAL FILL COMPACTION WITH RANDOM FIELD DENSITY TESTS IN ACCORDANCE WITH REQUIREMENTS OF "STRUCTURAL TESTS AND SPECIAL INSPECTIONS", IBC CHAPTER 17.
5. COMPACT STRUCTURAL FILL WITHIN 5'-0" OF RETAINING OR BASEMENT WALLS WITH LIGHT-WEIGHT, HAND-HELD EQUIPMENT. EXERCISE CARE TO AVOID DAMAGE TO WALLS.

FOUNDATIONS
1. FOUNDATION SIZES BASED ON AN ALLOWABLE SOIL BEARING PRESSURE OF 1,500 PSF DEAD AND LIVE/SNOW LOADS WITH AN ALLOWABLE ONE-THIRD INCREASE FOR WIND AND SEISMIC.
2. PLACE FOOTINGS ON FIRM, UNDISTURBED ORIGINAL SOIL, OR ON STRUCTURAL FILL. SEE "STRUCTURAL FILL OR BACK-FILL" NOTES FOR STRUCTURAL FILL INFORMATION.

CONCRETE REINFORCING STEEL

- REINFORCING STEEL SHALL BE ASTM A615, GRADE 60.
- DETAIL, FABRICATE AND PLACE REINFORCING ACCORDING TO ACI 315, DETAILS AND DETAILING OF CONCRETE REINFORCEMENT.
- TYPICAL REINFORCING (MINIMUM, UNLESS NOTED OTHERWISE ON DRAWINGS):
A. CORNERS AND INTERSECTIONS OF WALLS AND FOUNDATIONS, PRE-CAST PANEL CORNERS: CORNER BARS EQUAL IN SIZE AND NUMBER TO HORIZONTAL REINFORCING. LEG LENGTH: 48 BAR DIAMETER (2'-0" MINIMUM).
4. DO NOT FIELD BEND, DISPLACE, WELD, HEAT OR CUT REINFORCING UNLESS INDICATED ON THE DRAWINGS, OR APPROVED BY STRUCTURAL ENGINEER OF RECORD.
5. MINIMUM COVER FROM CONCRETE SURFACES TO REINFORCING:
3" TO BOTTOM OF FOOTING
CENTER OF SLABS-ON-GRADE
6. REINFORCING LAP SPLICES (INCHES): CONFORM WITH ACI 318 "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE", AS SHOWN BELOW, UNLESS NOTED OTHERWISE ON DRAWINGS:

BAR SIZE	3000 PSI		4000 PSI		5000 PSI	
	TOP BARS	OTHER BARS	TOP BARS	OTHER BARS	TOP BARS	OTHER BARS
#3	28	22	24	19	22	17
#4	37	29	32	25	29	22
#5	47	36	40	31	36	28
#6	56	43	48	37	43	33

LAP SPLICE NOTES:
A. TOP BARS ARE DEFINED AS HORIZONTAL BARS PLACED SUCH THAT MORE THAN 12" OF CONCRETE IS PLACED BELOW THE BARS.
B. SPLICE LENGTH BASIS: CLASS B, CASE 1 SPLICE, WITH CENTER-TO-CENTER BAR SPACING OF GREATER THAN 3 BAR DIAMETERS.

CAST-IN-PLACE CONCRETE
1. ALL CONCRETE MATERIALS, FORM WORK, MIXING, PLACING AND CURING SHALL BE IN ACCORDANCE WITH:
A. ACI 301 "STANDARD SPECIFICATION FOR STRUCTURAL CONCRETE";
B. ACI 305 "RECOMMENDED PRACTICE FOR HOT WEATHER CONCRETING" AND
C. ACI 306 "RECOMMENDED PRACTICE FOR COLD WEATHER CONCRETING".
2. CONCRETE MIX DESIGN:
UNLESS NOTED OTHERWISE, ALL CONCRETE STRENGTH SHALL BE:
3,000 PSI FOR: FOOTINGS
4,000 PSI FOR: INTERIOR SLABS-ON-GRADE (MAXIMUM WATER/CEMENT RATIO = 0.40; MINIMUM COARSE AGGREGATE SIZE = 1")
3,000 PSI FOR: OTHER CONCRETE
NOTES:
A. UNLESS NOTED OTHERWISE, CONCRETE STRENGTH SHALL BE OBTAINED AT A MINIMUM OF 28 DAYS AFTER PLACING AS DETERMINED BY LABORATORY-CURED CONCRETE CYLINDER TESTS.
B. NO WATER SHALL BE ADDED TO THE CONCRETE OTHER THAN THAT REQUIRED BY THE MIX DESIGN APPROVED BY THE ENGINEER OF RECORD. WATER ADDED AFTER INITIAL CONCRETE BATCHING SHALL BE SPECIAL INSPECTED.
C. PREPARE MIX DESIGNS FOR EACH TYPE OF CONCRETE BY EITHER LABORATORY TRIAL BATCH OR FIELD EXPERIENCE METHODS AS SPECIFIED IN ACI 301.
D. USE PORTLAND CEMENT TYPE I OR II; CONFORM WITH ASTM C 150; SUPPLY FROM 1 SOURCE.
E. AGGREGATES SHALL CONFORM WITH ASTM C 33 AND BE THOROUGHLY CLEANED AND WASHED PRIOR TO USE.
F. REPLACE UP TO 20% OF CEMENT WITH FLY ASH. FLY ASH SHALL CONFORM WITH ASTM C 618, CLASS C OR F. CONCRETE MIX STRENGTH TEST DATA SHALL BE PROVIDED.
G. CONCRETE EXPOSED TO WEATHER SHALL HAVE 5% ± 1% ENTRAINED AIR, BY VOLUME, AND SHALL CONFORM WITH ASTM C 260.
H. SLABS-ON-GRADE SHALL UTILIZE SUPER PLASTICIZERS.
3. CONCRETE MIX PROPORTIONS:
A. PROPORTION ACCORDING TO ACI 318, "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE";
B. SUBMIT MIX DESIGNS, WITH COMPLETE STATISTICAL BACKUP, FOR REVIEW.
4. SAMPLING AND TESTING OF CONCRETE:
A. CONCRETE COMPRESSIVE STRENGTH OF LABORATORY CURED CYLINDERS SHALL BE TESTED AFTER THE SPECIFIED PERIOD AT 28 DAYS OR 56 DAYS AS NOTED.
B. SAMPLE, CURE AND TEST CONCRETE CYLINDERS ACCORDING TO APPLICABLE ASTM SPECIFICATIONS.
C. ACCEPTANCE OF COMPRESSIVE STRENGTH TEST RESULTS SHALL BE GOVERNED BY ACI 318, CHAPTER 8.
D. TEST A MINIMUM OF 3 CONCRETE TEST CYLINDERS FOR EACH 150 CU. YARDS OF CONCRETE, NOT LESS THAN ONE FOR EACH 5,000 SQUARE FEET OF SURFACE AREA FOR SLABS AND WALLS, OR EACH DAY OF POUR, FOR EACH CONCRETE STRENGTH. TEST 1 CYLINDER AT 7 DAYS AND 2 CYLINDERS AT 28 DAYS.
E. CAST 1 ADDITIONAL CYLINDER FOR STRENGTH VERIFICATION, IF PROBLEMS HAVE DEVELOPED FROM PREVIOUS 28 DAY BREAKS.
5. JOINTS:
A. CONSTRUCTION JOINTS BETWEEN FOOTINGS AND WALLS, COLUMNS OR PLASTERS AND THE SLABS THEY SUPPORT AND WALL CONSTRUCTION JOINTS: ROUGHEN CONTACT AREA TO AN APPROXIMATE 14° ANGLE, LEAVING THE CONTACT SURFACE CLEAN AND FREE OF OIL. LEAVE UNFINISHED.
B. CONSTRUCTION JOINTS KEYWAYS: PROVIDE WHERE SHOWN ON DRAWINGS.
C. SUBMIT LOCATIONS AND DETAILS OF PROPOSED CONSTRUCTION JOINTS NOT DETAILED ON THE DRAWINGS FOR REVIEW.
6. CHAMFER EXPOSED CORNERS 3/4" UNLESS NOTED OTHERWISE.

POST-INSTALLED ANCHORS
FOR ANCHORS ON THE CONSTRUCTION DOCUMENTS NOT NOTED WITH A SPECIFIC PRODUCT TYPE OR MANUFACTURER, THE CONTRACTOR SHALL USE APPROVED ANCHORS SPECIFIED IN THE TABLE BELOW.

ITEM	APPROVED PRODUCTS	ICCB
EXPANSION ANCHOR (CONCRETE)	HILTI KWIK BOLT T2 SIMPSON STRONG BOLT Z DEWALT POWER STUD + SD2	ESR-1917 ESR-3037 ESR-2502
SHALLOW ADHESIVE ANCHOR (CONCRETE)	HILTI HIT-HY 200 SIMPSON SET-XP DEWALT AC208+ DEWALT PURE110+ DEWALT AC100+ GOLD	ESR-3187 ESR-2508 ESR-4027 ESR-3558 ESR-2582
SCREW ANCHOR (CONCRETE)	HILTI HUS-EZ SIMPSON TITEN HD DEWALT SCREW BOLT + DEWALT SNAKE +	ESR-3027 ESR-2713 ESR-3889 ESR-2272

COLD-FORMED STEEL CONNECTIONS
1. ALL PLATES AND LEDGERS SHALL BE ANCHORED WITH A MINIMUM OF 3 ANCHORS PER PIECE.
2. ALL FRAMING CONNECTORS SHALL BE SIMPSON OR APPROVED. FILL ALL HOLES WITH SCREWS AS SPECIFIED BY THE HANGER MANUFACTURER, UNLESS NOTED OTHERWISE.
3. ALL SCREWS TO BE #10 SELF-DRILLING SHEET METAL (SDSM) SCREWS, UNLESS NOTED OTHERWISE.

COLD FORMED STEEL FRAMING
1. ALL FABRICATION, ERECTION AND IDENTIFICATION OF COLD FORMED STEEL FRAMING SHALL CONFORM WITH IBC SECTIONS 2209, 2210 AND 2211, AND A.I.S.I. "SPECIFICATION FOR THE DESIGN OF COLD-FORMED STEEL STRUCTURAL MEMBERS".
2. MATERIAL:
A. ASTM A 653/653M, GRADE D (F_y = 80 KSI) FOR 54 MIL AND THICKER STOCK.
B. ASTM A 653/653M, GRADE A (F_y = 33 KSI) FOR 43 MIL AND THINNER STOCK.
3. FASTENING OF COMPONENTS SHALL BE WITH SELF-DRILLING SHEET METAL (SDSM) SCREWS, UNLESS NOTED OTHERWISE.
A. SCREW SPACING AND EDGE DISTANCE SHALL BE NOT LESS THAN 3X THE NOMINAL SCREW DIAMETER.
B. PENETRATIONS OF SCREWS THROUGH JOINED MATERIAL SHOULD NOT BE LESS THAN 3 EXPOSED THREADS.
C. WHERE FEASIBLE, INSTALL SCREWS FROM THINNER MATERIAL TO THICKER MATERIAL.
D. SCREWS SHALL BE INSTALLED AND TIGHTENED IN ACCORDANCE WITH SCREW MANUFACTURER'S RECOMMENDATIONS.
4. STEEL STUDS OR JOISTS SHALL HAVE STIFFENED LIPS, UNLESS NOTED OTHERWISE, AND MANUFACTURED BY MEMBERS OF THE STEEL STUD MANUFACTURER'S ASSOCIATION. SIZES AND GAUGE ARE AS NOTED ON DRAWINGS.
5. PROVIDE ALL ACCESSORIES INCLUDING, BUT NOT NECESSARILY LIMITED TO, TRACKS, CLIPS, WEB STIFFENERS, ANCHORS, FASTENING DEVICES AND OTHER ACCESSORIES REQUIRED FOR A COMPLETE AND PROPER INSTALLATION.
6. END BLOCKING SHALL BE PROVIDED WHERE JOIST ENDS ARE NOT OTHERWISE RESTRAINED FROM ROTATION.
7. JOISTS SHALL BE LOCATED DIRECTLY OVER BEARING STUDS, UNLESS NOTED OTHERWISE, WITHIN A TOLERANCE OF ±1/2".
8. SPLICES IN AXIALLY LOADED STUDS SHALL NOT BE PERMITTED.
9. ALL STUDS, JAMBS, HEADERS, AND SILLS SHALL BE FULL LENGTH MEMBERS BETWEEN SUPPORTS.
10. EACH FLANGE OF STUDS SHALL BE SECURELY ATTACHED TO FLANGES OF BOTH UPPER AND LOWER TRACKS.
11. WHEN METAL STUDS ARE USED IN BEARING WALL CONSTRUCTION, STUDS MUST FIT TIGHTLY INTO THE TOP AND BOTTOM TRACKS. END GAPS WILL NOT BE ALLOWED.

SPECIAL INSPECTION PROGRAM

INSPECTION TASK / TYPE OF WORK	CONTINUOUS*	PERIODIC*	COMMENTS
GRADING, EXCAVATION & FILL		X	REF. PROJECT SPECIFICATION
CONCRETE		X	
PLACEMENT OF REINFORCING STEEL		X	
PLACING OF REINFORCED CONCRETE	X		
TAKING OF TEST SPECIMENS	X		
COLD-FORMED STEEL FRAMING		X	
VERIFY MEMBER SIZES, CONNECTIONS & DEFLECTION HEADS		X	
VERIFY MEMBER SIZES AND CONNECTIONS FOR SEISMIC RESISTING SYSTEMS		X	PER IBC 1705 AND 1707.4
VERIFY MEMBER SIZES AND CONNECTIONS FOR WIND-RESISTING SYSTEMS AND COMPONENTS		X	PER IBC 1705.4
OTHER			PER ICC/IBC EVALUATION REPORTS
POST-INSTALLED ANCHORS IN CONCRETE AND MASONRY			

* FREQUENCY OF INSPECTION, WHICH MAY BE CONTINUOUS DURING THE TASK LISTED OR PERIODICALLY DURING THE TASK LISTED, AS DEFINED IN THE TABLE.

SPECIAL INSPECTION PROGRAM FOOTNOTES:
1. PROVIDE SPECIAL INSPECTION, SPECIAL TESTING, REPORTING AND COMPLIANCE PROCEDURES ACCORDING TO CHAPTER 17 OF THE INTERNATIONAL BUILDING CODE.
2. SPECIAL INSPECTOR QUALIFICATIONS: DEMONSTRATE COMPETENCE, TO THE SATISFACTION OF THE BUILDING OFFICIAL, FOR INSPECTION OF THE PARTICULAR TYPE OF CONSTRUCTION OR OPERATION IN QUESTION.
3. PRIOR TO THE BEGINNING OF CONSTRUCTION, REVIEW THE SPECIAL INSPECTION REQUIREMENTS WITH THE ARCHITECT, ENGINEER, BUILDING OFFICIAL, GENERAL CONTRACTOR AND SPECIAL INSPECTORS.
4. DUTIES OF THE SPECIAL INSPECTOR INCLUDE, BUT ARE NOT LIMITED TO:
A. OBSERVE THE WORK FOR CONFORMANCE WITH THE APPROVED PERMIT DRAWINGS AND SPECIFICATIONS. BRING DISCREPANCIES TO THE IMMEDIATE ATTENTION OF THE GENERAL CONTRACTOR FOR CORRECTION, THEN, IF UNCORRECTED, TO THE ENGINEER AND TO THE BUILDING OFFICIAL.
B. FURNISH INSPECTION REPORTS FOR EACH INSPECTION TO THE ARCHITECT, ENGINEER, GENERAL CONTRACTOR AND COR IN A TIMELY MANNER.
C. SUBMIT A FINAL REPORT STATING WHETHER THE WORK REQUIRING SPECIAL INSPECTION WAS INSPECTED, AND WHETHER THE WORK IS IN CONFORMANCE WITH THE APPROVED PERMIT DRAWINGS AND SPECIFICATIONS.
5. DUTIES OF THE GENERAL CONTRACTOR INCLUDE, BUT ARE NOT LIMITED TO:
A. NOTIFY SPECIAL INSPECTOR THAT WORK IS READY FOR INSPECTION AT LEAST 24 HOURS BEFORE INSPECTION IS REQUIRED.
B. MAINTAIN ACCESS TO WORK REQUIRING SPECIAL INSPECTION UNTIL IT HAS BEEN OBSERVED AND INDICATED TO BE IN CONFORMANCE BY THE SPECIAL INSPECTOR AND APPROVED BY THE BUILDING OFFICIAL.
C. PROVIDE THE SPECIAL INSPECTOR WITH ACCESS TO APPROVED PERMIT DRAWINGS AND SPECIFICATIONS AT THE JOB SITE.
D. MAINTAIN JOB-SITE COPIES OF ALL REPORTS SUBMITTED BY THE SPECIAL INSPECTOR.
6. DEFINITIONS:
A. CONTINUOUS INSPECTION: THE SPECIAL INSPECTOR IS OBSERVING THE WORK REQUIRING SPECIAL INSPECTION AT ALL TIMES.
B. PERIODIC INSPECTION: THE SPECIAL INSPECTOR IS ON SITE AS REQUIRED TO CONFIRM THAT THE WORK REQUIRING SPECIAL INSPECTION IS IN CONFORMANCE.

SPECIAL TESTING REQUIREMENTS
1. STRUCTURAL FILL OR BACK-FILL: VERIFY COMPACTION WITH RANDOM FIELD DENSITY TESTS.
2. STRUCTURAL CONCRETE: SAMPLE AND TEST ACCORDING TO STRUCTURAL NOTES.

Revisions:	Date:

CONSULTANT
ENGINEER
KRAMER GEHLEN & ASSOCIATES
400 COLUMBIA STREET, STE 240
VANCOUVER, WA 98660
360.693.1621

ARCHITECT/ENGINEER OF RECORD
A/E:
GDM
1000 W STEUBEN ST. UNIT 3
BINGEN, WA 98605
541.436.4723
ADAM GODDIN, PE

STAMP
REGISTERED PROFESSIONAL ENGINEER
13839
10/24/2022
SOUTH DAKOTA
EXP. 05/31/2022

PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC)
U.S. Department of Veterans Affairs

DRAWING TITLE
BUILDING T296 PLANS
APPROVED: Project Director

PHASE
100% CONSTRUCTION DOCUMENTS
FLS
FULLY SPRINKLERED

PROJECT TITLE
EHRM INFRASTRUCTURE UPGRADES
LOCATION
FORT MEADE, SOUTH DAKOTA
ISSUE DATE
05/25/2022
CHECKED BY
CNB
DRAWN BY
ATW

PROJECT NUMBER
568-21-701
BUILDING NUMBER
BLDG T296
DRAWING NUMBER
296-SF-100

DEMOLITION LEGEND

- INDICATES BUILT ITEM TO BE REMOVED
- INDICATES LIGHT FIXTURE TO BE REMOVED
- INDICATES EXTENT OF ICRA CLASS SCOPE
- CABLE INSTALLATION ROUTE. FIELD VERIFY CONDITIONS PRIOR TO COMMENCEMENT OF WORK. SEE TELECOMM DRAWINGS FOR EXTENT OF WORK

DEMOLITION GENERAL NOTES

1. SEE G SERIES SHEETS FOR ALL DEMOLITION NOTES & HAZARDOUS MATERIAL NOTES
2. MAINTAIN FIRE SUPPRESSION SYSTEM OPERATIONAL DURING CONSTRUCTION WORK. FIRE SUPPRESSION CONTRACTOR TO REMOVE DOWNWARD HEADS AND TURN UPWARDS. PROVIDE NEW FIRE SUPPRESSION HEAD IN TELECOMMUNICATION ROOMS (TR). WORK TO BE CONDUCTED WITHIN ONE WORKING SHIFT. SEE ADDITIONAL PROJECT NOTES ON COVER SHEET.



KEY NOTES

- 02-03 CAREFULLY REMOVE EXISTING DOOR, FRAME AND HARDWARE. RETURN TO OWNER
- 02-06 DEMO EXISTING WALL IN ITS ENTIRETY INCLUDING ANY WALL MOUNTED DEVICES. TERMINATE CONDUITS AT NEAREST J-BOX. PREP FLOOR TO RECEIVE NEW FINISH
- 02-07 CORE DRILL EXISTING WALL AND PREPARE FOR PLUMBING PIPE INSTALLATION. COORDINATE WITH MECHANICAL DRAWINGS. SEAL AND MAINTAIN WALL ENVELOPE AND INTEGRITY AFTER COMPLETION OF WORK
- 02-12 DEMORELOCATE EXISTING ELECTRICAL PANELS. SEE ELECTRICAL AND TELECOM DRAWINGS
- 02-25 CORE DRILL THROUGH FLOOR NEW PIPE OR CONDUIT INSTALLATION. APPLY APPROPRIATE HILT FIRE RATED SEAL FOR TYPE OF PENETRATION. SEE MEP OR TELECOM DRAWINGS FOR COORDINATION
- 02-32 INSTALL SELF LEVELING COMPOUND FULL EXTENT OF FLOORING REMOVAL. PREPARE TO RECEIVE NEW FINISHES IN TR ROOM. SEAL OTHERWISE
- 02-56 CONTRACTOR TO ROUTE CONDUIT IN LEAST DESTRUCTIVE MANNER TO LOCATIONS AS INDICATED IN TELECOMMUNICATION DRAWINGS. CONTRACTOR TO BE RESPONSIBLE TO VISIT SITE AND UNDERSTAND ROUTING AND MATERIAL TREATMENT. PATCH AND FINISH TO MATCH EXISTING MATERIALS. TYPICAL AT ALL DATA DROP LOCATIONS
- 05-02 SECURITY GRILL. 2" x 2" x 10GA WIRE MESH WELDED TO 1 1/2" x 1 1/4" x 13GA ROLL FORMED ANGLE FRAME. PROVIDE 3 CLIPS. ANCHOR DIRECTLY ONTO EXISTING WALL. CONTRACTOR TO VERIFY ACTUAL WINDOW SIZE PRIOR TO GRILL FABRICATION
- 09-02 PATCH ALL DAMAGED WORK ON EXISTING SURFACES ABOVE AND BELOW CEILING TILES. PAINT ALL WALLS. PROVIDE NEW RESILIENT 6TH RESILIENT WALL BASE
- 13-01 ICRA CLASS I. SEE SPEC SECTION 01 35 26 FOR REQUIREMENTS AND WORKING HOURS RESTRICTIONS
- 13-02 ICRA CLASS II. SEE SPEC SECTION 01 35 26 FOR REQUIREMENTS AND WORKING HOURS RESTRICTIONS
- 13-06 INFECTION PREVENTION. FIRE RATED. 6MM PLASTIC BARRIER SEALED TOP, BOTTOM, AND SIDES. PROVIDE VESTIBULE AREA FOR GOINING AND UNGOINING AND NEGATIVE PRESSURE WITHIN CONSTRUCTION AREA IN ICRA CLASS IV. SEE SPECS FOR OTHER ICRA CONSTRUCTION REQUIREMENTS
- 23-08 NEW REFRIGERANT PIPE LINES ROUTING SHOWN FOR REFERENCE ONLY. SEE MECHANICAL DRAWINGS FOR ACTUAL ROUTING. CONTRACTOR TO REMOVE CEILING TILES ALONG ROUTE OUTSIDE OF TR'S AND REPLACE WITHIN WORKING SHIFT. CONDUCT INFECTION PREVENTION MEASURES AS SPECIFIED
- 26-13 NEW CABLE TRAY ROUTING SHOWN FOR REFERENCE ONLY. SEE TELECOMMUNICATION DRAWINGS FOR ACTUAL ROUTING. CONDUCT INFECTION PREVENTION MEASURES AS SPECIFIED


ROOM ALLOCATION LEGEND

- PROPOSED NEW CABINET / TR / MCR LOCATION
- PROPOSED EXPANSION TO TR
- EXISTING TR WITH POWER AND FIBER UPGRADES. SEE TELECOM AND ELECTRICAL DRAWINGS
- ABANDONED ROOM
- ROOM TO REMAIN, NO WORK
- REMODEL REQUIRED DUE TO EHRM IMPACT


PROJECT KEY PLAN



2 BASEMENT TCB1 DEMOLITION PLAN
1/4" = 1'-0"



1 53 - BASEMENT DEMOLITION FLOOR PLAN
1/8" = 1'-0"



DEMOLITION LEGEND

- INDICATES BUILT ITEM TO BE REMOVED
- INDICATES LIGHT FIXTURE TO BE REMOVED
- - - - - INDICATES EXTENT OF ICRA CLASS SCOPE
- ▨ CABLE INSTALLATION ROUTE, FIELD VERIFY CONDITIONS PRIOR TO COMMENCEMENT OF WORK, SEE TELECOM DRAWINGS FOR EXTENT OF WORK

DEMOLITION GENERAL NOTES

1. SEE G SERIES SHEETS FOR ALL DEMOLITION NOTES & HAZARDOUS MATERIAL NOTES
2. IN HOSPITAL OCCUPANCY, CONTRACTOR ARE TO USE A CONSTRUCTION CONTAINMENT CUBE WITH HEPA VACUUM TO MAINTAIN NEGATIVE PRESSURE AS A MEANS TO ACCESS AREAS ABOVE CEILING TILES. THIS INCLUDES ALL PATIENT CORRIDORS AND ALL ACUTE CARE PATIENT AREAS. THIS IS IN CONJUNCTION WITH THE HOSPITALS INFECTION PREVENTION MEASURES AND ICRA PROTOCOLS.
3. MAINTAIN FIRE SUPPRESSION SYSTEM OPERATIONAL DURING CONSTRUCTION WORK. FIRE SUPPRESSION CONTRACTOR TO REMOVE DOWNWARD HEADS AND TURN UPWARS, PROVIDE NEW FIRE SUPPRESSION HEAD IN TELECOMMUNICATION ROOMS (TR). WORK TO BE CONDUCTED WITHIN ONE WORKING SHIFT. SEE ADDITIONAL PROJECT NOTES ON COVER SHEET.



KEYNOTES

- 02-03 CAREFULLY REMOVE EXISTING DOOR, FRAME AND HARDWARE, RETURN TO OWNER
- 02-06 DEMO EXISTING WALL IN ITS ENTIRETY INCLUDING ANY WALL MOUNTED DEVICES, TERMINATE CONDUITS AT NEAREST J-BOX, PREP FLOOR TO RECEIVE NEW FINISH
- 02-08 CAREFULLY REMOVE CEILING TILES AND OTHER CEILING MOUNTED DEVICES, CAREFULLY STORE IN NON-TRAFFICKED AREA AND PREPARE FOR REINSTALLATION AT COMPLETION OF WORK
- 02-17 PATCH/REPAIR ALL WALL DAMAGE AND PREPARE FOR NEW FINISHES, TYP. FRAME LOCATIONS OVER-HEAD
- 02-20 DEMO FLOOR & FLOOR BASE, PATCH WALLS, PREPARE FOR NEW FINISHES
- 02-24 CORE DRILL THROUGH MASONRY WALL AS REQUIRED, PROVIDE OPENING 1/2" LARGER THAN CONDUIT SIZE. SEE TELECOM DRAWINGS FOR CONDUIT SIZE AND QUANTITIES. PATCH AND ACOUSTICALLY SEAL ALL NEW PENETRATIONS. APPLY APPROPRIATE HILTI FIRE RATED SEAL FOR TYPE OF PENETRATION.
- 02-25 CORE DRILL THROUGH FLOOR TO FEED TELECOM CABLES, APPLY APPROPRIATE UL HILTI 2-HOUR FIRE RATED SEAL FOR TYPE OF PENETRATION SYSTEM SELECTED, SEE SPEC SECTION 07 84 00 FOR SUBMITTAL REQUIREMENTS
- 02-30 DEMO EXISTING CEILING TILE, LIGHT FIXTURES AND ANY CEILING MOUNTED DEVICES; REMOVE EXISTING SPRINKLER HEADS AND TURN UP DISCHARGE PIPE, PROVIDE NEW FIRE SUPPRESSION HEADS FOR EXPOSED CONDITIONS
- 02-45 DEMO WALL BASE AND PREPARE WALLS TO RECEIVE NEW FINISHES
- 02-47 REMOVE UNUSED CONDUITS FROM FLOOR, PATCH AND FILL, APPLY FLOOR LEVELING AS REQUIRED, PREPARE TO RECEIVE NEW FLOORING
- 02-56 CORE DRILL THROUGH CONCRETE SHEAR WALL TO INSTALL MECHANICAL DUCT WORK, SEE STRUCTURAL DRAWINGS
- 13-01 ICRA CLASS I, SEE SPEC SECTION 01 35 26 FOR REQUIREMENTS AND WORKING HOURS RESTRICTIONS
- 13-04 ICRA CLASS IV, SEE SPEC SECTION 01 35 26 FOR REQUIREMENTS AND WORKING HOURS RESTRICTIONS
- 13-06 INFECTION PREVENTION, FIRE RATED, 6MM PLASTIC BARRIER SEALED TOP, BOTTOM, AND SIDES. PROVIDE VESTIBULE AREA FOR GOWNING AND UNDOING AND NEGATIVE PRESSURE WITHIN CONSTRUCTION AREA IN ICRA CLASS IV. SEE SPECS FOR OTHER ICRA CONSTRUCTION REQUIREMENTS, COORDINATE LOCATION OF TEMPORARY INFECTION PREVENTION BARRIER WITH THE C.O.R. AND INFECTION PREVENTION REPRESENTATIVE.
- 13-11 INFECTION PREVENTION VESTIBULE WITH 24" X 36" TACK-MATS AT EACH SIDE OF BARRIER AND HAND SANITIZER AT EACH CONSTRUCTION ACCESS LOCATION.


ROOM ALLOCATION LEGEND

- PROPOSED NEW CABINET / TR / MCR LOCATION
- PROPOSED EXPANSION TO TR
- EXISTING TR WITH POWER AND FIBER UPGRADES, SEE TELECOM AND ELECTRICAL DRAWINGS
- ABANDONED ROOM
- ROOM TO REMAIN, NO WORK
- REMODEL REQUIRED DUE TO EHRM IMPACT

PROJECT KEY PLAN



16 113 - B01- DEMOLITION PLAN
 SCALE: 1/4" = 1'-0"
 NORTH



1 113 - BASEMENT DEMOLITION FLOOR PLAN
 SCALE: 1/16" = 1'-0"
 NORTH

Revisions:	Date:

CONSULTANT
 A/E:
 GDM
 1000 W STEUBEN ST. UNIT 3
 BINGEN, WA 98605
 541.436.4723
 ADAM GODDIN, PE

ARCHITECT/ENGINEER OF RECORD
 ARCHITECT
 A&E DESIGN
 124 NORTH 29TH STREET, #100
 BILLINGS, MONTANA 59101
 406.248.2633
 T. MARCELLO PIERROTTET, AIA

STAMP

PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC)
 VA U.S. Department of Veterans Affairs

DRAWING TITLE
 113-BASEMENT DEMOLITION PLAN

APPROVED: Project Director

PHASE
 100% CONSTRUCTION DOCUMENTS

FLS
 FULLY SPRINKLERED

PROJECT TITLE
 EHRM INFRASTRUCTURE UPGRADES

LOCATION
 FORT MEADE, SOUTH DAKOTA

ISSUE DATE
 04/15/2022

CHECKED BY
 TMP


DRAWN BY
 JPR

PROJECT NUMBER
 568-21-701


BUILDING NUMBER
 BLDG 113

DRAWING NUMBER
 113-AD-200


BIM 360://113_VA Medical Center - Ft Meade SD/112_Bldg 113_120.rvt
 2022-05-24 10:14:49
 VA FORM 08 - 6231




16 LEVEL 1 ROOM 192 DEMOLITION PLAN
1/4" = 1'-0"



11 LEVEL 1 ROOM 169 DEMOLITION PLAN
1/4" = 1'-0"



17 113- TC1A DEMO PLAN
1/4" = 1'-0"



18 LEVEL 1 EC1F DEMO PLAN
1/4" = 1'-0"


DEMOLITION GENERAL NOTES

- 1. SEE G SERIES SHEETS FOR ALL DEMOLITION NOTES & HAZARDOUS MATERIAL NOTES
2. IN HOSPITAL OCCUPANCY, CONTRACTOR ARE TO USE A CONSTRUCTION CONTAINMENT CUBE WITH HEPA VACUUM TO MAINTAIN NEGATIVE PRESSURE AS A MEANS TO ACCESS AREAS ABOVE CEILING TILES. THIS INCLUDES ALL PATIENT CORRIDORS AND ALL ACUTE CARE PATIENT AREAS. THIS IS IN CONJUNCTION WITH THE HOSPITALS INFECTION PREVENTION MEASURES AND ICRA PROTOCOLS.
3. MAINTAIN FIRE SUPPRESSION SYSTEM OPERATIONAL DURING CONSTRUCTION WORK. FIRE SUPPRESSION CONTRACTOR TO REMOVE DOWNWARD HEADS AND TURN UPWARDS, PROVIDE NEW FIRE SUPPRESSION HEAD IN TELECOMMUNICATION ROOMS (TR). WORK TO BE CONDUCTED WITHIN ONE WORKING SHIFT. SEE ADDITIONAL PROJECT NOTES ON COVER SHEET.



KEYNOTES

- 02-03 CAREFULLY REMOVE EXISTING DOOR, FRAME AND HARDWARE, RETURN TO OWNER.
02-04 DEMO CARPET, BASE, AND ADHESIVES. PREPARE FLOOR FOR NEW STATIC DISSIPATIVE RESILIENT FLOORING AND BASE.
02-06 DEMO EXISTING WALL IN ITS ENTIRETY INCLUDING ANY WALL MOUNTED DEVICES. TERMINATE CONDUITS AT NEAREST J-BOX, PREP FLOOR TO RECEIVE NEW FINISH.
02-08 CAREFULLY REMOVE CEILING TILES AND OTHER CEILING MOUNTED DEVICES. CAREFULLY STORE IN NON-TRACKED AREA AND PREPARE FOR REINSTALLATION AT COMPLETION OF WORK.
02-09 DEMO WALL AS REQUIRED TO RECEIVE NEW DOOR AND FRAME. EXTENT OF DEMOLITION WORK SHOWN DASHED.
02-11 PATCH/REPAIR ALL WALL DAMAGE AND PREPARE FOR NEW FINISHES, TYP. PRIME LOCATIONS OVERHEAD.
02-20 DEMO FLOOR & FLOOR BASE, PATCH WALLS, PREPARE FOR NEW FINISHES. CORE DRILL THROUGH MASONRY WALL AS REQUIRED. PROVIDE OPENING 12" LARGER THAN CONDUIT SIZE. SEE TELECOM DRAWINGS FOR CONDUIT SIZE AND QUANTITIES. PATCH AND ACoustically SEAL ALL NEW PENETRATIONS. APPLY APPROPRIATE HILTI FIRE RATED SEAL FOR TYPE OF PENETRATION.
02-25 CORE DRILL THROUGH FLOOR TO FEED TELECOM CABLES; APPLY APPROPRIATE UL HILTI 2-HOUR FIRE RATED SEAL FOR TYPE OF PENETRATION SYSTEM SELECTED. SEE SPEC SECTION 07 84 00 FOR SUBMITTAL REQUIREMENTS. DEMO EXISTING TILE FLOOR. APPLY SELF-LEVELING COMPOUND AND PREPARE TO RECEIVE NEW FLOORING.
02-30 DEMO EXISTING CEILING TILE, LIGHT FIXTURES AND ANY CEILING MOUNTED DEVICES; REMOVE EXISTING SPRINKLER HEADS AND TURN UP DISCHARGE PIPE. PROVIDE NEW FIRE SUPPRESSION HEADS FOR EXPOSED CONDITIONS. CORE THROUGH EXISTING GRADE BEAM FOR INSTALLATION OF PLUMBING DRAIN LINE FROM TRENCH DRAIN TO SUMP. COORDINATE WITH PLUMBING DRAWINGS FOR SIZE REQUIRED.
02-37 DEMO EXISTING WINDOW AND PERIMETER AS REQUIRED FOR INSTALLATION OF NEW DOOR.
02-45 DEMO WALL BASE AND PREPARE WALLS TO RECEIVE NEW FINISHES. CORE DRILL THROUGH MASONRY WALL TO INSTALL MECHANICAL DUCT WORK. SEE STRUCTURAL DRAWINGS.
02-56 CONTRACTOR TO ROUTE CONDUIT IN LEAST DESTRUCTIVE MANNER TO LOCATIONS AS INDICATED IN TELECOMMUNICATION DRAWINGS. CONTRACTOR TO BE RESPONSIBLE TO VISIT SITE AND UNDERSTAND ROUTING AND MATERIAL TREATMENT. PATCH AND FINISH TO MATCH EXISTING MATERIALS, TYPICAL AT ALL DATA DROP LOCATIONS.
13-03 ICRA CLASS III. SEE SPEC SECTION 01 35 26 FOR REQUIREMENTS AND WORKING HOURS RESTRICTIONS.
13-04 ICRA CLASS IV. SEE SPEC SECTION 01 35 26 FOR REQUIREMENTS AND WORKING HOURS RESTRICTIONS.
13-06 INFECTION PREVENTION. FIRE RATED, 6MM PLASTIC BARRIER SEALED TOP, BOTTOM, AND SIDES. PROVIDE VESTIBULE AREA FOR GOWNING AND UNGOWNING AND NEGATIVE PRESSURE WITHIN CONSTRUCTION AREA IN ICRA CLASS IV. SEE SPECS FOR OTHER ICRA CONSTRUCTION REQUIREMENTS. COORDINATE LOCATION OF TEMPORARY INFECTION PREVENTION BARRIER THE C.O.R. AND INFECTION PREVENTION REPRESENTATIVE. SEAL PERIMETER OF DOOR TO MAINTAIN NEGATIVE PRESSURE WITHIN CONSTRUCTION AREA. PROTECT FINISH DURING CONSTRUCTION. INFECTION PREVENTION VESTIBULE WITH 2' X 3' TACK MATS AT EACH SIDE OF BARRIER AND HAND SANITIZER AT EACH CONSTRUCTION ACCESS LOCATION.

DEMOLITION LEGEND




ROOM ALLOCATION LEGEND



PROJECT KEY PLAN

1 FIRST FLOOR PLAN
1/16" = 1'-0"



VA MEDICAL CENTER FORT MEADE, SD

Table with 2 columns: Revisions, Date. Includes a header for 'Revisions:' and a blank row for 'Date:'.

CONSULTANT: A/E: GDM, 1000 W STEUBEN ST. UNIT 3, BINGEN, WA 98605, 541.436.4723, ADAM GODDIN, PE. Includes GDM ARCHITECTS - ENGINEERS logo.

ARCHITECT/ENGINEER OF RECORD: ARCHITECT: A&E DESIGN, 124 NORTH 29TH STREET, #100, BILLINGS, MONTANA 59101, 406.248.2633, T. MARCELLO PIERROTTET, AIA. Includes a&e logo.

STAMP: STATE OF MONTANA, BILLINGS, ERIC P. KILGUS, LICENSED ARCHITECT. Includes a circular professional seal.

PROGRAM CONTRACTING ACTIVITY CENTRAL (PCAC). U.S. Department of Veterans Affairs logo.

DRAWING TITLE: 113-LEVEL 1 DEMOLITION PLAN. APPROVED: Project Director.

PHASE: 100% CONSTRUCTION DOCUMENTS. FULLY SPRINKLERED.

PROJECT TITLE: EHRM INFRASTRUCTURE UPGRADES. LOCATION: FORT MEADE, SOUTH DAKOTA. ISSUE DATE: 04/15/2022. CHECKED BY: TMP. DRAWN BY: JPR.

PROJECT NUMBER: 568-21-701. BUILDING NUMBER: BLDG 113. DRAWING NUMBER: 113-AD-201.

2022-05-24 10:15:56
B:\130\112\112_VA Medical Center - F1 Meade\SD21112_Bldg 113_130.rvt
VA FORM 08 - 6231

