## SIGNOFF / APPROVAL NOTES



Guldmann Inc. 14401 McCormick Drive Tampa FL, 33626 Unit A Toll Free: 1(800)-664-8934 Fac: 1(813)-880-9558 Email: Info@Guldmann pet

NOTES

ACCURATE TO 4" BASED ON PDF CONVERSION

- 1. HOIST = 770 LBS
- 2. FLUSHED RECESSED / TYPE P
- CEILING HEIGHT = 8' 0"
   AFF TO DECK = 11' 11"
- 4. ATTACHMENT TYPE =
  CONCRETE BEAM
  SPAN = 2' 0"

- 2. Electrical power source provided by the facility, position to be verified in the field.
- 3. Guldmann Inc. reserves the right to slightly modify the track layout if necessary without Facility approval. This includes lowering the system to avoid ceiling objects.
- 4. Guldmann Inc. will not be held responsible for any damages, inconvenience, resulting from hitting any non visible conduits during our installation process of which we have not been advised.

1. The facility structure capacity must be able to support the load specified on the installation drawing.


- 5. Modifications of door headers by the facility.
- 6. <u>Signed drawings are required prior to ordering and installation of ceiling lifts.</u>
  This signature of each drawing confirms agreement of all the conditions listed above.
- 7. Systems are tested at 1.5 times capacity. 550 lbs. tested at 825 lbs.; 770 lbs. tested at 1155 lbs.; 825 lbs. tested at 1238 lbs.; 1100 lbs. tested at 1650 lbs.

## MY SIGNATURE BELOW VERIFIES THAT I HAVE:

Reviewed all $\frac{8}{}$ pages, with a total quantity of _ the approbation of structure for each room.	$\frac{5}{2}$ room(s), $\frac{5}{2}$ system(s) for the approbation of layout for each room and
CUSTOMER APPROVAL:	DATE:

St. Cloud VA Healthcare St. Cloud VA Bldg. 51 L1 East 4801 Veteran Dr. St. Cloud, MN 56303 PROJECT ID:103896

				01/24/2024	IVIGE
	Revision Schedule				
Date	Issued by	Letter	Description	PROJECT NAME:	
06/02/2024	TRC	Α	UPDATED BACKGROUNDS, MINOR ADJUSTMENTS TOP RAILS FOR WALL, DOOR CHANGES	St. Cloud VA Bldg	j. 51 L1 East
06/17/2024	MGE	В	EXTENDED LIFTS RM 111, RM 117, RM 127. UPDATED CHART. MATERIAL	SHEET DESCRIPTION: FACILITY SI	GNOFF
				SHEET NO:	
				GUL10	11



SPAN CHART B-RAIL							
LOAD	LOAD LIMIT		CANTILEVER (SNGL)		/ER (PAR)	SPAN (BETWEEN SUPPORTS)	
KG	LBS	MM	INCHES	MM	INCHES	MM	INCHES
175	385	565	22 1/4	715	28	5500	215
205	450	525	20 ½	675	26 1/2	5250	205
255	560	485	19	635	25	4750	186
275	605	485	19	630	24 3/4	4500	176
300	660	455	17 ¾	605	23 ¾	4500	176
350	770	445	173/4	595	23 1/4	4000	157
375	825	425	16 ½	575	22 1/2	4000	157
400	880	425	16 ½	575	22 1/2	3750	147



3 B-RAIL SPAN CHART / WEIGHT / DIMS


Fixed rail systems
Fixed rail systems must be connected by Guldmann
Service Team or by a qualified installer.
A Guldmann dass I transformer must be used.
Installation to follow existing rules for authorized
electricians and according to IEC/UL 66601-1.

Terminals on transformers Class I
Double-insulated UL approved cable must be used
(Cable specification: UL category: AVLV2, min, 300V, min,
80° C, min, 18AWG (1 mm² ))
Transformer DK-13991

Transformer DK-13991 In: Terminal 1 = N Terminal 2 = 100-115V AC Terminal 3 = 230V AC Terminal 4 = Protective ground Out: Terminal 5 = 33V AC Terminal 6 = 33V AC

2 GH3 TRANSFORMER NTS

#### POWER TO BE WITHIN 15 FT OF END OF FIXED RAIL







Guldmann Inc. 14401 McCormick Drive Tampa FL, 33626 Unit A Toll Free: 1(800)-664-9834 Fac: 1(813)-880-9558 Email: Info@Guldmann.net

#### NOTES

- 1. HOIST = 770 LBS
- 2. FLUSHED RECESSED / TYPE P
- 3. CEILING HEIGHT = 8' 0" AFF TO DECK = 11' - 11"
- 4. ATTACHMENT TYPE = CONCRETE BEAM SPAN = 2' - 0"







2	FLUSH CEILING PROFILE
J,	NTC

Revision	Schedule

Jeeund by Number

Date	loou	o by	INUITIDE
06/02/2024	TF	RC	Α
06/17/2024	MGE		В
DATE:		DRAWN B	BY:
01/24/2024			MGE
APPROVED BY:			

#### PROJECT NAME:

St. Cloud VA Bldg. 51 L1 East


SHEET DESCRIPTION

SHEET NO:

GEN. INFO

GUL102

PROJECT ID:103896



# SEE 3/GUL102 FOR RAIL SPANS & ADDITIONAL DIMENSIONS Guldmann Inc. 14401 McCormick Drive Tampa FL, 33626 Unit A Toll Free: 1(800)-664-9834 Fax (813)-880-9558 Email: Info@Guldmann.net NOTES 1. HOIST = 770 LBS 2. FLUSHED RECESSED / TYPE - P 3. CEILING HEIGHT = 8' - 0" AFF TO DECK = 11' - 11" 4. ATTACHMENT TYPE = CONCRETE BEAM SPAN = 2' - 0" 3 GUL104 7' - 5 1/2" B.O. TRAVERSE/LINEAR RAIL 7' - 5 1/8" B.O. COMBI GATE - 0" CEILING 6' - 10 1/8" B.O. HOIST 1 TYP ELEVATION 3/4" = 1'-0" COMBI-BRACE Revision Schedule Date Issued by Number 06/02/2024 TRC COMBI-LOCK 01/24/2024 MGE 3 CEILING / COMBI-LOCK DETAIL 1 1/2" = 1'-0" PROJECT NAME: St. Cloud VA Bldg. 51 L1 East

SHEET DESCRIPTION:

SHEET NO:

PROJECT DETAILS

GUL104

PROJECT ID:103896

17" MAX

8" MIN

2 CEILING / HOIST DETAIL 1 1/2" = 1'-0"



Guldmann Inc. 14401 McCormick Drive Tampa FL, 33626 Unit A Toll Free: (1800)-684-9834 Fac. 1 (813)-880-9858 Email: Info@Guldmann.net

### NOTES

- 1. HOIST = 770 LBS
- 2. FLUSHED RECESSED / TYPE P
- CEILING HEIGHT = 8' 0"
   AFF TO DECK = 11' 11"
- 4. ATTACHMENT TYPE =
  CONCRETE BEAM
  SPAN = 2' 0"



— B rail

#### ACCURATE TO 4" BASED ON PDF CONVERSION

Hoist Transformer

Ceiling bracket, Extended

### Revision Schedule

Date	Date Issue		
06/02/2024	TF	RC OF	Α
06/17/2024	M	GE B	
DATE:		DRAWN E	BY:
01/24/2024			MGE

APPROVED BY:


#### PROJECT NAME:

St. Cloud VA Bldg. 51 L1 East

SHEET DESCRIPTION:

### RM 111

SHEET NO: GUL105





Guldmann Inc. 14401 McCormick Drive Tampa FL, 33626 Unit A Toll Free: (1800)-684-9834 Fac. 1 (813)-880-9858 Email: Info@Guldmann.net

### NOTES

- 1. HOIST = 770 LBS
- 2. FLUSHED RECESSED / TYPE P
- 3. CEILING HEIGHT = 8' 0" AFF TO DECK = 11' - 11"
- 4. ATTACHMENT TYPE = CONCRETE BEAM SPAN = 2' - 0"



Hoist Transformer

Ceiling bracket, Extended

Stabilizers



## ACCURATE TO 4" BASED ON PDF CONVERSION

### Revision Schedule

Date	Issued by		Number	
06/02/2024	TF	3C	Α	
06/17/2024	M	GE	В	
DATE:		DRAWN E	BY:	
01/24/2024			MGE	

PROJECT NAME:

St. Cloud VA Bldg. 51 L1 East

SHEET DESCRIPTION:

RM 117

SHEET NO: GUL106

