



MECHANICAL KEYNOTES: (○)

- DEMOLISH EXISTING HYDRONIC RADIANT CEILING PANELS. CAP PIPING AT MAINS (TYP. ALL).
- DEMOLISH EXISTING VAV BOX AND SALVAGE FOR RE-INSTALLATION. DEMOLISH EXISTING HWS AND HWR PIPING AS SHOWN. SALVAGE EXISTING HYDRONIC CONTROL VALVE FOR RE-INSTALLATION. SEE SHEET MP101 FOR NEW HWS AND HWR PIPING.
- DEMOLISH EXISTING VAV BOX AND SALVAGE FOR RE-INSTALLATION. EXISTING PIPING TO REMAIN. SEE SHEET MP101 FOR RECONNECTION OF EXISTING HWS AND HWR PIPING TO NEW VAV BOX.
- DEMOLISH EXISTING SINK, ASSOCIATED PIPING AND ACCESSORIES. CAP DOMESTIC WATER, VENT, AND SANITARY PIPING AT MAIN. PATCH WALL TO MATCH EXISTING.



2F NUCLEAR MEDICINE AREA MECHANICAL PIPING DEMOLITION PLAN
SCALE: 1/4" = 1'-0"



8C CT SCANNER AREA MECHANICAL DEMOLITION PLAN
SCALE: 1/4" = 1'-0"

File Path

VA FORM 08-6231

BID DOCUMENTS	10/10/2018
CONSTRUCTION DOCUMENTS 100% SUBMITTAL - UPDATE	9/28/2018
CONSTRUCTION DOCUMENTS 100% SUBMITTAL	9/7/2018
DESIGN DEVELOPMENT 90% SUBMITTAL	8/3/2018
SCHEMATIC DESIGN 36% SUBMITTAL 2	7/5/2018
SCHEMATIC DESIGN 35% SUBMITTAL	6/6/2018
Revisions:	Date:

CONSULTANT

Mechanical / Electrical Engineering:
Farris Engineering
12700 W Dodge Road
Omaha, NE 68154
(402) 330-5900
Robert Hotovy


Structural Engineering:
Shaffer & Stevens, P.C.
9910 N 48th Street
Omaha, NE 68152
(402) 455-7698
Donn Shaffer

ARCHITECT/ENGINEER OF RECORD

A/E:
CLH Architects
3705 N 200th St
Elkhorn, NE 68022
(402) 291-6941
Tim Werner



STAMP



Office of
Construction
and Facilities
Management



U.S. Department
of Veterans Affairs

Drawing Title

Mechanical Demolition Plan

Approved: Project Director

Phase

BID DOCUMENTS

FULLY SPRINKLERED

Project Title

Second CT Scanner
Site Prep Design

Location

Sioux Falls, SD

Issue Date

October 10, 2018

Checked

BDH

Drawn

AMM

Project Number

438-18-103

Building Number

5

Drawing Number

MD102




FARRIS ENGINEERING
OMAHA | LINCOLN | SIOUX FALLS | COLORADO SPRINGS
farris-usa.com


FE# 182035

MECHANICAL KEYNOTES: (C)

- RE-INSTALL EXISTING VAV BOX. PROVIDE NEW SUPPLY AIR DUCTWORK, TRANSITIONS, HANGERS, AND ASSOCIATED APPURTENANCES. RECONNECT CONTROL WIRING FROM THERMOSTAT TO VAV BOX AND FROM VAV BOX TO EXISTING HYDRONIC CONTROL VALVE. SEE DETAIL 1/M-701 (SIMILAR).
- RE-INSTALL EXISTING SUPPLY AIR DIFFUSER. THOROUGHLY CLEAN DIFFUSER PRIOR TO RE-INSTALLATION. RE-BALANCE TO CFM SHOWN.
- RE-INSTALL EXISTING RETURN AIR GRILLE. THOROUGHLY CLEAN GRILLE PRIOR TO RE-INSTALLATION. RE-BALANCE TO CFM SHOWN.
- PROVIDE NEW VAV BOX. PROVIDE NEW SUPPLY AIR DUCTWORK, TRANSITIONS, HANGERS, AND ASSOCIATED APPURTENANCES. CONNECT NEW CONTROL WIRING FROM NEW THERMOSTAT TO VAV BOX AND FROM VAV BOX TO NEW HYDRONIC CONTROL VALVE. SEE SHEET M-301 FOR NEW VAV BOX PERFORMANCE DATA. SEE DETAIL 1/M-701.
- PROVIDE NEW RETURN AIR DUCTWORK, TRANSITIONS, HANGERS, AND ASSOCIATED APPURTENANCES.
- RE-BALANCE TO CFM SHOWN.
- RE-INSTALL EXISTING THERMOSTAT. RE-CONNECT CONTROL WIRING.
- PROVIDE NEW RETURN AIR GRILLE. RECONNECT TO EXISTING DUCTWORK AND ADJUST LOCATION AS REQUIRED TO MATCH NEW CEILING GRID LAYOUT. SEE SHEET M-701 FOR DIFFUSER PERFORMANCE DATA.
- EXISTING DIFFUSERS TO REMAIN. RELOCATE AS REQUIRED TO MATCH NEW CEILING GRID LAYOUT.
- PROVIDE NEW SUPPLY AIR DIFFUSERS. SEE SHEET M-701 FOR DIFFUSER PERFORMANCE DATA.
- PROVIDE NEW VAV BOX. PROVIDE NEW SUPPLY AIR DUCTWORK, TRANSITIONS, HANGERS, AND ASSOCIATED APPURTENANCES. CONNECT NEW CONTROL WIRING FROM NEW THERMOSTAT TO VAV BOX. SEE SHEET M-501 FOR NEW VAV BOX PERFORMANCE DATA. SEE DETAIL 1/M-701 FOR NEW VAV BOX DETAIL.
- REMOVE EXISTING SPRINKLER HEADS AND REPLACE AS NECESSARY TO ACCOMMODATE NEW CEILING AND ROOM LAYOUT. NEW SPRINKLER LAYOUT SHALL BE LIGHT HAZARD. CONTRACTOR SHALL FIELD VERIFY IF EXISTING SPRINKLER HEADS ARE ON FLEXIBLE DROP. IF ON FLEXIBLE DROP REMOVAL AND REPLACEMENT IS NOT NECESSARY. NEW SPRINKLER DROP SHALL BE FLEXIBLE DROP.
- REMOVE EXISTING SPRINKLER HEADS AND REPLACE AS NECESSARY TO ACCOMMODATE NEW CEILING AND ROOM LAYOUT. NEW SPRINKLER LAYOUT SHALL BE ORDINARY HAZARD GROUP 1. NEW SPRINKLER DROP SHALL BE FLEXIBLE DROP.



2F NUCLEAR MEDICINE AREA HVAC PLAN
SCALE: 1/4" = 1'-0"



3C CT SCANNER AREA HVAC PLAN
SCALE: 1/4" = 1'-0"


BID DOCUMENTS	10/10/2018
CONSTRUCTION DOCUMENTS 100% SUBMITTAL - UPDATE	9/28/2018
CONSTRUCTION DOCUMENTS 100% SUBMITTAL	9/7/2018
DESIGN DEVELOPMENT 90% SUBMITTAL	8/3/2018
SCHEMATIC DESIGN 36% SUBMITTAL 2	7/5/2018
SCHEMATIC DESIGN 35% SUBMITTAL	6/6/2018
Revisions:	Date:

CONSULTANT	
Mechanical / Electrical Engineering:	Structural Engineering:
Farris Engineering	Shaffer & Stevens, P.C.
12700 W Dodge Road	9910 N 48th Street
Omaha, NE 68154	Omaha, NE 68152
(402) 330-5900	(402) 455-7698
Robert Hotovy	Donn Shaffer

ARCHITECT/ENGINEER OF RECORD	
A/E:	
CLH Architects	
3705 N 200th St	
Elkhorn, NE 68022	
(402) 291-6941	
Tim Werner	



STAMP



Office of
Construction
and Facilities
Management



Drawing Title	HVAC Plan
Approved: Project Director	

Phase	BID DOCUMENTS
FULLY SPRINKLERED	

Project Title	Second CT Scanner Site Prep Design
Location	Sioux Falls, SD
Issue Date	October 10, 2018
Checked	JDH
Drawn	JDH
Project Number	438-18-103
Building Number	5
Drawing Number	MH101