



## Fargo Veterans Affairs Health Care System

2101 Elm Street North, Fargo, ND 58102-2417

# EHRM Infrastructure Upgrades Issue For Bid Submittal

March 18, 2022

VA Contract Number: 36C26319D0044

VA Project No: 437-21-205

Bancroft-AE Project No: 18-121





---

## DEVELOPMENT OF DESIGN

Fargo Veterans Affairs Health Care System  
EHRM Infrastructure Upgrades

VA Contract Number: 36C26319D0044  
VA Project Number: 437-21-205  
Bancroft Project Number: 18-121

Issued For: User and VA approval

By:

Bancroft Architects + Engineers  
3300 Dundee Rd  
Northbrook, Illinois 60062  
847.952.9362 | [www.bancroft-ae.com](http://www.bancroft-ae.com)





# ISSUE FOR BID DESIGN DEVELOPMENT

## TABLE OF CONTENTS

- 1. Executive Summary
- 2. Architectural Basis of Design
- 3. Structural, Civil & Blast Basis of Design
- 4. Mechanical and Plumbing Basis of Design
- 5. Electrical Basis of Design
- 6. Fire Protection Basis of Design
- 7. Telecommunications and Electronic Security Basis of Design
- 8. Appendices



# BASIS OF DESIGN: EXECUTIVE SUMMARY

---

## 1

### Executive Summary

- Introduction
- Design Team
- Overview
- Project Scope
- Applicable Codes & Standards
- Construction Planning
- Budget
- Cost Analysis



## INTRODUCTION

This document is the Design Narrative / Basis of Design (BOD) for the 95% Design Development Submittal, a living document that will evolve through the duration of this project. This document was created starting from the following key elements of developmental discovery:

- BOD Submittal Design Meeting September 7, 2021
- Site Investigation September 13 & 14, 2021
- 35% VA Review Meeting October 8, 2021
- 50% VA Review Meeting November 16, 2021
- 75% VA Review Meeting January 07, 2022
- 95% VA Review Meeting February 17, 2022

It is not the BOD's function or intent to document every element of this entire process as it is developed; rather it is to perform as an organized summary of the key developments of the project process. In addition to the BOD, total documentation of the design process consists of project minutes of meetings, numerous design studies and options presented for consideration.

This version of the BOD is being submitted as a BOD Review submittal. Revisions of this document will be submitted with future submittals per project schedule:

The project schedule is as follows:

- 35% Schematic Design September 28, 2021
- 50% Design Development November 3, 2021
- 75% Design Development 2 December 22, 2021
- 95% Construction Documents February 17, 2022
- 95% Resubmittal March 04, 2022
- 100% Final Construction Documents March 18, 2022
- Final Acceptance March 23, 2022

## DESIGN TEAM

The lead firm for the project is Bancroft Architects + Engineers (BAE) and is providing architectural design, mechanical engineering and electrical engineering. Additional Consultants are included in the following Schedule of Design Team Members.

| <b>Responsible Person</b> | <b>Company Name</b>          | <b>Responsibility</b>  |
|---------------------------|------------------------------|--|
| John Robbins              | Bancroft AE                  | Project Manager / Director of Projects                             |
| Darlene Flook             | Bancroft AE                  | Project Manager  |
| Crotan Zakarija           | Bancroft AE                  | Project Architect / Director of Architecture                       |
| Dana Auman                | Bancroft AE                  | Project Architect  |
| John King                 | Bancroft AE                  | Plumbing Engineer  |
| David Greene              | Bancroft AE                  | Mechanical Engineer / Director of Engineering                      |
| David Gamble              | Bancroft AE                  | Mechanical Engineer  |
| Joshua Mikels             | Bancroft AE                  | Electrical Engineer / VP of Engineering                            |
| Walter Groszko            | Bancroft AE                  | Electrical Engineer  |
| Hilary P. Clifton         | Terracon Consultants, Inc.   | Abatement Consultant   |
| Jon Hammer                | Terracon Consultants, Inc.   | Abatement Consultant   |
| Jim Gusky, PE             | Calibre                      | Civil Engineer   |
| Travis Benjamin, PE       | Calibre                      | Structural Engineer  |
| Bill Macintosh            | BrightTree Studios           | Security and IT Consultant   |
| Bruce Yoch                | BrightTree Studios           | Security and IT Consultant/Certified Physical Security Consultant  |
| Andy Cooper               | Cooper Commissioning and CCX | Commissioning Consultant   |
| Kyle Hass                 | Hohbach-Lewin, Inc.          | Blast Protection Consultant/Certified Physical Security Consultant |
| Jeff Scott                | FP&C CONSULTANTS             | Life Safety & Fire Protection                                      |



## OVERVIEW

The Fargo VA HCS oversees the provision of health care to more than 34,000 Veterans living in North Dakota, 17 counties in northwest Minnesota, and one northeast South Dakota county. The Fargo VA HCS has approximately 333,000 outpatient visits annually. The Medical Center is affiliated with the University of North Dakota School of Medicine and Health Sciences, providing training to medical students, and Internal Medicine, Psychiatry, and Surgery resident physicians. The facility is also a training facility for nursing and allied health care students.

The Medical Center is located in a quiet north Fargo neighborhood near the Red River within walking distance to a bus stop, parks, walking/bike paths, and a golf course. An outdoor healing garden provides a place for recreation and therapy for Veterans and their families. The Medical Center is also just down the street from North Dakota State University, the Fargodome, restaurants, hotels, and downtown Fargo.

The Fargo VA HCS is continually innovating as evidenced by our many improvement and expansion projects. In recent years, the Fargo VA HCS opened several new and expanded departments, to include:

- New Imaging department with new state-of-the art equipment
- New Community Living Center with 38 private rooms, large recreation and dining atriums,
- and beautiful views of the Red River
- New Primary Care clinic space with 30 additional exam rooms
- New Laboratory
- New Intensive Care & Dialysis Unit
- New Emergency Department
- New CBOCs in Bemidji, Grafton, Minot, Dickinson, and Williston.

- New Community Resource and Referral Center in downtown Fargo.
- New main entrance and lobby.
- New PT/OT and Prosthetics

## PROJECT SCOPE

In 2018 the Department of Veterans Affairs (VA) began the replacement of its current Electronic Health Records systems with a new Electronic Health Records system known as the VA EHRM. In July of 2021, Bancroft AE was contracted to provide Architectural/Engineering design services for the Infrastructure Upgrades to the VA Health Care System in Fargo, ND.

The project focus is to include design for upgrading the fiber optic system throughout the campus buildings to each telecommunication room (TR), provide a redundant fiber run to each TR, provide a new main fiber line coming into the campus from the provider point, run new upgraded ethernet cabling from TRs to data drops, install additional IT outlets, install new electrical outlets throughout the campus, provide additional normal, critical and UPS outlets in TRs, upgrade campus power distribution as required, and increase twenty six TR footprints to meet new standards.

The work shall be conducted within multiple buildings on the campus with most of the work to be within Building 1/9/46. The design shall be in accordance with all current and applicable codes including, NFPA, JC, OSHA, UBC, EPA and the Department of Veterans Affairs publications including the Infrastructure Standard for Telecommunication Spaces and the OEHRM Site Infrastructure and End User Device (EUD) Requirements.

The scope of design services includes Investigative Services, Schematic Design, Design Development, and Construction Documents. The drawings will include but not be limited to:





## PROJECT SCOPE (CONT'D)

- Life Safety
- Infection Control (ICRA)
- Civil
- Structural (As Necessary)
- Hazardous Materials Abatement
- Demolition
- Architectural
- Fire Protection
- Plumbing (As Necessary)
- Mechanical
- Electrical
- Information Technology Infrastructure

## AREAS OF WORK

Building 1/9/46 Main Hospital: Floors Basement—5PH

Building 3 Administrative Office

Building 10 Boiler Plant

Building 11 Maintenance Garage

Building 12 Warehouse

Building 13 Laundry

Building 30 Administration


Building 40 VBA Regional Office—Floors 1-2

Building 51 HMRS

Building 52 Administrative Office—Floors 1-2

Building 56 Chiller Plant

Individual rooms to be addressed are presented in the Program Analysis as part of the Architectural Basis of Design that follows in this report.





## APPLICABLE CODES & STANDARDS

The following are Codes and Standards that will be used for this project as adopted by the VA:

- VA Directives, Space Planning Criteria, Design Manuals, Master Specifications, VA National CAD Standard Application Guide, and other Guidance on the Technical Information Library (TIL). (<http://www.cfm.va.gov/til/>)
- NFPA 101 Life Safety Code
- NFPA National Fire Codes with the exception of NFPA 5000 and NFPA 900
- VA Fire Protection Design Manual / 8th Edition—June 1, 2021
- International Building Code (IBC) (Only when specifically referenced in VA Design Documents).
- Occupational, Safety and Health Administration (OSHA) Standards.
- National Electrical Code (NEC)
- International Plumbing Code (IPC).
- Architectural Barriers Act Accessibility Standards (ABAAS) including VA supplement, Barrier Free Design Guide (PG-18-13)
- Building Code Requirements for Reinforced Concrete, American Concrete Institute and Commentary (ACI 318).
- Manual of Steel Construction, Load and Resistance Factor Design Specifications for Structural Steel Buildings, American Institute of Steel Construction (AISC).
- Energy Policy Act of 2005 (EPAct2005).
- International Energy Conservation Code (IECC).
- International Mechanical Code (IMC).
- Underwriter's Laboratories (UL)
- Sheet Metal and Air Conditioning Contractors Association (SMACNA)
- Factory Mutual (FM)

- Executive Order 13423: Strengthening Federal Environmental, Energy, and Transportation Management.
- The Provisions for Construction and Safety Signs. Stated in the General Requirements Section 01010 of the VA Master Construction Specification.
- Ventilation for Acceptable Indoor Air Quality – ASHRAE Standard 62.1 – 2016.
- Safety Standard for Refrigeration Systems – ASHRAE Standard 15 – 2007.

**Specific VA Manuals Guidelines and Assessments are used for this project:**

- Fargo VA healthcare System Local Design Standards
- VA Fire Protection Design Manual / 8th Edition—June 1, 2021
- VA Office of Electronic Health Record / OEHRM Site Infrastructure and End User Device (EUD) Requirements v2.0—April 15, 2021
- VA OIT Solution Delivery Data Center & Infrastructure Engineering—Basic Guidance: Zone PDU Distribution - July 13, 2020
- VA Office of Information and Technology / Design Narrative for Generic Small Data Center for Main Computer Rooms (MCRs) and other Campus Support Centers (CSCs) - March 25, 2020
- VA Office of Construction & Facilities Management / Physical Security Design Manual / Life Safety Protected Facilities — January 2015
- VA Office of Construction & Facilities Management / Physical Security and Resiliency Design Manual— October 1, 2020 / Revised April 1, 2021
- Infrastructure Standard for Telecommunications Spaces Version 3.1 July 1, 2021 | Solution Delivery-Data Center and Infrastructure Engineering
- Telecommunications and Special Telecom Systems Design Manual February 2016
- VA Office of Construction & Facilities Management / PG-18-9: Space Planning Criteria / Chapter 232: Office of Information & Technology (OIT)—October 3, 2016
- VA Office of Construction & Facilities Management / PG 18-12 Design Guide—Infrastructure Standard for Telecommunications Spaces (Office of Information & Technology—July 2021





## APPLICABLE CODES & STANDARDS (CONT'D)

- VA Office of Construction & Facilities Management / Infrastructure Standard for Telecommunications Spaces Standard Alert 017 R01—October 1, 2020
- EHRM SOCAMES 6 Design Alert 2 / Cable Distance Requirements—April 9, 2020
- HEFP SEP (SOCAMES 6) Design Alert's 1, 3-7.

## CONSTRUCTION PLANNING

It is to be anticipated that the EHRM infrastructure upgrades will impact normal operations. This is an important consideration that will need to be paid attention to during the design process. BAE is working with the VA Station staff to identify impacts and to assist in planning strategies to minimize such.

## BUDGET

As part of the Design Phase BAE is tasked with identifying 10% worth of Deduct Alternates to ensure that a construction contract can be issued for at or less than the ECC. BAE is continuing to work with the VA Station to identify best options for deduct alternates.

However, at the time of this submittal, the Station and BAE have only jointly identified one deduct alternate. This is identified as "Deduct Alternate No. 1 - Deletion of Work for installation of smoke detectors in Telecommunications Rooms (TRs).

As part of the 95% Submittal the Station has requested the inclusion of exterior stairs on the roof of the main hospital building (Building 1-9-46) for access to condensing units

serving the TRs. These are to replace existing access ladders. If acceptable to the Station, these stairs could be identified as Deduct Alternate No. 2.

## COST ANALYSIS

The Opinion of Probable Construction Cost (OPCC) for the 95% Design Submittal includes the items listed under the Project Scope of work and in this BOD.

The OPPC costs is developed and further broken down per the building constraints and based on the work at that specific location with the available labor pool and submitted at each subsequent submittal. It is to be noted that the OPCC is developed taking into account building and site constraints and using specific location factors (i.e., available material and labor) relative to latest published RS Means 2021 base rates.

Covid Factor

The opinion of total construction cost and "Covid Factor" with a breakdown of the costs are provided in a separate Opinion of Probable Construction Cost document, Appendix F.



# BASIS OF DESIGN: ARCHITECTURAL

---

## 2

### Architectural Basis of Design

- Summary
- Architectural Design
- Program Analysis
- Building Plan Analysis
- Floor Plans



## SUMMARY

The primary focus of this project is to prepare a coordinated design for upgrading the fiber optic system throughout the campus buildings to each telecommunication room (TR), new fiber to each TR, run new upgraded ethernet cabling from TRs to data drops, install additional IT outlets, install new electrical outlets throughout the campus, provide additional normal, critical and UPS outlets in TRs, upgrade campus power distribution as required, and increase twenty six TR footprints to meet new standards.

Upgrades to the existing Main Computer Room (MCR) will be included in the design as required to properly serve the upgrades the TRs. This will include at a minimum UPS to support the TRs, 3-phase power to the TRs and source A fiber to the TRs.

## ARCHITECTURAL DESIGN

The baseline architectural portion of the work is providing for demolition of existing walls and doors as necessary to accommodate expanded TR footprints, new walls and new or relocated doors as required. The existing finishes in the designated TR rooms are to be removed to bare walls, which will be prepped for paint and installation of fire-rated backboards. Any existing ceiling assemblies are to be removed. Any existing floor finishes are to be removed and the concrete substrate prepped for installation of static-dissipative tile. Rooms are to be finished out as described in the Room Finish Schedule as part of the contract drawings.

Walls surrounding each TR will be extended as required to the underside of deck above. Walls will be upgraded to be 1-hour rated - including fire-rated sealant at the tops and bottoms of each wall. All existing and new penetrations will receive re-enterable fire stop assemblies.

Target Design Criteria for each TR is as follows:

- In Healthcare/Mission Critical Areas
  - Minimum 100 SF for legacy space TRs to accommodate two (2) racks.
  - Minimum 170 SF for new TRs built as building additions to accommodate four (4) racks.
- All enclosure walls to be one hour rated construction.
  - Code– plus feature requested by the Station.
- All TR doors to be three-quarter hour rated construction.
  - Code– plus feature requested by the Station.
- TR doors to be minimum 3'-0" wide by 8'-0" high.
- Doors to be knock-down type frames per Station standard.
- Floors to be Static –dissipative tile.
- No finished ceilings, unless needed to meet fire separation requirements.

Where these criteria cannot be met due to existing construction limitations, BAE is working with the Station to develop a list of variance requests to submit to the EHRM National group. For example, it has been determined that an 8'-0" high door cannot be accommodated in the majority of locations. A variance will need to be requested for these locations.

Due to existing conditions constraints several buildings will not receive full TR enclosures. At those buildings existing telecommunication racks will be replaced with new cabinets or racks (as identified in the Program Analysis later in this report). These include Buildings 10, 11, 12, 13, 30 and 56. This approach has been vetted and approved by the Station and DCIE.

Building 51 was designated by the VA Station to receive a building addition to house a TR. The design developed to date has been vetted and approved by the Station and DCIE.



### PROGRAM ANALYSIS

The following spreadsheet was provided to BAE by the Station and has been adopted by the design team to track the required modifications of existing rooms in order to design the new TRs. This spreadsheet was initially verified during the September 13 through 14, 2021 site investigation and has been amended and updated following the 35% and 50% submittal review meetings as required to track development of the baseline design.



# 2 ARCHITECTURAL BASIS OF DESIGN

## PROGRAM ANALYSIS

| Location               | Official Station Name   | Function        | Station # | Bldg | Room      | Sq Feet | Expand TR | TR Crosswalk  | Rm Impacted          | Dept Impact | POC      | Request for Variance |
|------------------------|-------------------------|-----------------|-----------|------|-----------|---------|-----------|---|----------------------|-------------|----------|----------------------|
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | BA-30     | 101     | No        |   |                      |             |          |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | BB-92     | 140     | No        |   |                      |             |          |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | BC-02     | 116     | Yes       | Combine BC-02 and BC-24   | BC-24                | ITOPS       | Ray      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | BC-24     | 10      | Yes       | Combine BC-02 and BC-24   | BC-02                | ITOPS       | Ray      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | BD-02     | 129     | No        |   |                      |             |          |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | BD-84     | 105     | No        |   |                      |             |          |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 1A-54     | 56      | Yes       | Expand into 1A-55   | 1A-55                | PAO         | Ross     |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 1B-121B   | 49      | Yes       | Expand into the vestibule 1C-100  | 1C-100               | ED          | Julianna |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 1B-24     | 20      | Yes       | Move to 1A-54, abandon 1B-24  | 1A-54                | ITOPS       | Ray      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 1B-65     | 42      | Yes       | Move to 1A-54, abandon 1B-65  | 1A-54                | ITOPS       | Ray      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 1B-98     | 11      | Yes       | Move to 1C-99, abandon 1B-98  | 1C-99                | ITOPS       | Ray      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 1C-99     | 162     | No        |   |                      |             |          |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 1D-158    | 60      | No        | Only space to expand is 1D-156, but don't want to displace all of our dentists. |                      |             |          | Yes                  |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 1D-64A    | 72      | Yes       | Expand South into corridor and relocate in floor weigh station.                 | 1D-64                | PC          | Amanda   |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 2A-24     | 139     | Yes       | Expand into 2A-22A. Need to fit more racks than the current room can hold.      | 2A-22A               | Surgery     | Amy      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 2C-33     | 99      | Yes       | Combine with 2C-33 and 2C-38  | 2C-38                | ITOPS       | Ray      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 2C-37     | 45      | Yes       | Move to 2C-33, abandon 2C-37  | 2C-33                | ITOPS       | Ray      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 2C-38     | 15      | Yes       | Combine with 2C-33 and 2C-38  | 2C-33                | ITOPS       | Ray      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 2C-90A    | 60      | Yes       | Expand into 2C-90   | 2C-90                | WH          | Leah     |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 2D-110A   | 68      | Yes       | Move to 2D-18 and 2D-19, abandon 2D-110A  | 2D-18 & 2D-19        | CLC         | Jacklyn  |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 3B-23     | 84      | Yes       | Expand into 3B-25   | 3B-25                | 3M          | Sara     |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 3C-48     | 36      | Yes       | Move to 3B-23 abandon 3C-48   | 3B-23                | 3M          | Sara     |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 3C-96     | 80      | Yes       | Move to 3D-10, abandon 3C-96  | 3D-10                |             |          |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 4A-16     | 70      | Yes       | Move to 4B-23, abandon 4A-16  | 4B-23                | MH          | Deb      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 4D-02     | 42      | Yes       | Move to 4B-23, abandon 4D-02  | 4B-23                | MH          | Deb      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | 4E-19     | 4       | Yes       | Move to 4E-15A, abandon 4E-19   | 4E-15A               | MH          | Deb      |                      |
| VA Fargo               | Fargo VA Medical Center | Main Hospital   | 437       | 1    | Penthouse | 4       | Yes       | Build new (3) TR's ; 501, 502 & 503   | N/A                  | ENGR        |          |                      |
| VA Fargo               | Fargo VA Medical Center | Supply Chain    | 437       | 3    | 0001      | 4       | No        | Build New   | 0001                 |             |          | Yes                  |
| VA Fargo               | Fargo VA Medical Center | Boiler Plant    | 437       | 10   | Bldg-10   | 4       | No        | 45RU Self-Contained Network Cabinet (floor) aka Emcor                           | Mezzanine            | ENGR        | Shawn    | Yes                  |
| VA Fargo               | Fargo VA Medical Center | Garage          | 437       | 11   | 1         | 4       | No        | 24RU Network Cabinet (1/2 floor)  | NE Office Space      | ENGR        | Shawn    | Yes                  |
| VA Fargo               | Fargo VA Medical Center | Warehouse       | 437       | 12   | Bldg-12   | 47      | No        | 45RU Telecommunication Channel Rack (floor)                                     |                      |             |          | Yes                  |
| VA Fargo               | Fargo VA Medical Center | Laundry         | 437       | 13   | 0007      | 4       | No        | 26RU Wall Mounted Telecommunication Enclosure (wall)                            | 0007                 | EMS         | Troy     | Yes                  |
| VA Fargo               | Fargo VA Medical Center | Admin Offices   | 437       | 30   | Bldg-30   | 4       | No        | 45RU Network Cabinet (floor)  | Basement             |             |          | Yes                  |
| VA Fargo               | Fargo VA Medical Center | VBA Regional    | 437       | 40   | 102B      | 119     | Yes       | Expand South and take end of corridor   | Corridor             | VBO         | Paula    |                      |
| VA Fargo               | Fargo VA Medical Center | VBA Regional    | 437       | 40   | --        |         | Yes       | Build new TR in 202A and expand South and take end of corridor                  | 202A & Corridor      | VBO         | Paula    |                      |
| VA Fargo               | Fargo VA Medical Center | Human Resources | 437       | 51   | 1025      | 29      | Yes       | Build 100 sq ft 3 walled addition   |                      |             |          |                      |
| VA Fargo               | Fargo VA Medical Center | Admin Offices   | 437       | 52   | 111       | 61      | Yes       | expand into 100-C15   | 100-C15              | QSV         | Sarah    |                      |
| VA Fargo               | Fargo VA Medical Center | Admin Offices   | 437       | 52   | 211       | 61      | Yes       | Turn 211 into TR and expand into 200-C15  | 200-C15              | REC/HIMS    | Jim/Jody |                      |
| VA Fargo               | Fargo VA Medical Center | Chiller Plant   | 437       | 56   | Bldg-56   | 4       | No        | 24RU Network Cabinet (1/2 floor)  | Current Wall Cabinet | ENGR        | Shawn    | Yes                  |
| Site Building TR Total |                         |                 |           |      | 35        | 2156    | 26        |   |                      |             |          |                      |

|     |  |
|-----|--|
| Yes | Expansion/relocation is required - in scope        |
| No  | No expansion/relocation is required - out of scope |
| No  | No expansion/relocation is feasible - out of scope |




### BUILDING PLAN ANALYSIS

Following the Program Analysis spreadsheet are building floor plans for all buildings to be provided new TRs as part of this Scope of Work. The plans illustrate the locations of all new TRs and free standing server cabinets as part of the baseline design.



# 2 ARCHITECTURAL BASIS OF DESIGN



## KEY


- Modify existing room to meet EHRM TR requirements.
- Combine rooms to create EHRM TR
- Modify existing room: will not meet EHRM TR requirements.
- Replace existing rack with new cabinet or rack as identified in Program Analysis
- Building addition for new EHRM TR
- IT Equipment to be Replaced

1

BUILDING 1-9-46 - BASEMENT



# 2 ARCHITECTURAL BASIS OF DESIGN




## KEY

- Modify existing room to meet EHRM TR requirements.
- Combine rooms to create EHRM TR
- Modify existing room: will not meet EHRM TR requirements.
- Replace existing rack with new cabinet or rack as identified in Program Analysis
- Building addition for new EHRM TR
- IT Equipment to be Replaced

1 BUILDING 1-9-46 - FIRST FLOOR



# 2 ARCHITECTURAL BASIS OF DESIGN




## KEY

- Modify existing room to meet EHRM TR requirements.
- Combine rooms to create EHRM TR
- Modify existing room: will not meet EHRM TR requirements.
- Replace existing rack with new cabinet or rack as identified in Program Analysis
- Building addition for new EHRM TR
- IT Equipment to be Replaced

1 BUILDING 1-9-46 - SECOND FLOOR




# 2 ARCHITECTURAL BASIS OF DESIGN









## KEY







- Modify existing room to meet EHRM TR requirements.
- Combine rooms to create EHRM TR
- Modify existing room: will not meet EHRM TR requirements.
- Replace existing rack with new cabinet or rack as identified in Program Analysis
- Building addition for new EHRM TR
- IT Equipment to be Replaced






# KEY

-  Modify existing room to meet EHRM TR requirements.
-  Combine rooms to create EHRM TR
-  Modify existing room: will not meet EHRM TR requirements.
-  Replace existing rack with new cabinet or rack as identified in Program Analysis
-  Building addition for new EHRM TR
-  IT Equipment to be Replaced

-  Modify existing room to meet EHRM TR requirements.
-  Combine rooms to create EHRM TR
-  Modify existing room: will not meet EHRM TR requirements.
-  Replace existing rack with new cabinet or rack as identified in Program Analysis
-  Building addition for new EHRM TR
-  IT Equipment to be Replaced





## 2 ARCHITECTURAL BASIS OF DESIGN



| KEY |  |
|-----|--|
|     | Modify existing room to meet EHRM TR requirements.                               |
|     | Combine rooms to create EHRM TR  |
|     | Modify existing room: will not meet EHRM TR requirements.                        |
|     | Replace existing rack with new cabinet or rack as identified in Program Analysis |
|     | Building addition for new EHRM TR  |
|     | IT Equipment to be Replaced  |




## 2 ARCHITECTURAL BASIS OF DESIGN









N 1 **BUILDING 3 - OVERALL FLOOR PLAN**  
1/4"=1'-0"



## 2 ARCHITECTURAL BASIS OF DESIGN



### KEY

-  Modify existing room to meet EHRM TR requirements.
-  Combine rooms to create EHRM TR
-  Modify existing room: will not meet EHRM TR requirements.
-  Replace existing rack with new cabinet or rack as identified in Program Analysis
-  Building addition for new EHRM TR
-  IT Equipment to be Replaced



2


BUILDING 10 - MEZZANINE FLOOR PLAN

1/8"=1'-0"





## 2 ARCHITECTURAL BASIS OF DESIGN



### KEY


- Modify existing room to meet EHRM TR requirements.
- Combine rooms to create EHRM TR
- Modify existing room: will not meet EHRM TR requirements.
- Replace existing rack with new cabinet or rack as identified in Program Analysis
- Building addition for new EHRM TR
- IT Equipment to be Replaced



2


### BUILDING 11 - FIRST FLOOR PLAN

1/8"=1'-0"






## 2 ARCHITECTURAL BASIS OF DESIGN






| KEY |  |
|-----|--|
|     | Modify existing room to meet EHRM TR requirements.                               |
|     | Combine rooms to create EHRM TR  |
|     | Modify existing room: will not meet EHRM TR requirements.                        |
|     | Replace existing rack with new cabinet or rack as identified in Program Analysis |
|     | Building addition for new EHRM TR  |
|     | IT Equipment to be Replaced  |









## 2 ARCHITECTURAL BASIS OF DESIGN








**BUILDING 13 - FIRST FLOOR PLAN**  
 1/8"=1'-0"
 

### KEY

-  Modify existing room to meet EHRM TR requirements.
-  Combine rooms to create EHRM TR
-  Modify existing room: will not meet EHRM TR requirements.
-  Replace existing rack with new cabinet or rack as identified in Program Analysis
-  Building addition for new EHRM TR
-  IT Equipment to be Replaced



## 2 ARCHITECTURAL BASIS OF DESIGN



2


**BUILDING 30 - FLOOR PLAN**

1/8"=1'-0"











## 2 ARCHITECTURAL BASIS OF DESIGN





### KEY

-  Modify existing room to meet EHRM TR requirements.
-  Combine rooms to create EHRM TR
-  Modify existing room: will not meet EHRM TR requirements.
-  Replace existing rack with new cabinet or rack as identified in Program Analysis
-  Building addition for new EHRM TR
-  IT Equipment to be Replaced





## 2 ARCHITECTURAL BASIS OF DESIGN





## 2 ARCHITECTURAL BASIS OF DESIGN



**1 BUILDING 51 - FIRST FLOOR PLAN**  
1/8"=1'-0"





## 2 ARCHITECTURAL BASIS OF DESIGN



1 BUILDING 52 - FIRST FLOOR PLAN  
1/8"=1'-0"



1 BUILDING 52 - SECOND FLOOR PLAN  
1/8"=1'-0"




### KEY

- Modify existing room to meet EHRM TR requirements.
- Combine rooms to create EHRM TR
- Modify existing room: will not meet EHRM TR requirements.
- Replace existing rack with new cabinet or rack as identified in Program Analysis
- Building addition for new EHRM TR
- IT Equipment to be Replaced



## 2 ARCHITECTURAL BASIS OF DESIGN



### KEY

- Modify existing room to meet EHRM TR requirements.
- Combine rooms to create EHRM TR
- Modify existing room: will not meet EHRM TR requirements.
- Replace existing rack with new cabinet or rack as identified in Program Analysis
- Building addition for new EHRM TR
- IT Equipment to be Replaced



# BASIS OF DESIGN: STRUCTURAL, CIVIL & BLAST

---

## 3

### Structural, Civil and Blast Basis of Design

#### A. Structural

- Building Codes and References
- Project Description
- Existing Structures
- Site Design Criteria

#### B. Civil

#### C. Blast: See Separate Document



## BUILDING CODES AND DESIGN REFERENCES

The project will be designed and constructed in accordance with VA program guides, directives, design manuals, and specifications in conjunction with industry standard criteria.

### Building Codes and Design References

U.S. Department of Veterans Affairs, Master Specifications PG-18-1

U.S. Department of Veterans Affairs, VHA Program Guide PG-18-3, September 2013

U.S. Department of Veterans Affairs, National CAD Standards and Details PG-18-4

U.S. Department of Veterans Affairs, Construction Standards H-18-3

U.S. Department of Veterans Affairs, VA Directive 7512, 3 August 2017

U.S. Department of Veterans Affairs, Design Manuals PG-18-10

U.S. Department of Veterans Affairs, Design Submission Requirements PG-18-15C

2018 IBC, International Building Code

ACI 318-19, Building Code Requirements for Reinforced Concrete

ACI 360R-10, Specifications Guide to Design of Slabs-On-Ground

ASCE 7-16 Minimum Design Loads for Building and Other Structures

AISC 360-16, American Institute of Steel Construction Inc

AISC 325-17, Steel Construction Manual, 15<sup>th</sup> Edition

AWS D1.1, Structural Welding Code – Steel

TMS 402/602-16, Building Code Requirements and Specifications for Masonry Structures

## PROJECT DESCRIPTION

The purpose of the project is to upgrade the electric distribution, telecommunications distribution, and HVAC system to allow for the new Electronic Health Record Modernization (EHRM) project. This project will include the renovation of multiple spaces within the Fargo VAHCS Campus.

The structural scope includes the review of floor loading and existing primary structural frame to determine if adequate capacity exists for the new occupancies and equipment.

## EXISTING STRUCTURES

### BUILDING 1

Building 1 is 3-story building with a full basement and a full attic, constructed in 1928. The primary structure is constructed using a reinforced concrete pan joist system. Loads are transferred to regularly spaced concrete columns. The foundation is primarily constructed using spread footings and grade beams. The gabled roof is constructed using a reinforced concrete pan joist system. This roof slab is supported in the center by a concrete frame that transfers roof loads to the columns below.

The provided as-built drawing set for building 1 is incomplete and assumptions on design loads have been made. The VA should review their records to see if the missing information exists in another location.

Using UBC 1927 design live loading, Calibre has assumed the minimum original live loading for this building is 40 PSF. Following direction from the VA, the telecommunication design has removed the UPS from each individual server rack which significantly reduces the anticipated equipment live load. This reduced live load is less than the assumed original design live load and will not require structural reinforcement.



## EXISTING STRUCTURES (CONT'D)

### BUILDING 9

Building 9 is 4-stories with a full basement and an attic, constructed in 1945. The primary structure is constructed using reinforced concrete pan joist system. Loads are transferred to regularly spaced concrete columns. The foundation is primarily constructed using spread footings and grade beams. The gabled roof is constructed using 2x10 rafters at 14" on center. These rafters are supported in the center by a steel frame transfers roof loads to the columns below.

The existing building drawings for building 9 were damaged on the sheet (9-24) that showed building design loads. The VA should review their records to see if the missing information exists in another location.

Using UBC 1943 design live loading, Calibre has assumed the minimum original live loading for this building is 40 PSF. Following direction from the VA, the telecommunication design has removed the UPS from each individual server rack which significantly reduces the anticipated equipment live load. This reduced live load is less than the assumed original design live load and will not require structural reinforcement.

### BUILDING 46

Building 46 is a 5-story addition, constructed in 1983, that connects buildings 1 and 9. Each floor is constructed using a composite steel deck with lightweight structural concrete topping, on steel beams. Loads are transferred to regularly spaced steel columns. The foundation is primarily constructed using reinforced concrete spread footings and grade beams. Portions of the roof are also constructed using composite metal deck on steel beams while other sections only have bare metal deck on top of steel beams.

Building 46 has been expanded multiple times since originally constructed.

As a part of this project, the design team is proposing a new TR located the expanded mechanical penthouse. Per the existing drawing set, this floor slab in this area has adequate capacity for the reduced equipment live load and will not require structural reinforcement.

### BUILDING 51

Building 51 is an existing office building that will be getting a small 20'x12' addition to hold the new TR room. The new addition will be a standalone addition separated by an expansion joint from the existing building.

The new addition will be constructed of solid grouted CMU walls (for blast concerns) with steel roof beams and concrete on metal roof deck with over-framing trusses forming a gable roof. The concrete is also added for blast concerns. A 4" concrete slab on grade will be the floor. The foundations will be concrete stem wall and footings bearing on approved subgrade. There is not a project specific geotechnical report so a geotechnical engineer will need to be hired by the owner during the construction phase to confirm bearing capacities match or exceed the assumptions.

### OTHER BUILDINGS

The proposed infrastructure upgrades at the other buildings on campus not referenced in this document are not anticipated to affect the existing primary structure. Structural reinforcement or enhancement is not anticipated.



## SITE DESIGN CRITERIA

### DEAD LOADS

- Roofing & Insulation: 5 PSF
- Deck (Building 51 addition): 60 PSF
- Ceiling/Fireproofing: 5 PSF
- Miscellaneous: 5 PSF
- Structural Beams/Columns: Actual weight

### LIVE LOADS

- New TR Equipment: 250 lbs/rack
- New TR Live Load: 40 PSF

### SEISMIC DESIGN DATA

- a. Building Risk Category = IV
- b. Importance Factor = 1.5
- c. Soil Site Class = D (assumed)
- d.  $S_s = 0.059g$ ,  $S_1 = 0.019g$ ,  $S_{DS} = 0.062g$ ,  $S_{D1} = 0.03g$
- e. Seismic Design Category = A
- f. Building Frame System: Varies

### WIND DESIGN DATA

- a. Basic Wind Speed = 125 MPH (ASCE 7)
- b. Roughness Category = B
- c. Exposure Category = B
- d. Importance Factor = 1

### SNOW DESIGN DATA

- a. Ground Snow Load = 50 PSF
- b. Importance Factor = 1.2
- c. Exposure Factor  $C_e = 0.9$
- d. Thermal Factor Typical  $C_t = 1$
- e. Flat roof snow = 50 PSF
- f. Building 51 drift and gable roof snow loads shown on structural drawings

### CLIMATE DATA

- a. Frost Depth = 5'-0"
- b. Rainfall Intensity = 3.25" per hour



## BUILDING CODES AND DESIGN REFERENCES

The project will be designed and constructed in accordance with VA program guides, directives, design manuals, and specifications in conjunction with industry standard criteria.

U.S. Department of Veterans Affairs, Master Specifications PG-18-1

U.S. Department of Veterans Affairs, VHA Program Guide PG-18-3, September 2013

U.S. Department of Veterans Affairs, National CAD Standards and Details PG-18-4

U.S. Department of Veterans Affairs, Construction Standards H-18-3

U.S. Department of Veterans Affairs, VA Directive 7512, 3 August 2017

U.S. Department of Veterans Affairs, Design Manuals PG-18-10

U.S. Department of Veterans Affairs, Design Submission Requirements PG-18-15C

2018 IBC, International Building Code

ACI 318-19, Building Code Requirements for Reinforced Concrete

ACI 360R-10, Specifications Guide to Design of Slabs-On-Ground

ASCE 7-16 Minimum Design Loads for Building and Other Structures

AISC 360-16, American Institute of Steel Construction Inc

AISC 325-17, Steel Construction Manual, 15<sup>th</sup> Edition

AWS D1.1, Structural Welding Code – Steel

TMS 402/602-16, Building Code Requirements and Specifications for Masonry Structures

## PROJECT DESCRIPTION

The purpose of the project is to upgrade the electric distribution, telecommunications distribution and fiber optic systems for the improvements to the new Electronic Health Record Modernization (EHRM) project. This project will include the renovation of multiple spaces within the Fargo VAMC Campus, an expansion to building 51 and additional routing of new infrastructure to better connect the campus internally as well as new and additional connection to existing infrastructure outside of the campus.

The civil scope will include the evaluation of the existing telecommunication and fiber optic routing through the campus via existing utility tunnels, conduits and duct banks and the design of new duct banks to provide improved and secondary services. In addition to the external evaluation and design, a new expansion is being proposed to Building 51. The civil scope will include revised grading and utility connections as needed.

Additional information that will be included with the plans will be construction details and specifications as well as construction staging and activity details.



# BASIS OF DESIGN: MECHANICAL & PLUMBING

---

## 4

### MECHANICAL & PLUMBING BASIS OF DESIGN

- Design Criteria
- Weather Design Conditions
- Calculations
- Mechanical—HVAC
- Demolition—HVAC & Plumbing
- New Work—HVAC & Plumbing



# 4 MECHANICAL & PLUMBING BASIS OF DESIGN

## DESIGN CRITERIA

The design of the HVAC systems shall be in accordance with the following codes and standards:

- VA Directives, Space Planning Criteria, Design Manuals, Master Specifications, VA National CAD Standard Application Guide, and other Guidance on the Technical Information Library (TIL). (<http://www.cfm.va.gov/til/>)
- International Building Code 2021
- International Mechanical Code 2021
- NFPA 101 Life Safety Code 2021
- ASHRAE Standard 170. Ventilation of Health Care Facilities—2017
- ASHRAE Standard 90.1—2019
- ASHRAE Standard 62.1—2019
- Applicable National Fire Protection Association (NFPA) codes
- Sheet Metal and Air Conditioning Contractors Association (SMACNA)
- Underwriter's Laboratories (UL)
- VA HVAC Design Manual—March 1, 2020

## WEATHER DESIGN CONDITIONS

Outdoor design weather conditions are based on engineering weather data from VA HVAC Design Manual for Fargo. Winter design condition is the 99.6% occurrence design value. Summer design condition is the 0.4% occurrence design value.

- Outdoor Design Conditions:

Winter: -19.3° F ( -30 F per station directive)

Summer: 90.7° F (DB), 72° F (WB)

- Indoor design conditions: Computer/Data Rooms - Data Sheet VA HVAC Design Manual

Heating: 64° F

Cooling: 81° F (72° F Per station direction as sensed at Thermostat)

Ventilation rates shall be in accordance with the VA HVAC Design Manual 2020 or 2018 IMC.

## CALCULATIONS

Building cooling loads are calculated using commercial load calculation computer program (HAP version 5.11) capable of modeling systems over complete 8760-hour annual period, using ASHRAE load calculation techniques. EHRM guidelines Infrastructure Standard for Telecommunication Spaces (ISTS) Version 3.1 apply. Revised guideline recommendations from the Data Center and Infrastructure Engineering (DCIE) for data rack heat gain loads has been implemented as follows:

1 rack=5kW, 2 racks =7.0 kW, 3-racks =8.5 kW, 4 racks =10 kW



# 4 MECHANICAL & PLUMBING BASIS OF DESIGN

## MECHANICAL— HVAC

The Mechanical and Plumbing scope of work consists of providing dedicated room cooling to maintain required temperatures in each EHRM telecommunications room space to remove rejected heat from multiple IT data racks. Cooling loads for design are based on each rack maximum load of sensible heat rejection: 1 rack=17.1 MBH, 2 racks =23.8 MBH, 3-racks =29.0 MBH, 4 racks =34.1 MBH, 5 racks=42.6 MBH.

## DEMOLITION- HVAC AND PLUMBING

- Existing supply and return grilles from existing supply cooling, return and exhausts systems extended from outside of room are to remain as back up for new dedicated AC systems for each space. Exhaust fans, VAV boxes, reheat coils, related piping and controls shall remain also for back up operation.
- Existing VAV boxes ductwork, grilles and thermostats located in rooms are to remain as back up for new dedicated AC systems for each space.
- Where existing ceilings are to be removed, flexible duct and existing diffusers, registers, and hard ductwork shall be suspended from structure above.
- Sheet Metal and Air Conditioning Contractors Association (SMACNA)
- Relocated existing IT closets shall remain as is with no demolition or new work in the HVAC or plumbing scope of work.

## NEW WORK -MECHANICAL / PLUMBING

- New and renovated existing Telecommunication Rooms shall have new dedicated duct free split system cooling only DX air conditioning. This will have a wall mounted fan coil with DX evaporator coil and an outdoor wall or roof mounted air cooled condensing unit.
- Refrigerant piping and control wiring shall connect to indoor and outdoor DX split system components.

- Applied systems shall be variable refrigerant flow (VRF) to match current and future loads. Spaces requiring 3 data racks or more will have 2 systems in each space as per EHRM guidelines and DCIE maximum load directions.
- Split systems shall be manufactured by a air conditioning manufacture with cataloged optional low ambient features to operate and maintain cooling at -40F winter ambient operation. These shall be variable refrigerant flow (VRF) systems to match existing and maximum future loads from data equipment heat of rejection.
- Air conditioning equipment shall have factory installed and include temperature controls BAS interface devices to be viewed and monitored in the MCR for operational status and to send front end signals for all unit component failures and alarm conditions. Indoor units shall have full function programmable thermostats with unit status screen. A temperature and humidity sensor shall be installed at each room location by TC contractor for BAS room temperature and humidity monitoring and adjustable high temperature alarm. Separate rack temperature and humidity to also be viewed and monitored by the BAS in the MCR via separate sensors with locations as directed by data contractor.
- Units shall have wall mounted condensate pumps below indoor sections and an insulated copper condensate drain line to nearest sanitary drain line.
- Drain lines from the evaporator coils and condensate pumps with condensate drain line from unit extended to the indirect waste connections. Mop sinks, floor drains, hubs at sanitary lines. Where required through the wall condensate drain lines shall be 30" above grade with splash blocks below with heat tracing 4' before termination.
- Per discussions with VA personnel, humidification (small electrode or mist humidifiers) are not to be implemented for IT closet Telecommunication Room applications and will not be in this scope of new work.



# BASIS OF DESIGN: ELECTRICAL

---

## 5

### ELECTRICAL BASIS OF DESIGN

- Design Criteria
- Design Narrative



## DESIGN CRITERIA

The design of the Electrical Systems shall be in accordance with the latest published edition of the following codes and standards:

- International Building Code 2021
- Veterans Affairs Electrical Design Manual 2015 (PG-18-10)
- Veterans Affairs Master Specifications (PG-18-1)
- Veterans Affairs Design Guides (PG-18-12)
- National Electrical Code (NEC) – NFPA-70
- National Fire Alarm Code – NFPA-72
- Standard for Healthcare Facilities – NFPA-99
- Standard for the Installation of Stationary Energy Storage Systems—NFPA 855
- Standard for the Installation of Lightning Protection Systems- NFPA 780
- Underwriter’s Laboratories (UL)
- National Electric Manufacturers Association (NEMA)
- Institute of Electrical and Electronics Engineers (IEEE)
- American National Standards Institute (ANSI)
- ASTM International (Formerly American Society for Testing and Materials)
- Occupational Safety and Health Hazards (OSHA)
- American Institute of Steel Construction (AISC)
- Illuminating Engineering Society of North America (IESNA)

- ASHRAE Standard 90.1
- OEHRM Requirements Specification, June 5, 2019, Ver. 1
- OEHRM Site Infrastructure and End User Device (EUD) Requirements, April 15, 2021, Ver. 2.0
- OIT Infrastructure Standards for Communications Spaces, Ver. 3.1, July 1, 2021
- Generic Small Data Center for Main Computer Rooms (MCR”s) and Other Campus Support Centers, March 25, 2020

## DESIGN NARRATIVE

Communications equipment will be relocated from existing IT rooms to the new TR rooms. Bioengineering type services; Nurse Call, Security, etc. will also be relocated to the new TR room. The new TR rooms will be provisioned for OIT and CERNER equipment. UPS and Emergency receptacles are planned to be removed in the future after all equipment is removed from the abandoned IT rooms.

New TR rooms will be provisioned with dedicated UPS power from the large monolithic “A” UPS System that serves the Campus Computer Room, and buildings 1, 9, 40 and 46. Data Center racks will be designed for 5KVA and Telecommunication Room racks will be designed for 3.5KVA, but expected not to exceed 2.5KVA of ultimate load. Because UPS power will be provided from the monolithic UPS System, individual UPS’s are not required in buildings 1, 9, 40 and 46. To support the EHRM design requirements, a new monolithic UPS system and new UPS distribution system will be designed. The new “A” UPS System will replace the existing UPS System located in the basement Room BC 50A. The initial “A”



## DESIGN NARRATIVE (CONT'D)

### New UPS Power Distribution to TR Rooms in Bldgs 1, 9, 40, and 46.

The A UPS System design is a 208/120V, 400KVA UPS System. It will include the following design:

- The initial installation will be configured to feed both the old and new UPS equipment to allow for cutting over equipment from the old to the new UPS with minimum downtimes.
- A 400KVA UPS will be installed for the ultimate buildout. Two 200KVA UPS modules will be initially installed, to power existing and new equipment. One UPS module will be configured to 90KVA to prevent tripping of the existing 400A incoming power. The 2nd 200KVA UPS module will be installed and connected, but kept de-energized. A two year warrantee will be purchased for the 2nd UPS, so that it is in warrantee when energized after standing idle.
- To prepare for cutting over UPS power from old UPS to new UPS, all new and old UPS loads will be terminated to the output of the new UPS. This will involve short outages of existing IT equipment as it is moved to the new UPS.
- The configuration of new and old equipment on UPS will remain, until all old equipment is moved, at which time the old UPS panels and circuits can be removed.
- All output breakers on the new UPS will be metered and monitored to keep the load from exceeding the existing 400A feed from Em gen 9.
- DESCRIPTION OF TEMPORARY CONFIGURATION—Normal and Emergency Power to the UPS will remain from existing Switchgear 9 and Em Gen 9., as this

will temporarily support a 90KVA load on the UPS, including battery charging current, until a larger Em Gen is installed. Note that the 2021 UPS load is only 75KVA.

- The new UPS is composed of two 200KVA inverter modules, initially configured for about 23% of the ultimate load. The modules can be reconfigured when UPS load increases.
- A cabinet with VRL batteries sized to provide 14 min UPS uptime, will be initially installed. The stored battery energy will only be 50KWH, so conformance to NFPA 855 is not required.
- When the UPS is configured for more load, stored battery capacity will exceed 70KWH, and NFPA 855 requirements will need to be applied to the battery installation.
- Battery Monitoring System to manage batteries and determine maintenance intervals,
- Each UPS module will contain one Static Transfer Switch, and the UPS Bypass Switch will be housed in its own cabinet,
- A UPS Distribution Panel "EBUPS DSW" will have metering on all output breakers that feed UPS loads, to monitor TR UPS loads, and prevent overload and tripping.
- Basement UPS distribution to the TR rooms, will be directly from the new EBUPS DSW UPS breakers.
- Remaining UPS distribution will be from UPS Distribution panels in building 40, and floors 1, 2, 3, 4 and 5 in buildings 1, 9 and 46.



## DESIGN NARRATIVE (CONT'D)

- 1st Floor UPS distribution will be from two 150A UPS panels,
- 2nd Floor UPS distribution will mirror the 1st floor,
- 3rd Floor UPS distribution will be from one 150A panel,
- 4th Floor UPS distribution will be from one 150A panel,
- Penthouse UPS distribution will be from a 150A panel located Penthouse A.
- Each rack will be supplied from a 30A, 3 Phase branch circuit for UPS power.

Remote buildings will have a individual rack mounted UPS's installed in each TR Room rack. Each rack will be provisioned with one 120/208V 3-Phase PDU. When available, emergency power will be provided, otherwise normal power will power all TR room circuits.

- One light fixture in each TR room will be on Emergency Power if available. If Emergency Power is not available, battery backup will be provided.
- One receptacle in each TR room will also be on Emergency Power if available.

### UPS Power Feeders and UPS Panels

- The UPS distribution will be a separate system of dedicated feeders and panels,
- Each UPS panel will be upsized with a 200% Neutral Bus to conduct the 3rd Harmonic currents created by the IT equipment switching power supplies.

### Power Distribution to TR Rooms in Outlying Buildings

- Smaller buildings and rooms with minimal telecommunications requirements will be

provided with a enclosed wall mounted 24RU wall mounted cabinets. With internal UPS.

One rack in a building with a "harsh" environment, without TR rooms, will be housed in AFCCO Defender Basis of Design, enclosed rack. One 30A circuit will be provide power to the internal UPS. Emergency power will feed the UPS if available. An additional 30A 3-phase circuit will power the Heat Removal unit in the AFCCO Defender cabinet.

- One light fixture on Emergency Power or battery backup. Remaining lights on Normal Power.
- One receptacle on Emergency Power if available, remaining receptacles on Normal Power.

TR closets will be provided for locations with multiple racks. Each closet will be provisioned as follows:

- Rack mounted UPS, powered from Emergency Power if available,
- One light fixture on Emergency Power or battery backup. Remaining lights on Normal Power.
- One receptacle on Emergency Power if available, remaining receptacles on Normal Power.



# BASIS OF DESIGN: FIRE PROTECTION

---

## 6

### FIRE PROTECTION BASIS OF DESIGN

- Design Criteria
- General Description of Work
- Life Safety
- CD Checklist



## DESIGN CRITERIA

The design of the Fire Protection Systems shall be in accordance with the following codes and standards:

### Building Codes

- International Building Code 2021
- International Fire Protection Code 2021

### Veterans Administration

- Veterans Administration Fire Protection Design Manual (8<sup>th</sup> Edition) June 1, 2021
- Veterans Physical Security and Resiliency Design Manual
- Veterans Administration Master Specifications
- Veterans Administration Infrastructure Standard for Telecommunications Spaces
- Veterans Administration Standard Details

### National Fire Protection Association (NFPA) (Current Published Editions)

- Pamphlet #13 – 2019: Standard for the Installation of Sprinkler Systems
- Pamphlet #25 – 2020: Standard for the Inspection, Testing and Maintenance of Water-Based Fire Protection Systems
- Pamphlet #75 – 2020: Standard for the Fire Protection of Information Technology Equipment
- Pamphlet #99 – 2021: Health Care Facilities Code
- Pamphlet #101 – 2021: Life Safety Code

### Other

- Underwriter's Laboratories (UL)
- Factory Mutual (FM)

## GENERAL DESCRIPTION OF WORK

### Scope of Work Summary

- Modifications to the existing building(s) sprinkler piping systems in conjunction with architectural and electrical/mechanical modifications to existing room spaces for the purpose of building out new Telecommunication Rooms (TRs).

### Design Criteria & Code Basis

- The following evaluation and recommendations for fire protection for this project are based on requirements of the Eighth Edition of the VA Fire Protection Design Manual (VAFPD), NFPA 101 - Life Safety Code (2021 Edition) and the current editions in effect for the remaining NFPA codes and standards applicable to the scope of this work.
- The level of rehabilitation work under this project will be modifications based on the reconfiguration of the existing spaces identified for build-out as new or modified TRs. The existing means of egress for spaces outside of the areas of work will not be altered and will remain usable during the course of this project.
- Telecommunication Rooms (TRs) are required to be protected with wet pipe automatic sprinkler protection per Section 3.7.C of the VAFPD. Quick response sprinklers are permitted for TRs.
- All sprinkler pipes in TR's will be painted Red.
- Section 3.7.E of the VAFPD does not require smoke detection coverage for TRs. The designated new TR spaces are not typically arranged with smoke detection coverage. Per request of the Fargo VAHCS, smoke detection is being specified for each TR space. TR Room smoke detectors are being specified as supervisory alarm devices per the direction of the Fargo VA. New dedicated space cooling units will be provided in each TR. These units will serve the TR only and do not require duct smoke detection.



## 6 FIRE PROTECTION BASIS OF DESIGN

### (Cont'd) Design Criteria & Code Basis

- The fire alarm systems will be required to be placed on test status in accordance with the facility impairment procedures during work on the automatic sprinkler systems.

### Sprinkler Systems

- The existing building automatic sprinkler installations are observed meet the requirements of NFPA 13 and VA guidelines. Existing quick response, semi-recessed pendent or upright sprinklers are typically installed throughout the areas of work.
- Buildings 10, 11 and 13 are to have data racks installed in existing sprinklered room spaces. No modifications for sprinklers are required for these spaces. Building 56 is a non-sprinklered building. Additional smoke detection is not specified for these spaces.
- Existing sprinkler locations in new TR spaces will be relocated, where required, for compliant coverage for the new configuration of rooms. Relocation of sprinklers will require reworking existing sprinkler piping. Existing sprinkler branch lines will require modifications outside of the rooms of work only at locations noted on the drawings. Where applicable new sprinklers will be added to existing modified branch lines to provide compliant coverage per NFPA 13. All new or relocated (new) sprinklers will be upright quick response type installed with UL listed sprinkler guards. Sprinkler piping will be relocated where practical to not be located directly above the locations designated for new TR equipment racks.
- Sprinkler modifications indicated include maintaining compliant sprinkler coverage outside of the TR rooms in adjacent spaces where existing wall boundaries are altered.
- Several of the new TR spaces to be modified have suspended ceilings and are arranged with pendent sprinklers. All finished TRs will be open to the deck with no suspended ceilings.
- Sprinkler work will be specified to modify TR space sprinklers to the upright position prior to the removal of suspended ceiling tiles to maintain compliant sprinkler coverage of the room during the period of construction. This approach may require a second stage of piping modifications to occur for completion of a final sprinkler coverage coordination with the mechanical/electrical changes to occur.
- The scope of this work specifies sprinkler piping modifications required for compliant protection for existing TRs which will be abandoned. Changes in these rooms consist of alterations or removal of existing suspended ceilings.
- As noted above, modifications to the existing sprinkler piping systems consists of modifying a limited amount of sprinkler piping in each area of work. The hydrostatic testing requirements for the sprinkler system modifications will be specified to be conducted at the system working pressure in lieu of the 200 psi hydrostatic test pressure required for new piping systems as permitted by NFPA 13: 29.7.
- The piping modifications required for this scope of work will not alter the hydraulic characteristic of the existing sprinkler system coverage for the space. Hydraulic calculations will not be specified to be submitted for this work.

### Portable Fire Extinguishers

- The VAFPD Section 3.7.E requires each TR to be provided with a CO2 or clean agent type fire extinguisher. The extinguishers are required to be located outside of the TR in semi-recessed cabinets to be accessible for inspection and maintenance, within a 75 feet travel distance of the room.



## LIFE SAFETY

### Egress

- The areas of work will occur in rooms which open to health care corridors or in business office areas. The access to existing required exits will not be affected by this work.

### Compartmentation

- The project scope of work requires all TRs to be enclosed within 1-hour fire barriers per direction of the Fargo VA.
- Typical health care corridor walls which adjoin the TR spaces are constructed of materials to meet the performance for a 1-hour fire barrier rating. Existing walls in business areas are typically not identified as fire barriers, however existing construction of materials observed also meets the performance for a 1-hour fire barrier rating.
- This project requires existing walls that enclose all TRs which do not currently extend to the deck above to be infilled with a 1-hour fire barrier extending to the floor assembly or roof assembly above the TR.
- New TRs will be provided with new access door openings. TR door openings (new and existing) require a minimum 45-minute rated self-closing fire door and frame.

### Firestopping

- Firestopping for new and existing horizontal and vertical penetrations in all TR floors, ceilings and walls will be implemented. Additionally, routing of new cabling outside of TRs through fire rated floors requires firestopping.
- All penetrations into the TR's are to be an assembly that will allow 100% fill and be easily adjusted for new cabling and removal of old. Size and number of assemblies should be designed at 60% fill, when project is complete. All four walls should have at least (1) assembly. GC should fill all existing unprotected openings.



# 6 FIRE PROTECTION BASIS OF DESIGN

## LIFE SAFETY (CONT'D)

The following is a summary of the anticipated automatic sprinkler modifications required for each TR:

| Automatic Sprinkler Modifications |           |                                    |                |   |                   |  |
|-----------------------------------|-----------|------------------------------------|----------------|---|-------------------|--|
| Building/Floor                    | TR Room # | Sprinklers                         | Sprinkler Zone | Existing Ceiling                            | Modify Sprinklers | Construction Comments  |
| Medical Bldg -Basement            | BB-92     | (2) upright                        | B9 Bsmt        | Open to deck                                | No                |  |
|                                   | BA-30     | (1) upright                        | B9 Bsmt        | Open to deck                                |                   |  |
|                                   | BC-02     | (1) upright (1) pendent            | B46 Bsmt NW    | BC-02 Open to deck; BC-24 suspended ceiling | Yes               | Combine BC-02 & BC-24; structure is fire-proofed                                       |
|                                   | BD-02     | (2) upright                        | B46 Bsmt CTR   | Plaster ceiling at underside of deck        | Yes               | Remove plaster ceiling   |
|                                   | BD-84     | (1) upright                        | B1 Bsmt SE     | Open to deck                                | No                | Existing penetration firestopping needed   |
| Medical Bldg - First Floor        | 1D-64A    | (1) upright                        | B9 1st SW      | Open to deck                                | Yes               | Room will expand   |
|                                   | 1D-158    | (1) upright                        | B1 1st SE      | Open to deck                                | No                |  |
|                                   | 1C-99     | (2) upright                        | B1 1st CTR     | Open to deck                                | No                | Existing penetration firestopping needed   |
|                                   | 1A-54/55  | (1)upright 1A-54 (1) pendent 1A-55 | B9 1st North   | 1A-54 Open to deck; 1A-55 suspended ceiling | Yes               | Combine 1A-54 & 1A-55  |
|                                   | 1B-121B   | (1) upright                        | B1 1st East    | Open to deck                                | Yes               | Expand room to corridor; structure is fire-proofed                                     |
| Medical Bldg - Second Floor       | 2C-33     | (1) upright (1) pendent            | B46 2nd        | 2C-33 Open to deck; 2C-38 suspended ceiling | Yes               | Combine 2C-33 & 2C-38; structure is fire-proofed; firestopping needed at floor sleeves |
|                                   | 2C-90     | (2) pendent                        | B1 2nd CTR     | Suspended ceiling                           | Yes               |  |
|                                   | 2D-18     | (1) pendent                        | B1 2nd CTR     | Suspended ceiling                           | Yes               | Combine 2D 18&19   |
|                                   | 2D-19     | (2) pendent                        | B1 2nd CTR     | Suspended ceiling                           | Yes               |  |
|                                   | 2A-22A    | (2) pendent                        | B9 2nd South   | Suspended ceiling                           | Yes               | Combine 22A&24; north wall of 22A is partial height                                    |
|                                   | 2A-24     | (2) upright                        | B46 2nd Floor  | Open to deck                                | Yes               |  |



# 6 FIRE PROTECTION BASIS OF DESIGN

## LIFE SAFETY (CONT'D)

| Automatic Sprinkler Modifications |                          |   |                           |  |                   |  |
|-----------------------------------|--------------------------|---|---------------------------|--|-------------------|--|
| Building/Floor                    | TR Room #                | Sprinklers                                  | Sprinkler Zone            | Existing Ceiling                                       | Modify Sprinklers | Construction Comments  |
| Medical Bldg - Third Floor        | 3B-23                    | (1) upright                                 | B9 3rd North              | Open to deck   | Yes               | Combine 23&25  |
|                                   | 3B-25                    | (1) pendent                                 | B9 3rd North              | Suspended ceiling                                      | Yes               |  |
|                                   | 3D-10                    | (2) pendent                                 | B1 3rd CTR                | Suspended ceiling                                      | Yes               | Abandoned branch lines above ceiling. Existing penetration fire-stopping needed. Install new room sprinklers for 3d-10 and adjacent 3D-10A |
| Medical Bldg - Fourth Floor       | 4B-23                    | (1) pendent                                 | B9 4th East               | Suspended ceiling                                      | Yes               | North wall is built with a single layer of sheetrock above ceiling. Existing penetration firestopping needed                               |
|                                   | 4E-15A                   | (1) pendent                                 | B1 4th West               | Suspended ceiling                                      | Yes               | Two walls are partial height   |
| Medical Bldg - Pent-house         | New Room TR 501          | Attic dry pipe sprinkler - extend to new TR | B9- 5th Floor Attic       | New room build-out with deck below existing roof level | Yes               | Extend existing dry pipe sprinkler protection to new TR. New piping must be pitched to drain to connection take-off                        |
|                                   | New Room TR 502          | Wet pipe sprinkler - extend to new TR       | B9- 5th Floor Attic       | New room build-out with deck below existing roof level | Yes               | Extend existing dry pipe sprinkler protection to new TR. New piping must be pitched to drain to connection take-off                        |
|                                   | New Room TR 503          | Wet pipe sprinkler - extend to new TR       | B46- 4th Floor Eye Clinic | New room build-out open to existing roof level         | Yes               | Existing sprinklers do not require relocation. Replace existing sprinklers (3)   |
| Bldg 3-Upper Floor                | New interior TR Room     | Wet pipe sprinkler ceiling coverage         | B3                        | Suspended ceiling                                      | Yes               | Modify existing wet pipe sprinkler protection to cover new TR and adjacent open office   |
| Building 12 Warehouse             | Existing Room            | (1) pendent                                 | B12                       | Suspended ceiling                                      | Yes               | Modify existing wet pipe sprinkler protection to cover new TR and adjacent exit vestibule  |
| Bldg 51 Admin                     | New exterior TR location | Wet pipe sprinkler - extend to new TR       | B51                       |  | Yes               |  |



# 6 FIRE PROTECTION BASIS OF DESIGN

## LIFE SAFETY (CONT'D)

| Automatic Sprinkler Modifications |                           |   |                |                   |                   |  |
|-----------------------------------|---------------------------|---|----------------|-------------------|-------------------|--|
| Building/Floor                    | TR Room #                 | Sprinklers  | Sprinkler Zone | Existing Ceiling  | Modify Sprinklers | Construction Comments  |
| Bldg 52-First Floor               | 111                       | 1 upright   | B52            | Open to deck      | Yes               | Expand TR space into open office area. Modify adjacent sprinkler coverage. |
| Bldg 52-Second Floor              | 211                       | 1 upright   | B52            | Open to deck      | Yes               | Expand TR space into open office area. Modify adjacent sprinkler coverage. |
| Bldg 40 VBA-First Floor           | 102B                      | (1) upright   | VBA 1st Floor  | Open to deck      | Yes               | Room to expand. Modify adjacent sprinkler coverage.                        |
| Bldg 40 VBA-Second Floor          | 202A                      | (1) pendent   | VBA 2nd Floor  | Suspended ceiling | Yes               |  |
| Bldg 11 Maint Bldg                | Cabinet installation only | Wet pipe sprinkler ceiling coverage                     |                |                   | No                |  |
| Bldg 10-Boiler Plant              | Cabinet installation only | To be sprinklered - Wet pipe sprinkler ceiling coverage |                |                   | No                |  |
| Bldg 13- Laundry Bldg             | Cabinet installation only | Wet pipe sprinkler                                      |                |                   | No                |  |
| Bldg 56-Chiller Plant             | Cabinet installation only | Non-sprinklered   |                |                   | Not Applicable    |  |



LIFE SAFETY (CONT'D)

Automatic Sprinkler Modifications

ROOMS TO BE MOVED  
OUT OF:

| Building/Floor              | Existing TR Room # | Sprinklers   | Sprinkler Zone | Existing Ceiling      | Modify Sprinklers | Construction Comments |
|-----------------------------|--------------------|--------------|----------------|-----------------------|-------------------|-----------------------|
| Medical Bldg - First Floor  | 1B-65              | Yes          | B9 1st North   |                       | No                |                       |
|                             | 1B-98              | Yes          | B46 1st Floor  |                       | No                |                       |
|                             | 1B-24              | (1) pendent  | B9 1st North   | No                    | Yes               |                       |
| Medical Bldg - Second Floor | 2D-110             | (2) upright  | B1 2nd Zone 1  | No                    | No                |                       |
|                             | 2C-37              | (1) pendent  | B46 2nd Floor  | Partially installed   | Yes               |                       |
| Medical Bldg - Third Floor  | 3C-96              | (1) sidewall | B1 3rd CTR     | Partially installed   | Yes               |                       |
|                             | 3C-48              | (1) upright  | B46 3rd Floor  | No                    | No                |                       |
| Medical Bldg - Fourth Floor | 4A-16              | (1) pendent  | B9 4th CTR     | Yes - to be replaced? | Yes               |                       |
|                             | 4D-02              | (1) upright  | B1 4th Eye     | No                    | No                |                       |



# 6 FIRE PROTECTION BASIS OF DESIGN

CD CHECKLIST: 95%

| FIRE PROTECTION                                    | SD | DD | CD | Applicable | Check | Date     | Comments  |
|--|----|----|----|------------|-------|----------|---|
| Fire protection narrative: <sup>1</sup>            |    |    |    |            |       |          |   |
| Fire and smoke separation                          | X  |    |    | Yes        | JAS   | 02/18/22 | Classification of area of TR work areas separation requirements is a 1-hour fire barrier. This approach is described in the narrative.  |
| Fire sprinkler/standpipe system                    | X  |    |    | Yes        | JAS   | 02/18/22 | Modifications to existing sprinkler zone piping is described in narrative. Scope consists of relocating existing sprinklers.  |
| Size of fire pumps                                 | X  |    |    | NA         | JAS   | 02/18/22 | Existing facility fire pump or building fire service. TR modifications do not require a hydraulic analysis.   |
| Water supply available/max. demand                 | X  |    |    | NA         | JAS   | 02/18/22 | TR modifications do not require a hydraulic analysis.   |
| Water flow testing results                         |    |    |    | NA         |       | 02/18/22 | TR modifications do not require a hydraulic analysis.   |
| Fire alarm systems <sup>2</sup>                    | X  |    |    | NA         | JAS   | 02/18/22 | System identified in Specification 28 31 00   |
| Existing to be modernized                          | X  |    |    | NA         | JAS   | 02/18/22 | TR upgrades require no modification to the existing fire alarm system control equipment. TR spaces are specified to be provided with new smoke detection as an Add Alternate. |
| Base loop system for interface of new construction | X  |    |    | NA         | JAS   | 02/18/22 |   |
| Size of air handling unit                          | X  |    |    | Yes        | JAS   | 02/18/22 | New cooling systems to be installed will serve a single room area. HVAC changes will not require fire alarm interfaces.   |
| Exit paths from each zone                          | X  |    |    | NA         | JAS   | 02/18/22 | Existing small room modifications do not affect life safety circulation.  |
| Distances to stairs                                | X  |    |    | NA         | JAS   | 02/18/22 | Existing small room modifications do not affect existing travel distances.  |
| Occupancy of each area                             | X  |    |    | NA         | JAS   | 02/18/22 | Existing small room modifications within various occupancy types. Work areas are not hazardous rooms.   |
| Exit calculations for each floor                   | X  |    |    | NA         | JAS   | 02/18/22 | Existing small room modifications do not affect occupancy calculations.   |
| Smoke control features                             | X  |    |    | NA         | JAS   | 02/18/22 |   |



# 6 FIRE PROTECTION BASIS OF DESIGN

## CD CHECKLIST: 95% (Cont'd)

| FIRE PROTECTION  | SD | DD | CD | Applicable | Check | Date     | Comments   |
|--|----|----|----|------------|-------|----------|--|
| Smoke control features   | X  |    |    | NA         | JAS   | 02/18/22 |  |
| Floor Plans/Drawings: <sup>3 &amp; 4</sup>   |    |    |    |            |       | 02/18/22 |  |
| Sprinkler zones  | X  |    |    | Yes        | JAS   | 02/18/22 | Described in narrative and by notes on drawings.   |
| Fire alarm zones   | X  |    |    | Yes        | JAS   | 02/18/22 | Described in narrative. Existing fire alarm zones will not be modified.  |
| Smoke zones  | X  |    |    | Yes        | JAS   | 02/18/22 | Existing small room modifications occur within existing smoke zones. Work does not affect existing smoke zone boundaries.  |
| Building water supply  | X  |    |    | NA         | JAS   | 02/18/22 | Modifications do not require a water supply evaluation.  |
| Interior sprinkler supply lines  | X  |    |    | Yes        | JAS   | 02/18/22 | Work involves changes to existing sprinkler arm-over lines only.   |
| Standpipes   | X  |    |    | NA         | JAS   | 02/18/22 | Existing standpipes will not be altered.   |
| Fire extinguisher cabinets   | X  | X  | X  | Yes        | JAS   | 02/18/22 | Layout to be determined by Architect.  |
| Fireproofing of structural members   | X  |    |    | NA         | JAS   | 02/18/22 | Corrections for existing fireproofing to be determined by Architect.   |
| Sprinkler/standpipe riser supply piping  |    | X  | X  | NA         |       | 02/18/22 | Existing standpipes will not be altered.   |
| Termination of sprinkler main and inspector test drains                                      |    | X  | X  | NA         |       | 02/18/22 | Sprinkler modifications do not affect the existing drain piping arrangements.  |
| Sprinkler alarm valves   |    | X  | X  | NA         |       | 02/18/22 | Sprinkler modifications do not affect the existing alarm monitoring arrangements.  |
| Waterflow and tamper switches  |    | X  | X  | NA         |       | 02/18/22 | Sprinkler modifications do not affect the existing alarm monitoring arrangements.  |
| Sprinkler system fire department connections   |    | X  | X  | NA         |       | 02/18/22 |  |
| Sprinkler design hazards per NFPA 13   |    | X  | X  | Yes        | JAS   | 02/18/22 | Light Hazard protection indicated  |
| Exit signs and emergency lighting  |    | X  | X  | NA         |       | 02/18/22 | Areas of work do not required exit signs. Emergency lighting to be provided.   |
| Occupied areas not protected by automatic sprinklers   |    | X  | X  | NA         |       | 02/18/22 |  |
| Calculations   | X  | X  | X  | NA         | JAS   | 02/18/22 | The project scope of sprinkler modifications does not alter the existing hydraulic characteristic of the existing piping systems. Hydraulic calculations are not required for sprinkler relocations. |
| Estimated capacities for proposed air handling units in cubic meters (cubic feet) per minute |    | X  | X  |            | JAS   | 02/18/22 | Mechanical modifications do not require changes or adding fire alarm detection or control  |



## 6 FIRE PROTECTION BASIS OF DESIGN

CD CHECKLIST: 95% (Cont'd)

| FIRE PROTECTION                        | SD | DD | CD | Applicable | Check | Date     | Comments                |
|--|----|----|----|------------|-------|----------|-------------------------|
| <b>Location of:</b>                    |    |    |    |            |       | 02/18/22 |                         |
| Fire alarm system                      |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Annunciator panels                     |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Pull stations                          |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Flow switches                          |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Audio-visual devices                   |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Smoke detectors                        |    | X  | X  |            |       | 02/18/22 | Add Alternate indicated |
| Duct smoke detectors                   |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Smoke dampers                          |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Fire dampers                           |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Fire alarm risers <sup>5</sup>         |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Exit signs                             |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Emergency lighting                     |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Fire sprinklers                        |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Standpipes                             |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Fire hydrants                          |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Fire pumps                             |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Post indicator valves                  |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Sectional valves                       |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Fire extinguisher cabinets             |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |
| Electromagnetic door hold open devices |    | X  | X  | NA         |       | 02/18/22 | Existing - no change    |



## 6 FIRE PROTECTION BASIS OF DESIGN

### CD CHECKLIST: 95% (Cont'd)

| FIRE PROTECTION   | SD | DD | CD | Applicable | Check | Date     | Comments                                       |
|---|----|----|----|------------|-------|----------|--|
| Wall sections indicating fire resistive ratings                 |    | X  | X  | NA         |       | 02/18/22 | Existing - no change                           |
| Staff sleeping rooms  |    | X  | X  | NA         |       | 02/18/22 |  |
| Excavation plan signage   |    | X  | X  | NA         |       | 02/18/22 |  |
| Door and window schedule with fire rating or fire rated glazing |    |    | X  | YES        |       | 02/18/22 | See Architectural Schedules                    |
| Zoning of each fire alarm initiating device                     |    |    | X  | Yes        | JAS   | 02/18/22 | Zoning for new smoke detectors is indicated    |
| <b>Details:</b>   |    |    |    |            |       | 02/18/22 |  |
| Fire pump system (capacity and pressure)                        |    |    | X  | NA         |       | 02/18/22 |  |
| Elevation and isometric view of fire pump                       |    |    | X  | NA         |       | 02/18/22 |  |
| Stairwell sign  |    |    | X  | NA         |       | 02/18/22 |  |
| Annunciator panel   |    |    | X  | NA         |       | 02/18/22 |  |
| <b>Interconnection of fire alarm system with</b>                |    |    |    |            |       | 02/18/22 |  |
| Smoke dampers   |    |    | X  | NA         |       | 02/18/22 |  |
| Air handlers  |    |    | X  | NA         |       | 02/18/22 |  |
| Elevator controls   |    |    | X  | NA         |       | 02/18/22 |  |
| Kitchen fire extinguishing and fire pump system                 |    |    | X  | NA         |       | 02/18/22 |  |
| HVAC system with smoke duct detectors                           |    |    | X  | NA         |       | 02/18/22 |  |
| Single line riser diagram for fire alarm system                 |    |    | X  | NA         |       | 02/18/22 |  |
| Height/configuration of storage racks and shelving              |    |    | X  | NA         |       | 02/18/22 |  |
| Specifications  |    |    | X  | Yes        | JAS   | 02/18/22 | Sections 21 08 00 21 13 13 & 28 31 00 Provided |



---

## CD CHECKLIST: 95% (Cont'd)

### NOTES:

- 1** Indicate NFPA 220 and UBC fire resistive rating of the building, NFPA 101 occupancy type, and fire protection code analysis to access compliance with NFPA 101
- 2** Determine type, features, age, reliability, compliance with present day codes, capacity, zoning, supervision, control panel and power supplies, initiating devices and circuits, and auxiliary functions for existing fire alarm system. Indicate manufacturer, model number, voltage, and wiring style of existing alarm systems and devices. Provide recommendations for the proposed fire alarm work.
- 3** Provide information to meet JCAHO requirements; e.g. location of all fire rated barriers, smoke barriers, exit signs, fire extinguishers, manual pull stations, smoke detectors, and sprinkler flow switches. Show all interim life safety measures such as temporary systems Fire Alarm, Sprinkler, and Smoke.
- 4** At DD Submission, add room names, room numbers, door locations and swings, smoke and fire rated partitions, sprinkler/standpipe risers to floor plans. Identify psychiatric areas on drawings so areas for institutional type heads are identified. Add location of all valves (post indicator, sectional) and backflow preventer if provided.
- 5** Show new equipment and/or the necessary changes involved if modification to the existing system is required. Include any recommendations where certain requirements of VA criteria might be waived, in order to allow the existing equipment to be reused.



# Basis of Design: Telecommunications and Electronic Security

---

## 7

### Telecommunications and Electronic Security Basis of Design

- References and Design Criteria
- Telecommunications Spaces
- Modifications to Existing Telecommunication Spaces
- Horizontal Distribution / 100-Ohm Balance Twisted-Pair Cable
- Wireless Access Points
- Backbone Distribution / Optical Fiber and Copper UTP
- Grounding and Bonding
- Physical Security
- Telecommunications Site Routing Plan



## REFERENCES AND DESIGN CRITERIA

Design will be in accordance with current (as of Notice of Award date), VA Design Guides, VA Manuals, FGI 2018, NFPA, OSHA, and all other applicable standards including, but not limited to:

- U.S Department of Veterans Affairs Office of Construction & Facilities Management Technical Information Library (TIL).
- U.S Department of Veterans Affairs Office of Electronic Health Record Modernization OEHRM Site Infrastructure and End User Devices (EUD) Requirements Version 2.0 April 15, 2021
- U.S Department of Veterans Affairs Office of Information & Technology (OIT) Infrastructure Standards for Telecommunications Spaces Version 3.1 July 1, 2021
- U.S. Department of Veterans Affairs Office of Construction & Facilities Management Telecommunications and Special Telecommunications Systems Design Manual, February 2016
- U.S. Department of Veterans Affairs Office of Construction & Facilities Management Standards Alert 003C2B-SA-017 R01b, August 1, 2021
- The U.S. Department of Veterans Affairs, Physical Security and Resiliency Design Manual, October 1, 2020 – Revised September 1, 2021
- SOCAMES 6 Design Alert
- ANSI/NECA/BICSI 568, Standard for Installing Commercial Building Telecommunications Cabling
- ANSI/NECA/BICSI 568, Standard for Installing Commercial Building Telecommunications Cabling
- TIA TBS-162-A, Telecommunication Cabling Guidelines for Wireless Access Points
- ANSI/NECA/BICSI 607-C, Generic Telecommunications Bonding and Grounding (Earthing) for Customer Premises November 2015
- 802.3at-2009 - IEEE Standard for Information technology-- Local and metropolitan area networks-Amendment 3: Data Terminal Equipment (DTE) Power via the Media Dependent Interface (MDI) Enhancements
- 802.11ac-2013 - IEEE Standard for Information technology--Telecommunications and information exchange between systems— Amendment 4: Enhancements for Very High Throughput for Operation in Bands below 6 GHz.
- ISO/IEC 61935-1, Specification for the testing of balanced and coaxial information technology cabling - Part1: Installed balanced cabling as specified in ISO/IEC 11801 and related standards.
- International Organization for Standardization (ISO):
- ISO/IEC 14763-2, Information technology – Implementation and operation of customer premises cabling – Part 2: Planning and installation
- ISO/IEC 30129, Information Technology – Telecommunications bonding networks for buildings and other structures
- National Fire Protection Association (NFPA) - NFPA 70®, National Electrical Code® (NEC®)
- Telecommunication Industry Association (TIA):
- ANSI/TIA-455-78B; Optical Fibers – Part 1-40: Measurement Methods and Test Procedures – Attenuation
- ANSI/TIA-526-7-A; Measurement of Optical Power Loss of Installed Single-Mode Fiber
- Cable Plant, Adoption of IEC 61280-4-2 edition 2: Fiber-Optic Communications Subsystem Test Procedures – Part 4-2: Installed Cable Plant – Single-Mode Attenuation and Optical Return Loss Measurement



## REFERENCES AND DESIGN CRITERIA (CONT'D)

- ANSI/TIA-526-14-C, Optical Power Loss Measurement of Installed Multimode Fiber Cable Plant; Modification of IEC 61280-4-1 edition 2, Fiber-Optic Communications Subsystem Test Procedures- Part 4-1: Installed Cable Plant-Multimode Attenuation Measurement.
- ANSI/TIA-568.0-D, Generic Telecommunications Cabling for Customer Premises
- ANSI/TIA-568.2-D, Balanced Twisted-Pair Telecommunications Cabling and Components Standards
- ANSI/TIA-569-D, Telecommunications Pathways and Spaces
- ANSI/TIA-606-C, Administration Standard for Telecommunications Infrastructure
- ANSI/TIA-607-D, Generic Telecommunications Bonding and Grounding (Earthing) for Customer Premises
- ANSI/TIA-1152-A, Requirements for Field Test Instruments and Measurements for Balanced Twisted-Pair Cabling

## TELECOMMUNICATION SPACES

### Main Computer Room / Data Center

- The existing Main Computer Room (BC-50) shall remain in-use through this project. A new telecommunication channel rack shall be implemented to augment the existing MDA row (core distribution) to support new backbone distribution throughout the facility.

### Entrance Room

- The existing entrance room aka Telephone Equipment Room (BC-60) shall remain in-use through this project. Connectivity between the service provider point of presence and the facility distribution area shall be analyzed and augmented as required to support required bandwidth standards.

- Room 102B at Building 40 is designed to house a second redundant Entrance Facility. Service for this second entrance room is to be established at a later time.

### Telecom Rooms

- All Telecom Rooms shall be brought up to OEHRM standards including new telecommunication racks.
- Plywood backboard will be installed on a minimum of three walls. The backboard shall be 4 feet x 8 feet AC Grade ¾" trade size fire-rated plywood, mounted vertically, with the bottom of the plywood mounted 6 inches above the finished floor with the best side toward the room. Plywood shall be void-free with the A-side facing out. All plywood shall be finished with two coats of high-gloss fire-retardant paint on the face and edges, painting over the fire-rated stamp is not permitted. All plywood shall be painted prior to installation of any equipment. All plywood shall be permanently fastened to the wall by means of wall anchors utilizing galvanized, zinc plated, or stainless-steel hardware with a flat head. Finished installation shall have flush appearance with countersunk screw heads to prevent splitting of the plywood. – with the following exceptions:
  - ◊ Building 10 will receive a self-contained network cabinet, EMCOR or similar
  - ◊ Building 11 will receive a single sheet (approx. 4' x 8' pending existing conditions) AC Grade ¾" trade size fire-rated plywood to support a wall mounted Telecommunication Enclosure
  - ◊ Building 12 will receive a single sheet (approx. 4' x 8' pending existing conditions) AC Grade ¾" trade size fire-rated plywood to support a wall mounted Telecommunication Enclosure
  - ◊ Building 13 will receive a single sheet (approx. 4' x 8' pending existing conditions) AC Grade ¾" trade size fire-rated plywood to support a wall mounted Telecommunication Enclosure
  - ◊ Building 30 will receive a single sheet (approx. 4' x 8' pending existing conditions) AC Grade ¾" trade size fire-rated plywood to support a wall mounted Telecommunication Enclosure



## Telecom Rooms (Cont'd)

- ◊ Building 56 will receive a single sheet (approx. 4' x 8' pending existing conditions) AC Grade ¾" trade size fire-rated plywood to support a wall mounted Telecommunication Enclosure
- All horizontal cable tray shall be basket type cable tray. Ladder rack type tray is only permitted to be installed at vertical locations.
- A minimal 18" wide by 4" tall basket style cable tray cable will be mounted around the perimeter of the room and across the top of any equipment racks. Cable tray will be secured to walls and ceiling structure using appropriate mounting hardware – with the following exceptions:
  - ◊ Building 10 will receive a self-contained network cabinet, EMCOR or similar and utilize conduit for cable pathways.
  - ◊ Building 11 will utilize conduit pathways
  - ◊ Building 12 will utilize conduit pathways
  - ◊ Building 13 will utilize conduit pathways
  - ◊ Building 30 will utilize existing cable pathways
  - ◊ Building 56 will utilize existing conduit pathways
- All telecommunication channel racks, telecommunication cabinets, and telecommunication enclosures are to be white in color.
- All telecommunication channel racks, telecommunication cabinets, and telecommunication enclosures shall be properly anchored to the floor.
- Telecommunication Channel Racks (Ortronics MightyMo OR-MM2073038-W – or approved equal) sufficient to support active network switchgear, power distribution units, uninterruptable power supplies, optical fiber patch panels, balance twisted pair patch panels, and required cable management shall be provided with an allowance for 40% future capacity within each Telecom Room – with the following exceptions:
  - ◊ Building 10 will receive a self-contained air-conditioned network cabinet, EMCOR or similar

- ◊ Building 11 will receive a 26U network cabinet.
  - ◊ Building 13 will receive a wall mounted Telecommunication Enclosure
  - ◊ Building 30 will receive a 42U Telecommunication Enclosure
  - ◊ Building 56 will receive a 26U network cabinet.
- Vertical Cable Managers will be provided at the end of each row and in between each rack. – with the following exceptions:
  - ◊ Building 10 will receive a self-contained telecommunication cabinet, EMCOR or similar with horizontal cable managers.
  - ◊ Building 11 will receive a 26U network cabinet with horizontal cable managers.
  - ◊ Building 13 will receive a wall mounted Telecommunication Enclosure with horizontal cable managers.
  - ◊ Building 30 will receive a 42U Telecommunication Enclosure with horizontal cable managers.
  - ◊ Building 56 will receive a 26U network cabinet with horizontal cable managers.
- Cat 6A CU horizontal cabling will be terminated on 1U 48 port angled patch panels, eliminating the need for horizontal cable managers between patch panels.
- The upper most section of the first rack will be utilized for vertical optical fiber patch panels.
- Buildings 1, 9, 40, and 46: The bottom section of each rack will be utilized Owner Furnished Owner Installed (OFIO) active network components.
- Buildings 3, 10, 11, 12, 13, 30, 51, 52, and 56: The bottom section of each rack will be utilized to house UPS units. The area directly above the UPS and PDU units will be reserved for Owner Furnished Owner Installed (OFIO) active network components.
- Horizontal cable managers will be provided on top of and below each active network switch.
- The balance of the rack space will be utilized for horizontal CU patch panels.



## Telecom Rooms (Cont'd)

- All racks will be equipped with vertical power distribution units (APC AP8861 or Approved Equal) with the following exceptions:
  - ◊ Building 10 will receive a self-contained telecommunication cabinet, EMCOR or similar with horizontal power distribution units.
  - ◊ Building 11 will receive a 26U network cabinet with horizontal power distribution units.
  - ◊ Building 13 will receive a wall mounted Telecommunication Enclosure with horizontal power distribution units.
  - ◊ Building 30 will receive a 42U Telecommunication Enclosure with horizontal power distribution units.
  - ◊ Building 56 will receive a 26U network cabinet with horizontal power distribution units.
- All racks will include a horizontal rack Grounding Bar (RGB) located at the top rear of the rack.
- All metallic components will be bonded as per section 4.2.8 of the VA Infrastructure Standard for Telecommunication Spaces, Version 3.1, July 1, 2021
- UPS Power
  - ◊ Buildings 1, 9, 40, and 46: Will be served from a centrally located Monolithic UPS unit
  - ◊ Buildings 3, 10, 12, 51, and 52: Each rack or cabinet will contain one (1) 5 KW, 208V Uninterruptable Power Supply (UPS) (Eaton BladeUPS – or approved equal) units with NEMA L21-20P Input and L21-20R output.
  - ◊ Buildings 11, 13, and 56: Each cabinet will contain one (1) 2880VA metered L5-30 input/output Uninterruptable Power Supply (UPS) (APC SMX3000RMLV2U – or approved equal) units as per VA TE Guidelines.
  - ◊ Building 30: Network cabinet withing the basement level of building 30 will contain one (1) 2880VA metered L5-30 input/output Uninterruptable Power Supply (UPS) (APC SMX3000RMLV2U – or approved equal) units as this building lacks three phase power.
- Zone Power Distribution Units will not be utilized on this project.
  - ◊ Buildings 1, 9, 40, and 46: will contain two vertical rack PDUs. One energized by a centralized monolithic UPS, one energized by wall outlet.

- ◊ Buildings 3, 10, 12, 51, and 52: Will contain two vertical PDUs per rack. One energized by UPS, one energized by wall outlet. Rack Mounted UPS units will plug directly into local electrical outlets
- ◊ Buildings 11,13, 30, and 56: Will include two horizontal rack PDUs per rack. One energized by UPS, one energized by wall outlet. Rack Mounted UPS units will plug directly into local electrical outlets.

## MODIFICATIONS TO EXISTING TELECOMMUNICATION SPACES

- Modifications to existing spaces shall insure that all existing systems, regardless of if they are directly associated with this project, remain fully functional.
- Plans for extending services to existing systems effected by this project shall be accounted for within the design documents.
- Existing services and systems currently residing in Telecommunication spaces that are planned to be abandoned will remain in place. This project shall ensure that systems remaining within these spaces are not disrupted and are maintained through the project.
- Existing Radio and Paging Equipment, currently housed within Building 1 Penthouse, will not be relocated as part of this scope of work.



## HORIZONTAL DISTRIBUTION / 100-OHM BALANCE TWISTED-PAIR CABLE

- No horizontal UTP cable shall exceed 95 meters.
- All horizontal cabling shall be plenum rated.
- All horizontal cabling throughout the facility, rated CAT 6 and below, will be replaced including work area jacks and patch panels. All cabling new shall be plenum rated Cat 6A. Horizontal cabling shall conform with section 4.4.8 of the VA Infrastructure Standard for Telecommunication Spaces, Version 3.1, July 1, 2021 - with following exception:
  - ◊ Building 30 – Existing horizontal cabling to remain and be re-terminated within a new network cabinet being installed within the basement level of Building 30.
- The installation of all new CAT 6A cabling between the Telecom Room patch panel and end-user outlet (EUD) will utilize existing pathways where feasible. This includes utilizing existing non-continuous cable support (aka J-hooks) or raceways through interstitials and above ceilings. Where existing pathway are found to be inadequate, the installation of flex-conduit or Electrical Metal Tubing (EMT) conduit will be utilized. Conduit is required within hollow walls. Conduit is not required within accessible ceilings. Any conduit used will be marked appropriately with "low-voltage/data" at regular intervals to be visible in interstitial spaces with minimal effort. Conduit will be utilized in areas where cable is exposed to risk of damage, such as mechanical areas.
- The use of non-continuous cable supports (aka J-hooks) shall be limited to cable bundles of 12 cables or less and distances of less than 50 feet.
- In accordance with VA Infrastructure Standard for Telecommunication Spaces, Version 3.1, July 1, 2021 Section 4.4.1, Unshielded Twisted Pair cabling will be CAT 6A terminated to IEEE 568-B guidelines.
- Un-terminated "future capacity" cables are not permitted. All installed cables shall be terminated at each end and documentation, labeling and (where applicable) test

results provided. This applies to all permanently installed cable types.

- All in-building copper cabling will be terminated and labeled in accordance with section 5.1.5 of the VA Infrastructure Standard for Telecommunication Spaces, Version 3.1, July 1, 2021
- Cabling will be terminated to CAT 6A modular jacks capable of accepting and functioning with other modular (i.e.: RJ11) plugs without damage to the jack.
- Patch panels conforming to EIA/ECA 310-3 dimensions and suitable for mounting in standard equipment racks, with 48 RJ45 jacks aligned in two horizontal rows per patch panel will be provided and installed by vendor.
- Cabling will be combed and dressed neatly in all locations within the service bays.
- Installed cabling will utilize the following color scheme:

| <u>Permanent Cabling Jacket Colors</u> | <u>Patch Cabling Colors</u> |
|--|-----------------------------|
| Data – Blue                            | Voice – Gray                |
| Nurse Call – Green                     | PC – Yellow                 |
| Philips Telemetry – Orange             | BioMed – Green              |
| Guest Wi-Fi – White                    | Wireless – Blue             |
| Voice – White                          | Printer – Red               |
| Get Well Network – Purple              | Video/TMED - Black          |
| Verizon – White                        |                             |
| Fire Alarm – Red                       |                             |
| BAS – Black                            |                             |
| Video Surveillance – Purple            |                             |

## WIRELESS ACCESS POINTS

- All cabling to all wireless access points will be replaced with CAT6A cabling and terminated to single-jack surface-mounted outlet or modular plug terminated link (MPTL) in the drop-ceiling nearest the access point. No wireless access points will be replaced. All cabling for wireless access points will be labeled in accordance with section 5.1.5 of the VA Infrastructure Standard for Telecommunication Spaces, Version 3.1, July 1, 2021
- .CAT6A cable to AP compliant with VA Telecommunications and Special Telecommunications Systems Design Manual and TIA TBS-162-A, Telecommunication Cabling Guidelines for Wireless Access Points.



## (CONT'D) WIRELESS ACCESS POINTS

- 10 ft. service loop will be provided at each WAP location.
- The provision, installation, programming, and certification of access points will not be by contractor. All access points will remain in place, and the contractor will replace cabling only.

## BACKBONE DISTRIBUTION / OPTICAL FIBER AND COPPER UTP

- Backbone cabling shall conform with section 4.4.11 of the VA Infrastructure Standard for Telecommunication Spaces, Version 3.1 July 1, 2021.
- All backbone fiber will terminate via fusion splice LC type cassettes within lockable fiber distribution panels.

### Redundant and Diverse Pathways

- This scope of work shall include installation of a single optical fiber to each TR (Path "A").
- A forthcoming project will include the installation of a redundant and diverse optical fiber to each TR (Path "B").
- Care shall be taken to ensure that installation of Path "B" does impede or compromise the diverse installation of Path "A". Installation of Path "A" cabling shall be done in a way that allows for maximum separation of the diverse pathways including installing cabling as tight as possible to one side of a corridor.

### Intra-Building optical fiber and multi-pair copper

- The MDA located within COMPUTER ROOM BC-50 will connect directly to each Telecommunication Room.
- Intra-Building optical fiber shall be plenum rated armored cable.
- Intra-Building multi-pair copper shall be plenum rated. Each Telecommunication Room within Buildings 1, 9, 40, and 46 will receive new optical fiber backbone

cabling consisting of one (1) 24 strand OM4 multimode fiber optic cable, one (1) 12 strand OS1 single mode fiber optic cable, and one (1) 25 pair Cat 5e cable served from the new MDA established at MCR/DC B409.

- 25 pair Cat 5e cable will be installed to each TR.
  - ◊ Terminated at rack mounted 110blocks at Telephone Equipment Room BC-60.
  - ◊ Terminated at rack mounted 24 port Cat5e patch panels (one pair per port) at the TR.
- Routing plan for Buildings 1, 9, 40, and 46 shall take into consideration potential locations of future new MCR.
- A service loop of 300 feet shall be provided and neatly coiled at the MCR and BC-60 for TRs BA-92, BC-02, 1B-121, 1B-65 to help facilitate the future MCR relocation.

### Inter-building optical fiber and multi-pair copper

- The MDA located with COMPUTER ROOM BC-50 will connect directly to each Telecommunication Room in all campus buildings outside of the computer room building.
- Inter-building optical fiber and multi-pair copper shall be indoor / outdoor rated cable suitable for installation within underground duct bank.
- Each Telecommunication Room (or Telecommunication Cabinet) withing Buildings 3, 10, 11, 12, 13, 30, 51, 52, and 56 will receive one (1) 24 strand OS2 single mode fiber optic cable and one (1) 25 pair Cat 5e cable with fiber optic cable served from the existing MDA at COMPUTER ROOM BC-50 and Cat 5e cable served from the Entrance Facility located at TELEPHONE EQUIPMENT ROOM BC-60
- This fiber optic cable shall consist of a single jacket, non-armored loose tube fiber cable when installed within conduit.
- As this cable will transition between outdoor and indoor installation, the cable shall be rated accordingly for indoor/outdoor applications.
- Existing pathways and duct banks shall be utilized, as to the extent possible, for installation of new fiber optic cable.



## (Cont'd) Inter-building optical fiber and multi-pair copper

- 25 pair Cat 5e cable will be installed to each TR.
  - ◊ Terminated at rack mounted 110blocks at Telephone Equipment Room BC-60.
  - ◊ Terminated at rack mounted 24 port Cat5e patch panels (one pair per port) at the TR.
  - ◊ When Cat 5e cable transitions outside of Building 1, 9, 40, or 46, Building Entrance Terminals (BETs) lighting arrestor blocks will be provided at Room BC-60 and each TR. 25 pair Cat 5e will terminate on the BETs prior to terminating on the patch panel or 110 block. BETs shall properly grounded.
- A service loop of 300 feet shall be provided and neatly coiled at the MCR for optical fiber serving TRs within Buildings 10, 11, 12, 13, 30, 51, 52, and 56 to help facilitate the future MCR relocation. Care shall be taken to ensure cable is properly dressed and supported.

## GROUNDING AND BONDING

- A new telecommunication grounding system shall be established based on ANSI/TIA-607-D, Generic Telecommunications Bonding and Grounding (Earthing) for Customer Premises.
  - A single telecommunication grounding system will be established to support buildings 1, 9, 40, and 46.
  - Separate telecommunication grounding systems will be established to support Buildings 3, 10, 11, 12, 13, 30, 51, 52, and 56.
- Grounding and Bonding shall conform to section 4.2.8 of the VA Infrastructure Standard for Telecommunication Spaces, Version 3.1, July 1, 2021.
- All telecommunication spaces are to be bonded according to ANSI/TIA-607-C Generic Telecommunications Bonding and Grounding (Earthing) for Customer Premises, local

codes, the VA Electrical Design Manual, National Electrical Code, and National Electrical Safety Code.

## PHYSICAL SECURITY

- All rooms and spaces undergoing modifications and upgrades will include physical security enhancements complying with requirements dictated by the U.S. Department of Veterans Affairs, Physical Security and Resiliency Design Manual, October 1, 2020 – Revised September 1, 2021, and the U.S. Department of Veterans Affairs, Physical Security Design Manual for Mission Critical Facilities, January 2015
- Contractor shall verify existing conditions and promptly report any drawing discrepancies to the project COR and Architect.
- Project coordination – No systems or components shall be disrupted out of project sequence; Contractor shall coordinate all service disruptions with the project COR.
- Doors associated with Telecommunication spaces shall be equipped with dual authentication type card reader, door contacts/position switches, and required electronic locking hardware.
- Telecommunication spaces shall contain security surveillance cameras as well as motion detectors.
- Project scope includes modifications and additions to an existing access control system. Contractor to provide all labor and materials, including components, programming, licensing, and professional services, required for a fully functional system.
- Contractor shall match existing systems already in-use, to include manufacturer product and turn-key components that will comply with the expansion of that systems normal operation. Verify and include software updates and licensing as required to match and expand the operation capacity of each added device and/or new equipment.
- The existing access control system is SoftwareHouse. Modifications to the existing system must be fully compliant with the existing platform.




## PHYSICAL SECURITY (CONT'D)

with specification section 27 05 26.

- The existing access control system shall be expanded as required to support added devices.
- In addition to the expansion of existing access control panels, new panels will be required at the following locations:
  - Building 1: TR 503
  - Building 3: TR 0001
  - Building 10: Mezzanine Area
  - Building 11: Open Office Area
  - Building 12: TR 0005
  - Building 13: Office 101
  - Building 30: Basement
  - Building 56: Chiller Plant
- All new access control panels shall be provided with a minimum of 25% spare capacity.
- All TRs will have a dual authentication keypad/card reader that is compatible with the new VA PIV USAccess cards. Basis of design is the most current PIV 2-factor keypad from SIGNO.
- Motion detectors shall integrate with the access control system, providing individual alarms, utilizing hardwired inputs into the access control system.
- A complete network-based video surveillance solution, including all cameras, recording devices and licenses shall be provided.
- Video surveillance cameras and recording devices shall be NDAA compliant.
- Each video surveillance camera shall be provided with lens capable of being individually positioned (pan, tilt, roll, and twist) along a circular track.
- Coordinate final placement of surveillance cameras to avoid cable tray, cabling, and other objects that may impede the field of view. Final location shall be approved by project COR.
- All equipment shall be bonded to the grounding system in that room in accordance



# 7 TELECOMMUNICATIONS AND ELECTRONIC SECURITY



|                                 |  |  |  |  |                            |  |   |
|---------------------------------|--|--|--|--|----------------------------|--|---|
| Revisions:<br>03-18-22<br>Date: | <b>CONSULTANT</b><br>Telecom:<br>Bright Tree Studios<br>301 Brush Creek Road<br>Warrendale, PA 15238<br>(412)-212-7515 | <b>ARCHITECT/ENGINEER OF RECORD</b><br><br>3300 Dundee RD,<br>Northbrook, IL 60062<br>1-847-832-7592<br>www.bancroft-ae.com<br>Bancroft Project No. 18-021 | <b>STAMP</b><br>Office of<br>Construction<br>and Facilities<br>Management<br>VA U.S. Department<br>of Veterans Affairs | Drawing Title<br><b>TELECOMMUNICATION - SITE ROUTING<br/>         PLAN</b><br>SHEET of 281 | Phase <b>ISSUE FOR BID</b> | Project Title<br><b>EHRM INFRASTRUCTURE<br/>         UPGRADES</b><br>Location<br><b>FARGO VA HEALTH CARE SYSTEM</b><br>Issue Date<br>3/18/2022 | Project Number<br><b>437-21-205</b><br>Building Number<br><b>01, 09, 46</b><br>Drawing Number<br><b>TT-00-002</b> |
|---------------------------------|--|--|--|--|----------------------------|--|---|



## 8

---

### Appendices

- Appendix A - Terracon  
Asbestos and Lead Plans:  
8-2 - 8-11  
Asbestos and Lead Survey  
Plans and Report  
*(Printed as a Separate Document)*
- Appendix B - Hohbach-Lewin, Inc.  
Blast No Longer Part of BOD  
*(Separate Document)*
- Appendix C - Calibre Engineering  
Structural Calculations  
*(Printed as a Separate Document)*
- Appendix D -  
Mechanical Calculations and Cut Sheets  
*(Printed as a Separate Document)*
- Appendix E—Meeting Minutes
- Appendix F -  
OPCC *(Printed as a Separate Document)*





As part of the Fargo Veterans Administration Hospital Electronic Health Record Modernization (EHRM) Upgrade Project (Project), Terracon Consultants Inc. (Terracon) performed a Limited Asbestos and Lead-Based Paint Survey (Survey) of areas proposed to be impacted by the Project. Field work was completed from September 14 through September 16, November 17, 2021, from January 20 through 21, 2022, and February 9, 2022. The following materials were identified that may impact work in project areas:

### ASBESTOS CONTAINING MATERIAL

- 15 linear feet of magnesia pipe insulation on an 8-inch outside diameter pipe was identified in Room BD-02 of the main Hospital building. This is considered a Regulated Asbestos Containing Material (RACM).
- 196 square feet of black carpet mastic was identified in Room 3B-25 of the main Hospital building. This is considered a Category 1 Non-Friable Material in its current condition.

### LEAD-BASED PAINT

- Brown paint on the bathroom door in Building 10 was identified to contain lead above 1.0 mg/cm<sup>2</sup> threshold and therefore is considered Lead-Based Paint.






# APPENDIX A ASBESTOS AND LEAD ABATEMENT

Terracon

BUILDING 1/9/46

LEVEL BASEMENT



BASEMENT FLOOR PLAN  
SCALE: 1:250

| Table 1 – Identified Asbestos-Containing Materials by Homogenous Area (HA) |   |                           |                                  |                        |             |                     |                    |
|--|---|---------------------------|----------------------------------|------------------------|-------------|---------------------|--------------------|
| HA No.   | Material Description                                  | Location                  | Percent and Type Asbestos        | NESHAP Category        | Condition   | OSHA Classification | Estimated Quantity |
| 40   | Magnesia pipe insulation associated with 8" O.D. pipe | Main building, room BD-02 | 5% chrysotile<br>12% crocidolite | RACM                   | Not Damaged | TSI                 | 15 LF              |
| 50   | Black mastic associated with multicolored carpet      | Main building, room 3B-25 | 5% chrysotile                    | Category I non-friable | Not Damaged | Miscellaneous       | 196 SF             |

| Table 2: Identified Lead-Based Paint (LBP) >1.0 mg/cm² |                            |             |                 |                   |                  |
|--|----------------------------|-------------|-----------------|-------------------|------------------|
| Sample Nos.  | Location                   | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm²) |
| 165-168  | Building 10, bathroom door | Brown       | Wood            | Intact            | 3.71215 - >5.0   |

| Table 3: Identified Lead-Containing Paint (LCP) <1.0 mg/cm² |                               |             |                 |                   |                   |
|---|-------------------------------|-------------|-----------------|-------------------|-------------------|
| Sample Nos.   | Location                      | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm²)  |
| 27-29   | Main building, BD-02          | Peach       | Plaster         | Fair              | 0.15519 - 0.18238 |
| 48, 50  | Main building, 1C-99          | Tan         | Plaster         | Good              | 0.0022 - 0.06375  |
| 67, 68, 70  | Main building, 2C-60          | Tan         | GWB             | Good              | 0.00333 - 0.00423 |
| 71, 74, 75  | Main building, 2A-24          | Tan         | GWB             | Good              | 0.00208           |
| 78  | Main building, 2A-22A         | Tan         | GWB             | Good              | 0.00238           |
| 94  | Main building, 2D-19          | Tan         | GWB             | Good              | 0.30734           |
| 99  | Main building, 3C-66          | Tan         | GWB             | Good              | 0.00108           |
| 111, 112  | Main building, 3B-23          | Tan         | Plaster         | Good              | 0.08524 - 112     |
| 125   | Main building, 4E-15A         | Tan         | Metal           | Good              | 0.00787 - 0.02254 |
| 140   | Building 12, IRM              | White       | Brick           | Intact            | 0.00751           |
| 162   | Building 12, Break Room, door | Green       | Metal           | Intact            | 0.03597           |
| 170, 171  | Building 10, Upper Mezzanine  | White       | Brick           | Intact            | 0.01521 - 0.50088 |
| 179   | Building 11, Shop             | Tan         | Brick           | Intact            | 0.03891           |
| 180   | Building 11, Shop             | White       | Plaster         | Intact            | 0.03582           |
| 181   | Building 11, HAC              | Blue        | Plaster         | Intact            | 0.0274            |

| LEGEND |                                      |
|--------|--------------------------------------|
| ● 170  | IDENTIFIED ASBESTOS ACM LOCATIONS    |
| ● 170  | APPROXIMATE ASBESTOS SAMPLE LOCATION |
| ● 32   | APPROXIMATE LEAD SAMPLE LOCATION     |
| ● 27   | IDENTIFIED LCP (<1 MG/CM²) LOCATION  |
| ● 27   | IDENTIFIED LBP LOCATION              |

|  |  |  |  |       |  |  |  |  |  |               |  |                                      |  |                     |  |
|--|--|--|--|-------|--|--|--|--|--|---------------|--|--------------------------------------|--|---------------------|--|
| CONSULTANT                                   |  | ARCHITECT/ENGINEER OF RECORD                       |  | STAMP |  | Office of Construction and Facilities Management |  | Drawing Title  |  | Phase         |  | Project Title                        |  | Project Number      |  |
| Terracon Consulting Engineers and Scientists |  | Bancroft   |  |       |  | U.S. Department of Veterans Affairs              |  | EHRM BUILDING - BASEMENT FLOOR PLAN - ASBESTOS AND LEAD SAMPLE LOCATIONS |  | ISSUE FOR BID |  | EHRM INFRASTRUCTURE UPGRADES         |  | 437-21-205          |  |
| PROJECT NO. 1621701                          |  | 3200 Dunwoody Rd. NE, Suite 1000 Atlanta, GA 30328 |  |       |  |  |  | SHEET 281  |  |               |  | Location FARGO VA HEALTH CARE SYSTEM |  | Building Number     |  |
| ISSUE FOR BID                                |  | 03-16-22   |  |       |  |  |  |  |  |               |  | Issue Date 3/18/2022                 |  | Drawing Number H100 |  |
| Revisions:                                   |  | Date:  |  |       |  |  |  |  |  |               |  | Checked                              |  | Drawn               |  |



# APPENDIX A ASBESTOS AND LEAD ABATEMENT

Terracon

BUILDING 1/9/46

LEVEL 1





| Table 1 - Identified Asbestos-Containing Materials by Homogenous Area (HA) |   |                           |                           |                          |             |                     |                    |
|--|---|---------------------------|---------------------------|--------------------------|-------------|---------------------|--------------------|
| HA No.   | Material Description                                  | Location                  | Percent and Type Asbestos | NESHAP Category          | Condition   | OSHA Classification | Estimated Quantity |
| 40   | Magnesia pipe insulation associated with 8" O.D. pipe | Main building, room BD-02 | 5% chrysotile             | RACM                     | Not Damaged | TSI                 | 15 LF              |
| 54   | Black mastic associated with multicolored carpet      | Main building, room 3B-25 | 5% chrysotile             | Category I non-flammable | Not Damaged | Miscellaneous       | 196 SF             |

| Table 2: Identified Lead-Based Paint (LBP) >1.0 mg/cm² |                            |             |                 |                          |
|--|----------------------------|-------------|-----------------|--------------------------|
| Sample Nos.  | Location                   | Paint Color | Paint Substrate | Results (mg/cm²)         |
| 165-168  | Building 10, bathroom door | Brown       | Wood            | Intact<br>3.71215 - >5.0 |

| Table 3: Identified Lead-Containing Paint (LCP) <1.0 mg/cm² |                               |             |                 |                             |
|---|-------------------------------|-------------|-----------------|-----------------------------|
| Sample Nos.   | Location                      | Paint Color | Paint Substrate | Results (mg/cm²)            |
| 27-29   | Main building, BD-02          | Peach       | Plaster         | Fair<br>0.15519 - 0.18238   |
| 48, 50  | Main building, 1C-99          | Tan         | Plaster         | Good<br>0.0022 - 0.06375    |
| 67, 68, 70  | Main building, 2C-90          | Tan         | GWB             | Good<br>0.00333 - 0.00423   |
| 71, 74, 75  | Main building, 2A-24          | Tan         | GWB             | Good<br>0.00208             |
| 78  | Main building, 2A-22A         | Tan         | GWB             | Good<br>0.00238             |
| 94  | Main building, 2D-19          | Tan         | GWB             | Good<br>0.30734             |
| 99  | Main building, 3C-96          | Tan         | GWB             | Good<br>0.00108             |
| 111, 112  | Main building, 3B-23          | Tan         | Plaster         | Good<br>0.08524 - 112       |
| 125   | Main building, 4E-15A         | Tan         | Metal           | Good<br>0.00787 - 0.02254   |
| 140   | Building 12, IRM              | White       | Brick           | Intact<br>0.00751           |
| 162   | Building 12, Break Room, door | Green       | Metal           | Intact<br>0.03597           |
| 170, 171  | Building 10, Upper Mezzanine  | White       | Brick           | Intact<br>0.01521 - 0.50088 |
| 179   | Building 11, Shop             | Tan         | Brick           | Intact<br>0.03891           |
| 180   | Building 11, Shop             | White       | Plaster         | Intact<br>0.03582           |
| 181   | Building 11, HAC              | Blue        | Plaster         | Intact<br>0.0274            |

| LEGEND |                                      |
|--------|--------------------------------------|
| 170    | IDENTIFIED ASBESTOS ACM LOCATIONS    |
| 170    | APPROXIMATE ASBESTOS SAMPLE LOCATION |
| 32     | APPROXIMATE LEAD SAMPLE LOCATION     |
| 27     | IDENTIFIED LCP (<1 MG/CM²) LOCATION  |
| 27     | IDENTIFIED LBP LOCATION              |


Bancroft  
BANCROFT ARCHITECTS + ENGINEERS

|                             |  |  |  |   |  |       |  |  |  |  |  |                        |  |   |  |   |  |
|-----------------------------|--|--|--|---|--|-------|--|--|--|--|--|------------------------|--|---|--|---|--|
|                             |  | CONSULTANT   |  | ARCHITECT/ENGINEER OF RECORD  |  | STAMP |  | Office of Construction and Facilities Management |  | Drawing Title<br>EHRM BUILDING - FIRST FLOOR PLAN - ASBESTOS AND LEAD SAMPLE LOCATIONS |  | Phase<br>ISSUE FOR BID |  | Project Title<br>EHRM INFRASTRUCTURE UPGRADES |  | Project Number<br>437-21-205<br>Building Number |  |
|                             |  | <br>Consulting Engineers and Scientists<br>PROJECT NO. M1217911<br>5601 8th St NE LNKX<br>PRY 1/21/2023 04:03 |  | <br>BANCROFT ARCHITECTS + ENGINEERS<br>13201 Commerce Rd.<br>Hawthorne, CA 90250<br>P. 314.719.1232<br>www.bancroftarchitects.com<br>Bancroft Project No. 18-021 |  |       |  | VA U.S. Department of Veterans Affairs           |  | SHEET of 281   |  |                        |  | Location<br>FARGO VA HEALTH CARE SYSTEM       |  | Drawing Number<br>H101                          |  |
| ISSUE FOR BID<br>Revisions: |  | 03-18-22<br>Date:  |  | WEST FARGO, ND 58103<br>FAX: 1/21/2023 04:03  |  |       |  |  |  |  |  |                        |  | Issue Date<br>3/18/2022                       |  | Checked<br>Drawn                                |  |



# APPENDIX A ASBESTOS AND LEAD ABATEMENT

**Terracon**  
BUILDING 1/9/46  
LEVEL 2



SECOND FLOOR PLAN  
SCALE: 1:250

| Table 1 – Identified Asbestos-Containing Materials by Homogenous Area (HA) |   |                           |                                |                       |             |                     |                    |
|--|---|---------------------------|--------------------------------|-----------------------|-------------|---------------------|--------------------|
| HA No.   | Material Description                                  | Location                  | Percent and Type Asbestos      | NESHAP Category       | Condition   | OSHA Classification | Estimated Quantity |
| 40 (samples 118, 119, 120)   | Magnesia pipe insulation associated with 8" O.D. pipe | Main building, room BD-02 | 5% chrysotile, 12% crocidolite | RACM                  | Not Damaged | TSI                 | 15 LF              |
| 55 (samples 168, 169, 170)   | Black mastic associated with multicolored carpet      | Main building, room 3B-25 | 5% chrysotile                  | Category I non-frable | Not Damaged | Miscellaneous       | 198 SF             |

| Table 2: Identified Lead-Based Paint (LBP) >1.0 mg/cm <sup>2</sup> |                            |             |                 |                   |                               |
|--|----------------------------|-------------|-----------------|-------------------|-------------------------------|
| Sample Nos.  | Location                   | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm <sup>2</sup> ) |
| 165-168  | Building 10, bathroom door | Brown       | Wood            | Intact            | 3.71215 - >5.0                |

| Table 3: Identified Lead-Containing Paint (LCP) <1.0 mg/cm <sup>2</sup> |                               |             |                 |                   |                               |
|---|-------------------------------|-------------|-----------------|-------------------|-------------------------------|
| Sample Nos.   | Location                      | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm <sup>2</sup> ) |
| 27-29   | Main building, BD-02          | Peach       | Plaster         | Fair              | 0.15519 - 0.18238             |
| 48, 50  | Main building, 1C-09          | Tan         | Plaster         | Good              | 0.0022 - 0.06375              |
| 67, 68, 70  | Main building, 2C-00          | Tan         | GWB             | Good              | 0.00333 - 0.00423             |
| 71, 74, 75  | Main building, 2A-24          | Tan         | GWB             | Good              | 0.00208                       |
| 78  | Main building, 2A-22A         | Tan         | GWB             | Good              | 0.00236                       |
| 94  | Main building, 2D-19          | Tan         | GWB             | Good              | 0.30734                       |
| 99  | Main building, 3C-06          | Tan         | GWB             | Good              | 0.00108                       |
| 111, 112  | Main building, 3B-23          | Tan         | Plaster         | Good              | 0.08524 - 112                 |
| 125   | Main building, 4E-15A         | Tan         | Metal           | Good              | 0.00787 - 0.02254             |
| 140   | Building 12, IRM              | White       | Brick           | Intact            | 0.00751                       |
| 162   | Building 12, Break Room, door | Green       | Metal           | Intact            | 0.03597                       |
| 170, 171  | Building 10, Upper Mezzanine  | White       | Brick           | Intact            | 0.01521 - 0.50088             |
| 179   | Building 11, Shop             | Tan         | Brick           | Intact            | 0.03891                       |
| 180   | Building 11, Shop             | White       | Plaster         | Intact            | 0.03582                       |
| 181   | Building 11, HAC              | Blue        | Plaster         | Intact            | 0.0274                        |


| LEGEND |  |
|--------|--|
| ● 170  | IDENTIFIED ASBESTOS ACM LOCATIONS                |
| ● 170  | APPROXIMATE ASBESTOS SAMPLE LOCATION             |
| ● 32   | APPROXIMATE LEAD SAMPLE LOCATION                 |
| ● 27   | IDENTIFIED LCP (<1 MG/CM <sup>2</sup> ) LOCATION |
| ● 27   | IDENTIFIED LBP LOCATION                          |

|                             |  |  |   |       |  |  |               |  |                        |
|-----------------------------|--|--|---|-------|--|--|---------------|--|------------------------|
|                             |  | CONSULTANT   | ARCHITECT/ENGINEER OF RECORD  | STAMP | Office of Construction and Facilities Management | Drawing Title  | Phase         | Project Title  | Project Number         |
|                             |  | <b>Terracon</b><br>Consulting Engineers and Scientists<br>PROJECT NO. W1717071<br>885 9B-ST. AVE. SW<br>PH. (701) 281-8632 FAX. (701) 282-8635 | <b>Bancroft</b><br>BANCROFT ARCHITECTS + ENGINEERS<br>3300 Dunsmuir Rd.<br>Northbrook, IL 60062<br>TEL: 847.233.0262<br>www.bancroftarch.com<br>Bancroft Project No. 18-121 |       | VA U.S. Department of Veterans Affairs           | EHRM BUILDING - SECOND FLOOR PLAN - ASBESTOS AND LEAD SAMPLE LOCATIONS | ISSUE FOR BID | EHRM INFRASTRUCTURE UPGRADES                                       | 437-21-205             |
| ISSUE FOR BID<br>Revisions: |  | 03-18-22<br>Date:  |   |       |  | SHEET of 281   |               | Location<br>FARGO VA HEALTH CARE SYSTEM<br>Issue Date<br>3/18/2022 | Drawing Number<br>H102 |



# APPENDIX A ASBESTOS AND LEAD ABATEMENT

**Terracon**  
BUILDING 1/9/46  
LEVEL 3



THIRD FLOOR PLAN  
SCALE: 1/16" = 1'-0"

| Table 1 - Identified Asbestos-Containing Materials by Homogenous Area (HA) |   |                           |                                |                        |             |                      |
|--|---|---------------------------|--------------------------------|------------------------|-------------|----------------------|
| HA No.   | Material Description                                  | Location                  | Percent and Type Asbestos      | NESHAP Category        | Condition   | Estimated Quantity   |
| 40   | Magnesia pipe insulation associated with 8" O.D. pipe | Main building, room 3C-02 | 5% chrysotile, 12% crocidolite | RACM                   | Not Damaged | 15 LF                |
| 55   | Black mastic associated with multicolored carpet      | Main building, room 3B-25 | 5% chrysotile                  | Category I non-friable | Not Damaged | Miscellaneous 196 SF |

| Table 2: Identified Lead-Based Paint (LBP) >1.0 mg/cm² |                            |             |                 |                  |
|--|----------------------------|-------------|-----------------|------------------|
| Sample Nos.  | Location                   | Paint Color | Paint Substrate | Results (mg/cm²) |
| 165-168  | Building 10, bathroom door | Brown       | Wood            | 3.71215 - >5.0   |

| Table 3: Identified Lead-Containing Paint (LCP) <1.0 mg/cm² |                               |             |                 |                   |                   |
|---|-------------------------------|-------------|-----------------|-------------------|-------------------|
| Sample Nos.   | Location                      | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm²)  |
| 27-29   | Main building, 3C-02          | Peach       | Plaster         | Fair              | 0.15519 - 0.18238 |
| 48, 50  | Main building, 1C-99          | Tan         | Plaster         | Good              | 0.0022 - 0.06375  |
| 67, 68, 70  | Main building, 3C-90          | Tan         | GWB             | Good              | 0.00333 - 0.00423 |
| 71, 74, 75  | Main building, 2A-24          | Tan         | GWB             | Good              | 0.00208           |
| 78  | Main building, 2A-22A         | Tan         | GWB             | Good              | 0.00238           |
| 84  | Main building, 2D-19          | Tan         | GWB             | Good              | 0.30734           |
| 99  | Main building, 3C-96          | Tan         | GWB             | Good              | 0.00108           |
| 111, 112  | Main building, 3B-23          | Tan         | Plaster         | Good              | 0.08524 - 1.12    |
| 125   | Main building, 4E-15A         | Tan         | Metal           | Good              | 0.00787 - 0.02254 |
| 140   | Building 12, IRM              | White       | Brick           | Intact            | 0.00751           |
| 162   | Building 12, Break Room, door | Green       | Metal           | Intact            | 0.03597           |
| 170, 171  | Building 10, Upper Mezzanine  | White       | Brick           | Intact            | 0.01521 - 0.50088 |
| 179   | Building 11, Shop             | Tan         | Brick           | Intact            | 0.03891           |
| 180   | Building 11, Shop             | White       | Plaster         | Intact            | 0.03582           |
| 181   | Building 11, HAC              | Blue        | Plaster         | Intact            | 0.0274            |

**LEGEND**

- 170 IDENTIFIED ASBESTOS ACM LOCATIONS
- 170 APPROXIMATE ASBESTOS SAMPLE LOCATION
- 32 APPROXIMATE LEAD SAMPLE LOCATION
- 27 IDENTIFIED LCP (<1 MG/CM²) LOCATION
- 27 IDENTIFIED LBP LOCATION

**Bancroft**  
BANCROFT ARCHITECTS + ENGINEERS

|   |  |   |   |  |                        |   |   |
|---|--|---|---|--|------------------------|---|---|
| ISSUE FOR BID<br>Revisions:<br>Date: 03-18-22 | CONSULTANT<br><b>Terracon</b><br>Consulting Engineers and Scientists<br>PROJECT NO. M1217011<br>1800 N. ST. JOE AVE.<br>PH: (771) 362-8833 FAX: (771) 362-8836 | ARCHITECT/ENGINEER OF RECORD<br><b>Bancroft</b><br>BANCROFT ARCHITECTS + ENGINEERS<br>3000 Dundee Rd.<br>Northbrook, IL 60062<br>Tel: (847) 491-1000<br>Fax: (847) 491-1002<br>Bancroft Project No. 18-01 | STAMP<br>Office of Construction and Facilities Management<br>VA U.S. Department of Veterans Affairs | Drawing Title<br>EHRM BUILDING - THIRD FLOOR PLAN - ASBESTOS AND LEAD SAMPLE LOCATIONS<br>SHEET of 281 | Phase<br>ISSUE FOR BID | Project Title<br>EHRM INFRASTRUCTURE UPGRADES<br>Location<br>FARGO VA HEALTH CARE SYSTEM<br>Issue Date<br>3/18/2022 | Project Number<br>437-21-205<br>Building Number<br>Drawing Number<br>H103 |
|---|--|---|---|--|------------------------|---|---|



## ASBESTOS AND LEAD ABATEMENT

**Terracon**  
BUILDING 1/9/46  
LEVEL 4

FOURTH FLOOR PLAN  
SCALE: 1/16" = 1'-0"

Table 1 – Identified Asbestos-Containing Materials by Homogenous Area (HA)

| HA No.                        | Material Description                                  | Location                  | Percent and Type Asbestos        | NESHAP Category        | Condition   | OGHA Classification | Estimated Quantity |
|-------------------------------|---|---------------------------|----------------------------------|------------------------|-------------|---------------------|--------------------|
| 40<br>(samples 118, 119, 120) | Magnesia pipe insulation associated with 8" O.D. pipe | Main building, room BD-02 | 5% chrysotile<br>12% crocidolite | RCAM                   | Not Damaged | TSI                 | 15 LF              |
| 55<br>(samples 168, 169, 170) | Black mastic associated with multicolored carpet      | Main building, room 3B-25 | 5% chrysotile                    | Category I non-friable | Not Damaged | Miscellaneous       | 196 SF             |

Table 2: Identified Lead-Based Paint (LBP) >1.0 mg/cm<sup>2</sup>

| Sample Nos. | Location                   | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm <sup>2</sup> ) |
|-------------|----------------------------|-------------|-----------------|-------------------|-------------------------------|
| 165-168     | Building 10, bathroom door | Brown       | Wood            | Intact            | 3.71215 ~ >5.0                |

Table 3: Identified Lead-Containing Paint (LBP) <1.0 mg/cm<sup>2</sup>

| Sample Nos. | Location                      | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm <sup>2</sup> ) |
|-------------|-------------------------------|-------------|-----------------|-------------------|-------------------------------|
| 27-29       | Main building, BD-02          | Peach       | Plaster         | Fair              | 0.15519 - 0.18238             |
| 48, 50      | Main building, 1C-99          | Tan         | Plaster         | Good              | 0.0022 - 0.06375              |
| 67, 68, 70  | Main building, 2C-90          | Tan         | GWB             | Good              | 0.00333 - 0.04123             |
| 71, 74, 75  | Main building, 2A-24          | Tan         | GWB             | Good              | 0.00208                       |
| 78          | Main building, 2A-22A         | Tan         | GWB             | Good              | 0.00238                       |
| 94          | Main, building, 2D-19         | Tan         | GWB             | Good              | 0.30734                       |
| 99          | Main building, 3C-96          | Tan         | GWB             | Good              | 0.00108                       |
| 111, 112    | Main building, 3B-23          | Tan         | Plaster         | Good              | 0.08524 - 112                 |
| 125         | Main building, 4E-15A         | Tan         | Metal           | Good              | 0.00787 - 0.02254             |
| 140         | Building 12, 1RM              | White       | Brick           | Intact            | 0.00751                       |
| 162         | Building 12, Break Room, door | Green       | Metal           | Intact            | 0.03597                       |
| 170, 171    | Building 10, Upper Mezzanine  | White       | Brick           | Intact            | 0.01521 - 0.50088             |
| 179         | Building 11, Shop             | Tan         | Brick           | Intact            | 0.03891                       |
| 180         | Building 11, Shop             | White       | Plaster         | Intact            | 0.03582                       |
| 181         | Building 11, HAC              | Blue        | Plaster         | Intact            | 0.0274                        |


**LEGEND**

- 170 IDENTIFIED ASBESTOS ACM LOCATIONS  
 170 APPROXIMATE ASBESTOS SAMPLE LOCATION  
 32 APPROXIMATE LEAD SAMPLE LOCATION  
 27 IDENTIFIED LCP (<1 MG/CM<sup>2</sup>) LOCATION  
 77 IDENTIFIED LBP LOCATION

|                             |                   |  |  |   |  |                     |  |   |   |                        |
|-----------------------------|-------------------|--|--|---|--|---------------------|--|---|---|------------------------|
| ISSUE FOR BID<br>Revisions: | 03-15-22<br>Date: | CONSULTANT<br><br>Consulting Engineers and Scientists<br>PROJECT NO. M211071<br>840 9th ST NE Unit K WEST FARGO, ND 58078<br>PH: (701) 292-9033 FAX: (701) 292-9035 | ARCHITECT/ENGINEER OF RECORD<br><br>3000 Dunwoody RD.<br>(Interstate 4 & 400) S.E.<br>T: 847 522 5362<br>F: 847 522 5363<br>www.bancroft-arch.com<br>Bancroft Paved Inc. 18-121 | STAMP<br>Office of<br>Construction<br>and Facilities<br>Management<br>VA U.S. Department<br>of Veterans Affairs | Drawing Title<br>EHRM BUILDING - FOURTH FLOOR PLAN -<br>ASBESTOS AND LEAD SAMPLE LOCATIONS | Phase ISSUE FOR BID | Project Title<br>EHRM INFRASTRUCTURE<br>UPGRADES | Project Number<br>437-21-205<br>Building Number | Location<br>FARGO VA HEALTH CARE SYSTEM | Drawing Number<br>H104 |
|                             |                   |  |  |   | SHEET of 281   |                     | Issue Date<br>3/18/2022                          | Checked   | Drawn                                   |                        |



## ASBESTOS AND LEAD ABATEMENT



| Sample Nos. | Location                      | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm <sup>2</sup> ) |
|-------------|-------------------------------|-------------|-----------------|-------------------|-------------------------------|
| 27-29       | Main building, BD-02          | Peach       | Plaster         | Fair              | 0.15519 - 0.18238             |
| 48, 50      | Main building, 1C-09          | Tan         | Plaster         | Good              | 0.0022 - 0.06375              |
| 67, 68, 70  | Main building, 2C-90          | Tan         | GWb             | Good              | 0.00333 - 0.00423             |
| 71, 74, 75  | Main building, 2A-24          | Tan         | GWb             | Good              | 0.00208                       |
| 78          | Main building, 2A-22A         | Tan         | GWb             | Good              | 0.00238                       |
| 94          | Main building, 2D-19          | Tan         | GWb             | Good              | 0.30734                       |
| 99          | Main building, 3C-96          | Tan         | GWb             | Good              | 0.00106                       |
| 111, 112    | Main building, 3B-23          | Tan         | Plaster         | Good              | 0.08524 - 112                 |
| 125         | Main building, 4E-15A         | Tan         | Metal           | Good              | 0.00787 - 0.02254             |
| 140         | Building 12, IRM              | White       | Brick           | Intact            | 0.00751                       |
| 162         | Building 12, Break Room, door | Green       | Metal           | Intact            | 0.03597                       |
| 170, 171    | Building 10, Upper Mezzanine  | White       | Brick           | Intact            | 0.01521 - 0.50088             |
| 179         | Building 11, Shop             | Tan         | Brick           | Intact            | 0.03891                       |
| 180         | Building 11, Shop             | White       | Plaster         | Intact            | 0.03582                       |
| 181         | Building 11, HAC              | Blue        | Plaster         | Intact            | 0.0274                        |

| HA No.                  | Material Description                     | Location                  | Percent and Type of Asbestos     | HEHAP Category         | Condition   | OSHA Classification | Estimated Quantity |
|-------------------------|--|---------------------------|----------------------------------|------------------------|-------------|---------------------|--------------------|
| 40                      | Magnesia pipe insulation (118, 119, 120) | Main building, room ED-2  | 5% chrysotile<br>12% crocidolite | RACM                   | Not Damaged | TJSI                | 15                 |
| 55                      | Black mastic                             | Main building             | 5% chrysotile                    | Category I non-friable | Not Damaged | Micaceous           | 196                |
| (samples 168, 169, 170) | asbestos-laminated                       | Main building, room 3B-25 |                                  |                        |             |                     |                    |

**LEGEND**

- 170 IDENTIFIED ASBESTOS ACM LOCATIONS
- 170 APPROXIMATE ASBESTOS SAMPLE LOCATION
- 32 APPROXIMATE LEAD SAMPLE LOCATION
- 27 IDENTIFIED LCP (<1 MG/CM<sup>2</sup>) LOCATION
- 27 IDENTIFIED LBP LOCATION

[illegible]




# APPENDIX A

## ASBESTOS AND LEAD ABATEMENT

### Terracon

BUILDING 11



| LEGEND |                                      |  |  |
|--------|--------------------------------------|--|--|
| 170    | IDENTIFIED ASBESTOS ACM LOCATIONS    |  |  |
| 170    | APPROXIMATE ASBESTOS SAMPLE LOCATION |  |  |
| 32     | APPROXIMATE LEAD SAMPLE LOCATION     |  |  |
| 27     | IDENTIFIED LCP (<1 MG/CM²) LOCATION  |  |  |
| 27     | IDENTIFIED LBP LOCATION              |  |  |

| Table 1 - Identified Asbestos-Containing Materials by Homogenous Area (HA) |   |                           |                               |                        |             |                     |                    |
|--|---|---------------------------|-------------------------------|------------------------|-------------|---------------------|--------------------|
| HA No.   | Material Description                                  | Location                  | Percent and Type Asbestos     | NESHAP Category        | Condition   | OSHA Classification | Estimated Quantity |
| 40 (samples 118, 119, 120)   | Magnesia pipe insulation associated with 8" O.D. pipe | Main building, room BD-02 | 5% chrysotile 12% crocidolite | RACM                   | Not Damaged | TSI                 | 15 LF              |
| 50 (samples 168, 169, 170)   | Black mastic associated with multicolored carpet      | Main building, room 3B-25 | 5% chrysotile                 | Category I non-friable | Not Damaged | Miscellaneous       | 100 SF             |

| Table 2: Identified Lead-Based Paint (LBP) >1.0 mg/cm² |                            |             |                 |                   |                  |
|--|----------------------------|-------------|-----------------|-------------------|------------------|
| Sample Nos.  | Location                   | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm²) |
| 165-168  | Building 10, bathroom door | Brown       | Wood            | Intact            | 3.71215 - >5.0   |


| Table 3: Identified Lead-Containing Paint (LCP) <1.0 mg/cm² |                               |             |                 |                   |                   |
|---|-------------------------------|-------------|-----------------|-------------------|-------------------|
| Sample Nos.   | Location                      | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm²)  |
| 27-29   | Main building, BD-02          | Peach       | Plaster         | Fair              | 0.15519 - 0.18238 |
| 48, 50  | Main building, 1C-99          | Tan         | Plaster         | Good              | 0.00222 - 0.06375 |
| 67, 68, 70  | Main building, 2C-90          | Tan         | GWB             | Good              | 0.00333 - 0.00423 |
| 71, 74, 75  | Main building, 2A-24          | Tan         | GWB             | Good              | 0.00208           |
| 78  | Main building, 2A-22A         | Tan         | GWB             | Good              | 0.00238           |
| 94  | Main building, 2D-19          | Tan         | GWB             | Good              | 0.30734           |
| 99  | Main building, 3C-96          | Tan         | GWB             | Good              | 0.60108           |
| 111, 112  | Main building, 3B-23          | Tan         | Plaster         | Good              | 0.08524 - 112     |
| 125   | Main building, 4E-15A         | Tan         | Metal           | Good              | 0.00787 - 0.02254 |
| 140   | Building 12, IRM              | White       | Brick           | Intact            | 0.60751           |
| 162   | Building 12, Break Room, door | Green       | Metal           | Intact            | 0.03597           |
| 170, 171  | Building 10, Upper Mezzanine  | White       | Brick           | Intact            | 0.01821 - 0.50088 |
| 179   | Building 11, Shop             | Tan         | Brick           | Intact            | 0.03891           |
| 180   | Building 11, Shop             | White       | Plaster         | Intact            | 0.03582           |
| 181   | Building 11, HAC              | Blue        | Plaster         | Intact            | 0.0274            |

|                             |  |   |   |       |  |  |               |  |   |
|-----------------------------|--|---|---|-------|--|--|---------------|--|---|
|                             |  | CONSULTANT  | ARCHITECT/ENGINEER OF RECORD  | STAMP | Office of Construction and Facilities Management | Drawing Title                                    | Phase         | Project Title  | Project Number                            |
|                             |  | <b>Terracon</b><br>Consulting Engineers and Scientists<br>PROJECT NO. W1021111<br>480 SW ST. NE LAM K<br>PH: (771) 282-9633 FAX: (771) 282-9635 | <b>Bancroft</b><br>BANCROFT ARCHITECTS + ENGINEERS<br>3300 DUNDAS RD.<br>NORTH BAY, IL 60062<br>TEL: (847) 932-2562<br>www.bancroft-ae.com<br>Bancroft Project No. 18-121 |       | VA   | BUILDING 11 - ASBESTOS AND LEAD SAMPLE LOCATIONS | ISSUE FOR BID | EHRM INFRASTRUCTURE UPGRADES                                       | 437-21-205                                |
| ISSUE FOR BID<br>Revisions: |  | 03-18-22<br>Date:   |   |       |  | SHEET of 281                                     |               | Location<br>FARGO VA HEALTH CARE SYSTEM<br>Issue Date<br>3/18/2022 | Building Number<br>Drawing Number<br>H106 |



# APPENDIX A ASBESTOS AND LEAD ABATEMENT

## Terracon BUILDING 12



FLOOR PLAN  
SCALE: 1/8" = 1'-0"

| LEGEND |  |  |  |  |
|--------|--|--|--|--|
| 170    | IDENTIFIED ASBESTOS ACM LOCATIONS                |  |  |  |
| 170    | APPROXIMATE ASBESTOS SAMPLE LOCATION             |  |  |  |
| 32     | APPROXIMATE LEAD SAMPLE LOCATION                 |  |  |  |
| 27     | IDENTIFIED LCP (<1 MG/CM <sup>2</sup> ) LOCATION |  |  |  |
| 27     | IDENTIFIED LBP LOCATION                          |  |  |  |

| Table 1 - Identified Asbestos-Containing Materials by Homogenous Area (HA) |  |                           |                                  |                        |             |                     |
|--|--|---------------------------|----------------------------------|------------------------|-------------|---------------------|
| HA No.   | Material Description                                   | Location                  | Percent and Type Asbestos        | NESHAP Category        | Condition   | OSHA Classification |
| 40   | Magnesium pipe insulation associated with 8" O.D. pipe | Main building, room BD-02 | 5% chrysotile<br>12% crocidolite | RACM                   | Not Damaged | T3                  |
| 115, 119, 120  | Black mastic associated with multicolored carpet       | Main building, room 3B-25 | 5% chrysotile                    | Category 1 non-friable | Not Damaged | Miscellaneous       |
| 15A  |  |                           |                                  |                        |             |                     |
| 196 SF   |  |                           |                                  |                        |             |                     |

| Table 2: Identified Lead-Based Paint (LBP) >1.0 mg/cm <sup>2</sup> |                            |             |                 |                   |                               |
|--|----------------------------|-------------|-----------------|-------------------|-------------------------------|
| Sample Nos.  | Location                   | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm <sup>2</sup> ) |
| 165-168  | Building 10, bathroom door | Brown       | Wood            | Intact            | 3.71215 - >5.0                |

| Table 3: Identified Lead-Containing Paint (LCP) <1.0 mg/cm <sup>2</sup> |                               |             |                 |                   |                               |
|---|-------------------------------|-------------|-----------------|-------------------|-------------------------------|
| Sample Nos.   | Location                      | Paint Color | Paint Substrate | Surface Condition | Results (mg/cm <sup>2</sup> ) |
| 27-29   | Main building, BD-02          | Peach       | Plaster         | Fair              | 0.15519 - 0.18238             |
| 48, 50  | Main building, 1C-99          | Tan         | Plaster         | Good              | 0.0022 - 0.06375              |
| 67, 68, 70  | Main building, 2C-90          | Tan         | GWB             | Good              | 0.00333 - 0.00423             |
| 71, 74, 75  | Main building, 2A-24          | Tan         | GWB             | Good              | 0.00208                       |
| 78  | Main building, 2A-22A         | Tan         | GWB             | Good              | 0.00238                       |
| 94  | Main building, 2D-19          | Tan         | GWB             | Good              | 0.30734                       |
| 99  | Main building, 3C-98          | Tan         | GWB             | Good              | 0.00108                       |
| 111, 112  | Main building, 3B-23          | Tan         | Plaster         | Good              | 0.08524 - 112                 |
| 125   | Main building, 4E-15A         | Tan         | Metal           | Good              | 0.00787 - 0.02254             |
| 140   | Building 12, IRM              | White       | Brick           | Intact            | 0.00751                       |
| 162   | Building 12, Break Room, door | Green       | Metal           | Intact            | 0.03597                       |
| 170, 171  | Building 10, Upper Mezzanine  | White       | Brick           | Intact            | 0.01521 - 0.50088             |
| 179   | Building 11, Shop             | Tan         | Brick           | Intact            | 0.03891                       |
| 180   | Building 11, Shop             | White       | Plaster         | Intact            | 0.03582                       |
| 181   | Building 11, HAC              | Blue        | Plaster         | Intact            | 0.0274                        |

BANCROFT ARCHITECTS + ENGINEERS

|                             |                   |   |   |           |  |   |                        |   |   |
|-----------------------------|-------------------|---|---|-----------|--|---|------------------------|---|---|
| ISSUE FOR BID<br>Revisions: | 03-15-22<br>Date: | CONSULTANT<br><br>Consulting Engineers and Scientists<br>PROJECT NO: 44737071<br>880 9th ST NE SUITE 100<br>FARGO ND 58103<br>TEL: (701) 262-8833 FAX: (701) 262-8835 | ARCHITECT/ENGINEER OF RECORD<br><br>BANCROFT ARCHITECTS + ENGINEERS<br>3140 DUNDAS RD<br>FARGO ND 58103<br>TEL: (701) 262-8833 FAX: (701) 262-8835<br>www.terracon.com<br>Bancroft Project No: 18-127 | STAMP<br> | Office of Construction and Facilities Management<br>VA | Drawing Title<br>BUILDING 12 - ASBESTOS AND LEAD SAMPLE LOCATIONS<br>SHEET of 281 | Phase<br>ISSUE FOR BID | Project Title<br>EHRM INFRASTRUCTURE UPGRADES<br>Location<br>FARGO VA HEALTH CARE SYSTEM<br>Issue Date<br>3/18/2022<br>Checked<br>Drawn | Project Number<br>437-21-205<br>Building Number<br>H107 |
|-----------------------------|-------------------|---|---|-----------|--|---|------------------------|---|---|



*Please See Separate Document*

APPENDIX A  
**Limited Pre-Renovation Asbestos  
and Lead-Based Paint Survey**

Project No. 437-21-205EHRM Infrastructure Upgrades  
Fargo Veteran Administration Healthcare System  
2101 Elm Street North  
Fargo, Cass County, North Dakota 58102  
March 18, 2022  
Terracon Project No. M1217071  
Appendix A from the Basis of Design



**Prepared for:**  
Bancroft Architects + Engineers  
Northbrook, IL

**Prepared by:**  
Terracon Consultants, Inc.  
West Fargo, North Dakota

terracon.com

**Terracon**

Environmental   ■   Facilities   ■   Geotechnical   ■   Materials



# APPENDIX B

BLAST NARRATIVE  
& CALCULATIONS

***No Longer part of BOD—For Security Reasons***

***Please see Separate Document***





Please See Separate Document



Fargo VAMC EHRM Infrastructure Upgrade  
Fargo, North Dakota  
Project # 437-21-205

Structural Calculations Package  
Issue for Bid  
March 18, 2022



Design prepared under the supervision of Ed Sabia, PE



# APPENDIX D

## MECHANICAL CUT SHEETS & ROOM EQUIP MET HEAT GAIN VERIFICATION

***Please See Separate Document***



Fargo VA Health Care System

2101 Elm Street North

Fargo, ND 58102

VA Contract No. 36C26319D0044

VA Station Project No. 437-21-205

Bancroft-AE Project No. 18-121

### EHRM Infrastructure Upgrades

#### BASIS OF DESIGN - APPENDIX D

A: Room Equipment Heat Gain Verification

B: : Mechanical Cut Sheets

ISSUE FOR BID


March 18, 2022





# APPENDIX E

## MEETING MINUTES

| MEETING MINUTES  |   |  |                             |
|--|---|---|-----------------------------|
| <b>Project Name:</b> EHRM Infrastructure Upgrades<br>Fargo ND VA HCS | <b>Project No:</b> 437-21-205<br><b>Bancroft No:</b> 18-121 |   |                             |
| <b>Meeting Milestone/Purpose:</b> BOD 10% Review                     | <b>Date:</b> September 7, 2021<br>3:00 p.m. (CDT)           | <b>Meeting Location:</b> VA – Virtual   |                             |
| Attendees: <small>Indicates not in attendance: **</small>            | Company   | Phone   | E-mail                      |
| Anthony Wilson   | VA / CO-Post-Award  | xxx-xxx-xxxx  | Anthony.Wilson3@va.gov      |
| Christ Moorer  | (VHACLE)  | xxx-xxx-xxxx  | christ.moorer@va.gov        |
| Ronald A. Tollefson  | VA / COR-Post-Award   | 701-232-3241<br>#3866   | ronald.tollefson@va.gov     |
| Clifford Halvorson   | VA /  | 701-232-3241<br>#3905   | clifford.halvorson@va.gov   |
| Brady Wiesner  | VA /  | 701-232-3241<br>#3335   | brady.wiesner@va.gov        |
| Raymond Nelson   | VA / Area Manager   | 701-232-3241<br>#7914   | raymond.nelson2@va.gov      |
| Ricki Keller   | VA/ IT Specialist   | 701-232-3241<br>#7818   | rickie.keller@va.gov        |
| Jose Barbosa   | VA/ Contractor  | xxx-xxx-xxxx  | jose@varadaconsulting.com   |
| Jeffrey Zuczek   | VA/   | xxx-xxx-xxxx  | jeffrey.zuczek@va.gov       |
| John Robbins   | Bancroft AE / Project Manager                               | 224-265-2120  | jrobbins@bancroft-ae.com    |
| Darlene Flook  | Bancroft AE / Project Manager                               | 224-875-6881  | dflook@bancroft-ae.com      |
| Dana Auman   | Bancroft AE / Project Architect                             | 224-265-2115  | dauman@bancroft-ae.com      |
| Walter Groszko   | Bancroft AE / Project Electrical Eng                        | 224-366-1220  | wgroszko@bancroft-ae.com    |
| Bruce Yoch   | BrightTree  | xxx-xxx-xxxx  | byoch@brighttreestudios.com |
|  |   |   |                             |

| Item | Action Item | Comments and Notes   | Group/Person Responsible | Target Completion Date |
|------|-------------|--|--------------------------|------------------------|
| 1    |             | VA prepared f "redline" review w/ comments and will share on SharePoint  |                          |                        |
| 2    |             | VA requested identification of Certified Physical Security Specialist. Bruce Yoch of BriteTree confirmed he was, and Kyle Hass of Hobach-Lewin is as well. Will be indicated in BOD  | BAE                      |                        |
| 3    |             | Station infrastructure for which EHRM waivers will be required:<br>*No second entrance room for service provider.<br>*No redundant fiber source from MCR to TR's. (No physical space capability.)<br>*BAE will assist Station in preparing written waivers document to submit to ERHM. | VA                       |                        |
| 4    |             | 35% to be added to Schematic line  | BAE                      |                        |
| 5    |             | Codes and Standards: VA requests BAE delete those that are not applicable to this specific project.  |                          |                        |
| 6    |             | VA noted that the Main Hospital is actually three buildings and will need to be identified as such in future documents. Building Nos. are 1, 9 and 46.   |                          |                        |
| 7    |             | VA noted that Building 42 is the UND School of Medicine and is not affiliated with the VA. This building will not be part of the Scope of Work.  |                          |                        |
| 8    |             | VA noted that a new TR will be required to be constructed at the Main Hospital penthouse level (5th Floor). The COR will provide a plan subsequent to this meeting.  |                          |                        |
| 9    |             | VA Station requires (1) whole campus UPS, located in basement level of the Main Hospital Building. Currently there are more than one UPS located throughout the campus.  |                          |                        |
| 10   |             | VA noted that there is currently only single-phase power throughout Building 1/9/46 and will need to be changed to 3-phase power for all new TR's. 3-phase exists only in the MCR currently.   |                          |                        |
| 11   |             | VA indicated that there is presently no redundancy. In the future the Station will have redundant UPS throughout the campus. BAE to plan accordingly as part of this design.   |                          |                        |
| 12   |             | VA requires CAT6A cable installation only.   |                          |                        |
| 13   |             | The VA Station noted that each building is tracked individually, including Buildings 1, 9 and 46, and requests that the OPCC be broken down accordingly by Building. BAE will confirm but anticipates that this will be feasible.  | BAE                      |                        |
| 14   |             | BOD 1-5, VA notes that the site plan Scope of Work is to include Building 40, the link between Building 40 and the Main Hospital, and the link between the Main Hospital and the UND School of Medicine.   | BAE                      |                        |



# APPENDIX E

## MEETING MINUTES

| Item | Action Item | Comments and Notes   | Group/Person Responsible | Target Completion Date |
|------|-------------|--|--------------------------|------------------------|
| 15   |             | BOD 2-9, BAE can eliminate Building Connectivity Requirements schedule all buildings that are not in the Scope of Work.<br><i>*VA Station will review schedule further and provide BAE any additional clarifications and corrections by start of 9.13 through 9.14 site investigation visit.</i>   | VA                       |                        |
| 16   |             | BOD 2-1, VA requests a further breakdown of architectural design goals related to the MCR and TR's.  |                          |                        |
| 17   |             | VA Station confirmed that the "08182021 EHRM Space TR X-Matrix" document is current as of this meeting date. The program analysis schedules provided in the BOD report are to be updated accordingly.  | BAE                      |                        |
| 18   |             | BOD 3-1 All seismic codes/references can be omitted.   | BAE                      |                        |
| 19   |             | BOD 4-1, BAE to confirm weather design conditions are accurate for Fargo.  | BAE                      |                        |
| 20   |             | BOD 4-2, correct Infrastructure Standard for Telecommunications Spaces is now Version 3.1.   | BAE                      |                        |
| 21   |             | BOD 4-4, VA add references Factory Mutual for fire protection design criteria as well as Underwriter's Laboratories.   | BAE                      |                        |
| 22   |             | BOD 4-4, text of "General" paragraph two is cut off.   | BAE                      |                        |
| 23   |             | Bruce Yoch/BrightTree requested the following.<br><i>* Access Control manufacturer and preferred vendor</i><br><i>* Video Surveillance Solution and preferred vendor</i><br><i>* During Site Visit: Place tape to cover any IP addresses in MCR prior to teams arrival so that information is not inadvertently captures when taking pictures.</i><br><i>* Vertical Cable Plan</i> | VA                       |                        |
| 24   |             | BAE requests VA COR to confirm and schedule for September 13 and 14 site investigation:<br><i>*Design team has access to existing MCR and all existing TR's.</i><br><i>*Design team has access to all existing electrical closets.</i><br><i>*Design team has access to all existing mechanical rooms serving the MCR and TR's.</i>  | VA                       |                        |
| 25   |             | Design team will check in on September 13 at 8:00 a.m. at the main entrance to the Main Hospital building. Will meet Ron Tollefson   |                          |                        |

| MEETING MINUTES   |                                 |   |                             |
|---|---------------------------------|---|-----------------------------|
| Project Name: EHRM Infrastructure Upgrades<br>Fargo ND VA HCS |                                 | Project No: 437-21-205<br>Bancroft No: 18-121 |                             |
| Meeting Milestone/Purpose: Scope of Work Changes              |                                 | Date: October 19, 2021<br>2:00 p.m. (CDT)     | Meeting Location: Teams     |
| Attendees:  | Indicates not in attendance: ** | Company                                       | Phone                       |
| Christ Moorer   |                                 | PCAS- CS                                      | xxx-xxx-xxxx                |
| Ronald A. Tollefson   |                                 | VA / COR-Post-Award                           | 701-232-3241<br>#3866       |
| Clifford Halvorsen  |                                 | VA / Alternate COR                            | 701-232-3241<br>#3905       |
| Brady Wiesner   |                                 | VA /  | (701) 232-3241<br>ext. 3335 |
| John Robbins  |                                 | Bancroft AE / Project Manager                 | 224-265-2120                |
| Darlene Flook   |                                 | Bancroft AE / Project Manager                 | 224-875-6881                |
|   |                                 |   | E-mail                      |
|   |                                 |   | christ.moorer@va.gov        |
|   |                                 |   | ronald.tollefson@va.gov     |
|   |                                 |   | clifford.halvorsen@va.gov   |
|   |                                 |   | brady.wiesner@va.gov        |
|   |                                 |   | jrobbins@bancroft-ae.com    |
|   |                                 |   | dflook@bancroft-ae.com      |

| Item | Action Item | Comments and Notes  | Group/Person Responsible | Target Completion Date |
|------|-------------|---|--------------------------|------------------------|
| 1    |             | James Cullum has granted permission to use Emcor Defender air-conditioned Server-Racks (. <a href="https://www.emcorenclosures.com/product/defender/">https://www.emcorenclosures.com/product/defender/</a> ) for non-Clinical spaces, instead of expanding TR rooms. |                          |                        |
| 2    |             | Buildings 10 (Boiler Plant), 11 (Maintenance Garage), 13 (Laundry) 56 (Chiller Plant) and 3 (Admin) will use the cabinets.  |                          |                        |
| 3    |             | A variation will not be needed. A Summary Variation Report will be required at the end of the Design Phase.   | BAE                      |                        |
| 4    |             | Building 51 will keep TR addition, but will be reduced to 100 SqFt  | BAE                      |                        |
| 5    |             | Building 30 is required to receive Fiber  | BAE                      |                        |
| 6    |             | Correct BOD/Plans to reflect 100 SqFt for non-clinical TR rooms and 170 SqFt for Clinical/Mission Critical rooms.   | BAE                      |                        |
| 7    |             | Next OPCC to show "Covid Factor" Construction cost increase.  | BAE                      |                        |
| 8    |             | BAE to look at an alternative location for the Penthouse TR and also consider access to roof still needed.  | BAE                      |                        |
| 9    |             | VA to give detailed report on all non-IT Clinical/Security components that will be moved from old TR/OIT rooms to new rooms.  | VA                       |                        |
| 10   |             | Old TR's BAE will specify wall finishes, floor transition and light fixture. BAE recommends no drop in ceiling and leave open.  | BAE                      |                        |
| 11   |             | BAE will engage with Forensic Roof Company to diagnose leak on slanted metal roof.  | BAE                      |                        |
| 12   |             | Modifications will be required for the above items with justification on additional design fees and consultants, but Schedule cannot change.  | BAE                      |                        |



# APPENDIX E

## MEETING MINUTES

### Weekly Progress Updates

#### Meeting Agenda / Minutes Attendee List

|                       |            |
|-----------------------|------------|
| Bancroft Project No.: | 18-121     |
| Client:               | VA- Fargo  |
| Project Name:         | EHRM       |
| Client Project No.:   | 437-21-205 |



| Attendee Name         | Organization | Title     | Email address  | Phone No.          | MEETINGS       |   |   |
|-----------------------|--------------|-----------|--|--------------------|----------------|---|---|
|                       |              |           |  |                    | Meeting Number |   |   |
|                       |              |           |  |                    | 1              | 2 | 3 |
| (RT) Rpnald Tollefson | Fargo VAMC   | COR       | <a href="mailto:ronald.tollefson@va.gov">ronald.tollefson@va.gov</a>         | 701-232-3241 #3866 |                |   |   |
| (CH) Cliff Halvorson  | Fargo VAMC   | Alt. COR  | <a href="mailto:clifford.halvorson@va.gov">clifford.halvorson@va.gov</a>     | 701-232-3241 #3905 |                |   |   |
| (DF) Darlene Flook    | BAE          | PM        | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>           | 224-875-6881       | X              |   |   |
| (DA) Dana Auman       | BAE          | PA        | <a href="mailto:dauman@bancroft-ae.com">dauman@bancroft-ae.com</a>           | 224-265-2115       | X              |   |   |
| (JM) Jimmy McAllister | BAE          | Architect | <a href="mailto:jmcallister@bancroft-ae.com">jmcallister@bancroft-ae.com</a> | 224-577-1600       | X              |   |   |

#### Meeting Agenda / Minutes

|                       |            |
|-----------------------|------------|
| Bancroft Project No.: | 18-121     |
| Client:               | VA- Fargo  |
| Project Name:         | EHRM       |
| Client Project No.:   | 437-21-205 |



|  |   |
|--|---|
| <b>Item Identification:</b><br>A = Architectural<br>M = Mechanical/HVAC<br>E = Electrical<br>P = Plumbing<br>O = Other Project Items | <b>NOTE:</b> Closed / completed items will be grayed out and carried for ONE meeting cycle, then removed from current list. |
|--|---|

| Item  | Topic                   | Description / Discussion  | By whom | By when |
|-------|-------------------------|---|---------|---------|
| O-1-1 | 50% Review              | Virtual or On-Site Page Turn. This will determine date of next investigation site visit. (Nov 4-5 or Nov 18-19) | VA      |         |
| A-1-2 | TR Room Additions       | Building 51 Proposed location   | VA      |         |
| O-2-3 | TR/OIT Room Review      | On track for receiving information  | VA      |         |
| E-1-4 | Grounding               | Will remove from the Modification - BrightTree to arrange layout.   | BAE     |         |
| A-2-5 | Bldg 10, 11, 13, 3 & 56 | Clarification on leaving New Server Rack in same position or are we enclosing.                                  | VA      |         |
| A-3-6 | Penthouse TR Rack       | Can we get pictures of of areas, BAE will direct exact areas.   | VA      |         |
| O-3-7 | OIT Questions           | Door Size for TR Rooms, additional questions.   | VA      |         |

#### Meeting Agenda / Minutes Attendee List

|                       |            |
|-----------------------|------------|
| Bancroft Project No.: | 18-121     |
| Client:               | VA- Fargo  |
| Project Name:         | EHRM       |
| Client Project No.:   | 437-21-205 |



| Attendee Name         | Organization | Title     | Email address  | Phone No.          | MEETINGS       |   |   |
|-----------------------|--------------|-----------|--|--------------------|----------------|---|---|
|                       |              |           |  |                    | Meeting Number |   |   |
|                       |              |           |  |                    | 1              | 2 | 3 |
| (RT) Rpnald Tollefson | Fargo VAMC   | COR       | <a href="mailto:ronald.tollefson@va.gov">ronald.tollefson@va.gov</a>         | 701-232-3241 #3866 |                | X |   |
| (CH) Cliff Halvorson  | Fargo VAMC   | Alt. COR  | <a href="mailto:clifford.halvorson@va.gov">clifford.halvorson@va.gov</a>     | 701-232-3241 #3905 |                | X |   |
| (CM) Christ Moorer    | Fargo VAMC   | CS        | <a href="mailto:Christ.Moorer@va.gov">Christ.Moorer@va.gov</a>               |                    |                |   |   |
| (DF) Darlene Flook    | BAE          | PM        | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>           | 224-875-6881       |                | X |   |
| (DA) Dana Auman       | BAE          | PA        | <a href="mailto:dauman@bancroft-ae.com">dauman@bancroft-ae.com</a>           | 224-265-2115       |                | X |   |
| (JM) Jimmy McAllister | BAE          | Architect | <a href="mailto:jmcallister@bancroft-ae.com">jmcallister@bancroft-ae.com</a> | 224-577-1600       |                |   |   |

### Weekly Progress Updates

#### Meeting Agenda / Minutes

|                       |            |
|-----------------------|------------|
| Bancroft Project No.: | 18-121     |
| Client:               | VA- Fargo  |
| Project Name:         | EHRM       |
| Client Project No.:   | 437-21-205 |




|  |   |
|--|---|
| <b>Item Identification:</b><br>A = Architectural<br>M = Mechanical/HVAC<br>E = Electrical<br>P = Plumbing<br>O = Other Project Items | <b>NOTE:</b> Closed / completed items will be grayed out and carried for ONE meeting cycle, then removed from current list. |
|--|---|

| Item  | Topic                   | Description / Discussion  | By whom | By when  |
|-------|-------------------------|---|---------|----------|
| O-1-1 | 50% Review              | Virtual (11.12) or On-Site Page Turn. (Note: any site visits should be a deduct) This will determine date of next investigation site visit. (Nov 4-5 or Nov 18-19)<br>Visitors can align with 75% Page Turn.  | VA      | 10.21.21 |
| A-1-2 | TR Room Additions       | Building 51 Proposed location. VA will take measurements and get back with best location.   | VA      | 10.21.21 |
| O-2-3 | TR/OIT Room Review      | On track for receiving information. 10.27.21  | VA      | 10.21.21 |
| E-1-4 | Grounding               | Will remove from the Modification - BrightTree to arrange layout. VA will.  | BAE     | 10.21.21 |
| A-2-5 | Bldg 10, 11, 13, 3 & 56 | Clarification on leaving New Server Rack in same position or are we enclosing. Server RACKS (removed) will stay in same location except for Bldg 11 (move front second). All cabinets will be locked to floor/wall. BAE will provide a diagram of proposed E. | VA      | 10.21.21 |
| A-3-6 | Penthouse TR Rack       | Can we get pictures of of areas, BAE will direct exact areas. For 50% will show TR on roof as planned, next 51 visit; will look at new locations.   | VA      | 10.21.21 |
| O-3-7 | OIT Questions           | Door Size for TR Rooms, additional questions.   | VA      | 10.21.21 |
| O-4-8 | UPS- OPCC               | OPCC will price the initial UPS system for 50%, to be aligned with the plans.   |         |          |




# APPENDIX E

## MEETING MINUTES

| MEETING MINUTES   |  |   |  |  |  |
|---|--|---|---|--|--|
| Project Name: EHRM Infrastructure Upgrades<br>Fargo ND VA HCS               |  | Project No: 437-21-205<br>Bancroft No: 18-121 |   |  |  |
| Meeting Milestone/Purpose: Scope of Work Changes, UPS and Generator Changes |  | Date: November 05, 2021<br>9:00 a.m. (CDT)    | Meeting Location: Teams   |  |  |
| Attendees: <small>Indicates not in attendance: **</small>                   |  | Company                                       | Phone   | E-mail   |  |
| Ronald A. Tollefson   |  | VA / COR-Post-Award                           | 701-232-3241<br>#3866   | <a href="mailto:ronald.tollefson@va.gov">ronald.tollefson@va.gov</a>     |  |
| Clifford Halvorson  |  | VA / <span>Alternate COR</span>               | 701-232-3241<br>#3905   | <a href="mailto:clifford.halvorson@va.gov">clifford.halvorson@va.gov</a> |  |
| Darlene Flook   |  | Bancroft AE / Project Manager                 | 224-875-6881  | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>       |  |
| Walter  |  | Bancroft AE / Sr Electrical Engineer          | 630-939-0049  | <a href="mailto:wgroszko@bancroft-ae.com">wgroszko@bancroft-ae.com</a>   |  |
| Dana Auman  |  | Bancroft AE / Project Architect               | 847-877-1831  | <a href="mailto:Dauman@bancroft-ae.com">Dauman@bancroft-ae.com</a>       |  |

| Item | Action Item | Comments and Notes   | Group/Person Responsible | Target Completion Date |
|------|-------------|--|--------------------------|------------------------|
| 1    |             | Will proceed with Monolithic Design, not an EHRM standard.   | BAE                      | 11.16.21               |
| 2    |             | (RT) Agreed to 90KVA "Small Data Center" design that includes the EHRM JSA and EDS loads                                       | VA                       | 11.16.21               |
| 3    |             | EATON Basis of Design may be two units but still constitute "N" design,  | VA                       | 11.16.21               |
| 4    |             | Agreed, Modular UPS design will be expandable, but initially sized for existing load   | VA                       | 11.16.21               |
| 5    |             | (WG) Will design UPS Feeders up through building to power TR rooms,  | BAE                      | 11.16.21               |
| 6    |             | (RT) Clarified, each TR rack will be feed by only one UPS receptacle that feeds one Vertical PDU, (meaning no Rack redundancy) | VA                       | 11.16.21               |
| 7    |             | BLDG 46 generator will be sized starting at 1 MVA, and made one size larger to accommodate future loads, (1.25 or 1.5)         | VA                       | 11.16.21               |
| 8    |             | Final generator will be sized based on %Harmonics from two 500KVA UPS Systems operating at 50% load each                       | VA                       | 11.16.21               |
| 9    |             | VA agreed. BLDG 46 Em Generator will be upgraded based on related VA projects around BLDG 46                                   | VA                       | 11.16.21               |
| 10   |             | (RT) stated New Data Center location is not known at this time.  | VA                       | 11.16.21               |
| 11   |             | BAE design will focus on NEW UPS in existing location, and NEW Em generator feeding existing Data Center location              | BAE                      | 11.16.21               |
| 12   |             | Existing location to be looked at on next Site Investigation.  | BAE                      | 11.16/17.21            |
| 13   |             | Changes will need to be discussed with Consultants and Team to incorporate into design   | BAE                      | 11.08.21               |
| 14   | Priority    | Modification needed and EHRM Variance  | VA                       | 11.11.21               |


| MEETING MINUTES  |                                      |  |  |
|--|--------------------------------------|---|--|
| <b>Project Name:</b> EHRM Infrastructure Upgrades<br>Fargo ND VA HCS       |                                      | <b>Project No:</b> 437-21-205<br><b>Bancroft No:</b> 18-121                         |  |
| <b>Meeting Milestone/Purpose:</b> PAGE TURN<br>General notes and questions |                                      | <b>Date:</b> November 16, 2021<br>1:00 p.m. (CDT)                                   |  |
| <b>Meeting Location:</b> Fargo On-site and TEAMS                           |                                      |   |  |
| <b>Attendees:</b> Indicates in attendance via TEAMS: **                    | <b>Company</b>                       | <b>Phone</b>  | <b>E-mail</b>  |
| Ronald A. Tollefson  | VA / COR-Post-Award                  | 701-232-3241<br>#3866   | <a href="mailto:ronald.tollefson@va.gov">ronald.tollefson@va.gov</a>                     |
| Clifford Halvorson   | VA / Alternate COR                   | 701-232-3241<br>#3905   | <a href="mailto:clifford.halvorson@va.gov">clifford.halvorson@va.gov</a>                 |
| Darlene Flook  | Bancroft AE / Project Manager        | 224-875-6881  | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>                       |
| Walter Groszko   | Bancroft AE / Sr Electrical Engineer | 630-939-0049  | <a href="mailto:wgroszko@bancroft-ae.com">wgroszko@bancroft-ae.com</a>                   |
| Dana Auman   | Bancroft AE / Project Architect      | 847-877-1831  | <a href="mailto:Dauman@bancroft-ae.com">Dauman@bancroft-ae.com</a>                       |
| Kyle Haas  | Hohbach-Lewin, Inc.                  | 415-968-1731  | <a href="mailto:khaas@hohbach-lewin.com">khaas@hohbach-lewin.com</a>                     |
| Bruce Yoch   | BrightTree STUDIOS                   | 412.225.6749  | <a href="mailto:byoch@brighttreestudios.com">byoch@brighttreestudios.com</a>             |
| Aaron Mangione   | Calibre Engineering                  | 720-704-8488  | <a href="mailto:amangione@calibre-engineering.com">amangione@calibre-engineering.com</a> |
| Jimmy McAllister **  | Bancroft AE / Project Manager        |   | <a href="mailto:jmcallister@bancroft-ae.com">jmcallister@bancroft-ae.com</a>             |
| Hilary P. Clifton **   | Terracon                             | 701-282.9633  | <a href="mailto:Hilary.Clifton@terracon.com">Hilary.Clifton@terracon.com</a>             |
| Travis Benjamin **   | Calibre Engineering                  | 303-   952-1875   | <a href="mailto:tbenjamin@calibre-engineering.com">tbenjamin@calibre-engineering.com</a> |
| Anthony Wilson **  | VHACLE/CO                            |   | <a href="mailto:Anthony.Wilson3@va.gov">Anthony.Wilson3@va.gov</a>                       |





# APPENDIX E

## MEETING MINUTES


| MEETING MINUTES   |             |   |  |                        |
|---|-------------|---|---|------------------------|
| Project Name: EHRM Infrastructure Upgrades<br>Fargo ND VA HCS       |             | Project No: 437-21-205<br>Bancroft No: 18-121   |   |                        |
| Meeting Milestone/Purpose: PAGE TURN<br>General notes and questions |             | Date: November 16, 2021<br>1:00 p.m. (CDT)  | Meeting Location: Fargo On-site and TEAMS   |                        |
| Item  | Action Item | Comments and Notes  | Group/Person Responsible  | Target Completion Date |
| 1   |             | <b>BOD: Blast</b><br>Blast Narrative to reference Appendix. Coordinate w/BAE<br>Remove Sandroom<br>Update TR's that are now Emcore Cabinets<br>Remove screening statement<br>Add changes for 75%  |   |                        |
| 2   |             | <b>BOD: OPCC</b><br>Fix appendix<br>Need 1/9/46 split in costs. Use each TR as reference of which bldg. work will be listed under   |   |                        |
| 3   |             | <b>BOD: General</b><br>QAQC revisions<br>Bldg 3 ,remove cabinet add TR<br>Replace Matrix, has been updated by COR.<br>Fix circle colors 2-6 etc. as it pertains to TR<br>Bldg. 12, do not expand TR, construct full fire-rated enclosure.<br>IT/Security- Change J-Hook comment<br>Terracon update errors on plans<br>Meeting notes, highlight dates<br>Smoke devices are to be designed for TR's and noted as a deduct-alternate.                |   |                        |
| 4   |             | <b>Drawings - HVAC:</b><br>Temperature should be at 70 degrees Min<br>Add humidity alarm  |   |                        |
| 5   |             | <b>Drawings - IT/Security:</b><br>Maximize racks<br>BC-60 is where copper line will terminate<br>Bldg. 30 remove rack<br>Leave 2Ft. service loop at each pull<br>Need plan for "B" route<br>BrightTree looking into Card Access for racks.<br>New Concrete Vaults<br>(4) conduits to be used in Fiber run. A, B Spare, Spare<br>Need loop for Fiber A & B (future)<br>TR -Plywood to be specified on all (4) walls<br>Do not use existing sleeves |   |                        |

|    |  |   |  |  |
|----|--|---|--|--|
| 6  |  | <b>Drawings - Fire Protection:</b><br>Need locations of recessed Fire Extinguisher Cabinets<br>If sprinkler heads are not moving in TR's then, heads to be replaced with new<br>Guard to be specified on all heads<br>All pipes to be Red<br>Deduct-alternate- Smoke detectors in all TR's  |  |  |
| 7  |  | <b>Drawings - Electrical:</b><br>1/9/46 will receive Monolithic UPS System confirmed<br>Out-Buildings will receive UPS in racks<br>Overhead light fixture to change to correct symbol<br>Move room numbers so they do not interfere with layout<br>Fix Building Key<br>Station confirmed direction to proceed w/Monolithic UPS design.<br>Station confirmed direction to tie UPS to Building 9 Generator.<br>Station confirmed direction to design for a new Generator to now handle UPS design.<br>This may require enlarging building footprint housing Generator. Will also require a MOD.<br>Station noted that Generator will need to be located out of the existing floodplain.<br>Station requesting a (2) story addition above existing Bldg.9 Generator Room. The new Generator will be located on the 2 <sup>nd</sup> Level (above floodplain) The ATS components will be located on first floor.<br>The existing Generator Room (0 Level) will be abandoned, and VA will determine future use. |  |  |
| 8  |  | <b>Drawings - Architectural/General:</b><br>Need to include note of a scalable # for horizontal/vertical openings to be fire-stopped<br>Bldg . 30 no upgrades<br>Bldg. 56 & 30 are not sprinklered<br>Fix Drawing Index for all drawings; use "0" for Basement not "B",<br>Add Sheet # of #<br>Add GC note Concrete Patching for Vertical openings, so GC has a # (i.e.; 200 SqFt)<br>Add GC note; recommendation of (2) Superintendents on site, one to always be present to avoid work stop.<br>G101 -Include ICRA/PCRA/ILSM on sheet<br>Note to GC; responsible for full underground survey of campus prior to site demolition. Use ground penetrating Radar as GC is responsible for any line/pipe that is nicked/damaged.<br>Language will be included in Specification Section 02-21-13 Site Surveys and Drawings.<br>Project considered Class IV, will need anterooms for construction.<br>TR- Plywood to be specified on all (4) walls  |  |  |
|    |  | Station requests the 2-story Generator addition be constructed to accommodate a future 3 <sup>rd</sup> floor.   |  |  |
| 9  |  | <b>Drawings - Civil/Structural:</b><br>DM01- Adjust line weights<br>CU01 - Add note to Manhole Spec, CentryLink or Equal to   |  |  |
| 10 |  | <b>Drawings - ALL:</b><br>Condense plans into a few pages as possible.<br>All Consultants- remove notes that do not pertain to project.<br>Shift plans to make sure nothing is cut off<br>Show rated walls  |  |  |
| 11 |  | <b>Building 12</b><br>Ron awaiting permission to make room smaller than the standard.   |  |  |
| 12 |  | <b>Building 51</b><br>Corridor needs to be heated<br>New design for TR was approved   |  |  |



# APPENDIX E

## MEETING MINUTES

| MEETING MINUTES   |   |  |  |
|---|---|---|--|
| Project Name: EHRM Infrastructure Upgrades<br>Fargo ND VA HCS       | Project No: 437-21-205<br>Bancroft No: 18-121   |   |  |
| Meeting Milestone/Purpose: PAGE TURN<br>General notes and questions | Date: November 16, 2021<br>1:00 p.m. (CDT)  | Meeting Location: Fargo On-site and TEAMS   |  |
| 13  | TR's-<br>Ron to confirm door finishes<br>Phillips equipment to remain in abandoned TR's<br>Walls without receptacles, add one.<br>Lighting Sensors in TR's<br>If rooms are too tight, do not add extra rack.<br>2' min clearance if necessary<br>BrightTree: Structural Engineers will need plans highlighting rooms with additional racks.<br>TR Floor finish to be sealed concrete only. No anti-static coating (per Station directive) |   |  |
| 14  | Existing Finishes-<br>Ron to send list  |   |  |
| 15  | Existing OIT/Non- IT equipment-<br>Ron to send completed list   |   |  |

### Meeting Agenda / Minutes Attendee List

|                       |               |
|-----------------------|---------------|
| Bancroft Project No.: | 18-121        |
| Client:               | VA- Fargo     |
| Project Name:         | EHRM          |
| Client Project No.:   | 437-21-205    |
| Contract No.:         | 36C26319D0044 |



| Attendee Name         | Organization | Title                                | Email address  | Phone No.             | MEETINGS       |          |          |
|-----------------------|--------------|--------------------------------------|--|-----------------------|----------------|----------|----------|
|                       |              |                                      |  |                       | Meeting Number |          |          |
|                       |              |                                      |  |                       | 1              | 2        | 3        |
|                       |              |                                      |  |                       | 10/21/21       | 10/28/21 | 12/02/21 |
| (RT) Ronald Tollefson | Fargo VAMC   | COR, Engineering Department          | <a href="mailto:ronald.tollefson@va.gov">ronald.tollefson@va.gov</a>         | 701-232-3241<br>#3866 | X              | X        | X        |
| (CH) Cliff Halvorson  | Fargo VAMC   | Alt. COR, Engineering Department     | <a href="mailto:clifford.halvorson@va.gov">clifford.halvorson@va.gov</a>     | 701-232-3241<br>#3905 | X              |          | X        |
| (CM) Christ Moorer    | VA,VHA       | CS                                   | <a href="mailto:Christ.Moorer@va.gov">Christ.Moorer@va.gov</a>               |                       | X              |          | X        |
| (AW) Anthony Wilson   | VA,VHA       | CO                                   | <a href="mailto:Anthony.Wilson3@va.gov">Anthony.Wilson3@va.gov</a>           |                       |                |          | X        |
| (BW) Brady Wiesner    | Fargo VAMC   | Assistant Chief, Engineering Service | <a href="mailto:Brady.Wiesner@va.gov">Brady.Wiesner@va.gov</a>               |                       |                |          | X        |
| (DF) Darlene Flook    | BAE          | PM                                   | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>           | 224-875-6881          | X              | X        | X        |
| (DA) Dana Auman       | BAE          | PA                                   | <a href="mailto:dauman@bancroft-ae.com">dauman@bancroft-ae.com</a>           | 224-265-2115          | X              | X        |          |
| (JM) Jimmy McAllister | BAE          | Architect                            | <a href="mailto:jmcallister@bancroft-ae.com">jmcallister@bancroft-ae.com</a> | 224-577-1600          | X              | X        | X        |

### Meeting Agenda / Minutes

|                       |            |
|-----------------------|------------|
| Bancroft Project No.: | 18-121     |
| Client:               | VA- Fargo  |
| Project Name:         | EHRM       |
| Client Project No.:   | 437-21-205 |



|   |  |
|---|--|
| Item Identification:<br>A = Architectural<br>M = Mechanical/HVAC<br>E = Electrical<br>P = Plumbing<br>O = Other Project Items | NOTE: Closed / completed items will be grayed out and carried for ONE meeting cycle, then removed from current list. |
|---|--|

| Item   | Topic               | Description / Discussion  | By whom | By when |
|--------|---------------------|---|---------|---------|
| O-5-9  | Generator Direction | How to proceed.<br>(RT) reported that the Generator addition will be part of the MCR project, at a later date.<br>(RT) Awaiting lead numbers from BAE - ME & EE, to include cooling loads for 1/9/46 generators.  | VA      |         |
| O-6-10 | Penthouse TR        | Consensus on Roof Top TR or (2) individual TR Rooms<br>(RT) Gave direction, to proceed with the Roof Top TR. It was requested that the load be reduced on materials used, so reinforcement of below columns could be avoided. Will discuss with Calibre. If weight cannot be reduced can tubular steel be used instead for reinforcing columns. | VA      |         |
| O-7-11 | Various TR 's       | (RT) Will look into if variances from PD5M are needed on Level 4 TR and Level 1 TR  |         |         |
| O-8-12 | EMCOR Cabinets      | (RT) Stated . DCIE reported from Iowa City, that the cabinets are not approved. Floor mounted (Cemetery Facility Guidelines) cabinets will be used. With the exception of the Boiler House cabinet. That will be Emerson.   |         |         |
| M-1-13 | TR In-line cooling  | (RT) reiterated, those are not desired by IT Team and standard cooling is to be used.   |         |         |





# APPENDIX E

## MEETING MINUTES

Weekly Progress Updates

### Meeting Agenda / Minutes Attendee List

|                       |               |
|-----------------------|---------------|
| Bancroft Project No.: | 18-121        |
| Client:               | VA- Fargo     |
| Project Name:         | EHRM          |
| Client Project No.:   | 437-21-205    |
| Contract No.:         | 36C26319D0044 |



### MEETINGS Meeting Number

| Attendee Name         | Organization | Title                                | Email address  | Phone No.          | 12/03/21 | 12/09/21 | 12/16/21 |
|-----------------------|--------------|--------------------------------------|--|--------------------|----------|----------|----------|
| (RT) Ronald Tollefson | Fargo VAMC   | COR. Engineering Department          | <a href="mailto:ronald.tollefson@va.gov">ronald.tollefson@va.gov</a>         | 701-232-3241 #3866 | X        | X        |          |
| (CH) Cliff Halvorson  | Fargo VAMC   | Alt. COR. Engineering Department     | <a href="mailto:clifford.halvorson@va.gov">clifford.halvorson@va.gov</a>     | 701-232-3241 #3905 | X        |          |          |
| (CM) Christ Moorer    | VA, VHA      | CS                                   | <a href="mailto:Christ.Moorer@va.gov">Christ.Moorer@va.gov</a>               |                    | X        | X        |          |
| (AW) Anthony Wilson   | VA, VHA      | CO                                   | <a href="mailto:Anthony.Wilson3@va.gov">Anthony.Wilson3@va.gov</a>           |                    | X        | X        |          |
| (BW) Brady Wiesner    | Fargo VAMC   | Assistant Chief, Engineering Service | <a href="mailto:brady.wiesner@va.gov">brady.wiesner@va.gov</a>               |                    | X        |          |          |
| (DF) Darlene Flook    | BAE          | PM                                   | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>           | 224-875-6881       | X        | X        |          |
| (DA) Dana Auman       | BAE          | PA                                   | <a href="mailto:dauman@bancroft-ae.com">dauman@bancroft-ae.com</a>           | 224-265-2115       |          | X        |          |
| (JM) Jimmy McAllister | BAE          | Architect                            | <a href="mailto:jmcallister@bancroft-ae.com">jmcallister@bancroft-ae.com</a> | 224-577-1600       | X        |          |          |

### Meeting Agenda / Minutes

|                       |            |
|-----------------------|------------|
| Bancroft Project No.: | 18-121     |
| Client:               | VA- Fargo  |
| Project Name:         | EHRM       |
| Client Project No.:   | 437-21-205 |



#### Item Identification:

A = Architectural  
M = Mechanical/HVAC  
E = Electrical  
P = Plumbing  
O = Other Project Items

NOTE: Closed / completed items will be grayed out and carried for ONE meeting cycle, then removed from current list.

| Item   | Topic               | Description / Discussion  | By whom | By when                             |
|--------|---------------------|---|---------|-------------------------------------|
| O-5-9  | Generator Direction | How to proceed.<br>(RT) reported that the Generator addition will be part of the MCR project, at a later date.<br>(RT) Awaiting load numbers from BAE - ME & EE, to include cooling loads for 1/9/46 generators.  | VA      | Meeting to discuss W/Walter 12.9.21 |
| O-6-10 | Penthouse TR        | Consensus on Roof Top TR or (2) individual TR Rooms<br>(RT) Gave direction, to proceed with the Roof Top TR. It was requested that the load be reduced on materials used, so reinforcement t of below columns could be avoided. Will discuss with Calibre. If weight cannot be reduced can tubular steel be used instead for reinforcing columns. | VA      |                                     |
| O-7-11 | Various TR 's       | (RT) Will look into if variances from PD5M are needed on Level 4 TR and Level 1 TR.<br>(RT) has said we will address these variance issues at the end of the project.   |         |                                     |
| O-8-12 | EMCOR Cabinets      | (RT) Stated , DCIE reported from Iowa City, that the cabinets are not approved. Floor mounted (Cemetery Facility Guidelines) cabinets will be used. With the exception of the Boiler House cabinet. That will be Emcor. (RT) stated we shall look at if these cabinets can be wall mouted. Does Emcor cabinet have a filter?                      |         |                                     |
| M-1-13 | TR In-line cooling  | (RT) reiterated, those are not desired by IT Team and standard cooling is to be used.   |         |                                     |

|         |          |   |     |  |
|---------|----------|---|-----|--|
| O-9-14  | Schedule | BAE has requested an adjustment to the schedule, to accommodate the changes that were just approved. RFI 012<br>(RT) Agrees with scheudle change and will submitt Schedule and Paperwork to (AW) & (CM) for scheudle approval.  | BAE |  |
| O-10-15 | RFI's    | Still waiting for responses to the following RFI's. All if which are critical for the Consultants and Mechanical to proceed.<br>RFI 016 - Building 51 Finishes<br>RFI 013 - Building 46 Roof<br>RFI 015 - Condesor Unit Locations<br>RFI 014 - Racks vs. cooling<br>RFI 013 - There are no other drawings for this roof area.<br>RFI 014- What Dave stated in RFI, is the direction that will be taken. with the exception 2.5KW per rack. The only rooms with 5-6 racks should be Room# 1A54 & 2A 22/24 (serves OR)<br>RFI 015- Calibre does not have current locaitons of units, that (RT) and Dave discussed. Dave to give new outline to Calibre.<br>RFI 016- Ron getting finishes together | BAE |  |



# APPENDIX E

## MEETING MINUTES

| MEETING MINUTES  |   | Meeting Location: Teams |  |
|--|---|-------------------------|--|
| <b>Project Name:</b> EHRM Infrastructure Upgrades<br>HCS<br>Fargo ND VA              | <b>Project No:</b> 437-21-205<br><b>Bancroft No:</b> 18-121 |                         |  |
| <b>Meeting Milestone/Purpose:</b><br>EHRM: Racks vs. Cooling Requirements<br>RFI 014 | <b>Date:</b> December 09, 2021<br>1:30 p.m. (CDT)           |                         |  |
| <b>Attendees:</b> Indicates not in attendance: **                                    | <b>Company</b>  | <b>Phone</b>            | <b>E-mail</b>  |
| Bruce Yoch   | BrightTree Studios  | 412.225.6749            | <a href="mailto:byoch@brighttreestudios.com">byoch@brighttreestudios.com</a> |
| David Gamble   | Bancroft AE / Sr Mechanical Engineer                        | 224.875-6896            | <a href="mailto:dgamble@bancroft-ae.com">dgamble@bancroft-ae.com</a>         |
| Darlene Flook  | Bancroft AE / Project Manager                               | 224-875-6881            | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>           |
| Walter Groszko   | Bancroft AE / Sr Electrical Engineer                        | 630-939-0049            | <a href="mailto:wgroszko@bancroft-ae.com">wgroszko@bancroft-ae.com</a>       |
| Dana Auman   | Bancroft AE / Project Architect                             | 847-877-1831            | <a href="mailto:Dauman@bancroft-ae.com">Dauman@bancroft-ae.com</a>           |

| Room #           | # of Racks | Notes   |
|------------------|------------|---|
|                  |            | Below is a list of Room numbers with their quantity of racks @ 2.3KW per/rack |
| BD-02            | (2)        |   |
| BB-92            | (3)        |   |
| BD-84            | (2)        |   |
| BA-30            | (3)        |   |
| BC-02            | (3)        |   |
| MCR/Data Center  | (1)        | No power required   |
| 1B-121           | (1)        |   |
| 1A-54            | (5)        |   |
| 1C-99            | (3)        |   |
| 1D-64A           | (3)        |   |
| 1D-158           | (2)        | 12.16.21 Bruce can only fit (1)   |
| 2A-24            | (5)        | Serving OR's  |
| 2C-33            | (3)        |   |
| 2C-90A           | (4)        |   |
| 2D-18            | (4)        |   |
| 3B-23            | (4)        |   |
| 3D-10            | (4)        |   |
| 4B-23            | (3)        | Roof Repair   |
| 4E-15A           | (3)        |   |
| 502 Penthouse TR | (4)        |   |

|                           |           |   |
|---------------------------|-----------|---|
| Building 3                | (1)       |   |
| Building 10 Mezzanine     | Emcor (1) |   |
| Building 11               | TE        | Floor or Wall                           |
| Building 12               | (1)       | Wall unit or move wall to make unit fit |
| Building 13               | TE        | Floor or Wall                           |
| Building 30               | TE        | Floor or Wall                           |
| Building 40 LL 102B       | (4)       |   |
| Building 40 UL 202A       | (3)       |   |
| Building 51 Addition 1030 | (2)       |   |
| Building 52 111           | (2)       |   |
| Building 52 211           | (2)       |   |
| Chiller Plant             | TE        | Floor or Wall                           |





# APPENDIX E

## MEETING MINUTES

### Meeting Agenda / Minutes Attendee List

|                       |               |
|-----------------------|---------------|
| Bancroft Project No.: | 18-121        |
| Client:               | VA- Fargo     |
| Project Name:         | EHRM          |
| Client Project No.:   | 437-21-205    |
| Contract No.:         | 36C26319D0044 |



| Attendee Name         | Organization | Title                                | Email address  | Phone No.          | MEETINGS       |   |   |
|-----------------------|--------------|--------------------------------------|--|--------------------|----------------|---|---|
|                       |              |                                      |  |                    | Meeting Number |   |   |
|                       |              |                                      |  |                    | 3              | 4 | 5 |
| (RT) Ronald Tollefson | Fargo VAMC   | COR, Engineering Department          | <a href="mailto:ronald.tollefson@va.gov">ronald.tollefson@va.gov</a>         | 701-232-3241 #3866 | X              | X | X |
| (CH) Cliff Halvorson  | Fargo VAMC   | Alt. COR, Engineering Department     | <a href="mailto:clifford.halvorson@va.gov">clifford.halvorson@va.gov</a>     | 701-232-3241 #3905 | X              |   |   |
| (CM) Christ Moorner   | VA,VHA       | CS                                   | <a href="mailto:Christ.Moorner@va.gov">Christ.Moorner@va.gov</a>             |                    | X              | X |   |
| (AW) Anthony Wilson   | VA,VHA       | CO                                   | <a href="mailto:Anthony.Wilson3@va.gov">Anthony.Wilson3@va.gov</a>           |                    | X              | X |   |
| (BW) Brady Wiesner    | Fargo VAMC   | Assistant Chief, Engineering Service | <a href="mailto:Brady.Wiesner@va.gov">Brady.Wiesner@va.gov</a>               |                    | X              |   | X |
| (DF) Darlene Flook    | BAE          | PM                                   | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>           | 224-875-6881       | X              | X | X |
| (DA) Dana Auman       | BAE          | PA                                   | <a href="mailto:dauman@bancroft-ae.com">dauman@bancroft-ae.com</a>           | 224-265-2115       |                | X |   |
| (JM) Jimmy McAllister | BAE          | Architect                            | <a href="mailto:jmcallister@bancroft-ae.com">jmcallister@bancroft-ae.com</a> | 224-577-1600       | X              |   |   |
| (CR) Connor Rollins   | BAE          | Architect                            | <a href="mailto:crollins@bancroft-ae.com">crollins@bancroft-ae.com</a>       |                    |                |   | X |
| (PP) Petko Petrovich  | BAE          | Project Architect                    | <a href="mailto:ppetrovich@bancroft-ae.com">ppetrovich@bancroft-ae.com</a>   |                    |                |   | X |

### Meeting Agenda / Minutes

|                       |            |
|-----------------------|------------|
| Bancroft Project No.: | 18-121     |
| Client:               | VA- Fargo  |
| Project Name:         | EHRM       |
| Client Project No.:   | 437-21-205 |




|                         |  |
|-------------------------|--|
| Item Identification:    | NOTE: Closed / completed items will be grayed out and carried for ONE meeting cycle, then removed from current list. |
| A = Architectural       |  |
| M = Mechanical/HVAC     |  |
| E = Electrical          |  |
| P = Plumbing            |  |
| Q = Other Project Items |  |

| Item    | Topic              | Description / Discussion  | By whom | By when |
|---------|--------------------|---|---------|---------|
| Q-9-14  | Schedule           | BAE has requested an adjustment to the schedule, to accommodate the changes that were just approved. RFI 012 (RT) Agrees with schedule change and will submit Schedule and Paperwork to (AW) & (CM) for schedule approval.  | BAE     |         |
| Q-10-15 | RFI's              | Still waiting for responses to the following RFI's. All of which are critical for the Consultants and Mechanical to proceed.<br>RFI 016 - Building 51 Finishes<br>RFI 013 - Building 46 Roof<br>RFI 015 - Condenser Unit Locations<br>RFI 014 - Racks vs. cooling<br>RFI 013 - There are no other drawings for this roof area.<br>RFI 014- What Dave stated in RFI, is the direction that will be taken, with the exception 3.5KW per rack. The only rooms with 5-6 racks should be Room# 1A5A & 2A 22/24 (serves DR)<br>RFI 015- Calibre does not have current locations of units; that (RT) and Dave discussed. Dave to give new outline to Calibre.<br>RFI 016- Ron getting finishes together.   | BAE     |         |
| A-4-16  | Rooftop TR Options | Option 1: Construct the TR as planned. This would require the below.<br>*Reinforce Columns below for several floors<br>*Existing roof would need to be re-built as the bar joists would also not support weight and snow-drifting loads.<br>*33 ft. steel spans would need to be brought to the roof via tower crane (footing for this would also be an expense)<br>Option 2: Construct a TR that goes through the gabled roof to the West of 1st proposed.<br>*This would not require re-build of roof below<br>*BAE is not certain of the area below gabled roof.<br>*A door with roof access and a ladder will still be installed for condenser unit access. Option 3: Build as originally proposed, 2 TR's at each end of the Penthouse to meet the | VA      |         |



# APPENDIX E

## MEETING MINUTES


| MEETING MINUTES  |   |  |  |  |
|--|---|---|--|--|
| <b>Project Name:</b> EHRM Infrastructure Upgrades<br>Fargo ND VA HCS                     | <b>Project No:</b> 437-21-205<br><b>Bancroft No:</b> 18-121   |   |  |  |
| <b>Meeting Milestone/Purpose:</b> PAGE TURN – 75% Submittal. General notes and questions | <b>Date:</b> January 07, 2022<br>8 :30a.m. – 3:00p.pm (CDT)   | <b>Meeting Location:</b> Fargo On-site and TEAMS                                    |  |  |
| <b>Attendees:</b> Indicates in attendance via TEAMS: **                                  | <b>Company</b>  | <b>Phone</b>  | <b>E-mail</b>  |  |
| Ronald A. Tollefson  | VA / COR-Post-Award   | 701-232-3241<br>#3866   | <a href="mailto:ronald.tollefson@va.gov">ronald.tollefson@va.gov</a>                     |  |
| Christ Moore**   | VA / CS   |   | <a href="mailto:christ.moorer@va.gov">christ.moorer@va.gov</a>                           |  |
| Brandon Meske**  | VA/ Information Technology Specialist                         |   | <a href="mailto:Brandon.Meske@va.gov">Brandon.Meske@va.gov</a>                           |  |
| Ricki Keller**   | VA/ Deputy Assistant Secretary for Information and Technology |   | <a href="mailto:Rickie.Keller@va.gov">Rickie.Keller@va.gov</a>                           |  |
| Todd G. Dalzell**  | VA/ Project Engineer  |   | <a href="mailto:Todd.Dalzell@va.gov">Todd.Dalzell@va.gov</a>                             |  |
| Darlene Flook**  | Bancroft AE / Project Manager                                 | 224-875-6881  | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>                       |  |
| Dana Auman   | Bancroft AE / Project Architect                               | 847-877-1831  | <a href="mailto:Dauman@bancroft-ae.com">Dauman@bancroft-ae.com</a>                       |  |
| Dick Englemen  | Bancroft AE/ Sr Cost Estimator                                | 224-265-0326  | <a href="mailto:dengleman@bancroft-ae.com">dengleman@bancroft-ae.com</a>                 |  |
| David Gamble**   | Bancroft AE/ Sr Mechanical Engineer                           | 207-245-5830  | <a href="mailto:dgamble@bancroft-ae.com">dgamble@bancroft-ae.com</a>                     |  |
| Josh Mikels**  | Bancroft AE / VP of Engineering                               |   | <a href="mailto:jmikels@bancroft-ae.com">jmikels@bancroft-ae.com</a>                     |  |
| Bruce Yoch   | BrightTree Studios  | 412.225.6749  | <a href="mailto:byoch@brighttreestudios.com">byoch@brighttreestudios.com</a>             |  |
| Aaron Mangione**   | Calibre Engineering   | 720-704-8488  | <a href="mailto:amangione@calibre-engineering.com">amangione@calibre-engineering.com</a> |  |
| Travis Benjamin **   | Calibre Engineering   | 303- 952-1875   | <a href="mailto:tbenjamin@calibre-engineering.com">tbenjamin@calibre-engineering.com</a> |  |
| Kyle Haas**  | Hohbach-Lewin, Inc.   | 415-968-1731  | <a href="mailto:khaas@hohbach-lewin.com">khaas@hohbach-lewin.com</a>                     |  |
| Mona **  | Hohbach-Lewin, Inc.   |   | <a href="mailto:mzahedi@hohbach-lewin.com">mzahedi@hohbach-lewin.com</a>                 |  |
| Jeff Scott**   | FP&C  |   | <a href="mailto:jscott@fpc-consultants.com">jscott@fpc-consultants.com</a>               |  |

| Item | Action Item | Comments and Notes   | Group/Person Responsible | Target Completion Date |
|------|-------------|--|--------------------------|------------------------|
| 1    |             | <b>95% Submittal Notes:</b> <ul style="list-style-type: none"><li>• Spec book – turn of text edits</li><li>• Spec book – submit one copy only</li><li>• Drawings – 2 full size, 1 half size</li><li>• Drawings - Subcontractor logos in border file</li><li>• Room BC-60 – no remodel work as part of Scope of Work</li></ul>  |                          |                        |
| 2    |             | <b>BOD – OPCC:</b> <ul style="list-style-type: none"><li>• Change title to include appendix letter</li><li>• Pg 4/Line 32- Added duct banks around perimeter costs, includes hauling out material</li><li>• End budget amount went up 2.2 mil, DE explained multiplier 10% to catch things missed or added. Building Costs are 12.2% higher.</li><li>• Building Break-outs 1/9/46 -to be corrected</li></ul>   |                          |                        |
| 3    |             | <b>BOD – General:</b> <ul style="list-style-type: none"><li>• Table of Contents &amp; Executive Summary missing</li><li>• 1.5 design alerts repeated</li><li>• 2.1 Executive Summary missing</li><li>• 2.5 Circles deleted</li><li>• 2.6 Circles to be corrected</li><li>• 2.7 IT Equipment to be replaced, change to, to be relocated</li><li>• 2.9 Missing Arrow</li><li>• Building 52 Missing</li><li>• Appendix – Picture of Cover for each &amp; state each document is a separate document</li><li>• Terracon Appendix Tables missing, explain samples better</li><li>• Appendix B – Blast. Distance around building clarity.</li><li>• Missing Calibre Calculations</li><li>• Abatement Appendix : No Building 1-9-46 Penthouse level samples taken by Terracon? (Not included in report or in BOD.) If not, survey needed.</li><li>• Abatement Appendix: Lead containing paint in BD-02? Terracon to verify. If not, lead containing paint spec section can be removed.</li><li>• Building 52 drawings provided by Station. To be forwarded to Calibre Civil asap.</li></ul> |                          |                        |
| 4    |             | <b>BOD - IT/Security:</b> <ul style="list-style-type: none"><li>• Open IT racks can be against walls if sides are accessible. Rack to be changed to open sided. Station to request variance from OEHRM to deviate from rack design requirements to go to open sides.</li></ul>   |                          |                        |



# APPENDIX E

## MEETING MINUTES (CONT'D)


| MEETING MINUTES   |  |   |  |  |
|---|--|--|--|--|
| <b>Project Name:</b> EHRM Infrastructure Upgrades<br>Fargo ND VA HCS                        |  | <b>Project No:</b> 437-21-205<br><b>Bancroft No:</b> 18-121  |  |  |
| <b>Meeting Milestone/Purpose:</b> PAGE TURN –<br>75% Submittal. General notes and questions |  | <b>Date:</b> January 07, 2022<br>8 :30a.m. – 3:00p.pm (CDT)<br><b>Meeting Location:</b> Fargo On-site and TEAMS  |  |  |
| 4   |  | <ul style="list-style-type: none"><li>Fiber pathway - add note to account for source b future pathway for cable, even if just at opposite sides of corridor if 60' spacing cannot be accomplished. Source B needs to be one side of corridor, A on the other side</li></ul>  |  |  |
| 5   |  | <b>BOD – Mechanical:</b> <ul style="list-style-type: none"><li>Temperature and humidity are to be Monitored and Alarmed</li></ul>  |  |  |
| 6   |  | <b>BOD – Electrical:</b> <ul style="list-style-type: none"><li>UPS Power Distribution, change statement.</li></ul>   |  |  |
| 7   |  | <b>BOD- Fire Protection:</b> <ul style="list-style-type: none"><li>All TR's openings are to be fire-stopped, not just new.</li></ul>   |  |  |
| 8   |  | <b>BOD - Architecture:</b> <ul style="list-style-type: none"><li>Plywood in TR's to be placed vertically.</li><li>BOD page 2-14 – Hold on review comment until COR talks to IT</li></ul>   |  |  |
| 9   |  | <b>Drawings - Architectural/General:</b> <ul style="list-style-type: none"><li>COR to verify with Station engineers as to whether the steam tunnel may be used as part of the site fiber routing. <u>Note: Asbestos in tunnel</u></li><li>All designated vertical cores on architectural –Indicate three cores<ul style="list-style-type: none"><li>1 for Source A fiber</li><li>1 for electrical</li><li>1 for future Source B fiber</li></ul></li><li>Regarding fiber routing through Healing Garden:<ul style="list-style-type: none"><li>Spec for contractor to photograph prior to work to document final appearance to be restored.</li><li>Spec for 2 year warranty of work.</li></ul></li><li>Demolition note to be provided –<ul style="list-style-type: none"><li>Assume 1,000 SF of hard plaster ceiling above drop ceilings to be removed.</li><li>Assume ICRA protection required for this Work.</li></ul></li><li>Prior to the page turn, the Station engineering group leadership vetoed locating the Penthouse TR east of the elevator machine room (south of the current proposed TR addition). This leaves placing the TR locations at the north and south ends of the original building penthouse level.</li><li>Penthouse -exterior access stairs installed as part of the Scope. Deduct Alternate</li></ul> |  |  |
| 10  |  | <b>Drawings - Civil/Structural:</b> <ul style="list-style-type: none"><li>Need note telling GC to consider traffic routing on demo plan.</li><li>Specify conduit seals at manholes.</li><li>Look into high-water alarms.</li></ul>   |  |  |

|    |  |  |  |  |
|----|--|--|--|--|
|    |  | <ul style="list-style-type: none"><li>Fix Building # overlap</li><li>Legend- fix light to dark re; water main</li><li>Show outline of Building 52Note 4- GC reusing existing conduit, delete.</li><li>CF100 Asset Schedule. Delete. Change title</li><li>Missing drawing # on grading plan, need key</li><li>CU100 Overall utility Plan. Show reference only. GC to verify locations.</li><li>CU106 where does vault enter hospital?</li><li>CU107 mis-labeled buildings</li><li>Rebar is talked about but not shown. Spacing not given.</li><li>Centrelink – note or approved equal</li></ul>   |  |  |
| 11 |  | <b>Drawings – Fire Protection:</b> <ul style="list-style-type: none"><li>Smoke detectors. Per COR – to be incorporated into the design with removal from scope as part of a deduct alternate.</li><li>Method of installing smoke detectors,<ul style="list-style-type: none"><li>COR questions whether terminal strips are acceptable to the VA.</li><li>COR to contact Station and national VA fire protection engineers to confirm.</li></ul></li><li>S-003 – Quality assurance note 3 – to be eliminated</li><li>COR notes that clean agent fire extinguishers apparently have same appearance as type ABC fire extinguishers. Would like BAE to investigate a way to distinguish between types so that later extinguishers will not be mistakenly exchanged from their proper locations.</li><li>Branch line key needs to be fixed</li><li>Key Plan to be on all plans</li><li>General notes #4 sprinkler head Factory Mutual not UL</li><li>All pipes are Red</li><li>FXO412 Existing to move. No pipe shown, can it be deleted</li><li>Detail 5 need to define</li><li>VA/Ron to email National Life Safety w/drawing about servicing Smoke Detectors.</li></ul> |  |  |
| 12 |  | <b>Drawings – IT/Security:</b> <ul style="list-style-type: none"><li>Use 4x8 plywood in all out-buildings (not 4x4) Vertically.</li><li>Extend areas of work to include extended lengths of cable tray as requested by VA review comments.</li><li>Wireless access point - make note for 10' service loop</li><li>Room 1B-121 – Must have 2 racks.<ul style="list-style-type: none"><li>Shift door to garage.</li></ul></li><li>Room 1A-54 – 6 racks required.</li></ul>   |  |  |



# APPENDIX E

## MEETING MINUTES (CONT'D)

| MEETING MINUTES   |  |  |
|---|--|---|
| Project Name: EHRM Infrastructure Upgrades<br>Fargo ND VA HCS                         | Project No: 437-21-205<br>Bancroft No: 18-121        |   |
| Meeting Milestone/Purpose: PAGE TURN –<br>75% Submittal. General notes and questions. | Date: January 07, 2022<br>8 :30a.m. – 3:00p.pm (CDT) |   |
|   |  | Meeting Location: Fargo On-site and TEAMS   |

|  |   |  |  |
|--|---|--|--|
|  | <ul style="list-style-type: none"><li>Room 1C-99 – 5 racks required.</li><li>OIT Rooms – IT equipment to be migrated –<ul style="list-style-type: none"><li>Do not designate "to be abandoned".</li><li>Note for non-IT equipment to remain operational.</li></ul></li><li>Room 1D-64A – 4 racks required.</li><li>Room 2A-24 – 6 racks required.<ul style="list-style-type: none"><li>Back of racks to be 36% off wall.</li></ul></li><li>Room 2D-18 – Flip door location.</li><li>Room 3B-23 – 5 racks required.</li><li>Room 4B-23 – 4 racks required.</li><li>Room 4E-15A – Remove 1 rack.</li><li>TT-00-001<ul style="list-style-type: none"><li>Add See detail TT-xxx at symbols with details</li><li>Delete pay phones</li><li>Reference "VA" instead of COR</li><li>#9 delete "fire rated" and add "on both sides"</li><li>#12 further clarify 295 feet maximum</li><li>#13 add service loop language for WAP</li><li>Rack details</li><li>All walls are to be rated</li></ul></li><li>TT-00-002<ul style="list-style-type: none"><li>Clarify cores</li><li>Revise per site visit</li><li>Specifications should provide detail for landscaping</li></ul></li><li>TT-01-100.A<ul style="list-style-type: none"><li>Add analog frame rack in BC-60. To terminate Cat5e onto.</li><li>Ron to send analog rack pic from St Cloud</li></ul></li><li>TT-01-100.C<ul style="list-style-type: none"><li>Mover text out to white space</li><li>Revise text re. Rated partition (common for all sheets with this note)</li><li>Extend cable tray at bottom left into room to right</li><li>Cable counts - see spreadsheet that Ron provided - some discrepancies</li></ul></li><li>TT-01-101.B<ul style="list-style-type: none"><li>Review/revise areas served</li></ul></li><li>TT-01-101.C<ul style="list-style-type: none"><li>Extend tray per Ron's notes</li></ul></li><li>Add table for sleeves with cable count. Allow for future expansion.</li></ul> |  |  |
|--|---|--|--|


|    |  |  |  |
|----|--|--|--|
|    | <ul style="list-style-type: none"><li>TT-01-103.A<ul style="list-style-type: none"><li>Fix detail 5/xxx. Should be 4</li></ul></li><li>TT-01-103.C<ul style="list-style-type: none"><li>Extend cable tray per Ron's notes</li><li>Clean up fire rated pathways at cable tray - bold lines hide these</li></ul></li><li>TT-01-105.A<ul style="list-style-type: none"><li>Avoid elevator equipment room- this will be changed anyways...</li><li>Clean up detail 2/TT-01-105.A</li></ul></li><li>TT-01-401<ul style="list-style-type: none"><li>Match architectural</li><li>Use square for demo keynotes</li><li>General notes still say 50%</li></ul></li><li>TT-01-402<ul style="list-style-type: none"><li>Delete BAE note at rack</li></ul></li><li>Add note to provide xx number of extender brackets - based on Cisco sku that Ron will provide</li><li>TT-TD504<ul style="list-style-type: none"><li>eliminate some of the details to create typical for each rack (one with UPS, one without)</li></ul></li><li>TT-TD505<ul style="list-style-type: none"><li>change 110 blocks to rack mounted</li><li>TT-TD506</li><li>change Emcore to 45 RU</li></ul></li><li>Expand general notes to require expanding ACS and VMs platforms</li><li>Replace all card readers with new</li><li>Add ACS panel to penthouse</li><li>Add ACS to building 3</li><li>Ad CRs and DCs to cabinets in out buildings</li></ul> |  |  |
| 13 | <p><b>Drawings – Structural:</b></p> <ul style="list-style-type: none"><li>SC001 Change note to be project specific<ul style="list-style-type: none"><li>Note #4 GC to look @ all drawings</li><li>Note #11 STEM reference UOM missing from abbreviation</li><li>Note to GC about Truss design/supplier</li></ul></li><li>SC002 detail 1 where is rebar being used?<ul style="list-style-type: none"><li>Note for People to be moved for reinforcing</li></ul></li><li>Concrete<ul style="list-style-type: none"><li>Note #2 Testing lab, GC to select.</li></ul></li></ul>  |  |  |



# APPENDIX E

## MEETING MINUTES (CONT'D)



| MEETING MINUTES  |  |    |  |  |
|--|--|---|--|--|
| <b>Project Name:</b> EHRM Infrastructure Upgrades<br>Fargo ND VA HCS                         |  | <b>Project No:</b> 437-21-205<br><b>Bancroft No:</b> 18-121   |  |  |
| <b>Meeting Milestone/Purpose:</b> PAGE TURN –<br>75% Submittal. General notes and questions. |  | <b>Date:</b> January 07, 2022<br>8 :30a.m. – 3:00p.pm (CDT)<br><b>Meeting Location:</b> Fargo On-site and TEAMS   |  |  |
|  |  | <ul style="list-style-type: none"><li>o Notes 5.6.7 Who is verifying.</li><li>• Post installed anchor notes #3- Need general note for condensing units</li><li>• S003 Statement VA employs inspector, delete – VA AHJ</li><li>• S5101 GC needs proper signage , note to be directed to life safety plan</li><li>• S5130 Too much white space<ul style="list-style-type: none"><li>o Plans should read L-R, Top-Bottom</li><li>o Detail #4 No dims on how deep</li><li>o Note about frost depth</li><li>o More details to be added</li></ul></li></ul> |  |  |
| 14   |  | <b>Abatement:</b> <ul style="list-style-type: none"><li>• HA001 Need report #, zoom in on room</li><li>• G002A Drawing Index , Fix #'s</li><li>• GI201 Fix Map</li></ul>  |  |  |
| 15   |  | <b>Building 11:</b> <ul style="list-style-type: none"><li>• Change cemetery rack to floor mounted half rack.<ul style="list-style-type: none"><li>o Removable sides</li><li>o No fans</li><li>o All sides, front, back vented</li><li>o No glass (preferred)</li></ul></li></ul>  |  |  |
| 16   |  | <b>Building 12</b> <ul style="list-style-type: none"><li>• Wall mounted half rack</li><li>• Removable sides</li><li>• No fans</li><li>• All sides and front vented</li><li>• No glass (preferred)</li></ul>   |  |  |
| 17   |  | <b>Building 13:</b> <ul style="list-style-type: none"><li>• Wall mounted half rack</li><li>• Same features as above</li></ul>   |  |  |
| 18   |  | <b>Building 30:</b> <ul style="list-style-type: none"><li>• Floor mounted full rack</li><li>• Same features as Building 11</li></ul>  |  |  |
| 19   |  | <b>Building VBA 40:</b> <ul style="list-style-type: none"><li>• Go back to two racks</li></ul>  |  |  |
| 20   |  | <b>Building 51:</b> <ul style="list-style-type: none"><li>• Flip racks</li><li>•</li></ul>  |  |  |
| 21   |  | <b>Building 56:</b> <ul style="list-style-type: none"><li>• Floor mounted half rack –</li><li>• Same features as Building 11</li></ul>  |  |  |



# MEETING MINUTES

## 8-29



# MEETING MINUTES

## 8-30



# MEETING MINUTES

### Weekly Progress Updates

## Meeting Agenda / Minutes

|  |  |
|--|--|
| <b>Item Identification:</b><br>A = Architectural<br>M = Mechanical/HVAC<br>E = Electrical<br>P = Plumbing<br>O = Other Project Items | NOTE: Closed / completed items will be grayed out and carried for ONE meeting cycle, then removed from current list. |
|--|--|

[illegible]



# APPENDIX E

## MEETING MINUTES

### Weekly Progress Updates

#### Meeting Agenda / Minutes Attendee List

|                       |               |
|-----------------------|---------------|
| Bancroft Project No.: | 18-121        |
| Client:               | VA- Fargo     |
| Project Name:         | EHRM          |
| Client Project No.:   | 437-21-205    |
| Contract No.:         | 36C26319D0044 |



| Attendee Name         | Organization | Title                                | Email address  | Phone No.          | Meeting Number |    |    |
|-----------------------|--------------|--------------------------------------|--|--------------------|----------------|----|----|
|                       |              |                                      |  |                    | 9              | 10 | 11 |
| (RT) Ronald Tollefson | Fargo VAMC   | COR, Engineering Department          | <a href="mailto:ronald.tollefson@va.gov">ronald.tollefson@va.gov</a>         | 701-232-3241 #3866 | X              |    |    |
| (CH) Cliff Halvorson  | Fargo VAMC   | Alt. COR, Engineering Department     | <a href="mailto:clifford.halvorson@va.gov">clifford.halvorson@va.gov</a>     | 701-232-3241 #3905 | X              |    |    |
| (CM) Christ Moorer    | VA,VHA       | CS                                   | <a href="mailto:Christ.Moorer@va.gov">Christ.Moorer@va.gov</a>               |                    |                |    |    |
| (AW) Anthony Wilson   | VA,VHA       | CO                                   | <a href="mailto:Anthony.Wilson3@va.gov">Anthony.Wilson3@va.gov</a>           |                    |                |    |    |
| (BW) Brady Wiesner    | Fargo VAMC   | Assistant Chief, Engineering Service | <a href="mailto:Brady.Wiesner@va.gov">Brady.Wiesner@va.gov</a>               |                    |                |    |    |
| (DF) Darlene Flook    | BAE          | PM                                   | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>           | 224-875-6881       | X              |    |    |
| (DA) Dana Auman       | BAE          | PA                                   | <a href="mailto:dauman@bancroft-ae.com">dauman@bancroft-ae.com</a>           | 224-265-2115       | X              |    |    |
| (JM) Jimmy McAllister | BAE          | Architect                            | <a href="mailto:jmcallister@bancroft-ae.com">jmcallister@bancroft-ae.com</a> | 224-577-1600       |                |    |    |
| (WG) Walter Groszko   | BAE          | Project Electrical Engineer          | <a href="mailto:wgroszko@bancroft-ae.com">wgroszko@bancroft-ae.com</a>       | 630-939-0049       |                |    |    |
| (DE) Dick Engleman    | BAE          | Senior Cost Estimator                | <a href="mailto:dengleman@bancroft-ae.com">dengleman@bancroft-ae.com</a>     | 224-265-0326       |                |    |    |

### Weekly Progress Updates


#### Meeting Agenda / Minutes


|                       |            |
|-----------------------|------------|
| Bancroft Project No.: | 18-121     |
| Client:               | VA- Fargo  |
| Project Name:         | EHRM       |
| Client Project No.:   | 437-21-205 |



|                             |  |
|-----------------------------|--|
| <b>Item Identification:</b> | NOTE: Closed / completed items will be grayed out and carried for ONE meeting cycle, then removed from current list. |
| A = Architectural           |  |
| M = Mechanical/HVAC         |  |
| E = Electrical              |  |
| P = Plumbing                |  |
| O = Other Project Items     |  |

| Item    | Topic                           | Description / Discussion   | By whom | By when |
|---------|---------------------------------|--|---------|---------|
| O-16-23 | Building 51                     | Review of Building 51 Revisions/Alternate Plans                                | BAE     |         |
| O-24    | BrightTree Page-Turn Attendance | Extent of comments to BrightTree's drawings. Should BT be onsite for Page-Turn | VA      |         |

|      |                         |   |    |  |
|------|-------------------------|---|----|--|
| O-25 | BrightTree DCIE Comment | <p>BrightTree needs further direction regarding this comment. Is this in regards to the locations where we were directed to place the back of the racks up against the wall.</p> <p>Sheet MH-01-401 (applies to multiple). Racks in TRs should not abut the wall. Center the racks, providing 3' clearance on at least 3 sides and as much is as left on the remaining side to allow technicians to access the lashing points on the network channel racks.</p> <p>"I guess this might get a couple inches on the other end of the rack so please have Bruce and Dana adjust."</p> <p>This situation occurs at the following two locations:</p> <p>Building 1 / TR BD-02 - in this room we can pull the racks off of the wall to provide 36" to the front and aprox 25 to the rear.</p> <p>Building 12 / TR 0005 - in this room, the best we can do is provide 36" on the front side of the rack.</p> | VA |  |
| O-25 | BrightTree DCIE Comment |  <p>2 BUILDING 1-9-46 - ENLARGED PLAN RM BD-02</p> <p>image.png</p>   | VA |  |

| Item | Topic                   | Description / Discussion  | By whom | By when |
|------|-------------------------|---|---------|---------|
| O-25 | BrightTree DCIE Comment |  <p>2 BUILDING 12 - ENLARGED PLAN - RM 0005</p> <p>image</p> |         |         |
| O-26 | Building 51             | Road and Sidewalk will not be changed. During construction, sidewalk, curb and small portion of road will be sectioned-off for excavation etc.    |         |         |
| O-27 | Electrical              | See Notes sent with Agenda.   |         |         |
| O-28 | OPCC                    | Discuss Increase in the OPCC  |         |         |



APPENDIX E

MEETING MINUTES

| MEETING MINUTES  |  | <div><div></div><div>Bancroft</div><div>BANCROFT ARCHITECTS + ENGINEERS</div></div> |  |
|--|--|---|--|
| Project Name: EHRM Infrastructure Upgrades<br>Fargo ND VA HCS                    | Project No: 437-21-205<br>Bancroft No: 18-121    |   |  |
| Meeting Milestone/Purpose: PAGE TURN – 95% Rejection General notes and questions | Date: February 17, 2022<br>8:00am – 4:00pm (CDT) | Meeting Location: Fargo On-site and TEAMS   |  |
| Attendees: Indicates in attendance via TEAMS: **                                 | Company  | Phone   | E-mail   |
| Ronald A. Tollefson  | VA / COR-Post-Award                              | 701-232-3241<br>#3866   | <a href="mailto:ronald.tollefson@va.gov">ronald.tollefson@va.gov</a>                     |
| Clifford Halvorson   | VA / Alternate COR                               | 701-232-3241<br>#3905   | <a href="mailto:clifford.halvorson@va.gov">clifford.halvorson@va.gov</a>                 |
| Shawn J. Bergan  | VA   |   |  |
| Brady N. Wiesner   | VA   |   |  |
| Raymond A. Nelson  | VA/ Area Mgr, D3 MW, T1, FAR                     |   |  |
| Rickie J. Keller   | VA/ IT Spec, D3 MW, T1, FAR                      |   |  |
| Brandon M. Meske **  | VA/  |   |  |
| Darlene Flook  | Bancroft AE / Project Manager                    | 224-875-6881  | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>                       |
| Dana Auman   | Bancroft AE / Project Architect                  | 847-877-1831  | <a href="mailto:Dauman@bancroft-ae.com">Dauman@bancroft-ae.com</a>                       |
| Walter Groszko **  | Bancroft AE / Sr Electrical Engineer             | 630-939-0049  | <a href="mailto:wgroszko@bancroft-ae.com">wgroszko@bancroft-ae.com</a>                   |
| Mark Tomuta **   | Bancroft AE / Mechanical Engineer                |   | <a href="mailto:mtomuta@bancroft-ae.com">mtomuta@bancroft-ae.com</a>                     |
| Dick Engleman  | Bancroft AE / Senior Cost Estimator              | 224-265-0326  | <a href="mailto:dengleman@bancroft-ae.com">dengleman@bancroft-ae.com</a>                 |
| Mona Zahedi **   | Hohbach-Lewin, Inc.                              | 415-968-1732  | <a href="mailto:mzahedi@hohbach-lewin.com">mzahedi@hohbach-lewin.com</a>                 |
| Bruce Yoch   | BrightTree STUDIOS                               | 412.225.6749  | <a href="mailto:byoch@brighttreestudios.com">byoch@brighttreestudios.com</a>             |
| Aaron Mangione **  | Calibre Engineering                              | 720-704-8488  | <a href="mailto:amangione@calibre-engineering.com">amangione@calibre-engineering.com</a> |

This summary constitutes the writer's understanding of the basic matters discussed and the conclusions reached. The participants are requested to review the following and notify Bancroft-AE, of any exceptions, in writing, within ten (10) days of receipt of these meeting minutes. In the absence of such notice, these meeting minutes will be considered accurate.

1 of 7

File Name: K:\CCG\_PROJECTS\2018\18-121 36C26319D0044 VISN 23 IDIQ (North Dakota + Iowa)\437-21-205 EHRM Fargo, ND\200- Communication\201-Meeting Minutes

|                     |                               |               |  |
|---------------------|-------------------------------|---------------|--|
| Jimmy McAllister ** | Bancroft AE / Project Manager |               | <a href="mailto:jmcallister@bancroft-ae.com">jmcallister@bancroft-ae.com</a>             |
| Jon Hammer **       | Terracon                      | 970-397-5289  | <a href="mailto:Jon.Hammer@terracon.com">Jon.Hammer@terracon.com</a>                     |
| Ed Sabia **         | Calibre Engineering           | 303-951-8943  | <a href="mailto:esabia@calibre-engineering.com">esabia@calibre-engineering.com</a>       |
| Travis Benjamin **  | Calibre Engineering           | 303- 952-1875 | <a href="mailto:tbenjamin@calibre-engineering.com">tbenjamin@calibre-engineering.com</a> |
| Jeff Scott **       | FP&C CONSULTANTS              | 816-872-6098  | <a href="mailto:jscott@fpc-consultants.com">jscott@fpc-consultants.com</a>               |



| Item | Action Item | Comments and Notes   | Group/Person Responsible | Target Completion Date |
|------|-------------|--|--------------------------|------------------------|
| 1    |             | <b>BOD:</b><br>Remove all references to Estimated Costs  |                          |                        |
| 2    |             | <b>BOD: OPCC</b><br>2 Mil Covid factor, based on market fluctuations<br>Locality factor based at 10%, can drop depending on competitive bidding at time of Bid<br>Total went up, due to Electrical, Cable Trays and Civil  |                          |                        |
| 3    |             | <b>Drawings/ General:</b><br>Consultants print drawings to check backgrounds, PDF's are not always true.<br>Check all key plans are dark enough<br><u>Friday, 2/25/22 - 12:00 Noon/CST.</u><br>Set of in-progress drawing pdfs due to BAE for internal QA/QC review and Cost Estimating. BAE will provide a dated border file for your use for the in-progress drawings.<br><u>Wednesday, March 2 - 8:00sm/CST.</u><br>95% Resubmittal drawings due to BAE.Dated 3/4/22.BAE will provide a dated border file for the drawings.<br><u>Friday, March 4 - 12:00 Noon/CST.</u> Responses to 95% Submittal drawing comments due to BAE.<br>Reduce white space on drawings |                          |                        |
| 4    |             | <b>Drawings - Abatement:</b><br>HA001/Detail 1 Bldg background too light.<br>HA002, can be eliminated<br>Abetment material can be handled in Anteroom, use Edge Guard infection control system.  |                          |                        |
| 5    |             | <b>Drawings - Fire Protection/Life Safety:</b><br>Remove references to smoke detectors as a deduct alternate.<br>Supervisory Alarms<br>Make Rm #'s darker on key plan<br>Move Key Note (Diamond 3) to better identify sprinkler head<br>FX-01-412 Bldg 9 North zone, not West<br>Make sure existing pipes are called out<br>Rm 503 to be Fire rated<br>ICRA/PCRA/ILSM sample to be placed in Plan  |                          |                        |
|      |             | <b>Drawings - Civil:</b><br>C100 path needs to change to match others<br>BAE to include note for GC- remove fence for temp. NW entrance  |                          |                        |

This summary constitutes the writer's understanding of the basic matters discussed and the conclusions reached. The participants are requested to review the following and notify Bancroft-AE, of any exceptions, in writing, within ten (10) days of receipt of these meeting minutes. In the absence of such notice, these meeting minutes will be considered accurate.

3 of 7



|   |  |   |  |  |
|---|--|---|--|--|
| 6 |  | Make steam tunnel more prominent<br><u>Building 11</u> , change demo that goes through bldg., stop at bldg., change note 8 to NW entrance.<br>Add GC note, "drawings not guaranteed for accuracy"<br>Building 51, leave rock w/trickle pan. Calibre to spec.<br>Building 12 & 13, identify loading docks<br>Chiller plant , note retaining wall<br>Calibre, fix random numbers on plans<br>CU102, building 39 missing<br>Stam Tunnel notes, Bruce/BrightTree to coordinate with Calibre<br>CU104 begin plans to work clockwise around site<br>Vaults/Duct Banks are large, Bruce/BrightTree and Aarron/Calibre to coordinate stacking and making smaller. |  |  |
| 7 |  | <b><u>Drawings – Structural:</u></b><br>General Note: "GC to look at all drawings"<br>Calibre to look at text overlap, fix<br>S101 show sidewalk/road, note to civil<br>Check detail naming<br>Fix floating numbers on plans<br>Stairs on roof, are to be 4'<br>Openings through masonry walls for cables – lintels needed. To be coordinated between telecom, structural and architectural.  |  |  |
| 8 |  | <b><u>Drawings - Architectural/General:</u></b><br>Index flip Mechanical and Elec, order good<br>G1002 Special notes: #7 add #'s<br>Include ICRA/PCRA/ILSM on sheet<br>Buildings 12 & 13, loading dock locations. Show phasing<br>All penetrations 2hrs<br>Add note; 10% pf ceiling removal impairs sprinkler system<br>Ceiling Legend, remove sprinkler heads<br>Fix electrical symbols for demo, check other symbols as well<br>Fire extinguisher cabinets, all rated<br>A-100.2 add note , which signage indicates area<br>Notes calling out Chase details<br>102.4 add hatch notes<br>Details needed on how to enter building, vault to bldg          |  |  |

This summary constitutes the writer's understanding of the basic matters discussed and the conclusions reached. The participants are requested to review the following and notify Bancroft-AE, of any exceptions, in writing, within ten (10) days of receipt of these meeting minutes. In the absence of such notice, these meeting minutes will be considered accurate.

|   |  |   |  |  |
|---|--|---|--|--|
|   |  | Penthouse TR 503 – Coordinate with BrightTree as to final room size.<br>Penthouse Level roof access door – min. 7'-0" high access door.<br>Clarify TR plywood/gypsum partition type<br>A-25101 Shift Fire Ext Cabinet<br>A301 Legend for wall details<br>Note to GC. All wood to be treated<br>Remove plumbing Notes<br>A302 add Fire Ext Cabinet height<br><b>QAQC check grammar</b><br><u>Finish Schedule:</u> Storage LVT Finish<br><u>Signage:</u> Fix Signage room's, Bldg 10 add Fire Ext sign<br>Rockwool Insulation<br>Detail for Cable Tray penetrations into older/brick walls, how supported?  |  |  |
| 9 |  | <b><u>Drawings – Electrical:</u></b><br>Building 1-9-46 – all power to TRs to be routed to panels within same building<br>Remove unnecessary notes that do not pertain to project (have been told on each submission)<br>Shrink room call-out lines to just room, not surrounding rooms<br>Call-outs on conduits, some missing. Use different line-types<br>Key Note: Tell all room numbers, Walter to send Ron, panel notes page<br>Check ceiling fixtures are consistent<br>2 cooling units on wall, each to different panels, redundancy<br>Add emergency power to open walls in TR<br>Reduce white space on drawings<br>3D10 Show power for office wall<br>All cooling to be on Emergency Power<br>No UPS on Penthouse, cannot use. Rm 501 verify panel, 502 needs to be on Emergency not critical<br>Bldg 10, Ron to get new layout to Walter<br>Bldg 11 Remove other project name, check current panel #<br>Bldg 12 show Panel on lighting plan<br>Bldg 30 full rack coordinate w/Bruce<br>40-101 call out Surge Protection Device<br>Bldg 51 coordinate w/Mechanical heater in vestibule<br>Bldg. 52 Fix Key note #6<br>Bldg 56 Show panel in room, fix common notes, no emergency power<br>E501 Remove defender canine #5 |  |  |

This summary constitutes the writer's understanding of the basic matters discussed and the conclusions reached. The participants are requested to review the following and notify Bancroft-AE, of any exceptions, in writing, within ten (10) days of receipt of these meeting minutes. In the absence of such notice, these meeting minutes will be considered accurate.



|    |  |   |  |  |  |  |
|----|--|---|--|--|--|--|
|    |  | E601 Asterisk on schedule, no note. Denote or remove. Panel naming convention follow Va   |  |  |  |  |
| 10 |  | <p><b>Drawings – Mechanical:</b></p> <p>QAQC</p> <p>ADDRESS ALL NOTES WRITTEN ON PLAN</p> <p>THERMOSTAT NOTES CONFUSING Locations are same, change symbol to clarify</p> <p>To many locations not showing chase. Pipe exposed?</p> <p>Security grates not shown on most drawings</p> <p>No BAS details?</p> <p>Show where floor drains go</p> <p>Valves not shown on condensing units</p> <p>Check Electrical notes are coordinated with Electrical</p> <p>Equipment Schedule: units mounted by whom?</p> <p>Notes calling out Chase details</p> <p>Revisit all chase locations</p> <p>Building 51 Condenser to sit on concrete pad north of the building addition. Heater needed in vestibule.</p> <p>Lighting in TRs – General note: Light positions shown are for diagrammatic purposes only.</p> <p>GC shall coordinate with COR for their final positions.</p> <p>M01-100 Avoid SPS storage/ SPS 400</p> <p>2C90- Remove humidifier, replace w/straight duct</p> <p>Bldg 3, no flex duct through walls</p> |  |  |  | <p>Detail for Cable Tray penetrations into older/brick walls, how supported?</p> <p>Change cable trays, as Ron noted in meeting</p> <p>More details on wall penetrations</p> |
| 11 |  | <p><b>Drawings IT-</b></p> <p>Room B2-02 – third rack not needed.</p> <p>Floor mounted cabinets, show bolt details</p> <p>Wall mounted cabinets, top 6' A.F.F.</p> <p>Bldg 30 full cabinet</p> <p>Remove all references to TV in notes</p> <p>Check background line weights</p> <p>Detail of conduit up to Buildings, detail on how to bring fiber into bldgs.</p> <p>Ron to send basement ACAD plans</p> <p>Fox leader lines</p> <p>Indicate what dashed lines are</p> <p>Cable trays to have 2hr sleeves</p> <p>Make sure Cable Tray details are same as plans</p> <p>Revise rates wall legend</p> <p>Extra data drops in TR for phones</p>   |  |  |  |  |

This summary constitutes the writer's understanding of the basic matters discussed and the conclusions reached. The participants are requested to review the following and notify Bancroft-AE, of any exceptions, in writing, within ten (10) days of receipt of these meeting minutes. In the absence of such notice, these meeting minutes will be considered accurate.

File Name: K:\CCG\_PROJECTS\2018\18-121 36C26319D0044 VISN 23 IDIQ (North Dakota + Iowa)\437-21-205 EHRM Fargo, ND\200- Communication\201-Meeting Minutes



# APPENDIX E

## MEETING MINUTES

### Meeting Agenda / Minutes Attendee List

|                       |               |
|-----------------------|---------------|
| Bancroft Project No.: | 18-121        |
| Client:               | VA- Fargo     |
| Project Name:         | EHRM          |
| Client Project No.:   | 437-21-205    |
| Contract No.:         | 36C26319D0044 |



| Attendee Name         | Organization | Title                                | Email address  | Phone No.             | Meeting Number |                |                |
|-----------------------|--------------|--------------------------------------|--|-----------------------|----------------|----------------|----------------|
|                       |              |                                      |  |                       | 10<br>02.10.22 | 11<br>02.24.22 | 12<br>03.03.22 |
| (RT) Ronald Tollefson | Fargo VAMC   | CDR, Engineering Department          | <a href="mailto:ronald.tollefson@va.gov">ronald.tollefson@va.gov</a>       | 701-232-3241<br>#3866 | X              | X              |                |
| (CH) Cliff Halvorsen  | Fargo VAMC   | ALT. CDR, Engineering Department     | <a href="mailto:clifford.halvorsen@va.gov">clifford.halvorsen@va.gov</a>   | 701-232-3241<br>#3905 | X              |                |                |
| (CM) Christ Moorer    | VA,VHA       | CS                                   | <a href="mailto:Christ.Moorer@va.gov">Christ.Moorer@va.gov</a>             |                       |                | X              |                |
| (AW) Anthony Wilson   | VA,VHA       | CO                                   | <a href="mailto:Anthony.Wilson3@va.gov">Anthony.Wilson3@va.gov</a>         |                       |                |                |                |
| (BW) Brady Wiesner    | Fargo VAMC   | Assistant Chief, Engineering Service | <a href="mailto:Brady.Wiesner@va.gov">Brady.Wiesner@va.gov</a>             |                       |                |                |                |
| (DF) Darlene Flook    | BAE          | PM                                   | <a href="mailto:dflook@bancroft-ae.com">dflook@bancroft-ae.com</a>         | 224-875-6881          | X              | X              |                |
| (DA) Dana Auman       | BAE          | PA                                   | <a href="mailto:dauman@bancroft-ae.com">dauman@bancroft-ae.com</a>         | 224-265-2115          | X              | X              |                |
| (JM) Jimmy McAllister | BAE          | Architect                            | <a href="mailto:jmcalister@bancroft-ae.com">jmcalister@bancroft-ae.com</a> | 224-577-1600          |                |                |                |
| (WG) Walter Groszko   | BAE          | Project Electrical Engineer          | <a href="mailto:wgroszko@bancroft-ae.com">wgroszko@bancroft-ae.com</a>     | 630-939-0049          |                |                |                |
| (DE) Dick Engleman    | BAE          | Senior Cost Estimator                | <a href="mailto:deengleman@bancroft-ae.com">deengleman@bancroft-ae.com</a> | 224-265-0326          |                |                |                |

### Weekly Progress Updates

### Meeting Agenda / Minutes

|                       |            |
|-----------------------|------------|
| Bancroft Project No.: | 18-121     |
| Client:               | VA- Fargo  |
| Project Name:         | EHRM       |
| Client Project No.:   | 437-21-205 |



#### Item Identification:


A = Architectural  
M = Mechanical/HVAC  
E = Electrical  
P = Plumbing  
O = Other Project Items

NOTE: Closed / completed items will be grayed out and carried for ONE meeting cycle, then removed from current list.

| Item | Topic           | Description / Discussion   | By whom | By when |
|------|-----------------|--|---------|---------|
| O-29 |                 | Nothing Discussed 02.24.22   |         |         |
| O-30 | ReSubmittal 95% | Comments, Drawings and BOD/OPCC all due to arrive tomorrow   | BAE     |         |
| O-31 | MOD             | Need clarification on MOD request  | VA      |         |
|      |                 | 1.This looks like the timeline of what has happened and your costs so far, what we need to pay you for. You also need to estimate your time for the 95% and 100% of these buildings designs. Add those two dollar figures together and that will then be the total design costs for what is being done.  |         |         |
|      |                 | 2.The other number is the total design costs of what is no longer being done. So I need to see your estimated hours and design effort for the 50%, 75%, 95%, & 100% if all four of these buildings had remained with the original design intent of full TRs. Add all of them together and that would have been the total of what was going to be done. | VA      |         |
|      |                 | 3.Subtract the costs of what is being done from what was going to be done and the remainder will be the amount of the deduct.     2 – 1 = DEDUCT AMOUNT  |         |         |



*Please see OPCC Details Booklet for full report.*



U.S. Department  
of Veterans Affairs

## Opinion of Probable Construction Cost -Appendix "F"

### EHRM INFRASTRUCTURE UPGRADES

Fargo VA Health Care System

2101 Elm Street North  
Fargo, ND 58102-2417

#### BUILDING NUMBER

1-9-46, 3, 10, 11, 12, 13, 30, 40, 51, 52, 56

#### CONTRACT NUMBER

36C26319D0044

#### PROJECT NUMBERS

Project No. 437-21-205  
BAE #: 18-121

Bancroft Architects + Engineers

#### ISSUE SUBMISSION PHASE

IFB OPCC

#### DATE:

3/18/2022

BANCROFT ARCHITECTS + ENGINEERS  
3300 Dundee Road  
Northbrook, IL 60062



BANCROFT ARCHITECTS + ENGINEERS  
102



## SOCAMES 6 Design Alert 1

### Problem

During a recent construction activity of cable upgrades to an existing telecommunication room (TR) at an Initial Operating Capability (IOC) site, it was discovered during cable testing procedures that some of the cables being upgraded were greater in length to the end user device than standards allows.

### Background

ANSI/TIA-568.D, "Balanced Twisted-Pair Telecommunications Cabling and Components" (Sep 2018) version of industry standards for telecommunication room fixed cabling installation, limits the total length of a network Unshielded Twisted Pair (UTP) cable segment to 100 meters. The 100 meters is broken down as 10 meters for patch cables and 90 meters for total fixed cabling. Cable length requires a three-dimensional assessment to ensure that the fixed cables being installed do not exceed the specified UTP cable segment of 90 meters of fixed cable length.

There are several scenarios that require an assessment to occur to ensure that a telecommunication rooms UTP cable segments do not exceed 90 meters.

*Scenario 1:* The installation of a new telecommunication room to serve an area.

*Scenario 2:* The relocation of an existing telecommunication room to serve an area.

*Scenario 3:* The installation of new cabling upgrades in a telecommunication room that will remain in place to serve an area.

*Scenario 4:* An existing telecommunication room that will not receive any cabling upgrades.

### Solution

To ensure that an assessment is performed for each of the four telecommunication room scenarios listed above, our office in conjunction with the SD-DCIE team is providing a recommended three-dimensional estimation approach that can be shared with your respective facility leads and design team to verify all telecommunication rooms do not exceed the specified UTP cable segment of 90 meters.

**Step 1:** Ensure you have an accurate floor plan that depicts the locations of the telecommunication rooms serving the facility.

**Step 2:** Utilizing AutoCAD or rule, center on the location of the telecommunication room being assessed. From the center of the room project out lines, 80 meters in length from that point, in the plan north, south, east and west respectively.

**Step 3:** At the end each of the 80 meters lines created, connect a line 45 degrees from that point out to the next end point creating a diamond.

**Step 4:** Validate that all areas served by that telecommunication room fall within the parameters of the diamond overlay.



Step 5: If the area served by that telecommunication room is within the diamond overlay then the distance, as provided by the estimation tool, is adequate for that telecommunication room.


Step 6: If the area served by that telecommunication room is outside the diamond overlay then the distance, as provided by the estimation tool, is inadequate for that telecommunication room and further investigation is required by electronically testing the cable lengths to see if they pass or physical measurement. Any UTP cabling that does not pass testing protocols and is too long will need to have further design considerations to remedy the distance issue.

## Notes

Since it is necessary to account for vertical cable distance, installation of slack for bypassing obstructions, cable management, bend radii and other in-situ obstacles 80 meters is utilized instead of the 90 meters acceptable length. This is to provide a realistic estimation of coverage of the representative telecommunication room.

This estimation tool is a recommended approach to validate fixed cable lengths meet the standards. Designers and installers remain responsible for ensuring actual cable distances do not exceed the limits in the standards.

Below is a diagram of an example demonstrating the use of the estimation tool.





## HEFP SEP (SOCAMES 6) Design Alert 2

### Problem

VA OEHRM previously required an on-site or near campus Help Desk during Go-Live. To better serve facilities during Go-Live, the Help Desk will now be remote and supported out of Kansas City.

### Background

VHA HEFP SEP provided guidance in the *Electronic Health Record Modernization Training and Support Space, HEFP SEP Space Planning Job Aid*, 11/10/2020 revised 1/27/2021, that required 1,800 square feet of space for the Help Desk as part of the Command Center.

### Solution

The *Electronic Health Record Modernization Training and Support Space, HEFP SEP Space Planning Job Aid*, has been updated to reflect the new requirements. The requirement for Help Desk space within the Go-Live Command Center was deleted, therefore, space is not needed for this activity.

### Notes

Please use this link, [Electronic Health Record Modernization Training and Support Space, HEFP SEP Space Planning Job Aid](#), 11/10/2020 revised 3/16/2021 to find the most up-to-date information.



## HEFP SEP (SOCAMES 6) Design Alert 3

### Problem

VA OEHRM previously planned for 3.5 classes per end user and either 8 seats per class with social distancing or 15 seats per class without social distancing. However, during the recent VHA EHRM Strategic Review, it was determined that each end user shall have 5 classes and that there will be either 8 seats per class with social distancing or 12 seats per class without social distancing. The changes described result in a larger space need.

### Background

VHA HEFP SEP provided guidance in the *Electronic Health Record Modernization Training and Support Space, HEFP SEP Space Planning Job Aid*, 11/10/2020 revised 1/27/2021, that required 3.5 classes per end user and either 8 seats per class with social distancing or 15 seats per class without social distancing. VA OEHRM and VHA determined that more class time per end user and a decrease in the overall class size are needed.

### Solution

The *Electronic Health Record Modernization Training and Support Space, HEFP SEP Space Planning Job Aid*, has been updated to reflect the new requirements. The following classroom calculations were revised.

#### Previous classroom calculations:

#### Standard Room Calculations

VAMC Total rooms = Number of end users x **3.5 classes per end user / 15 seats per class** / 8 weeks of EUT / 5 days of training per week

CBOC Total rooms = Number of end users x **3.5 classes per end user / 15 seats per class** / 8 weeks of EUT / 5 days of training per week.

#### Social Distanced Room Calculations

VAMC Total rooms = Number of end users x 3.5 classes per end user / 8 seats per class / 8 weeks of EUT / 5 days of training per week



CBOC Total rooms = Number of end users x 3.5 classes per end user / 8 seats per class / 8 weeks of EUT / 5 days of training per week.

#### New classroom calculations:

##### Standard Room Calculations

VAMC Total rooms = Number of end users x **5 classes per end user / 12 seats per class** / 8 weeks of EUT / 5 days of training per week

CBOC Total rooms = Number of end users x **5 classes per end user / 12 seats per class** / 5 weeks of EUT / 5 days of training per week.

##### Social Distanced Room Calculations

VAMC Total rooms = Number of end users x 5 classes per end user / 8 seats per class / 8 weeks of EUT / 5 days of training per week

CBOC Total rooms = Number of end users x 5 classes per end user / 8 seats per class / 5 weeks of EUT / 5 days of training per week.

## Notes

Please use this link, [Electronic Health Record Modernization Training and Support Space, HEFP SEP Space Planning Job Aid](#), 11/10/2020 revised 4/20/2021 to find the most up-to-date information.



## HEFP SEP (SOCAMES 6) Design Alert 4

### Problem

Clarification to the field is needed regarding the design of space for Telecommunications Rooms (TRs) in existing facilities for the Electronic Health Record Modernization (EHRM) initiative. The design reference, *Infrastructure Standards for Telecommunications Spaces – Version 3.0* requires 170 sq ft TRs for clinical spaces. However, due to existing space and structural constraints, HEFP SEP requires, at a minimum, only 100 sq ft TRs for clinical spaces in **existing** buildings.

### Background

The *Infrastructure Standards for Telecommunications Spaces – Version 3.0* was developed by the Solution Delivery-Data Center and Infrastructure Engineering (OIT SD-DCIE) team and published to the TIL August 21, 2020. HEFP SEP identifies the following references as standards for all Information Technology (IT) physical infrastructure design and construction projects: *Infrastructure Standards for Telecommunications Spaces – Version 3.0* and *VA OEHRM Site Infrastructure and End User Device Requirements*. These references are discussed and provided to each station during and after their scheduled scoping session to identify the work needed to modernize IT infrastructure across the enterprise.

During the site scoping sessions, HEFP SEP uses the Generic Floor Plan for TRs (Two Rack Requirement), detail 3, page 155 in Appendix B-7 of the *Infrastructure Standards for Telecommunications Spaces – Version 3.0* to communicate and coordinate space requirements for **existing** TRs to support EHRM. The baseline TR template is a 10 ft x 10 ft (100 sq ft) generic floor plan with two 2 ft x 4 ft racks to house the IT infrastructure.

*Infrastructure Standards for Telecommunications Spaces – Version 3.0* specifies that a clinical TR should have a generic floor plan layout of 170 sq ft to support four 2 ft x 4 ft racks. This specification for clinical TRs has created a conflict with the standardized baseline TR of 100 sq ft that HEFP SEP works with the sites to achieve.

HEFP SEP discussed the conflict in TR size requirements with the OIT SD-DCIE team. HEFP SEP identified that due to VAMC/CBOC space deficits, **existing** building footprints, and the number of TRs, it is difficult to meet the 170 sq ft space requirement without a detrimental impact to healthcare operations. Furthermore, based on the average number of end users associated with each TR, most TRs only house 2 racks and require 100 sq ft of space. HEFP SEP and OIT SD-DCIE agreed that the 100 sq ft baseline standard was the practical approach in **existing** buildings.



## Solution

All EHRM projects that require TR work in **existing** spaces shall minimally use the Generic Floor Plan for TRs (Two Rack Requirement), detail 3, page 155 in Appendix B-7 of the *Infrastructure Standards for Telecommunications Spaces – Version 3.0* which requires a 10 ft x 10 ft space to support two 2 ft x 4 ft racks. Room dimensions shall be increased by 20 sq ft for any additional 2 ft x 4 ft racks.

All new construction of clinical spaces should adhere to the standards as written.

## Notes

Please use this link, <https://www.cfm.va.gov/til/dguide/OIT-InfrastrucStdTelecomSpaces.pdf> to locate the current version of Infrastructure Standard for Telecommunication Spaces – Version 3.0 published August 21, 2020.



## HEFP SEP Design Alert 5

### Problem

Clarification is required regarding the need to replace or install new fire suppression systems in the data center during design and construction of Electronic Health Record Modernization (EHRM) facility infrastructure projects and the need for a third-party fire engineer review of HEFP SEP EHRM Infrastructure Upgrades Projects.

### Background

On June 1, 2021 the new [Fire Protection Design Manual](#) was published and posted to the Technical Information Library (TIL). The manual contains fire protection engineering design for Department of Veterans Affairs facilities. EHRM facility infrastructure projects, and specifically work conducted in the Data Centers, may require an upgrade or replacement of the existing fire suppression system in accordance with NFPA 75 as stated in the [Fire Protection Design Manual](#) Paragraph 3.7.

### Solution

VHA field engineers are required to ensure that the Architect-Engineer designer of record applies all applicable NFPA 75 requirements for work needed in the Data Center. Field engineers should use the Healthcare Environment and Facilities Programs (HEFP) Fire Code Plan Review Contract to review all EHRM Infrastructure Upgrades and Data Center projects. The fire code plan review should focus on compliance with the newly published Fire Design Manual dated June 1, 2021 and ensure that all associated NFPA fire and life safety codes are indicated in the designs.

Guidance to the Architect-Engineer is as follows:

For EHRM Infrastructure Upgrade and Data Center projects, the work conducted in the Data Centers (which will upgrade spaces to an ANSI/TIA-942-B, Rating 3) generally requires compliance with all requirements of NFPA 75. The most design intensive of these requirements is the addition of a gaseous fire suppression system as described in the [Fire Protection Design Manual](#), Paragraph 3.7. Compliance with NFPA 75 is also likely to involve, but not necessarily be limited to, these additional retrofit requirements:

- Revise the sprinkler protection in the computer room to a dedicated sprinkler zone.
- Ensure a minimum 1-hour boundary around the computer room.



- Combination smoke/fire dampers at the duct penetrations through the 1-hour boundary of the computer room.
- Electrical power off button(s) at computer room exit(s).
- HVAC power off button(s) at computer room(s).

## Notes

Please use this link, [Fire Code Plan Reviews | Healthcare Environment and Facilities Programs \(va.gov\)](#) to request third-party fire engineer review for your EHRM upgrades projects.




## HEFP SEP (SOCAMES 6) Design Alert 6

### Problem

HEFP SEP is working with OIT to create a process for installation of the additional geographically diverse path for the Wide Area Network (WAN) to ensure compliance with the VA OERHM Site Infrastructure Requirements (SIEUDR), version 2.0, paragraph 2.1.1.2.B (see below). However, HEFP SEP determined that there is currently no national OIT or OEHRM process to coordinate this work with the OIT contracted providers.

#### 2.1.1.2 VAMC Sites

- B. Facility shall have end-to-end, geographically diverse and carrier-diverse circuits with minimum fiber pathways separation: service provider public rights-of-way 75 ft, Egress 20 ft, and cabinet 10 ft. See below Figure 1.





## Background

HEFP SEP completed scoping sessions in preparation for the Cerner deployment. HEFP SEP is in the process of finalizing scoping at all sites by November 2021. During these scoping sessions, HEFP SEP validates whether a site has a geographically diverse path to meet the requirement cited above. If the site did not have existing geographically diverse WAN paths, HEFP SEP identified this as a deficiency, included design and construction of the WAN paths in the scope of work and allocated funding in the ROM IGCE the scoping session. The purpose was to ensure the work was included in the scope and provide a magnitude cost estimate to design and construct the secondary conduit run to meet this requirement.

HEFP SEP has discovered that there is currently no national OIT or OEHRM process to coordinate this work with the OIT contracted providers. HEFP SEP is in discussions with OIT and OEHRM to clarify the process of working with OIT contracted providers so that guidance can be provided to the field. Without a clear process to work with OIT contracted providers, it is difficult, and sometimes not possible, to identify the location of the provider's entrance at the property boundary and the resulting pathway to the main service entrances.

## Solution

Due to the contractual discussions OIT must have with the WAN providers to coordinate this work, HEFP SEP cannot provide adequate guidance to field engineers to ensure that this requirement is met.

To prevent delay and ambiguity in meeting this requirement, if a VAMC is unable to identify or locate the boundary entrance point, HEFP SEP recommends that the site discontinue this effort in current EHRM NRM projects and de-scope this work from the design and/or construction contracts (whichever applies). At this time, HEFP SEP will not provide updated IGCEs, but VAMCs may adjust cost estimates, as they find appropriate.

If a site has successfully coordinated this work with OIT and included diverse pathways in their designs, please reach out directly to James Cullum and Mike Vulpis so that HEFP SEP can ensure OIT agrees on a case-by-case basis.

When HEFP SEP clarifies the OIT process for implementing this requirement with contracted providers, our office will schedule supplementary scoping sessions with the field to scope this work under a separate EHRM NRM project.

## Notes



Please use this link, [VHA HEFP EHRM - 00 VA OEHRM Site Infrastructure Requirements - 2.0 Signed.pdf - All Documents \(sharepoint.com\)](#) to locate the current version of OERHM Site Infrastructure Requirements – 2.0.



## HEFP SEP (SOCAMES 6) Design Alert 7

### Problem

There are specific circumstances when construction of a conditioned Telecommunication Room (TR) is infeasible or impractical in non-clinical buildings such as engineering/maintenance buildings, warehouses, temporary modular trailers and quarters that were converted to administrative space. In cases where existing space, structural or other constraints do not practically allow for construction of a TR, the use of a Telecommunication Enclosure (TE) is appropriate.

### Background

HEFP SEP has seen a considerable increase in variance requests to deviate from the 80 square foot TR space standard as defined in the *Infrastructure Standards for Telecommunications Spaces* (ISTS). The variance requests specifically address low use, non-clinical TRs where expansion or new construction are not viable solutions due to space and/or environmental constraints.

### Solution

The site should make every reasonable effort to comply with the current ISTS standard for all TRs in non-clinical buildings. However, where space and/or environmental constraints cannot support a new TR, both a Standard TE and Non-Standard TE are available for consideration under the conditions described below.

**A Variance is NOT REQUIRED for a STANDARD TE (fan-cooled) if all the following criteria are met:**

1. **Space Classification:** The space is one of the following:
  - a) Parking structures
  - b) Technical spaces such as warehouses, kitchens, laundries, mechanical/electrical plant buildings, chiller or boiler plants, garages, and paint shops
  - c) Historical quarters converted to administrative use
  - d) Buildings with no VA staffing presence and no requirements for connectivity to the VA LAN or guest Wi-Fi
  - e) Temporary modular trailers. *Temporary* buildings and trailers must be validated as temporary, with a planned removal date and no history of previous deferred or cancelled removal plans.



## HEFP SEP (SOCAMES 6) Design Alert 7

2. **Usage:** Usage is limited to a maximum of 96 Work Area Outlets (WAOs). Each data jack in a workspace telecommunications outlet, wired back to the patch panels in the TE, is considered a WAO for these purposes. Where 1-48 WAOs are planned, a 12RU (half-height) standardized TE is used. Where 49-96 WAOs are planned, a 26RU (full height) standardized TE is used.
3. **Environment:** Spaces meet the environmental envelope conditions for a TR, as described in Figure 19 and Table 24 of the Infrastructure Standard for Telecommunications Spaces. Ambient air conditions in the space are between 41°F-95°F dry bulb, 8-80% RH, and dew point less than 82.4°F, measured at the intake point of the TE.

Standard TE's (or equal) are provided below:

12RU - <https://www.chatsworth.com/en-us/products/cabinets-enclosures-containment/wall-mount-cabinets/swing-frame/cube-it-wall-mount-cabinet/11900-e24>

26RU - <https://www.chatsworth.com/en-us/products/cabinets-enclosures-containment/wall-mount-cabinets/swing-frame/cube-it-wall-mount-cabinet/12419-e48>

**If all the above criteria are met, except for paragraph 4. *Environment*, a NON-STANDARD (Environmentally Conditioned) TE may be considered, and a Variance is REQUIRED. To request a NON-STANDARD TE Variance:**

1. Determine if another space in the building meets the environmental and physical security criteria for the installation of a standardized TE. If so, a standardized TE shall be relocated to the environmentally appropriate space in the building.
2. If no other spaces in the building meet the environmental and physical security criteria, submit a Variance request to DCIE for installation of a non-standard (environmentally conditioned) TE. Select which non-standard TE is proposed for use and submit the installation plan, showing the location on an as-built drawing.
3. A sampling of vendors that may meet the intent of a non-standard (environmentally conditioned) TE solution include:
  - a. Liebert (Vertiv) MCR Mini Computer Room Enclosure  
<https://www.vertiv.com/en-us/products-catalog/facilities-enclosures-and-racks/integrated-solutions/mcr---mini-computer-room-enclosure/>
  - b. Hoffman Spectracool – A side-mount A/C unit capable of attaching to many common manufacturer's cabinets (comes in a variety of sizes)  
[https://hoffman.nvent.com/sites/g/files/hdkjer316/files/acquiadam/2021-05/Spec-00728.pdf?asset\\_type=Spec](https://hoffman.nvent.com/sites/g/files/hdkjer316/files/acquiadam/2021-05/Spec-00728.pdf?asset_type=Spec)



## HEFP SEP (SOCAMES 6) Design Alert 7

- c. EIC Solutions Protector Series, Wall-Mount Enclosure S723616 Wall-mount AC Enclosure - 72"H x 36"W x 16"D with EIC Solutions CB Series, Compressor-Based, Side-Mount, Hazardous Location Enclosure CBIQ6000V16XP2 - 6,000 BTU Hazardous Location Air Conditioner <https://www.eicsolutions.com/protector-series-air-conditioned-electronic-enclosures/> and <https://www.eicsolutions.com/product/cbiq6000v16xp2/>

### Notes

Variance request information is in the [\*Infrastructure Standard for Telecommunication Spaces \(ISTS\)\*](#) standard, Section 1.3.1 and Appendix A.

Once approved, the designer of record **MUST** incorporate the approved TE into the design documents.



## HEFP SEP (SOCAMES 6) Design Alert 8

### Problem

A conflict was noted between the [Infrastructure Standard for Telecommunication Spaces \(ISTS\) v3.1](#) and the [HVAC Design Manual](#) concerning design parameters for temperature and relative humidity ranges in Telecommunication Spaces.

### Background

This Design Alert provides temporary guidance on temperature and relative humidity design ranges for Telecommunication Spaces. This Design Alert will remain in effect until the Infrastructure Standard for Telecommunications Spaces and the HVAC Design Manual publish updates that reconcile the temperature and relative humidity parameters.

### Solution

The HVAC Design Manual requires a dry bulb temperature of 64° F for heating and 81° F for cooling and a relative humidity of 30% RH to 60% RH for Telecommunication Spaces, (pp. 6-106 for Data Centers and pp. 6-109 for TRs). These temperatures are supply temperatures. The ISTS requires rack inlet temperatures in telecommunications rooms between 41°F and 95°F and between 72°F and 80.6°F in computer rooms with a relative humidity range of 8% to 80%. Please use the [Computational Fluid Dynamics \(CFD\) Modeling Guide](#) for CRAC and rack inlet temperature design in Data Centers while meeting the more stringent of the two standards. To summarize, AC supply temperature set points must be between 64°F and 81°F per the HVAC Design Manual while maintaining rack inlet temperatures between 72°F and 80.6°F in computer rooms. Relative humidity in all telecommunications spaces will be maintained at the more stringent HVAC Design Manual requirements of 30% to 60%.