

Clarification to Scope of Work:

1. Materials used in the creation of the HVAC duct chase wall located in room 213A, will match existing. Including, but not limited to:
 - a. Paint. Prime coat to be white in color. Finish paint basis of design is Benjamin Moore Eco Spec, or approved equal, color to match existing. Field verify and provide sample color match during submittal process.
 - b. Resilient Base. Reuse existing resilient base as able. Replace if damaged during removal. Match existing. Vinyl base is assumed to be Fawn color. Field confirm manufacturer, size, profile, and color. Provide sample during submittal process.
 - c. ACT and grid. Acoustical Tile: USG 2110 2' x 2' Field confirm and match existing ACT tile and grid.
2. Exhaust Grill (12x24) standard type: Fixed horizontal face bars set at 30° to 45° approximately 30mm (1¼-inch) margin.
3. Space exhaust grills and supply registers to allow proper room air circulation. Align with existing suspended grid layout (Grid: USG Donn DX). Ensure exhaust system will not short cycle with supply.

Clarification to Construction Drawings:

Individual changes to drawings are outlined below.

1. Create dormer space with header for bearing wall. Contractor to verify best practice for installation.
 - a. Suggested installation: (3) 2x6's on (2) jack studs and (1) king stud – Each side.
 - b. Cripple as needed.

