



- ACOUSTICAL PLASTER
- FLOOR TILE MASTIC
- ABATE ACOUSTICAL PLASTER IN ACCORDANCE WITH 02 82 11.
- ABATE FLOOR TILE MASTIC IN ACCORDANCE WITH 02 82 13.19
- ABATE THERMAL SYSTEM INSULATION IN ACCORDANCE WITH 02 82 13.13
- ABATE TRANSITE PANELS LOCATED BEHIND RADIATORS IN ACCORDANCE WITH 02 82 13.31

**GENERAL ABATEMENT NOTES**

1. CONTRACTOR MUST COMPLY WITH INFECTIOUS DISEASE CONTROL REQUIREMENTS.
2. SOLID WALLS INDICATE EXISTING CONSTRUCTION TO REMAIN.
3. DASHED LINES INDICATE EXISTING CONSTRUCTION TO BE REMOVED.
4. REFER TO ARCHITECTURAL, STRUCTURAL, MECHANICAL, ELECTRICAL, PLUMBING AND CIVIL DRAWINGS TO DETERMINE EXACT EXTENT OF DEMOLITION REQUIRED TO COORDINATE WITH NEW CONSTRUCTION.
5. CONTRACTOR TO CAREFULLY AND PRUDENTLY PERFORM ABATEMENT AS INDICATED. CONTRACTOR SHOULD CAREFULLY OBSERVE EXISTING CONDITIONS PRIOR TO ANY AND ALL WORK AND COORDINATE SUCH WORK WITH NEW CONSTRUCTION. ARCHITECT SHALL BE NOTIFIED IMMEDIATELY IF ANY DISCREPANCIES ARISE.
6. CONTRACTOR TO PROTECT AND SHORE ADJACENT AREAS THAT ARE TO REMAIN INTACT DURING DEMOLITION AND ENSURE MAINTENANCE OF EXISTING STRUCTURAL INTEGRITY.
7. CONTRACTOR IS RESPONSIBLE FOR ALL DEMOLITION NECESSARY TO ACCESS MATERIALS TO BE ABATED.
8. DEMOLITION WORK INCLUDES DISCONNECTIONS, CAPPING AND/OR REMOVAL OF ALL ELECTRICAL, PLUMBING AND HVAC LINES AND/OR EQUIPMENT WHICH IS FOUND WITHIN OR ADJACENT TO SPECIFIC ITEMS NOTED TO BE DEMOLISHED. CONFIRM ANY DISCREPANCIES WITH ARCHITECT IN WRITING. SEE MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS.
9. SERVICE COORDINATE WITH MECHANICAL, ELECTRICAL AND PLUMBING CONTRACTORS WHERE DEMOLITION INVOLVES ABANDONMENT OF EXISTING MECHANICAL, ELECTRICAL AND PLUMBING SERVICE. COORDINATE WITH MECHANICAL, ELECTRICAL AND PLUMBING CONTRACTORS.
10. CONTRACTOR TO COORDINATE WITH THE OWNER THE DISCONNECTION OR INTERRUPTION OF ANY MECHANICAL, PLUMBING, ELECTRICAL, DATA OR COMMUNICATION SERVICES PRIOR TO DEMOLITION. CONTRACTOR TO COORDINATE WITH THE OWNER THE NEED FOR AND LOCATION OF TEMPORARY SERVICES.
11. EXISTING CONDITIONS WHICH ARE DISCOVERED DURING DEMOLITION THAT WILL INTERFERE WITH THE FINAL FLOOR PLAN ARE TO BE REPORTED TO THE ARCHITECT IMMEDIATELY.

**ADDENDUM 1**

**THIRD FLOOR ABATEMENT PLAN**  
 1/8" = 1'-0"

Scale: As indicated

Revisions:	Date

**ENGINEERS/CONSULTANTS:**

WOOLPERT, INC. 343 FOUNTAINS PARKWAY SUITE 100 FAIRVIEW HEIGHTS, IL 62208 314-436-0865 314-436-0884 fax	SCI ENGINEERING, INC 130 POINT WEST BLVD. ST. CHARLES, MO 63301 636-949-8200 636-949-8269 fax
--	---

**SEAL**

GLEN GRISSOM  
 ABATEMENT DESIGNER  
 SOUTH DAKOTA  
 DEPARTMENT OF NATURAL  
 RESOURCES CERTIFICATE  
 #7074

**ARCHITECT:**

*Chiodini*

Architecture / Interior Design / Graphics  
 1401 S. Cherokee Blvd. Suite 3711 St. Louis, Missouri 63114  
 314-724-0581 | info@chiodini.com

THE ARCHITECT EXPRESSLY RESERVES HIS COMMON LAW AND STATUTORY LAW COPYRIGHT AND OTHER PROPERTY RIGHTS FOR THESE ARCHITECTURAL WORKS AND TECHNICAL DOCUMENTS, AND ANY DERIVATIVES THEREOF. THESE DRAWINGS AND DOCUMENTS ARE NOT TO BE REPRODUCED, COPIED OR COPIED IN ANY MANNER WHATSOEVER FOR ANY USE WITHOUT FIRST OBTAINING THE EXPRESS WRITTEN CONSENT OF LOUIS G. CHIODINI ARCHITECTS ASSOCIATES, INC. ANY SUCH USE BY ANY PARTY WITHOUT FIRST OBTAINING SAID WRITTEN PERMISSION AND CONSENT IS STRICTLY PROHIBITED AND WILL BE PROSECUTED TO THE FULL EXTENT OF THE LAW.

Drawing Title  
**THIRD FLOOR ABATEMENT PLAN**

Approved: Project Director  
 Approver

Project Title  
**VA HEALTH CARE SYSTEM**

Location  
 VAS 438-16-104 BLDG. 5 CHAPEL  
 SIOUX FALLS, SD 57105

Date  
 2017.03.23

Checked  
 GAG

Drawn  
 C.J.N.

Project Number 438-16-104	2016.052
Building Number 5	
Drawing Number <b>X-1</b>	
Owner	